THE UNIVERSITY
OF ILLINOIS
LIBRARY
540
At8c5

Return this book on or before the
Latest Date stamped below.

University of Illinois Library

NOV 22 1955

L161—H41

Digitized by the Internet Archive
in 2017 with funding from
University of Illinois Urbana-Champaign Alternates

https://archive.org/details/chemistrygeneral00attf_0

CHEMISTRY:

GENERAL, MEDICAL, AND PHARMACEUTICAL.

INCLUDING

THE CHEMISTRY OF THE U. S. PHARMACOPŒIA.

A MANUAL

ON THE GENERAL PRINCIPLES OF THE SCIENCE, AND THEIR APPLICATIONS TO MEDICINE AND PHARMACY.

BY

JOHN ATTFIELD, PhD., F.C.S.,

PROFESSOR OF PRACTICAL CHEMISTRY TO THE PHARMACEUTICAL SOCIETY OF GREAT BRITAIN;

FORMERLY DEMONSTRATOR OF CHEMISTRY AT ST. BARTHOLOMEW'S HOSPITAL, LONDON;

HONORARY MEMBER OF THE AMERICAN PHARMACEUTICAL ASSOCIATION;

HONORARY MEMBER OF THE COLLEGES OF PHARMACY OF PHILADELPHIA, NEW YORK, MASSACHUSETTS, AND CHICAGO;

HONORARY CORRESPONDING MEMBER OF THE SOCIETY OF PHARMACY OF PARIS;

SECRETARY OF THE BRITISH PHARMACEUTICAL CONFERENCE.

FIFTH EDITION.

REVISED FROM THE FOURTH (ENGLISH) EDITION BY THE AUTHOR.



PHILADELPHIA:

HENRY C. LEA.

1873.

"But the greatest error of all is, mistaking the ultimate end of knowledge; for some men covet knowledge out of a natural curiosity and inquisitive temper; some to entertain the mind with variety and delight; some for ornament and reputation; some for victory and contention; many for lucre and a livelihood; and but few for employing the Divine gift of reason to the use and benefit of mankind. Thus some appear to seek in knowledge a couch for a searching spirit; others, a walk for a wandering mind; others, a tower of state; others, a fort, or commanding ground; and others, a shop for profit or sale, instead of a storehouse for the glory of the Creator and the endowment of human life."—Lord Bacon.

Entered according to the Act of Congress, in the year 1873, by

HENRY C. LEA,

in the Office of the Librarian of Congress. All rights reserved.

COLLINS, PRINTER.

540
At8c5

PREFACE.

THE short title on the back of a book, and even the words on the title-page, are generally, and even necessarily, imperfect descriptions of the contents, and hence not unfrequently induce at the outset misconceptions in the minds of readers. The Author of "Chemistry, General, Medical, and Pharmaceutical" would at once state, therefore, that his sole aim is to teach the *general* truths of *chemistry* to *medical* and *pharmaceutical* pupils. Only in a conventional sense would he speak of such subjects as Medical and Pharmaceutical Chemistry; for the truths of Chemistry are the same for all students—crystalline verities which cannot be expanded or compressed to suit any class of workers. The leading principles of the science, however, can be as easily illustrated by or deduced from those facts which have interest as from those which have little or no special interest to the class addressed; and such a course is adopted in this volume.

This manual is intended, then, as a systematic exponent of the general truths of Chemistry, but is written solely for the pupils, assistants, and principals engaged in medicine and pharmacy. It will be found equally useful as a reading-book for gentlemen having no opportunities of attending lectures or performing experiments, and as a handbook for college pupils; while its comprehensive Index, containing six thousand references, will fit the work for after-consultation in the course of business or professional practice.

From other chemical text-books it differs in three particulars: first, in the exclusion of matter relating to compounds which at present are only of interest to the scientific chemist; secondly, in containing more or less of the chemistry of every substance recognized officially, or in

281952

general practice, as a remedial agent; thirdly, in the paragraphs being so cast that the volume may be used as a guide in studying the science experimentally.

The order of subjects is that which, in the author's opinion, best meets the requirements of medical and pharmaceutical students in Great Britain and America. Introductory pages are devoted to a few leading properties of the elements. A review of the facts thus unfolded affords opportunity for stating the views of philosophers respecting the manner in which these elements influence each other. The consideration in detail of the relations of the elementary and compound radicals follows, synthetical and analytical bearings being pointed out, and attention frequently directed to connecting or underlying truths or general principles. The chemistry of substances naturally associated in vegetables and animals is next considered. Practical toxicology and the chemical as well as microscopical characters of morbid urine, urinary sediments, and calculi are then given. The concluding sections form a laboratory-guide to the chemical and physical study of quantitative analysis. In the appendix is a long table of tests for impurities in medicinal preparations—also a short one of the saturating-powers of acids and alkalies, designed for use in prescribing and dispensing.

In the course of the treatment outlined in the preceding paragraph, it will be observed that the whole of the elements are first noticed superficially and then fully, and that the chemistry of the common metallic radicals precedes that of the rarer; while the sections on the acidulous radicals are similarly divided. The basylous radicals will be found to be arranged according to analytical relations, the common acidulous according to exchangeable value or quantivalence, and the rarer acidulous radicals alphabetically. It will be apparent, also, that in certain cases the same classes of facts and principles are brought three or four times under consideration, the points of view, however, differing according as interest is concentrated on physical, synthetical, analytical, or quantitative properties. This

arrangement of matter was adopted partly from the belief that the separate and general truths of chemistry never enter the mind in the order of any scientific classification at present possible. In the current state of chemical knowledge, consistency in the methodical arrangement even of elements can only be carried out in one direction, and is necessarily accompanied by inconsistencies in other directions, a result most perplexing to learners, and hence totally subversive of the chief advantage of classification. For this reason the writer has preferred to lead up to, rather than follow, scientific classification—has allowed analogies and affinities to suggest, rather than be suggested by, classification. Among the acidulous radicals, especially, any known system of classification would have given undue prominence to one set of relations and undeserved obscurity to others. Then, by separating more important from less important matter, instruction is adapted to the wants of gentlemen whose opportunities of studying chemistry vary greatly, and are unavoidably insufficient to enable them to gain a thorough knowledge of the science. One great advantage of the mode of treatment is that difficulties of nomenclature, notation, chemical constitution, and even those arising from conventionality of language, are explained as they arise, instead of being massed under the head of "Introductory Chapters," "Preliminary Considerations," or "General Remarks," which are commonly too difficult to be understood by a beginner, too voluminous to be remembered except by the aid of subsequent lessons, and are consequently the cause of much trouble and confusion. This plan has also admitted of greater prominence being given to "The General Principles of Chemical Philosophy," the only section which the student is asked frequently to return to and employ in the interpretation of the phenomena obtained by experiment. An elementary knowledge of the subjects of Gravitation, Heat, Light, Sound, Electricity, and Magnetism cannot be too strongly recommended to the student of Chemistry. The first portion

of this Manual would have been devoted to an exposition of these branches of Physics, so far as they bear on Chemistry, did not the many special books on Physics render such a course unnecessary. Quantitative chemical analysis frequently involving determinations of temperature, specific gravity, and atmospheric pressure, a few paragraphs on these subjects are made introductory to the sections on quantitative operations.

Dalton's hypothesis of the atomic condition of all matter is adopted in this book, the author believing that, in the present state of knowledge and education, philosophic conceptions regarding chemistry can only be taught to medical, pharmaceutical, and the great majority of general students in some such objective manner.

The chemical notation of the work is in accordance with modern theories. Equations illustrative of pharmacopœial processes have a name attached to each formula.

Chemical nomenclature has been modernized to the extent of defining the alkali-metal and earthy salts as those of potassium, sodium, ammonium, barium, calcium, magnesium, and aluminium, instead of potash, soda, ammonia, baryta, lime, magnesia, and alumina. The author confidently believes that this change, founded on views now adopted by all prominent writers on chemistry, and used in the Pharmacopœia of the United States, will be accepted and become popular with pharmacists; it is a step in the direction of simplicity and consistency, and involves far less hypothesis than is contained in the old system. The name nitrate of potash, for example, was based on the pure assumption that nitre contained oxide of potassium or potash and nitric anhydride, then erroneously termed acid. By the modern name nitrate of potassium, all that is intended to be conveyed is that nitre contains the element common to all potassium compounds, and the group of elements common to all nitrates. Under the old method, students always experienced difficulty in distinguishing salts of the metal from salts of its oxide—salts of potassium, for instance, from salts of potash; under the new

view no such difficulty arises. Names such as potassium nitrate or potassic nitrate are also consistent with modern views, but for general adoption are too unlike the original. The contractions in Latin for names like "nitrate of potassium" are identical with those names resembling "nitrate of potash;" an accidental circumstance that will much facilitate the general introduction of the former among medical practitioners and pharmacists, and a practical advantage that must determine the choice over the other chemically equivalent names just mentioned. The author ventures to express his extreme gratification at the adoption of this system of nomenclature in the recently published Pharmacopœia of the United States (1873).

The Metric System of Weights and Measures (that which, doubtless, is destined to supersede all others) is alone used in the sections on Quantitative Analysis. In other parts of the Manual avoirdupois weights and imperial measures are employed.

It is hoped that the numerous etymological references scattered throughout the following pages will be found useful. Words in Greek have been rendered in English characters, letter for letter. The word "official" is used throughout for things recognized officially by the compilers of the Pharmacopœia; "officinal" in its original application to the officina or shop.

Students are strongly recommended to test their progress by frequent examination. To this end appropriate questions are appended to each subject.

The Author's ideal of a Manual of Chemistry for medical and pharmaceutical students (one he is conscious of not having yet realized) is one in which the chemistry of every substance having interest for the followers of medicine and pharmacy is noticed at more or less length in proportion to its importance, and at least its position in relation to the leading principles of chemistry set forth with all attainable exactness. Such a work will doubtless in certain parts partake of the character of a dictionary; but this is by no means a fault, especially if a good index

be appended; for the points of contact between pure and applied chemistry are thus multiplied, and abundant outlets supplied, by which a lover of the science may pass into other chemical domains by aid of other guides, or even into the regions of original research. Among the rarer alkaloids, bitter bodies, glucosides, salts of organic radicals, solid fats, fixed oils, volatile oils, resins, oleo-resins, gum-resins, balsams, and coloring-matters, mentioned in this volume, will be found many such points whence the ardent student may start for the well-known obscure or untrodden paths of scientific chemistry.

Within five years a demand has arisen for five editions of this Manual. The First was intended as a handbook of practical chemistry for medical and pharmaceutical pupils; but the notes and remarks made respecting most of the experiments were found to be so useful by students that this portion of the volume was in the Second Edition sufficiently extended to render the book more fairly complete in itself. In response to a call from professional friends in the United States in 1870, the work was revised by the Author for the followers of medicine and pharmacy in America, the chemistry of the Preparations and Materia Medica of the United States Pharmacopœia being introduced, and such other adaptations included as to form a Third Edition. A Fourth was presented to English workers in the autumn of 1872, and on that is now founded this Fifth Edition for American students. Each of the latter editions is entirely distinct from the other; but both contain such corrections and additions (altogether about seventy pages) as seemed necessary to present the science in its latest developments—also a rewritten chapter on the General Principles of Chemical Philosophy, and black-letter headings to all paragraphs relating to Preparations of the respective Pharmacopœias.

17 Bloomsbury Square, London,
March, 1873.

APPARATUS FOR EXPERIMENTS IN ANALYSIS.

List of Apparatus suitable for a three months' course of practical chemistry in the summer session of medical schools, or for any similar series of lessons—including the preparation of elementary gases, analytical reactions of common metals and acidulous radicals, analysis of single salts, chemical toxicology, and the examination of urine, urinary sediments, and calculi:—

- One dozen test-tubes.
- Test-tube stand.
- Test-tube cleaning-brush.
- A few pieces of glass tubing, 8 to 16 in. long, with a few inches of India-rubber tubing to fit.
- Small flask.
- Two small beakers.
- Two small funnels.
- Two watch-glasses.
- Two or three glass rods.
- Wash-bottle.
- Small pestle and mortar.
- A 2-pint earthenware basin.
- A 2-inch and a 3-inch evap. basin.
- Two porcelain crucibles.
- Blowpipe.
- Crucible tongs.
- Round file.
- Triangular file.
- Small retort-stand.
- Sand-tray.
- Wire triangles.
- Platinum wire and foil.
- Test-paper.
- Filter-paper.
- Towel.
- Two dozen corks.

(*This set, packed in a deal-box, can be obtained of any chemical-apparatus maker for about seven dollars.*)

APPARATUS FOR EXPERIMENTS IN SYNTHESIS AND ANALYSIS.

A larger set, suitable for the performance of most of the synthetical as well as analytical experiments described in this manual:—

- A set of evaporating-basins, of the following sizes:—
  - One $8\frac{1}{2}$-inch. One 4-inch.
  - One $7\frac{1}{4}$-inch. Two 3-inch.
  - One $6\frac{1}{2}$-inch.
- One retort-stand and three rings.
- Two test-glasses.
- One half-pint flask.
- One half-quire filter-paper.
- Two porcelain crucibles.
- One measure-glass, 5 oz.
- Blowpipe, 8-inch, Black's.
- Two glass funnels.
- One doz. test-tubes (German glass).
- One test-tube brush.
- One pair of 8-inch brass crucible-tongs.
- Two soup-plates.
- One flat-plate.
- Two spatula knives.
- One pair of scissors.
- One round file.
- One triangular file.
- One half-pound glass rod.
- One half-pound glass tubing.
- One ft. small India-rubber tubing.
- Three dozen corks of various sizes.
- Platinum wire and foil.
- Test-papers.
- A nest of three beakers.

(*This set, packed in a case, can be obtained of any chemical-apparatus maker for about twelve dollars.*)

A sponge, towels, and note-book may be included.

FURNITURE OF A LABORATORY.

The following apparatus should be ready to the hand of students following an extended course of practical chemistry, in a room set apart for the purpose :—

- A bench or table and stool.
- Water-supply and waste-pipe.
- A cupboard attached to a chimney with an outward draught.
- A furnace fed with coke; tongs, hot-plate, or sand-bath, etc.
- A waste-box.
- Shelves for chemicals and other materials in jars or bottles.
- Gas-supply and lamp with flexible tube (or a spirit lamp and spirit).
- Test-tube rack, two dozen holes.
- Iron stand or cylinder for supporting large dishes.
- Iron adaptors for fitting dishes to cylinder.
- Pestle and mortar, 5 or 6 inches.
- One 6-inch funnel.
- Brown pan, 1 or 2-gallon.
- White jug, 1-gallon.
- Water-bottle, quart.
- Twenty-eight test-bottles, 6-oz.

Other articles, such as flasks, retorts, receivers, condensers, large evaporating-dishes, may be obtained as wanted. In Quantitative Analysis the apparatus described in the sections on that subject will be required.

REAGENTS.

Certain chemicals are used so frequently in analytical processes that it is desirable to have small quantities placed in bottles in front of the operator. As these reagents or "tests" are generally employed in a state of solution, nearly all the solid salts may at once be dissolved (in distilled water). The bottles employed should be well stoppered, and of 5 or 6 ounces capacity. The bottles should not be more than three-quarters full; single drops, if required, can then be poured out with ease and precision. The following list of test solutions is recommended; directions for methods of preparing those not readily purchasable will be found by referring to the Index :—

- Sulphuric Acid, strong.
- Nitric Acid, strong.
- Hydrochloric Acid, strong.
- Acetic Acid, strong.
- Sol. of Potash, 5 per cent. or B.P.
- " Soda, 5 to 15 per cent.
- " Ammon. 10 per cent. or B.P.
- Lime-water, saturated.

The next nine may contain about 10 per cent. of solid salt :—

- Carbonate of Ammonium, with a little solution of Ammonia added.
- Chloride of Ammonium.
- Phosphate or Arseniate of Ammonium.
- Sulphydrate of Ammonium.
- Chloride of Barium.
- Chloride of Calcium.
- Phosphate of Sodium.
- Neutral Chromate.

The succeeding seven may have a strength of about 5 per cent. :—

Ferrocyanide of Patassium.
Ferridcyanide of Potassium.
Iodide of Potassium.
Oxalate of Ammonium.
Perchloride of Iron.
Nitrate of Silver.
Perchloride of Platinum.

LISTS OF CHEMICALS.

List of chemicals necessary for the practical study of the non-metallic elements mentioned on pp. 13 to 28. The quantities are sufficient for several experiments.

Chlorate of Potassium	1 oz.	Phosphorus	½ oz.
Black Oxide of Manganese	1 oz.	Hydrochloric Acid	1 oz.
Zinc	1 oz.	Sulphur	½ oz.
Oil of Vitriol	2 oz.	Iodine	¼ oz.

List of chemicals necessary for the *analytical* study of the metallic and acidulous radicals (pages 51 to 310). The quantities will depend on the frequency with which experiments are repeated or analysis performed; those mentioned are sufficient for one or two students. The articles are given in the order in which they will be required. The eight substances mentioned in the above list are included.

The set of test solutions described on the previous page.		Bicarbonate of Potassium	1 oz.
		Acetate of Lead	1 oz.
		Cyanide of Potassium	½ oz.
Carbonate of Potassium	1 oz.	Hyposulphite of Sodium	1 oz.
Tartaric Acid	1 oz.	A Lithium salt	10 grs.
Litmus	¼ oz.	Nitrate of Strontium	¼ oz.
Sulphate of Magnesium	1 oz.	Black Oxide of Manganese	½ lb.
Sulphate of Zinc	1 oz.	Chloride of Manganese	¼ oz.
Alum	1 oz.	Chloride of Cobalt	50 grs.
Sulphide of Iron	1 lb.	Nitrate of Nickel	¼ oz.
Oak-galls	1 oz.	Chloride of Chromium	¼ oz.
Sulphocyanate of Potassium	¼ oz.	Gold leaves	2 or 3.
White Arsenic	½ oz.	Chloride of Cadmium	¼ oz.
Zinc	½ lb.	Nitrate of Bismuth	¼ oz.
Charcoal	½ lb.	Bromide of Potassium	¼ oz.
Sulphate of Iron	1 oz.	Starch	1 oz.
Copper Foil	1 oz.	Nitrate of Potassium	1 oz.
Sulphate of Copper	1 oz.	Copper borings or turnings	1 oz.
Tartar Emetic	½ oz.	Indigo	¼ oz.
Mercury	1 oz.	Chlorate of Potassium	1 oz.
Corrosive Sublimate	½ oz.	Iodine	½ oz.
Calomel	½ oz.	Spirit of Wine	1 oz.
Tin	1 oz.	Sulphur	1 oz.

Acid Oxalate of Potassium	1 oz.	Benzoic Acid	50 grs.
Citric Acid	1 oz.	Fluor Spar	1 oz.
Phosphorus	1 oz.	Tannic Acid	50 grs.
Borax	1 oz.	Gallic Acid	50 grs.
Turmeric	1 oz.	Pyrogallic Acid	50 grs.

The quantities of materials required for the study of chemistry *synthetically* will necessarily vary with the desires and tastes of the operator, or according to the number and requirements of students working together.

CONTENTS.

PAGE

PREFACE iii

APPARATUS ix

REAGENTS x

LISTS OF CHEMICALS xi

INTRODUCTION 13

GENERAL PROPERTIES OF THE NON-METALLIC ELEMENTS 15

SYMBOLS AND DERIVATION OF NAMES OF ELEMENTS . 28

THE GENERAL PRINCIPLES OF CHEMICAL PHILOSOPHY . 32

COMMON METALLIC ELEMENTS, THEIR OFFICIAL PREPARATIONS, AND TESTS:—

SALTS OF POTASSIUM, SODIUM, AMMONIUM, BARIUM, CALCIUM, MAGNESIUM, ZINC, ALUMINIUM, IRON, ARSENICUM, ANTIMONY, COPPER, MERCURY, LEAD, SILVER 52

ANALYTICAL CHARTS, FOR ORDINARY METALS . . . 197

RARER METALLIC ELEMENTS, THEIR OFFICIAL PREPARATIONS, AND TESTS:—

SALTS OF LITHIUM, STRONTIUM, MANGANESE, COBALT, NICKEL, CHROMIUM, TIN, GOLD, PLATINUM, CADMIUM, BISMUTH 200

ANALYTICAL CHARTS, FOR ALL METALS 229

COMMON ACIDULOUS RADICALS, OFFICIAL ACIDS, AND TESTS:—

CHLORIDES, BROMIDES, IODIDES, CYANIDES, NITRATES, CHLORATES, ACETATES, SULPHIDES, SULPHITES, SULPHATES, CARBONATES, OXALATES, TARTRATES, CITRATES, PHOSPHATES, BORATES 235

PAGE

Salts of Rarer Acidulous Radicals:—

Benzoates, Cyanates, Formates, Hippurates, Ferrocyanides, Ferridcyanides, Fluorides, Hypophosphites, Hyposulphites, Lactates, Malates, Meconates, Metaphosphates, Nitrites, Phosphites, Pyrophosphates, Silicates, Sulphocyanates, Tannates, Gallates, Urates, Valerianates 298

Analytical Chart for Acidulous Radicals . . . 326

Systematic Analysis 328

Alkaloids, Amylaceous and Saccharine Substances, Glucosides, Alcohol and Allied Bodies, Albumenoid and Gelatigenous Substances, Pepsine, Fatty Bodies, Resinoid Substances, Coloring-matters 338

Toxicology 418

Examination of Morbid Urine and Calculi . . . 429

Official Galenical Preparations 442

Official Chemical Preparations 444

Quantitative Analysis:—

Introductory Remarks 445

Measurement of Temperature 447

Estimation of Weight 452

Weights and Measures 453

Specific Gravity 463

Correction of the Volume of Gases for Pressure and Temperature 469

Volumetric Analysis 475

Gravimetric Analysis 497

Dialysis 537

PAGE

Appendix:—

Table of Official Tests for Impurities in Preparations of the British Pharmacopœia . . 541

Saturation Tables 549

The Elements, their Symbols and Atomic Weights 551

Index 553

CHEMISTRY:

GENERAL, MEDICAL, AND PHARMACEUTICAL.

INTRODUCTION.*

The infinite variety of solid, liquid, and gaseous substances of which our earth and atmosphere are composed, may be resolved with more or less difficulty into sixty-three distinct forms of matter. These are appropriately termed Elements, for by no known means can they be further decomposed or subdivided. Only a few (such as gold) occur naturally in the uncombined state, but the greater number are combined in so subtle a manner as to conceal them from ordinary methods of observation. Thus none of the common properties of water indicate that it is composed of two elements, both gases, but differing much from each other: nor can the senses of sight, touch, and taste, or other common means of examination, detect in their concealment the three elements of which sugar is composed. The art by which these and all other compound substances are resolved into their elements, is termed Chemistry, derived possibly from the Arabic word *kamai*, to conceal, whence *al kimia*, or alchemy, an art which at the time the name alchemy was given had but little more for its object than the transmutation of the baser metals into gold. The *art* of chemistry also includes the construction of compounds from elements, and the conversion of substances of one character into those of another. The general principles or leading truths relating to the elements, to the manner in which they severally combine, and to the properties of the compound substances formed by their union, constitute the *science* of chemistry.†

* Students using this book as a guide in following chemistry practically should read the first three pages, and then commence work by preparing oxygen.

† Persons who practise the art and science of Chemistry are known as Chemists, though conventionally the latter name includes those

From these few words concerning the nature of the art and science of chemistry, it will be seen that in most of the occupations that engage the attention of man chemistry plays an important part—in few more so than in the practice of Therapeutics* and Pharmacy.†

Air, water, food, drugs, and chemicals, in short all material substances, are composed of a few elements. An intimate knowledge of the properties of these, and of the various substances they form by combining with each other, a knowledge of the power or force (the chemical force, or chemical affinity) by which the elements contained in those compounds are held together, and an application of such knowledge to Pharmacy and Medicine, must be the objects sought to be attained by the learner, for whom this work has been especially written.

The Elements.—Of the sixty-three known elements thirty-nine are of medical or pharmaceutical interest; of these, about two-thirds are metals, and one-third non-metals: the remainder are so seldom met with in nature as to have received no practical application either in medicine, art, or

who simply deal in chemicals. Hence have risen the distinguishing appellations of Analytical, Pharmaceutical, and Manufacturing Chemists. The compounder of medicine is by common consent a chemist only because he is constantly engaged in operations with chemical substances used as remedial agents, his moral right to the name depending on the amount of chemical knowledge he possesses concerning those substances. If he keep an open shop, he is in Great Britain known as a *Chemist and Druggist*, his higher title being *Pharmaceutical Chemist;* these respective designations he legally assumes on passing the Minor and Major Examinations, conducted by the Pharmaceutical Society of Great Britain in accordance with the provisions of the Pharmacy Acts of 1852 and 1868. These classes are frequently spoken of collectively as *Pharmaceutists*, a term also used in the United States.

* Therapeutics (θεραπευτικος, *therapeutikos*, from θέραπευω, *therapeuo*, to nurse, serve, or cure) is that branch of medicine which treats of the application of remedies for diseases; it includes dietetics. The therapeutist also takes cognizance of hygiene, that department of medicine which respects the preservation of health.

† Pharmacy (from φάρμακον, *pharmakon*, a drug) is the generic name for the operations of preparing or compounding medicines, whether performed by the Medical Practitioner or by the Chemist and Druggist. It is also sometimes applied, like the corresponding term 'Surgery,' to the apartment in which the operations are conducted.

manufacture. Before intimately studying the elements, it is desirable to acquire some general notions concerning them: such a procedure will also serve to introduce the practical student to his apparatus, and make him better acquainted with the various methods of manipulation.*

Metallic Elements.—With regard to the metallic elements, it may be safely assumed that the reader has sufficient knowledge for present purposes; but little, therefore, need now be said respecting them. He has an idea of the appearance, relative weight, hardness, etc., of such metals as gold, silver, copper, lead, tin, zinc, and iron. If he has not a similar knowledge of mercury, antimony, arsenicum, platinum, nickel, aluminium, magnesium, potassium, and sodium, he should commence his studies by seeing and handling specimens of each of these metals.

Non-Metallic Elements.†—With regard to the non-metallic elements, it is here supposed that the student has no general knowledge. He should commence his studies therefore by a series of operations as follows, on eight out of their number.

OXYGEN.

Preparation.—As oxygen is the most abundant element in nature, forming, though in a combined state, about one-half of the whole weight of our globe, it may safely be assumed that this element can readily be obtained in the free condition in a state of purity. In fact, the air itself contains about one-fifth of its bulk of oxygen, though that element cannot be separated sufficiently easily and readily for experimental purposes. It is preferable to apply heat—that force which will often be noticed as antagonistic, so to speak, to chemical union; heat generally separating particles of matter further from each other, while chemical attraction tends to bind them closer together—it is better to heat certain compounds containing oxygen;

* This allusion to apparatus need not discourage the youngest pupil. With the aid of a few phials, wine-glasses, or other similar vessels always at hand, he may, by studying the following pages, learn the chemical reactions which are constantly occurring in the course of making up medicines, understand the processes by which medicinal preparations are manufactured, and detect adulterations, impurities, or faults of manufacture. Among the substances used in medicine, will be found nearly all the chemicals required. If, in addition, a dozen test-tubes, and a few feet of glass tubing be procured, many of the experiments described may be performed. For full lists of apparatus and chemicals see introductory pages.

† These bodies are sometimes termed *metalloids* (from μέταλλον, *metallon*, a metal, and εἶδος, *eidos*, likeness); but the name is not appropriate, for the non-metallic elements have no likeness to metals.

the latter is then evolved in its normal, natural condition of gas. Several substances, when heated, yield oxygen; but, for convenience and economy, the crystalline body known as chlorate of potassium is best fitted for the experiment. The size and form of the vessel in which to heat it will mainly depend on the quantity required; but for the purposes of the student the best is a *test-tube*, an instrument in constant requisition in studying practical chemistry. It is simply a thin tube of glass, a few inches in length, and half or three-quarters of an inch in diameter, closed by fusion at one end. It is made of thin glass, in order that it may be rapidly heated or cooled without risk of fracture.

Outline of the Process.—Heat chlorate of potassium (say, as much as will lie on a shilling) in a test-tube, by means of a spirit- or gas-flame ; gaseous oxygen is quickly evolved. Before applying heat, however, provision should be made for collecting the gas.

Collection of Gases.—Procure a piece of glass tubing about the thickness of a quill pen, and a foot or eighteen inches long, and fit it accurately to the test-tube by means of a cork. (Longer tubes may be neatly cut to any size by smartly drawing the edge of a triangular file across the glass at the required point, then clasping the tube, the scratch being between the hands, and pulling the portions asunder, force being exerted in a *slightly* curved direction so as to open out the crack which the file has commenced.) The tube is fixed in the cork through a round hole made by the aid of a red-hot wire, or, better, a rat-tail file, or, best of all, by one of a set of cork-borers—pieces of brass tubing sharpened at one end and having a flat head at the other. Setting aside the test-tube for a few minutes, proceed to bend the long piece of tubing to the most convenient shape for collecting the gas.

To bend Glass Tubes.—Hold the part of the tube required to be bent in any gas- or spirit-flame (a fish-tail gas-jet answers very well), constantly rotating it, so that about an inch of the glass becomes heated. It will soon be felt to soften, and will then, yielding to the *gentle* pressure of the fingers, assume any required angle. In the present case, the tube should be heated at about four inches from the extremity to which the cork is attached, and bent to an angle of about 90 degrees.

Source of Heat.—The source of heat for the test-tube may be the flame of an ordinary spirit-lamp, or, still better where coal-gas is procurable, a mixture of the latter with air. The simple flame of a common argand gas-burner is preferred by some operators, especially

when the usual gas chimney is replaced by a metal one about four or five inches long. If a piece, or cap, of wire gauze be fixed on to the top of the metal chimney, then the unlit gas which issues from the jets of the argand burner become mixed with air inside the chimney, and the mixture, when lit on the outer side of the gauze, burns with a flame as smokeless and as little colored as that of a spirit-lamp. Gas-lamps especially constructed to burn a mixture of coal-gas and air are sold by chemical-apparatus manufacturers.

Collection, etc. (*continued*).—Fit the cork and bent tube into the test-tube; the apparatus will then be ready for delivering gas at a convenient distance from the heated portion of the arrangement. To collect it, have ready three or four test-tubes (or small wide-mouthed bottles) filled with water, and inverted in a basin, or other similar vessel, also containing water, taking care to keep the mouths of the tubes a little below the surface. Now apply heat to the chlorate contained in the test-tube, and so arrange the open end of the bent tube under the water that the gas which presently issues may bubble into and gradually fill the inverted test-tubes. The first tubeful may be rejected, as it probably consists of little more than the air originally in the apparatus, and which has been displaced by the oxygen. That which comes afterwards will be pure oxygen.

As each tube or bottle is collected, the mouth (still under the surface of the water) may be closed by a cork and set aside; or a little cup (such as a porcelain crucible or small gallipot) may be brought under the mouth, and the cup, with the mouth of the tube in it, be lifted out of the water and placed close by till wanted, the water remaining in the cup effectually preventing the gas from escaping.

On the large scale, oxygen may be made in the same way, larger vessels (glass flasks or iron bottles) being employed. Less heat also will be necessary if the chlorate of potassium be previously mixed with very fine sand, or, still better, with about an equal weight of common black oxide of manganese.

Note on the Collection and Storage of Gases.—It may be as well to state that nearly all gases, whether for experimental or practical purposes, are collected and stored in a similar manner. Even coal-gas is generated at gas-works in iron retorts very much the shape of test-tubes, only they are as many feet long as a test-tube is inches; and the well-known gigantic gas-holders may be viewed as inverted iron test-tubes of great diameter.

Properties.—Oxygen is a colorless gas. It cannot be liquefied or solidified. Obviously it is not very soluble

in water, or it could not be collected by the aid of that liquid.

Oxygen is soluble to a certain extent, however (about 3 volumes in 100, at common temperatures), or fishes could not breathe.

Other noticeable features are its want of taste and smell. Next, to show the relation of oxygen to combustion, remove one of the tubes from the water by placing the thumb over its mouth, apply for a second a lighted wood match to the orifice; the gas will be found to be incombustible. Extinguish the flame of the match, and then quickly introduce the still incandescent carbonaceous extremity of the wood halfway down the test-tube; the wood will at once burst into flame, owing to the extreme violence with which oxygen supports combustion. These tests of the presence of oxygen may also be applied at the extremity of the delivery-tube whilst the gas is being evolved. (It is desirable to retain two tubes of the gas for use in subsequent experiments; also one tube in which only one-third of the water has been displaced by oxygen.)

Relation of Oxygen to Animal and Vegetable Life.—Not only the carbon at the end of a piece of charred wood, but any other substance that will burn in air (which, as will be seen presently, is diluted oxygen) will burn more brilliantly in pure oxygen. The warmth of the body of animals is kept up by the continuous burning of the carbonaceous matter of the blood in the oxygen of the air drawn into the lungs. The product of this combustion is a gaseous compound of carbon and oxygen termed carbonic acid gas, a gas which, in sunlight, is decomposed in the cells of plants with fixation of the carbon and liberation of the oxygen; hence the atmosphere is kept constant in composition.

Memorandum.—At present it is not advisable that the reader should trouble himself with the consideration of the chemical action which occurs either in the elimination of oxygen from its compounds, or in the separation of any of the following non-metallic elements from their combinations. It is to the properties of the elements themselves that he should restrict his attention. Working thus from simple to more complex facts, he will in due time find that the comprehension of such actions as occur in the preparation of these few elements will be easier than if he attempted their full study now.

HYDROGEN.

Preparation and Collection.—The element of hydrogen is also a gas,* and is obtainable from its commonest com-

* Graham obtained alloys of hydrogen with palladium and other metals, compounds in which several hundred times its bulk of gas

pound, water (of which one-ninth by weight is hydrogen), by the agency of hot zinc or iron, but more conveniently by the action of either of these metals on cold diluted sulphuric acid. The apparatus used for making oxygen may be employed for this experiment; but no lamp is required. Place several pieces of thin zinc* in the generating-tube, or in any common glass bottle, and cover them with water. The collecting-tubes (these may be wide-mouthed bottles) being ready, add strong sulphuric acid (oil of vitriol) to the zinc and water, in the proportion of about 1 volume of acid to 5 of water, and fit on the delivery-tube; the hydrogen is at once evolved. Having rejected the first portions (or having waited until the air originally in the bottle may be considered to be all expelled), collect four or five tubes of the gas in the manner described under Oxygen.

In making larger quantities bottles of appropriate size may be employed.

Other metals, notably potassium and sodium, liberate hydrogen the moment they come into contact with water; but the processes are not economical.

Properties.—Like oxygen, hydrogen is invisible, inodorous, and tasteless. If made with iron it has a strong smell, but this is due to impurities contained in the metal.

Apply a flame to the mouth of the delivery tube (care being taken that the gas is coming off briskly—a guarantee that no air remains in the generating vessel); ignition of the hydrogen ensues, showing that, unlike oxygen, it is combustible.

Immerse a lighted match into a tube (or wide-mouthed bottle) containing hydrogen; the gas is ignited, but the match becomes extinguished. This shows that hydrogen is not a supporter of combustion.

is retained by the metal in vacuo or even at a red heat. This is physical confirmation of the opinion long held by chemists, that hydrogen is a gaseous metal. Graham termed it hydrogenium (other chemists *hydrium*), and considered its relative weight in the solid state to be nearly three-fourths that of water.

* The best form is *granulated zinc* (*Zincum Granulatum*, B. P.) made by heating scraps of common sheet zinc in a ladle over a fire, and as soon as melted pouring, in a slow stream, into a pail of water from a height of 8 or 10 feet. Each drop of zinc thus yields a thin little bell, which, for its weight, presents a large surface to the action of the acid water. If the zinc is allowed to become hotter than necessary, the little bells will not be formed.

Hydrogen in burning unites with the oxygen of the air and forms water, which may be condensed on a cool glass or other surface. Prove this by holding a glass vessel a few inches above a hydrogen-flame. In burning the hydrogen contained in one of the tubes or bottles, the flame is best seen when the tube is held mouth upwards, and water poured in so as to force out the gas gradually.

If, instead of this gradual combination of the two elements oxygen and hydrogen, they be mixed together in the right proportions and then ignited, they will rapidly combine, in other words, explosion results. Prepare a mixture of this kind by filling up with hydrogen a test-tube from which one-third of the water has been expelled by oxygen. Remove the tube from the water, placing a finger over the mouth, and, having a lighted match ready, apply the flame; a slight explosion will result, owing to the instantaneous combination of the two elements, and the expansive force of the steam produced. If anything larger than a test-tube is employed in this experiment, it should be a soda-water bottle, or some such vessel equally strong.

These two gases thus unite at a temperature considerably above that of boiling water, two volumes of hydrogen and one of oxygen yielding two volumes of gaseous water (true steam).

The noise of such explosions is caused by concussion between the particles of the gaseous body and those of air.

The force of the explosion, or, in other words, the expansive force of the highly-heated steam produced, is exceedingly slight, certainly very far below that necessary to break the test-tube. Some force, however, is exerted, and hence the necessity of the precaution previously suggested of allowing all the air which may be in a hydrogen-apparatus to escape before proceeding with the experiments. If a flame be applied to the delivery-tube before all the air is expelled, the probable result will be ignition of the mixture of hydrogen and oxygen (of the air) and consequent explosion. But even in this case the generating-vessel is not often fractured unless it be large and of thin glass, the ordinary effect being that the cork is blown out, and the delivery-tube broken on falling to the ground.

Hydrogen is a prominent constituent of all the substances used for producing artificial light, such as tallow, oil, and coal-gas. The explosive force of large quantities, such as a roomful, of coal-gas and air, though vastly below that of an equal weight of gunpowder, is well known to be sufficient at least to blow out that side of the room which offers least resistance.

The composition of water can be proved analytically as well as synthetically, a current of electricity decomposing it into its constituent gases, twice as much hydrogen as oxygen, by volume, being produced.

Combustion (from *comburo*, to burn).—The experiments with hydrogen and oxygen illustrate the true character of combustion. Whenever chemical combination is sufficiently intense to be accompanied by heat and light, the materials are said to undergo combustion. Combustion only occurs at the line of contact of the combining bodies; a jet of oxygen will burn in an atmosphere of hydrogen quite as easily as a jet of hydrogen in oxygen. A jet of air (diluted oxygen) will burn as readily in a jar of coal-gas as a jet of coal-gas burns in air; each is combustible, each supports the combustion of the other. Hence the terms *combustible* and *supporter of combustion* are purely conventional, and only applicable so long as the circumstances under which they are applied remain the same. In the case of substances burning in air, the conditions are, practically, always the same; hence no confusion arises from regarding air as the great supporter of combustion, and bodies which burn in it as being combustible.

Structure of Flame.—A candle-flame or oil-flame is a jet of gas intensely heated; the central portion is unburnt gas; the next envelope is formed of partially burnt and very dense gaseous particles heated sufficiently high to give light, and the outer cone of completely burnt gases. Air made, by any mechanical contrivance of burner, to mix with the interior of a flame at once burns up, or perhaps prevents the formation of dense gases, giving a hotter, but non-luminous, jet. The "Bunsen" gas-burners commonly used in chemical laboratories are constructed on this principle: their flame has the additional advantage of not yielding a deposition of soot.

In the Bunsen gas-burner a mixture of gas and air passes along a pipe. It only burns at the end, and not within the pipe, because the metal of the burner, by conducting heat away, cools the mixture below the temperature at which it can ignite. The *Davy safety-lamp* acts on the same principle: a wire-gauze cage surrounds an oil-flame; an inflammable mixture of gas (fire-damp) and air can pass through the gauze and catch fire and burn inside; but the flame cannot be communicated to the mixture outside, because the metal of the gauze and other parts cools down the gas below the temperature at which it can burn.

Properties (continued).—Hydrogen is the lightest substance known. It was formerly used for filling balloons, but was soon superseded by coal-gas. Coal gas is not so light as hydrogen, but is cheaper and more easily obtained. The lightness of hydrogen may be rendered evident by the following experiment: Fill two test-tubes with the gas, and hold one with its mouth downwards and the other with its mouth upwards. The hydrogen will have escaped from the latter in a few seconds, whereas the former will still contain the gas after the lapse of some minutes. This may be proved by applying a lighted match to the mouths of the respective tubes.

The relative weight or specific gravity of oxygen is sixteen times that of hydrogen. A vessel holding one grain of hydrogen will hold sixteen grains of oxygen. The relation of the weight of hydrogen to air is as 1 to 14.44 or as 0.0693 to 1.0. One grain of hydrogen by weight would measure about 27 fluidounces.

Mem.—It is desirable to retain two tubes of hydrogen for use in subsequent experiments.

Diffusion of Gases.—Hydrogen cannot be kept in such vessels as the inverted test-tube; for, though much lighter than air, it *diffuses* downwards into the air, while the air, though much heavier, diffuses upwards into the hydrogen. This power of *diffusion* is characteristic of all gases, and proceeds according to a fixed law, namely, "in inverse proportion to the square root of the specific gravity of the gas" (Graham). Thus hydrogen diffuses four times faster than oxygen.

PHOSPHORUS.

Appearance and Source.—Phosphorus (*Phosphorus*, B. P. and U. S. P.) is a solid element, in appearance and consistence resembling white wax; but it gradually becomes yellow by exposure to light. It is a characteristic constituent of bones, and is always prepared from that source by a process which will be subsequently described.

Caution.—Phosphorus, on account of its great affinity for oxygen, takes fire very readily, and should therefore be kept under water. When wanted for use it must be cut under water. It is employed in tipping lucifers, though *red* or *amorphous phosphorus* (*vide* Index) is least objectionable for this purpose.

Properties.—Dry a piece about one-fourth the size of a pea by quickly and carefully pressing it between the folds of porous (filter or blotting) paper; place it on a plate, and ignite by touching it with a piece of warm wire or wood. Observe that the product of combustion is a dense white smoke, which must be confined at once by placing an inverted tumbler, test-glass, or other similar vessel over the phosphorus. The fumes rapidly aggregate, and fall in white flakes on the plate. When this has taken place, and the phosphorus is no longer burning, moisten the powder with a drop or two of water, and observe that some of the water is converted into steam, an effect due to the intense affinity with which the two combine.

The powder produced by the combustion of phosphorus is phosphoric anhydride; the combination of the latter with the elements of water produces a variety of phosphoric acid which dissolves in the water, forming on standing a dilute solution of ordinary phosphoric acid. The Diluted Phosphoric Acid of the British and United States Pharmacopœias is a somewhat similar solution, made, however, in a different way, and of a definite strength.

NITROGEN.

Source.—The chief source of this gaseous element is the atmosphere, nearly four-fifths of which consists of nitrogen (the remaining fifth being almost entirely oxygen).

Preparation.—Burn a piece of dried phosphorus, the size of a pea, in a confined portion of air. The oxygen is thus removed, and nitrogen alone remains. The readiest mode of performing this experiment is to fix a piece of earthenware (the lid of a small porcelain crucible answers very well) on a thin piece of cork, so that it may float in a dish of water. Place the phosphorus on the lid, ignite by a warm rod, and then invert a tumbler, or any glass vessel of about a half-pint capacity, over the burning phosphorus, so that the glass may dip into the water. Let the arrangement rest for a short time for the fumes of phosphoric anhydride to subside and dissolve in the water, and then decant the gas into test-tubes in the manner already indicated, using a vessel of water of sufficient depth to admit of the glass containing the nitrogen to be turned on one side without air gaining access.

Larger quantities are made in the same way. Other combustibles, such as sulphur or a candle, might be used to burn out the oxygen from a given quantity of air, but none answer so quickly and completely as phosphorus; added to which, the product of their combustion would not always be dissolved by water, but would remain with and contaminate the nitrogen.

Mem.—The statement concerning the composition of the air is roughly confirmed in preparing nitrogen, about one-fifth of the volume of the air originally in the glass vessel having disappeared, its place being occupied by water from the dish.

Properties.—Like oxygen and hydrogen, nitrogen is invisible, tasteless, and inodorous. It is only slightly soluble in water. It is distinguished from all other gases by the absence of any characteristic or positive properties. Apply a flame to some contained in a tube; it will be found to be incombustible. Immerse a lighted match in the gas; the flame is extinguished, showing that nitrogen is a non-supporter of combustion.

The chief office of nitrogen in the air is to dilute the energetic oxygen, a mere *mechanical* mixture resulting. The *chemical* compounds of nitrogen and oxygen are numerous (*vide* Index). The compound formed by the union of nitrogen with hydrogen is gaseous ammonia.

Nitrogen is fourteen times as heavy as hydrogen.

The air is nearly fourteen and a half (14.44) times as heavy as hydrogen. Its average composition, including minor constituents, which will be referred to subsequently, is as follows:—

Composition of the Atmosphere.

	In 100 volumes.
Oxygen	20.61
Nitrogen	77.95
Carbonic acid gas	.04
Aqueous vapor	1.40
Nitric acid, Ammonia, Carburetted hydrogen	traces.
Sulphuretted hydrogen, Sulphurous acid	traces in towns.

The above proportions are by volume. By weight there will be nearly 23 parts of oxygen to nearly 77 of nitrogen, oxygen being the heavier in the ratio of 16 to 14. Ozone (*vide* Index) is also said to be a normal constituent of air.

CHLORINE.

Source.—This element is a gas. Its chief source is common salt, more than half of which is chlorine.

Preparation.—About a quarter of an ounce of salt and the same amount of black oxide of manganese are placed in a test-tube with sufficient water to cover them; on adding a small quantity of sulphuric acid, the evolution of chlorine commences.

Another Process.—As the action of the sulphuric acid on the salt in the above process is mainly to give hydrochloric acid, the latter acid (about 4 parts) and the black oxide of manganese (about 1 part) may be used in making the gas, instead of salt, sulphuric acid, and black oxide of manganese. This is the process of the British and United States Pharmacopœias.

Larger quantities may be made from hydrochloric acid and black oxide of manganese (about 4 parts to 1) in a Florence flask, fitted with a delivery-tube, the flask being supported over a flame by the ring of a retort stand or any similar mechanical contrivance.

Mem.—Flasks and similar glass vessels are less liable to fracture if protected from the direct action of the flame by being placed on a piece of wire gauze 2 to 4 inches square, or on a *sand-bath*, that is, a saucer-shaped tray of sheet iron, on which a *thin* layer of sand is placed.

Collection and Properties.—Chlorine is a most suffocating gas. Great care must consequently be observed in

experimenting with this element. As soon as its penetrating odor indicates that it is escaping from the test-tube, the cork and delivery-tube should be fitted on, and the gas allowed to pass to the bottom of another test-tube half filled with water. When thirty or forty small bubbles have passed, their evolution being assisted by slightly heating the generating-tube, the latter should be removed to the cupboard usually provided in laboratories for performing operations with noxious gases, or dismounted, and the contents washed away. The water in the collecting-tube will now be found to smell of the gas, chlorine being, in fact, soluble in about half its bulk of water. Chlorine-water is official* in the British and United States Pharmacopœias (*Liquor Chlori*, B. P., *Aqua Chlorinii*, U. S. P.).

The *Vapor Chlori*, B. P., or Inhalation of Chlorine, is simply moist chlorinated lime so placed that some of the chlorine given off may be inhaled.

During these manipulations the operator will have noticed that chlorine is of a light green color. That tint is readily observed when the gas is collected in large vessels. As it is soluble in water ($2\frac{1}{3}$ vols. in 1 vol. at 60° F.), it cannot be economically stored over that liquid. Being, however, nearly twice and a half as heavy as air, it may be collected by simply allowing the delivery-tube to pass to the bottom of the test-tube or dry bottle.

The distinctive property of chlorine is its bleaching-power. Prepare some colored liquid by placing a few chips of logwood or other dyeing material in a test-tube half full of hot water. Pour off some of this red decoction into another tube, add a few drops of the chlorine-water, and note how rapidly the red color is destroyed.

Chlorine readily decomposes noxious gases, and hence is one of the most powerful of the *deodorizers*. Used in excess it arrests and prevents putrefaction, hence it is one of the best of *disinfectants*.

* The Pharmacopœia and all in it are official (*office*, Fr. from L. *officium*, an office). There are many things which in pharmacy are officinal (Fr. from L. *officina*, a shop) but not official. To restrict the word *officinal* to the contents of a pharmacist's shop, and to that portion of the contents which is Pharmacopœial, is radically wrong, and should be avoided. "An *official* formula is one given under authority. An *officinal* formula is one made in obedience to the customary usage of the shop (*officina*). To state that any preparation under the sanction of the Pharmacopœia is officinal, is a misapprehension of the meaning of the word."—*Brough*.

Combination of Hydrogen with Chlorine, forming Hydrochloric Acid.—If an opportunity occurs of generating the gas in a closed chamber or in the open air, a test-tube of the same size as one of those in which hydrogen has been retained from a previous operation, is filled with the gas. The hydrogen-tube is then inverted over that containing the chlorine, the mouths being kept together by encircling them with a finger. After the gases have mixed, the mouths of the tubes are quickly in succession brought near a flame, when explosion occurs, and fumes of hydrochloric acid combined with the moisture of the air are formed. The Hydrochloric Acid of pharmacy (*Acidum Hydrochloricum*, B. P., *Acidum Muriaticum*, U. S. P.) is a solution of the gas (made in a more economical way) in water.

The foregoing experiment affords evidence of the powerful affinity of chlorine and hydrogen for each other. Chlorine dissolved in water will, in sunlight, slowly remove hydrogen from some of the water and liberate oxygen. The bleaching-power of chlorine is generally referred to this oxidizing effect which it produces in presence of water; for dry chlorine does not bleach.

Density.—Chlorine is thirty-five and a half times as heavy as hydrogen.

SULPHUR, CARBON, IODINE.

The physical properties of those elements (color, hardness, weight, etc.) are familiar. Their leading chemical characters will also be understood when a few facts concerning each are made the subject of experiment.

Sulphur.—Burn a small piece of sulphur; a penetrating odor is produced, due to the formation of a colorless gas, the same as that formed on igniting a sulphur-tipped lucifer match.

This product is a perfectly definite chemical compound of the oxygen of the air with the sulphur. It is termed sulphurous anhydride or sulphurous acid gas.

Carbon is familiar in the forms of soot, coke, charcoal, graphite (plumbago, popularly termed blacklead), and diamond. The presence of carbon in wood, and in other vegetable and animal matter, is at once rendered evident by heat. Place a little tartaric acid on the end of a knife in a flame; the blackening that occurs is due to the separation of carbon. The black matter at the extremity of a piece of half-burned wood is also carbon.

Carbon, like hydrogen, phosphorus, and sulphur, has a great affinity for oxygen at high temperatures. A striking evidence of that affinity is the evolution of sufficient heat to make the materials concerned red or even white-hot. When ignited in the dilute oxygen of the air, carbon simply burns with a moderate glow, as seen in an ordinary coke or charcoal fire, but when ignited in pure oxygen, the intensity of its combination is greatly exalted. The product of the combination of the two elements, if the oxygen be in excess, is an invisible gaseous body termed carbonic acid gas; if the carbon be in excess, another invisible gas termed carbonic oxide results.

IODINE.—A prominent chemical characteristic of iodine is its great affinity for metals. Place a piece of iodine, about the size of a pea, in a test-tube with a small quantity of water, and add a few iron-filings or small nails. On gently warming this *mechanical* mixture, or even shaking if longer time be allowed, the color and odor of the iodine disappear; it has *chemically* combined with the iron; a *chemical compound* has been produced. If the solution be filtered, a clear aqueous solution of the compound of the two elements is obtained.

This compound is an iodide of iron. Its solution, made as above, and mixed with sugar, forms, when of a certain strength, the ordinary Syrup of Iodide of Iron of pharmacy (*Syrupus Ferri Iodidi*, B. P. and U. S. P.). A strong solution mixed with sugar and liquorice-root (sugar, liquorice, liquorice-root, gum Arabic, and reduced iron, U. S. P.) constitutes the corresponding Pill (*Pilula Ferri Iodidi*, B. P. and U. S. P.). The solid iodide (*Ferri Iodidum*, B. P.) is obtained on removing the water of the above solution by evaporation.

Sulphur and *Iron*, also, when very strongly heated, *chemically combine* to form a substance which has none of the properties of a *mixture* of sulphur and iron, that is, has none of the characters of sulphur and none of iron, but new properties altogether. The product is termed Sulphide of Iron. Its manufacture and uses will be alluded to in treating of the compounds of iron: it is mentioned here as a simple but striking illustration of the difference between a *chemical compound* and a *mechanical mixture.*

THE ELEMENTS, THEIR SYMBOLS, ETC.

From the foregoing statements a general idea will have been obtained of the nature of several of the more frequently occurring elements. Some additional facts concerning them may be gathered from the following Table, which gives the name in full, the symbol (or short-hand character*) of the name, and its origin.

* The symbol is also much more than the short-hand character, as will be presently apparent.

For the purposes of study the elements may be divided into three classes, viz., those frequently used in pharmacy, those seldom, and those never used.

Name.	Symbol.	Derivation of Name.
Oxygen	O	From ὀξὺς (oxūs) *acid*, and γένεσις (genesis) *generation*, i. e., generator of acids. It was supposed to enter into the composition of all acids when first discovered.
Hydrogen	H	From ὕδωρ (hudōr) *water*, and γένεσις (genesis) *generation*, in allusion to the product of its combustion in air.
Nitrogen	N	From νίτρον (nitron), and γένεσις (genesis), *generator of nitre.*
Carbon	C	From *carbo*, *coal*, which is chiefly carbon.
Chlorine	Cl	From χλωρὸς (chlōros) *green*, the color of this element.
Iodine	I	From ἰον (ion) *a violet*, and εἶδος (eidos) *likeness*, in reference to the color of its vapor.
Sulphur	S	From *sal* a *salt*, and πῦρ (pūr) *fire*, indicating its combustible qualities. Its common name, *brimstone*, has the same meaning, being the slightly altered Saxon word *brynstone*, i. e., burnstone.
Phosphorus.....	P	φῶς (phōs) *light*, and φέρειν (pherein) *to bear*. The light it emits may be seen on exposing it in a dark room.
Potassium..... (Kalium.)	K	*Kalium*, from *kali*, Arabic for *ashes*. Manufactories in which certain compounds of potassium and allied sodium salts are made are called alkali-works to this day. *Potassium*, from *pot-ash;* so called because obtained by evaporating the lixivium of wood-ashes in pots. From such ashes the element was first obtained, hence the name.
Sodium..... (Natrium.)	Na	*Natrium*, from *natron*, the old name for certain natural deposits of carbonate of sodium. *Sodium*, from *soda-ash* or *sod-ash*, the residue of the combustion of masses or *sods* of marine plants. These were the sources of the metal.
Ammonium.....	Am (NH_4)	This body is not an element; but its components exist in all ammoniacal salts, and apparently play the part of such elements as potassium and sodium. Sal ammoniac (chloride of ammonium) was first obtained from near the temple of Jupiter Ammon in Libya; hence the name.
Barium.....	Ba	From βαρὺς (barūs) *heavy*, in allusion to the high specific gravity of "heavy spar," the most common of the barium minerals.

Name.	Symbol.	Derivation of Name.
Calcium	Ca	*Calx*, *lime*, the oxide of calcium.
Magnesium	Mg	From *Magnesia*, the name of the town (in Asia Minor) near which the substance now called "native carbonate of magnesia" was first discovered.
Iron ..... (Ferrum.)	Fe	The spelling is from the Saxon *iren*, the pronunciation probably from the kindred Gothic "*iarn*;" the derivation is unknown to the author.
Aluminium	Al	The metallic basis of alum was at first confounded with that of sulphate of iron, which was the alum of the Romans, and was so called in allusion to its tonic properties, from *alo*, *to nourish*.
Zinc	Zn	The derivation of this word is unknown to the author.
Arsenicum	As	Ἀρσενικὸν (arsenikon), the Greek name for orpiment, a sulphide of arsenicum. Common white arsenic is an oxide of arsenicum.
Antimony ..... (Stibium.)	Sb	Στίβι (stibi); or στίμμι (stimmi), was the Greek name for the native sulphide of antimony. The word *antimony* is said to be derived from ἀντὶ (anti) *against*, and *moine*, French for *monk*, from the fact that certain monks were poisoned by it.
Copper ..... (Cuprum.)	Cu	From *Cyprus*, the name of the Mediterranean island where this metal was first worked.
Lead ..... (Plumbum.)	Pb	The Latin word is expressive of "something heavy," and the Saxon *lœd* has a similar signification.
Mercury ..... (Hydrargyrum.)	Hg	*Hydrargyrum*, from ὕδωρ (hudōr) *water*, and ἄργυρος (arguros) *silver*, in allusion to its liquid and lustrous characters. *Mercury*, after the messenger of the gods, on account of its susceptibility of motion. The old name *quicksilver* also indicates its ready mobility and argentine appearance.
Silver ..... (Argentum.)	Ag	Ἄργυρος (arguros) *silver*, from ἀργὸς (argos) *white*. Words resembling the term *silver* occur in several languages, and indicate a white appearance.

The following are the names of some of the less frequently occurring elements, compounds of which, however, are alluded to in the British and U. S. Pharmacopœias, or met with in pharmacy.

Name.	Symbol.	Derivation of Name.
Bromine	Br	From βρῶμος (brōmos), a *stink*. It has an intolerable odor.
Fluorine	Fl	Fluo, *to flow*. Fluoride of calcium, its source, is commonly used as a flux in metallurgic operations.
Boron	Bo	From *borax* or *baurak*, the Arabic name of *borax*, the substance from which the element was first obtained.
Silicon	Si	From *silex*, Latin for *flint*, which is nearly all silica (an oxide of silicon).
Lithium	L	From λίθειος (litheios) *stony*, in allusion to its supposed existence in the mineral kingdom only.
Strontium	Sr	This name is commemorative of *Strontian*, a mining village in Argyleshire, Scotland, in the neighborhood of which the mineral known as *strontianite* or carbonate of strontium was first found.
Cerium	Ce	Discovered in 1803, and named after the planet *Ceres*, which was discovered on Jan. 1, 1801. The oxalate, $CeC_2O_4,3H_2O$, is official, but seldom used.
Chromium	Cr	From χρῶμα (chrōma) *color*, in allusion to the characteristic appearance of its salts.
Manganese	Mn	Probably a mere transposition and repetition of most of the letters of the word magnesia, with whose compounds those of manganese were confounded till the year 1740.
Cobalt	Co	*Cobalus* or *Kobold* was the name of a demon supposed to inhabit the mines of Germany. The ores of cobalt were formerly troublesome to the German miners, and hence received the name their metallic radical now bears.
Nickel	Ni	*Nickel*, from *nil*, is a popular German term for *worthless*. The mineral now known as nickel ore was formerly called by the Germans *Kupfernickel*, *false copper*, on account of its resemblance to copper (*Kupfer*) ore. When a new metallic element was found in the ore, the name nickel was retained.
Tin (Stannum)	Sn	Both words are possibly corruptions of the old British word *staen*, or the Saxon word *stan*, a stone. Tin was first discovered in Cornwall, and the ore (an oxide) is called *tinstone* to the present day.

Name.	Symbol.	Derivation of Name.
Gold (Aurum) ...	Au	*Aurum* (Latin) from a Hebrew word signifying the color of fire. *Gold*, an old Saxon word expressive of *yellow*, the color of this metal
Platinum.....	Pt	From *platina* (Spanish), diminutive of *plata, silver*, in allusion to its inferiority in lustre, but otherwise general resemblance to silver.
Bismuth	Bi	Slightly altered from the German *Wismuth*, derived from *Wiesematte* "a beautiful meadow," a name given to it originally by the old miners in allusion to the prettily variegated tints presented by the freshly exposed surface of this crystalline metal.
Cadmium.....	Cd	Καδμεία (Kadmeia) was the ancient name of calamine (carbonate of zinc), with which carbonate of cadmium was long confounded, the two often occurring together.

Gold, Platinum, Tin, and Silicon are classed with the less important elements, because their salts are seldom used in pharmacy.

It will be noticed that the symbol of an element is simply the first letter of its Latin name, which is generally the same as in the English. Where two names begin with the same letter, the less important has an additional letter added.

QUESTIONS AND EXERCISES.

1. Of how many elements is terrestrial matter composed?
2. In what state do the elements occur in nature?
3. Distinguish between the *art* and the *science* of chemistry.
4. What is the difference between an element and a compound?
5. Enumerate the chief non-metallic elements.
6. Describe a process for the preparation of oxygen.
7. How are gases usually stored?
8. Mention the chief properties of oxygen.
9. What is the source of animal warmth?
10. State the proportion of oxygen in air.
11. Is the proportion constant, and why?
12. Give a method for the elimination of hydrogen from water.
13. State the properties of hydrogen.
14. Why is a mixture of hydrogen and air explosive?
15. Explain the effects producible by the ignition of large quantities of coal-gas and air.
16. What is the nature of combustion?
17. Define a *combustible* and a *supporter of combustion.*

18. Describe the structure of flame.
19. State the principle of the Davy safety-lamp.
20. To what extent is hydrogen lighter than oxygen?
21. What do you mean by *diffusion* of gases?
22. State Graham's law concerning diffusion.
23. Name the source of phosphorus, and give its characters.
24. Why does phosphorus burn in air?
25. What remains when ignited phosphorus has removed all the oxygen from a confined portion of air?
26. Mention the properties of nitrogen.
27. What office is fulfilled by the nitrogen of air?
28. State the proportions of the chief constituents of air.
29. Mention the minor or occasional constituents of air.
30. What is the proportion by weight of nitrogen to oxygen in the atmosphere?
31. Give the specific gravity of nitrogen.
32. How is chlorine prepared?
33. Enumerate the properties of chlorine.
34. Define the terms *deodorizer* and *disinfectant*.
35. Explain the bleaching effect of chlorine.
36. What proportion of hydrogen to chlorine is necessary for the formation of hydrochloric acid gas?
37. State the prominent physical and chemical characters of sulphur.
38. State the prominent characters of carbon.
39. State the prominent characters of iodine.
40. Give the derivations of the names of some of the elements.
41. What are the symbols of oxygen, hydrogen, nitrogen, carbon, chlorine, iodine, sulphur, phosphorus?

THE LEARNER IS RECOMMENDED TO READ THE FOLLOWING PARAGRAPHS ON THE GENERAL PRINCIPLES OF CHEMICAL PHILOSOPHY CAREFULLY ONCE OR TWICE, THEN TO STUDY (EXPERIMENTALLY, IF POSSIBLE) THE SUCCEEDING PAGES, RETURNING TO AND READING OVER THE GENERAL PRINCIPLES FROM TIME TO TIME UNTIL THEY ARE THOROUGHLY COMPREHENDED.

THE GENERAL PRINCIPLES OF CHEMICAL PHILOSOPHY.

Definition of Chemical Action.

The learner may now proceed to study the manner in which substances act chemically on each other. By acting *chemically* it will be obvious, from the preceding experiments, that what is meant is so affecting each other that the substances are greatly altered in properties. A *mixture* of oxygen and hydrogen is still a gas; *a chemical compound* of oxygen and hydrogen is a liquid, namely

water. Iodine is only slightly soluble in water, and forms a brown-colored solution, and iron is insoluble; but when iodine and iron are *chemically* combined the product is very soluble in water, forming a light-green solution in which the eye can detect neither iodine nor iron, and which is utterly unlike iron or iodine in any one of their properties. Sand, sugar, and butter rubbed together form *a mere mixture*, from which water would extract the sugar, and ether dissolve out the butter, leaving the sand. Tartaric acid, carbonate of sodium, and water added to each other form a *chemical compound* containing neither tartaric acid, nor carbonate of sodium, these bodies having attacked each other and formed fresh combinations. Either of these illustrations shows that *chemical* action is distinguished from all other actions by producing an entire change of properties in the bodies on which it is exerted. Chemical action is further distinguished by the fact that it only takes place between definite weights and volumes of matter; a subject that will be more fully discussed immediately.

Atoms.

In a chemical compound what has become of the constituents? Let the reader place before him specimens of sulphur, iron, and sulphide of iron; or iodine, iron, solid iodide of iron and its solution in water or syrup (*Syrupus Ferri Iodidi*, B. P. and U. S. P.). In the sulphide of iron what has become of the sulphur and of the iron from which it was made? The *mixture* of sulphur and iron in *combining* to form sulphide of iron has not lost weight, and, indeed, by certain processes it is possible to recover its sulphur as sulphur, and its iron as iron; so that we are compelled to believe, we cannot avoid the conclusion, that sulphide of iron contains particles of sulphur and of iron. But how small must be those particles! Rub a minute fragment to dust in a mortar and place a trace of the powder under the highest power of the best microscope; no yellow particle is visible, not the minutest portion of lustrous metal, but dull-brown miniature fragments of the original mass. The elementary particles of sulphur and iron, or of the elements in any other compound (the chlorine and sodium in common salt or the iodine and iron in solution of iodide of iron), are, in short, too small to be seen. Can they be imagined? Again, no. The mind cannot conceive of a particle of anything (sulphur, iron, sulphide of iron, or what not) so small but what the next instant the imagination has divided it. Yet learner and teacher must have some common platform on which to reason and converse. The difficulty is met by speaking of these inconceivably small particles as *atoms* (ἄτομος, *atomos*, indivisible; from the privative α and τέμνω, *temnō*, to cut—that which cannot be cut, or divided) an expedient suggested by our countryman Dalton at the commencement of the present century. It is a somewhat unsatisfactory expedient, no doubt, but the only one possible to the majority of minds in the present state of knowledge and education. We cannot speak of iodine and iron uniting lump to lump, as two bricks are cemented together or blocks of wood glued together, for such is not the kind of action. We cannot select a minute fragment of each to regard as the combining

portions, for the minutest fragment we could obtain is visible, and iodide of iron contains neither visible iodide nor visible iron. And yet iodide of iron contains both iodine and iron, or, at least, a given weight of the compound is obtained from the same weight of constituents, and the same weight of constituents is obtainable from an equal weight of the compound. We might say that molecules are concerned in the operation, but molecules means little masses of—of what? there is positively no word left with which to carry on conversation and description but *atoms*. Any other mode of treating the matter is too subjective for general employment. Moreover any difficulty in forming a definite conception of an atom concerns the student of physics rather than of chemistry, the chemist regarding an atom as, in the words of Kekulé, "a particle of matter which undergoes no further division *in chemical metamorphoses*."

The Chemical Force.

What power binds the atoms of a chemical compound together in such marvellous closeness of union that in the couple or group they lose all individuality? Clearly an attractive force of enormous power, a force remotely resembling, perhaps, that which attracts a piece of iron to a magnet. Only by such an assumption can we conceive that common salt contains chlorine and a metal (sodium), or that wood contains carbon, hydrogen, and oxygen. Were not this force thus all-powerful the carbon in wood would show its blackness and other qualities, and the hydrogen and oxygen give indications of their gaseous and other characters. This attractive force is commonly termed the *chemical force*, sometimes *chemical affinity*. The word *chemism* has also been proposed for it, just as the magnetic force is termed magnetism, but has not been generally adopted.

Molecules.

A single, free, uncombined atom cannot exist in a state of isolation for any appreciable length of time. For an atom is the home of an attractive force of great intensity, and the moment it is liberated from a state of combination (hydrogen from water for instance, or chlorine from salt) finds itself in proximity to another atom having similar desires for union, so to speak; the result is an impetuous rushing together and formation of either couples, trios, or groups, according to the nature of the atoms. It would be as difficult to conceive of separate atoms as to imagine that a strong magnet and a piece of steel could be suspended close to each other without being drawn together. These pairs and other groups of atoms are conveniently designated by the one word *molecule*, the diminutive of *mole*, a mass; literally, little masses. Dissimilar kinds of atoms seem to have greater attraction for each other than similar kinds; for, first, the masses of matter met with in nature in the great majority of cases contain two or more dissimilar elements; and, secondly, at the moment certain elements are liberated from their combination, they are far more active towards other elements than afterwards, when the atoms have probably united to form molecules.

Recapitulation.

It is desirable that the learner should here make some experiment which will serve to bring again under notice in an applied form what has just been stated respecting the substances termed *chemical compounds*, and concerning the character of that *chemical force* which resides in the *atoms* of *molecules*. The following will usefully serve this purpose; it is the process for detecting a trace of sulphurous acid in common liquid hydrochloric acid.

As already proved, hydrogen gas and chlorine gas, when united, form hydrochloric acid gas: the latter dissolved in water is the ordinary liquid of the shops termed *Hydrochloric Acid*, the *Acidum Hydrochloricum* of Pharmacopœias. Commercial samples of this liquid not unfrequently contain as an impurity a trace of sulphurous acid gas, a body also already mentioned and experimentally prepared —a trace too small to be detected by its odor. Obtain a specimen of common liquid hydrochloric acid containing as an impurity a trace of sulphurous acid, or adopt the more simple course of purposely adding a few drops of aqueous solution of sulphurous acid (*Acidum Sulphurosum*,* B. P.) to some hydrochloric acid. (If no sulphurous acid is at hand, the object may be accomplished by pouring a quarter or half an ounce of liquid hydrochloric acid into a wide-mouthed bottle, then burning a fragment of sulphur on a wire or strip of wood inside the bottle for a few seconds, and shaking the gas and liquid together.) Pour some of the impure liquid hydrochloric acid into a test-tube, add about an equal bulk of water, and then drop in some fragments of the metal zinc. Effervescence will occur, due to the escape of inodorous hydrogen gas, together with a small quantity of another badly-smelling gas termed sulphuretted hydrogen gas. Bring the mouth of the tube under the nose; the presence of sulphuretted hydrogen will at once be recognized.

The hydrochloric acid has now been *tested* for sulphurous acid. If the experiment be performed on any commercial specimen of the acid, and a smell of sulphuretted hydrogen be observed, the operator would at once be able to state that the specimen contains sulphurous acid as an impurity.

The true explanation of what occurs in the successive steps of the foregoing experiment is as follows:—

Hydrochloric acid is a *chemical compound* of hydrogen and chlo-

* These aqueous solutions of acids are generally, for the sake of brevity, simply termed acids.

rine. That it is a chemical compound, and not a mere mechanical mixture of hydrogen and chlorine, is shown by the fact that its properties are altogether different from the properties of its constituents. The attractive power or *chemical force* resident in the *atoms* of chlorine and of hydrogen have caused them to combine in the closest manner imaginable and form pairs of atoms or *molecules* of the chemical compound—hydrochloric acid. Zinc being introduced into the acid, and the atoms of zinc and chlorine having, as a matter of fact, even still greater attraction for each other than the hydrogen for the chlorine, the zinc and chlorine atoms combine and form a new molecule (termed chloride of zinc) which remains in the liquid, while the hydrogen atoms, having the atoms of no other element to combine with, if the acid is pure, unite to form pairs, or molecules of hydrogen, and in that state escape from the vessel. If the acid be impure from the presence of sulphurous acid (sulphurous acid gas, it will be remembered, is a compound of sulphur and oxygen), some of the hydrogen atoms, at the moment of their birth, their *nascent* state (from *nascor*, to be born), finding the atoms of other elements present, namely, the atoms of sulphur and oxygen of the sulphurous acid, combine by preference with these atoms and form new molecules, the sulphur and hydrogen forming sulphuretted hydrogen, and the oxygen and hydrogen producing water: the former escapes with the great bulk of the hydrogen, while the water remains with the water already in the vessels.

Conditions and nature of the manifestation of the Chemical Force.

The exertion of chemical affinity is only possible when substances are in close contact. Thus it was necessary to bring the oxygen, hydrogen, phosphorus, chlorine, sulphur, carbon, iodine, and iron into intimate contact before reaction occurred. The exact nature of these actions, as indeed of all in which substances act chemically, would seem to be an interchange, most generally a mutual one, of the atoms of which the molecules consist—a change of partners, so to speak. Thus in the experiment in which hydrogen and chlorine gases united to form hydrochloric acid gas, a pair of atoms in a hydrogen molecule, and a pair of atoms in a chlorine molecule, finding themselves opposite to each other, re-paired with each other, the atoms of each of the old molecules unlinking, so to say, and pairing off in fresh couples—as two brothers who for many years have been close companions, and two sisters similarly united, thrown freshly into each other's society soon accept new and still more congenial couplement.

$$\begin{matrix}\text{Hydrogen}\\\text{Hydrogen}\end{matrix} \text{ and } \begin{matrix}\text{Chlorine}\\\text{Chlorine}\end{matrix} \text{ become } \begin{matrix}\text{Hydrogen}\\\text{Chlorine}\end{matrix} \text{ and } \begin{matrix}\text{Hydrogen}\\\text{Chlorine.}\end{matrix}$$

Or, using the symbols of these elements instead of the full names,

H H and Cl Cl become H Cl and H Cl.

Still further economizing space and trouble, the same statement may be made in the following form:

H_2 and Cl_2 become 2HCl.

Once more, by using the *plus* sign (+) instead of the words "and" or "added to," and the sign or symbol = or *equal* instead of the words "become" or "are equal to," we reach the shortest method of expressing this chemical action:—

$$H_2 + Cl_2 = 2HCl.$$

This is the form in which such an action may be expressed in the student's note-book. It is the shortest and most convenient form, and is instructive and suggestive to the mind.

Chemical Notation.

We have thus gradually arrived at a spot in the path of chemical philosophy at which we must halt to more fully discuss the usual method of recording chemical travels. We have arrived at the subject of *chemical notation* (from *noto*, to mark), the art or practice of recording chemical facts by short marks, letters, numbers, or other signs. Already the first capital letter, or the first and one of the following small letters of the Latin names of the elements have been employed as contractions, or short-hand expressions, or *symbols* of the whole name. Thus H has been used for the word "hydrogen," and Cl for "chlorine." A second function of such a symbol is that of indicating one atom. Thus H stands not only for the word or substance "hydrogen," but for one atom of hydrogen. Large and small figures (2 or $_2$) indicate a corresponding number of atoms, the small figure only multiplying the one particular symbol to which it is attached, while a larger figure multiplies all the symbols it precedes. Thus H_2 means two atoms of hydrogen, and Cl_2 two atoms of chlorine; while 2HCl means two atoms of hydrogen and two atoms of chlorine, or, in one word, two molecules of hydrochloric acid gas. A third function of such a symbol as H or Cl is that of indicating one volume of the element in the gaseous state. Thus H, Cl, or O stand, first, for the substances named hydrogen, chlorine, and oxygen; secondly, for single atoms of hydrogen, chlorine, and oxygen; and thirdly, for single and equal volumes (be they gallons, pints, or minims) of chlorine, hydrogen, and oxygen. It will be remembered that one test-tubeful of hydrogen and an equal sized test-tubeful of chlorine were employed in forming hydrochloric acid gas, HCl.

The position of symbols tells for something. Thus HCl indicates not only the substances hydrogen and chlorine, single atoms of each of the substances, and equal volumes of each, but also that the two substances are joined together by the chemical force. If the two letters were placed one under the other, or at some distance apart, or were separated by a comma or a plus sign (+), they would be understood to mean a mere mixture of the elements; but placed as close as the printer's types will conveniently and consistently allow, they must be considered to stand for a compound of the elements, that is to say, hydrochloric acid gas (HCl). The collection of symbols representing a molecule is termed a *formula*. H_2, Cl_2, and HCl are the *formulæ* of hydrogen, chlorine, and hydrochloric acid gas,

$$H_2 + Cl_2 = 2HCl.$$

Such a set of letters, figures, and marks as those on the above line are collectively termed an *equation*, because indicating the equality of the number and nature of the atoms before and after chemical action. On the left-hand of the sign of equality are shown two molecules, and on the right-hand two molecules; but, of the molecules on the left, one contains two atoms of hydrogen and the other two atoms of chlorine, while of the molecules on the right each contains one atom of hydrogen and one of chlorine. The equation forms a short and convenient plan of recording the facts of experiment.

Instead of an equation, a *diagram* may be employed to exhibit the same facts. Thus:

Relation of Gases to Liquids and Solids.

The molecules of a gas are not close together, for a quantity of gas may be compressed with very little force to half or one-fourth its bulk, in short to such an extent that in many cases the molecules sufficiently approximate to form a liquid. Moreover from recent researches there would seem to be no sharp line of demarcation between the gaseous and liquid condition of a substance (Andrews). In a liquid the molecules are still free to glide about with ease amongst each other; and though in solids they exhibit less mobility, still even solids may be compressed by powerful pressure, so that probably in no instance are molecules in absolute contact. Why a gas under pressure should immediately return to its original bulk when the pressure is removed, while a liquefied or solidified gas only slowly resumes the gaseous or vaporous state, is a question which requires for discussion a knowledge of the nature of forces other than the chemical: here chemistry joins the domain of physics. It was necessary, however, to state thus much respecting the condition of the molecules of a gas in order that the learner might be prepared for the fact, that mixtures of certain gaseous elements, in combining to form gaseous compounds, diminish considerably in volume. Thus, while a pint of hydrogen and a pint of chlorine give a quart of hydrochloric acid gas, two pints of hydrogen and one of oxygen are necessary to produce a quart of gaseous water (steam). It will be remembered that two volumes of hydrogen and one of oxygen were necessary in a previous experiment in which water was formed. With regard to the notation of the matter, it will be sufficient to state here that while a *symbol* represents one volume of any gas, *a formula of any gas or vapor represents two volumes.* By remembering this general rule we may, by looking at a formula, tell how many volumes of constituents were concerned in the formation of a compound, and therefore what amount of condensation, if any, occurred during the act of

formation. By thus reading and interpreting the formula for water, H_2O, we see that two volumes of steam (at any temperature) may be obtained from two volumes of hydrogen and one volume of oxygen (at the same temperature) and thus that the extent of condensation when hydrogen and oxygen (at a stated temperature) unite to form gaseous water (at the same temperature) is from three to two. This subject will again be treated of in connection with those of Chemical Combination and Specific Gravity of Gases.

Further Remarks on Chemical Notation.

We may now take the experiment just alluded to as an additional example of chemical action, and the best and simplest way of expressing the same by notation. When two volumes of hydrogen and one of oxygen were caused to combine, the production of flame and noise proved that chemical action of some kind had taken place; had the experiment been performed in dry vessels, evidence of the precise action would have been found in the bedewment or moisture produced by the condensation of the water on the sides of the tube. Similar evidence was afforded on holding a cool glass surface over the hydrogen-flame. The action is expressed in the following equation:—

$$2H_2 + O_2 = 2H_2O.$$

Instead of an equation, the following diagram may be employed:—



The foregoing aggregation of symbols or short-hand characters, or *formula*, H_2O, is, then, a convenient picture of the facts that have already come before us, viz., that water is formed of the elements hydrogen, H, and oxygen, O; moreover, that it is formed of two measures or volumes of hydrogen, H_2, to one of oxygen, O; and, thirdly, that the molecule of water (H_2O) is formed of two atoms of hydrogen (H_2) and one of oxygen (O). The formula also fulfils the fourth function of indicating that the two volumes of hydrogen and one of oxygen in combining condensed to two volumes of steam. That the resulting bulk of steam afterwards shrunk most considerably in condensing to water is another matter altogether, a physical and not a chemical result, and due to the approximation of the molecules of water *after* formation.

Another experiment already performed, illustrating the character of the manifestations of chemical force, and its symbolic expression, was that in which the red-hot carbon of wood was plunged into oxygen. The evidence of chemical action in that case was the sudden inflammation of the carbonaceous extremity of the wood. The particles of carbon and oxygen, having intense attraction or affinity for

each other at that temperature, rushed together so impetuously as suddenly to produce a large additional quantity of heat, an amount sufficient to cause the particles to emit an intense white light. The action between carbon and oxygen is expressed on paper in either of the following ways:—

$$C_2 + 2O_2 = 2CO_2$$



CO_2 is the formula of the well-known gaseous body commonly termed carbonic acid gas.

The reader should here draw for himself equations or diagrams similar to the three just given, and thus show the formation of the three bodies he has already produced —namely, phosphoric anhydride (P_2O_5), sulphurous acid gas (SO_2), and iodide of iron (FeI_2), submitting the same, if possible, to a tutor or other authority to assure himself of their correctness.

Note.—In the foregoing experiments several illustrations occur of the formation of compounds having the gaseous, liquid, and solid conditions, in one of which three forms all matter in the universe exists.

Laws of Chemical Combination (by Weight).

Chemistry as a science is little more than a hundred years old, though very many of the facts and operations we now term chemical have been known as isolated items of knowledge for centuries. Thus, the ancient Egyptians made glass, vitriol, soap, and vinegar; and the Greeks started the idea that matter was composed of a few elements, imagining earth, air, fire, and water to be elements. But the great general principles which interlace and bind together separate facts, those which from their extensive application and importance are denominated *laws*, have all been brought to light since the year 1770. Between 1785 and 1800, Bryan Higgins, William Higgins, Wenzel, Richter, and Proust made analyses and researches which led up to the following generalizations: *When compounds unite to form definite chemical substances, they always combine in the same proportions.* The curious character of this fact could but be most striking, and indeed is so now, to the mind receiving it for the first time. Thus water added to quicklime gives slaked lime, a perfectly definite chemical substance. But whereas sand and water, sugar and water, sand and sugar, and such mixtures may be obtained by adding together the ingredients in any proportions whatever, say, 90 of sugar

and 10 of sand, or 10 of sugar and 90 of sand, slaked lime invariably results from the combination of 75¾ of quicklime and 24¼ of water. If a larger proportion than 75¾ per cent. of quicklime be employed, the excess remains as quicklime mixed with the slaked lime; and if more than 24¼ per cent. of water be used, an excess of water remains with the slaked lime and evaporates if the mixture be exposed to the air. Dalton discovered that when *elements* unite to form a definite substance, they, like compounds, always combine in the same proportions; and he was the first to set forth the law in a clear manner.

First Law of Chemical Combination.

A definite compound always contains the same elements in the same proportions.

Thus common salt always contains 39⅓ per cent. of the metal sodium to 60⅔ of chlorine, and water always 89 of oxygen to 11 per cent. of hydrogen (more exactly 88.89 to 11.11). As with the quicklime and water, so with the chlorine and sodium, and the constituents of many other chemical compounds; in such cases if either be added to the other in any quantity beyond stated proportions, the excess plays no part whatever in the act of combination. (In some cases, as will be seen directly, excess of either plays a very simple but very remarkable part.) In short, whether a compound be made directly from its elements, or by the combination of other compounds, or indirectly as one of two products of the action of substances chemically on each other, whatever be its origin, if it is a definite compound it always contains the same elements in the same proportions.

Dalton further made such experimental researches as enabled him to lay down a second great law. He found that, while many substances only united chemically in one proportion, others combined in two or even more, and he studied several such naturally related bodies. He found that while carbonic oxide (a gas formed when charcoal is burned with an insufficient supply of air) contains such a percentage of carbon and oxygen as is represented by (to use the simplest figures) 3 and 4, carbonic acid (a gas formed when charcoal is burned with excess of air) contains 3 of carbon to exactly twice 4 of oxygen. He proved that a similar relation existed between two compounds of carbon and hydrogen, and between a cluster of compounds of nitrogen and oxygen. The first of the latter, to a given quantity of nitrogen, contains a certain proportion of oxygen; the next, to the same quantity of nitrogen, had twice the proportion of oxygen; and the others have respectively three, four, and five times as much oxygen as the first, the quantity of nitrogen remaining the same throughout. Dalton thus generalized these facts:—

Second Law of Chemical Combination.

When two elements unite in more than one proportion, the resulting compounds contain, to a constant proportion of one element, simple multiple proportions of the other—or the weights of the constituent elements bear some similar simple relation to each other.

Thus carbonic oxide gas is a definite compound always containing fixed proportions of carbon and oxygen, and carbonic acid gas also a definite compound always containing fixed proportions of carbon and oxygen. Both thus obey the first law of combination. But whereas carbonic oxide contains, or may be made from, 30 parts (ounces, grains, or other weights) of carbon and 40 of oxygen, carbonic acid contains, or may be made from, 30 parts of carbon and exactly twice 40 of oxygen.

This second law cannot but be as striking as the first when freshly unveiled to the mind. Sand and sugar, or any substances which do not act *chemically* on each other, may be mixed in the proportions of 30 to 40, 30 to 80, 30 to 60, or any other quantities; but if an attempt be made to burn 30 parts of carbon in 60 of oxygen, the elements will themselves naturally assert their own special combining powers, and refuse, so to say, to unite in these proportions: the 30 of carbon will first combine with 40 of oxygen and form 70 of carbonic oxide, and this gas, which, had it the opportunity, would combine with 40 more of oxygen and form carbonic acid gas, finding only half that quantity, namely, 20 of oxygen present, contents itself by one half (that is 35 of carbonic oxide) accepting the 20 of oxygen and becoming carbonic acid gas, while the other half remains as carbonic oxide. This is a most wonderful fact. Again, if 30 parts of carbon be burnt in more than 80, say 85, of oxygen, only 80 will be used, the other 5 remaining as oxygen merely *mixed* with the resulting carbonic acid gas. If we attempt to burn 30 parts of carbon in less than 40 of oxygen, the oxygen will take up three-fourths its weight of carbon and form carbonic oxide, while the excess of carbon will remain as carbon.

Careful consideration of the foregoing two great laws has suggested an important truth sometimes termed *The Third Law of Chemical Combination*, namely: *The proportions in which two elements unite with a third are the proportions (or simple multiples or submultiples of the proportions) in which they unite with each other.* Thus oxygen in proportions of 16 unites with hydrogen, and carbon in proportions of 12 unites with hydrogen; therefore 16 and 12 are the proportions in which oxygen and carbon will unite with each other.

The Atomic Theory.

The laws which Dalton (1803 to 1808) so largely aided to unveil—two grand and wonderful truths—he explained and correlated by a simple and beautiful hypothesis. *Dalton suggested that matter was not infinitely divisible, but composed of minute particles or* ATOMS *having an invariable character.* In the words of Wurtz, "*To an old and vague notion he attached an exact meaning by supposing that the atoms of each kind of matter possess a constant weight, and that combination between two kinds of matter takes place not by penetration of their substance, but by juxtaposition of their atoms.*"

Thus under this hypothesis, or atomic theory as it is generally termed, carbonic oxide is a definite compound always containing the same elements in the same proportions, because each particle of it is composed of an atom of carbon and an atom of oxygen chemically united, the weights of the atoms being in the proportion of 3 and 4, that is, having a constant weight of 12 and 16, as we now believe. Carbonic acid gas is also a definite compound always containing the same elements in the same proportions, and the proportion of oxygen is just double that in carbonic oxide, because each particle of it is composed of an atom of carbon (weighing 12) and two atoms of oxygen (each weighing 16).



Imaginary pictures of molecules of carbonic oxide gas and carbonic acid gas *

Again, the facts that with 12 of carbon oxygen unites in the proportion of 16, or a multiple of 16; that with 12 of carbon sulphur unites in the proportion of 32, or a multiple of 32 (the liquid known as disulphide of carbon is a chemical compound of 12 of carbon to twice 32 of sulphur); and, thirdly, that oxygen and sulphur unite in proportions of 16 and 32, are at once explained on the assumption that these elements exist in atoms which have the respective weights mentioned. Existing in indivisible particles (atoms) which weigh 16, 12, and 32, oxygen, carbon, and sulphur *must* unite in indivisible weights of 16, 12, and 32.

Atomic Weights.

What has just been stated respecting two or three elements is true of all the elements. It is a fact, that, when elements unite with one

* The size of atoms, their shape, their absolute weight—whether or not they are in actual contact—whether or not they are fixed in relation to each other, free to move about each other, or in a constant state of motion—and whether or not the chemical force actuates them as the force of gravitation influences our earth and moon and solar systems, are matters of which at present we known nothing. The two pictures are not intended to convey any impression that the following formulæ do not give: CO or OC, OCO or OOC or COO or CO_2.

another in the peculiar and intimate manner termed chemical, they do not combine in the haphazard proportions of a mere mixture, but in one fixed and constant proportion. Such proportions or weights represent, according to Dalton, the weights of their atoms. Oxygen unites with other elements in proportions of 16, therefore 16 is the weight of the atom of oxygen. Chlorine unites with other elements in proportions of $35\frac{1}{2}$, therefore $35\frac{1}{2}$ is the atomic weight of chlorine. And for a similar reason the atomic weights of hydrogen will be 1, carbon 12, sulphur 32, nitrogen 14, and iodine 127. Of course it will be understood that these are the *relative* weights of atoms, for we cannot know the absolute weights. All that is known is that the chlorine atom, for instance, is 35.5 times as heavy as the hydrogen atom, whatever the absolute weight of the latter may be, and the iodine atom 127 times as heavy. The quantity of metal which with 35.5 of chlorine will form a chloride, and with twice 35.5 a second chloride (dichloride or bichloride), will require 127 of iodine to form an iodide, and twice 127 of iodine to form a second iodide (a diniodide or biniodide).*

Laws of Chemical Combination (by Volume).

In 1809 Gay-Lussac showed it to be a fact that when gaseous elements unite with one another in the intimate manner termed chemical, they do not combine in the haphazard proportions (that is, proportions by measure or volume) of a mere mixture, but in constant proportions in the case of any single definite compound, and in simple multiple proportions in cases where two elements form more than one definite compound. He thus proved that the laws respecting the constancy of weight with which elements combine hold good with reference to volume, at all events in those cases in which elements exist in or can be made to assume the gaseous condition. A volume of hydrogen gas and an equal one of chlorine gas give hydrochloric acid gas. Two volumes of hydrogen and one of oxygen give water-vapor or steam. Such volumes or simple multiples are alone the proportions by bulk in which elements combine. If any excess of either gas be mixed and combination attempted, only the stated proportions really combine, the excess remaining unaltered. Further, following Gay-Lussac, on weighing these similar and equal volumes of hydrogen, chlorine, and oxygen, we find that the chlorine is 35.5 times as heavy as hydrogen, and oxygen 16 times as heavy as hydrogen.

In 1811 and 1814, Avogadro and Ampère, reasoning on the fact that all gases are similarly affected by variations of temperature and pressure, concluded that all must have been similarly constituted—similarity in properties always indicating similarity in character or nature; in other words, that, if equal volumes of gases be taken, each will contain the same number of molecules, similar in size and equally

* Only the atomic weights of the above and a few of the chief metallic elements need be committed to memory; others can be sought out as occasion may require. A complete Table of Atomic Weights is given at the end of the volume.

distant apart. The deduction is obvious. The weights of molecules *of elements* (that is, of pairs of atoms, and therefore of atoms themselves) must differ to the extent that the weights of equal volumes of those elements differ. Equal volumes of hydrogen, chlorine, and oxygen, weighing respectively 1, 35.5, and 16, and each of these volumes containing an equal number of molecules, each formed of two atoms, it follows that the relative weights of the atoms will be 1, 35.5, and 16.

It will thus be seen that the weight of the *volume* in which an element combines, and the *actual weight* in which it combines, irrespective of volume, are identical. For instance, we should find by experiment that, as a simple matter of fact, oxygen unites with other elements in proportions of 16 by weight, while hydrogen combines in proportions of 1. Turning, then, to experiments on the volumes in which hydrogen or oxygen combine, and having ascertained those volumes, and then having weighed them, we should find that the oxygen volume weighs 16, while the hydrogen weighs 1. In compounds in which hydrogen were found in proportions of 1 grain, oxygen would be found in proportions of 16 grains. In gaseous compounds in which hydrogen were found in proportions of, say, 27 ounces by measure, oxygen would be found in proportions of 27 ounces by measure; the 27 ounces of hydrogen would be found to weigh 1 grain, and the 27 ounces of oxygen to weigh 16 grains.

Thus the two great facts or laws respecting chemical compounds which Dalton laid down by ascertaining the exact weights in which bodies combine, Gay-Lussac confirmed by experiments on the exact volumes in which elements combine. Further, Gay-Lussac's experiments and Avogadro's reasoning strongly supported Dalton's theory of atoms.

Recapitulation.

What are atomic weights or combining weights? First, they are represented by the smallest proportion (relative to 1 part of hydrogen) in which an element migrates from compound to compound. Thus 1 part by weight of hydrogen can be eliminated from 18 similar parts of water by action of certain metals, leaving 1 of hydrogen and 16 of oxygen combined with the metal. From the latter compound 1 more of hydrogen is eliminated by a second experiment with more metal, leaving 16 of oxygen combined with the metal. In these and other well-known reactions 16 parts of oxygen take part in the various operations; 16, therefore, is the probable atomic weight of oxygen; and so with other elements and radicals. Secondly, the weights of the atoms, or the atomic weights of the gaseous elements already studied, must differ from each other to the extent that equal volumes of those elements differ in weight. For equal volumes of an element contain an equal number of molecules equal in size (Avogadro's and Ampère's law), and each molecule is composed of two atoms; so that equal volumes of elements contain an equal number of atoms. Now, bulk for bulk, chlorine is thirty-five and a half (35.5) times as heavy as hydrogen; so that the molecule of chlorine must be 35.5 times the weight of the molecule of hydrogen; for

molecules are equal in bulk. And as the molecules of chlorine and hydrogen contain two atoms each, the atom of chlorine must be 35.5 times as heavy as that of hydrogen. The actual weight of atoms can never be ascertained, but that is of little consequence if we can only determine, with exactitude, their comparative weights. Comparing, then, all atomic weights, sometimes obscurely termed equivalents, with each other, and selecting hydrogen as the standard of comparison (because it is the lightest body known, and therefore, probably, will have the smallest atomic weight), and assigning to it the number 1, we see that the atomic weight of chlorine will be represented by the number 35.5. By parity of reasoning the atomic weight of oxygen is 16; for oxygen is found, by experiment, to be 16 times as heavy as hydrogen. Similarly the atomic weight of nitrogen is found to be 14. The atomic weight of carbon is 12—not because its vapor has been proved to be 12 times as heavy as hydrogen, for it has never yet been converted into the gaseous state, but because no gaseous compound of carbon, which has been analyzed, has been found to contain in 2 volumes (one of which, if hydrogen, would weigh 1 part) less than 12 parts of carbon.

By thus weighing equal volumes of gaseous elements, or equal volumes of gaseous compounds of non-volatile elements, and ascertaining by analysis the proportion of the non-volatile element whose atomic weight is being sought, to the volatile element, whose atomic weight is known, the atomic weights of a large number of the elements have been determined. Some of the elements, however, do not form volatile compounds of any kind; the stated atomic weights of these elements, therefore, are at present simply the proportions by weight in which they combine with or displace elements whose atomic weights have been determined, the proportion being in most cases checked by isomorphic considerations and the relation of the element to other forces, especially heat.* (*Vide infra.*)

Molecular Weight and Molecular Volume.

The weight of the molecule is simply the sum of the weights of its atoms; thus

$$H_2 = 2,\quad O_2 = 32,\quad Cl_2 = 71,\quad H_2O = 18,\quad HCl = 36.5.$$

Molecular Volume.—If the quantities just mentioned be weighed out (in grains or other weights), or if the molecular weight of any gases or liquids be taken and exposed to similar (high) temperatures

* *Isomorphous* bodies (from ἴσος, *isos*, equal, and μορφή, *morphē*, form) are those which are similar in the shape of their crystals. The identity in crystalline form is so commonly associated with similarity of constitution that non-crystalline substances resembling each other in structure are often regarded as isomorphous. When one element unites with another in more than one proportion, and consequently its atomic weight is uncertain, the isomorphism of either of its compounds with some other compound of known constitution is usually accepted as decisive evidence as to which proportion is atomic. The specific heat of elements will be treated of subsequently.

and pressures, *they will all be found to occupy the same volume.* Conversely, if equal volumes of gases or vapors be measured out, and then the whole weighed, the resulting figures (all referred to 2 of hydrogen as a starting-point or standard) are the molecular weights of the respective substances. Thus a measure of hydrogen (about half a gallon) which, at a temperature of, say, 300° F. or 400° F., and common atmospheric pressure, would weigh 2 grains, would in the case of vapor of water (steam) weigh 18 grains. Hence we are justified in considering, indeed compelled to consider, the molecule of water to contain two atoms of hydrogen (=2) and one of oxygen (=16), and its formula to be H_2O (=18), and not H_4O_2, in which case its vapor would be twice as heavy as it really is found to be.

Construction of Formulæ.—The composition of hydrochloric acid (HCl), water (H_2O), ammonia (NH_3), carbonic acid gas (CO_2), or any other compound, as well as the weight of an element that may be concerned in its formation, cannot be ascertained by actual experiment until the student is far advanced in practical chemistry—until he is able to *analyze* not only *qualitatively*, but, by help of a balance, *quantitatively.* The percentage composition of a substance having been detetermined by quantitative analysis, its formula is constructed by aid of the foregoing and other theoretical considerations. The correctness of such formulæ can be verified by expert analysts, but must be taken for granted by learners. This subject will again be referred to in the latter part of this Manual.

Quantivalence of Atoms.

Turning from the *weights* of atoms, their *value* may now be considered; their *quantivalence* (from *quantitas*, quantity, and *valens*, being worth) may be stated. The chemical value of atoms in relation to each other may be compared to the exchangeable value of coins. As compared with a penny (1*d.*) a groat (4*d.*) is four-valued; as compared with hydrogen carbon is quadrivalent. Here again hydrogen is conventionally adopted as the standard of comparison. An atom of oxygen in its relations to an atom of hydrogen is bivalent (pronounced thus, biv′-a-lent; of double worth, from *bis*, twice, and *valens*); an atom of it will displace two atoms of hydrogen, or combine with the same number; nitrogen is usually trivalent (triv′-a-lent; from *tres*, three, and *valens*); and carbon quad-riv′-a-lent (from *quatuor*, four, or *quater*, four times, and *valens*). Chlorine, iodine, and bromine, as well as potassium, sodium, and silver among the metals, are, like hydrogen, univalent (u-niv′-a-lent; from *unus*, one, and *valens*). Barium, strontium, calcium, magnesium, zinc, cadmium, mercury, and copper, like oxygen, are bivalent. Phosphorus, arsenicum, antimony, and bismuth, like nitrogen, usually exhibit trivalent properties; but the composition of certain compounds of these elements shows that the several atoms are sometimes quinquivalent (quin-quiv′-a-lent; *quinquies*, five times, and *valens*). Gold and boron are trivalent. Silicon (the characteristic element of flint and sand), tin, aluminium, platinum, and lead resemble carbon in being quadrivalent. Sulphur, chromium, manganese, iron, cobalt, and nickel are sexivalent (sex-iv′-a-lent; from *sex*, six, or *sexies*, six

times, and *valens*), but frequently exert only bivalent, trivalent, or quadrivalent activity. This *quantivalence* (quant-iv'-a-lence; from *quantitas*, quantity, and *valens*), also termed *atomicity* (maximum quantivalence), *dynamicity*, and *equivalence* of elements, may be ascertained at any time on referring to the Table of the Elements at the end of this volume, where Roman numerals, I, II, III, IV, V, VI, are attached to the symbols of each element to indicate atomic univalence, bivalence, trivalence, quadrivalence, quinquivalence, or sexivalence. Dashes (H′, O″, N‴) similar to those used in accentuating words are often used instead of figures in expressing quantivalence. The quantivalence of elements, as they one after another come under notice, should be carefully committed to memory; for the composition of compounds can often be thereby predicated with accuracy and remembered with ease. For instance, the hydrogen compounds of chlorine, Cl′, oxygen, O″, nitrogen, N‴, and carbon, C⁗, will be respectively H′Cl′, H'_2O'', H'_3N''', and H'_4C'''',—one univalent atom, H′, balancing or saturating one univalent atom Cl′; two univalent atoms, H'_2, and one bivalent atom O″, saturating each other; three univalent atoms, H'_3, and one atom having trivalent activity, N‴, saturating each other; and four univalent atoms, H'_4, and one quadrivalent atom, C⁗, saturating each other. Carbonic acid gas, $C^{IV}O^{II}_2$, again, is a saturated molecule containing one quadrivalent and two bivalent atoms.

The subject of quantivalence will be further explained after the first six metals have been studied, when abundant illustrations of its applications will have occurred.

DEFINITIONS.

Chemistry is the study of the chemical force.

The Chemical Force, like other forces, cannot be described, for, like them, it is only known by its effects. It is distinguished from other forces by the fact that it produces an entire change of properties in the bodies on which it is exerted. The chemical force resides in the atoms of elements; it is exerted only between definite weights and volumes of matter.

An Element is a substance which cannot by any known means be resolved into any simpler form of matter.

An Atom of any element is a particle so small that it undergoes no further subdivision in chemical transformations.

A Molecule is the smallest particle of matter that can exist in a free state.

A mere Mixture of substances is one in which each ingredient retains its properties.

A Chemical Compound is one in which definite weights of constituents have combined, and during combination have undergone an entire change of properties. A "compound" in pharmacy is an intimate mixture of substances, but still only a mixture; it is not a *chemical* compound, the ingredients have not entered into *chemical* union or combination.

Combustion is a variety of chemical combination, a variety in

which the chemical union is sufficiently intense to produce heat and, generally, light.

The Law of Diffusion is one under which gases mix with each other at a rate which is in inverse proportion to the square root of their relative weights; that is, irrespective of and even in spite of their comparative lightness or heaviness.

A Chemical Symbol is a capital letter, or a capital and one small letter. It has four functions, namely:—

1. It is short-hand for the name of the element.
2. It represents one atom of the element.
3. It stands for a constant weight of the element—the atomic weight or combining weight.
4. Symbols represent single and equal volumes of gaseous elements.

A Chemical Formula represents a molecule either of an element or of a compound. It also has four functions:—

1. It indicates at a glance the names of the elements in a molecule.
2. Its symbol, or symbols, together with a small figure attached to the foot of any symbol, show the number of atoms in a molecule.
3. It stands for a constant weight of a compound—the molecular weight, that is, the sum of the weights of the atoms in a molecule.
4. It represents two volumes of the substance in the state of gas or vapor. (In the case of bodies which cannot be volatilized this statement is only probably correct.)

A Chemical Equation or *a Chemical Diagram* is a collection of formulæ and symbols so placed on paper as to form a picture or illustration of the state of things before and after that attack of molecules on each other which results in the formation of molecules of new substances.

A Solid is a substance the molecules of which are more or less immobile, though probably not in absolute contact.

A Liquid is a substance the molecules of which so freely move about each other that it readily assumes and retains the form of any vessel in which it is placed.

A Gas is a substance the molecules of which are so far apart that they seem to have lost all attraction for each other, and, indeed, to have acquired the property of repulsion to such an extent that they are only prevented from receding to a still greater extent by the pressure of surrounding matter. Motion is especially characteristic of gaseous fluids.

The Three Laws regulating Chemical Combination (either by weight or volume).

First. A definite compound always contains the same elements and the same proportions of those elements—by weight or volume.

Second. When two elements unite in more than one proportion, they do so in simple multiples of that proportion.

Third. The proportions in which two elements unite with a third, are the proportions in which they unite with each other.

Atomic Weights are, first, the proportions in which elements are found to combine with each other by weight. (The figures showing these proportions are purely relative, but all chemists agree to make this relation fixed by giving the number 1 to hydrogen.) Secondly, they are the weights of equal volumes of elements in the state of gas (relative to 1 of hydrogen).

Molecular Weights.—These are the weights of equal volumes of gases or vapors, under equal circumstances of temperature and pressure, and relative not to 1 but to 2 of hydrogen. In the case of non-volatile bodies molecular weight is deduced from the observed analogies of bodies with those whose molecular weight admits of proof.

Quantivalence of Atoms.—The observed power, force, or value for work of an atom—relative to 1 of hydrogen.

THE LEARNER IS RECOMMENDED TO READ THE FOREGOING PARAGRAPHS ON THE GENERAL PRINCIPLES OF CHEMICAL PHILOSOPHY CAREFULLY ONCE OR TWICE, THEN TO STUDY (EXPERIMENTALLY, IF POSSIBLE) THE FOLLOWING PAGES, RETURNING TO AND READING OVER THE GENERAL PRINCIPLES FROM TIME TO TIME, UNTIL THEY ARE THOROUGHLY COMPREHENDED.

QUESTIONS AND EXERCISES.

42. What do you understand by *chemical* action? Give examples.

43. How is the chemical distinguished from all other forces?

44. Adduce evidence that elements exist in compounds; that sulphide of iron, for instance, still contains particles of sulphur and iron, though it possesses properties so different from these elements.

45. Define the term atom.

46. What condition is essential for the manifestation of chemical force?

46. Can an atom exist in an uncombined state? and when are the atoms of an element most potent to enter into chemical combination?

48. What is a molecule?

49. How may the results of chemical reactions be expressed on paper?

50. Enumerate the functions of a symbol.

51. Give the additional functions of a chemical formula.

52. Describe by a diagram or an equation the reaction which ensues when red-hot charcoal is plunged into oxygen gas.

53. Draw diagrams representing the formation of P_2O_5, SO_2, and FeI_2 respectively.

54. Enumerate the differences between the physical state of the molecules in a solid, a liquid, and a gas.

55. State the law of constant proportions.

56. State the law of multiple proportions.
57. State the law of reciprocal proportions.
58. Give illustrations of the above laws.
59. Describe the origin and use of the atomic theory.
60. What do you understand by the atomic weight, and the molecular weight of an element?
61. Representing the weight of an atom of hydrogen as 1, what will be the atomic weights of carbon, sulphur, nitrogen, and iodine? Give reasons for considering the stated weights to be correct.
62. In what proportion, by volume, do elements in the gaseous state chemically combine?
63. What relation exists between the volumes of elements in the gaseous state and their atomic weights? Give the explanation for this.
64. Is there any difference between the molecular volume of a simple or of a compound gas?
65. Define isomorphism.
66. Explain the value of isomorphism as evidence of atomic weight.
67. What is to be understood by the quantivalence of an element? Give examples of univalent, bivalent, trivalent, and quadrivalent atoms.
68. How may the quantivalence of an element be expressed in its atomic symbol?
69. Give the formulæ of two or three compounds in which the quantivalence of one atom is saturated by the combined quantivalence of others.

The reader is also recommended to question himself, or be questioned, on the "definitions" given on pages 48 to 50.

THE ELEMENTS AND THEIR COMPOUNDS.

Having thus obtained a general idea of the nature of such elements as have especial interest for the medical and pharmaceutical student, and which indeed are all with which any student of chemistry should at present occupy his attention, we may pass on to consider in detail the relations of the elements to each other. The elements themselves, in the free condition, are seldom used in medicine, being nearly always associated, bound together by the chemical force; in this combined condition, therefore, they must be studied. Each combination of elements or chemical compound will, in the following pages, be regarded as containing two parts or roots, two radicals: the one usually metallic, or, to speak more generally, basylous; the other commonly a non-metallic, simple or complex, acidulous radical. The basylous radicals, or metals, will be considered first, the acidulous radicals afterwards. Each radical will be studied from two points of view, the synthetical and the analytical: that is to say, the properties of an element on which the preparation of its compounds

depends will be illustrated by descriptions of actual experiments (usually performed on a small scale), and thus the chemistry of the Pharmacopœia be systematically learnt; then the reactions by which the element is detected, though combined with other substances, will be performed, and so the student be instructed in qualitative analysis. Synthetical and analytical reactions are, in truth, frequently identical, the object with which they are performed giving them synthetical interest on the one hand, or analytical interest on the other.

A good knowledge of chemistry may be acquired synthetically by preparing considerable quantities of the salts of the different metals, or analytically by going through a course of pure qualitative analysis. But the former plan demands a larger expenditure of time than most students have to spare, while under the latter system they generally lose sight of the synthetical interest which attaches to analytical reactions. Hence the more useful system, now offered, of studying each metal, etc., from both points of view, time being economized by the operator preparing only small specimens of compounds.

Chemical synthesis and analysis, thoughtfully and conscientiously followed, will insensibly carry the principles of chemistry into the mind and fix them there indelibly.

POTASSIUM.

Symbol K. Atomic weight 39.

Formula K_2. Probable molecular weight 78.

Memoranda.—The chief sources of the potassium salts* are the chloride found at Staasfurt, in Prussia, in the form of the mineral *Carnallite* (chloride of potassium 50, chloride of sodium 25, and chloride of magnesia 25, in 100 parts); the nitrate, found in soils, especially in warm countries, and the compounds of potassium existing in plants. The latter, vegetable salts of potassium, are converted into carbonate with some sulphate, etc., when the wood or other parts are burned to ashes. If the ashes be lixiviated with water, and the solution evaporated to dryness, the residue, when fused, constitutes *crude potashes.* The residue, calcined on the hearth of a reverberatory furnace till white, gives the product termed *pearlash* (*Potassii Carbonas Impura*, U. S. P.). Large quantities of carbonate are thus produced in North America and Russia. From the native chloride and from the carbonate purified by treating the pearlash with its own weight of distilled water, filtering and evaporating the solution until it thickens, and stirring constantly "so as to form a granular salt" (*Potassii Carbonas*, U. S. P.), nearly all other compounds of potassium are made. Exceptions occur in cream of tartar (*Potassæ Tartras Acida*, B. P.; *Potassii Bitartras*, U. S. P.), which is simply the purified natural potassium salt of the grape-vine, and in nitrate of potassium. Potassium is a constituent

* The term *salt* includes any definite solid chemical substance, but more especially those which assume a crystalline form.

of between forty and fifty chemical or Galencial preparations of the British Pharmacopœia.

Carbonate of potassium is a white crystalline or granular powder, insoluble in alcohol, very soluble in water, rapidly liquefying in the air through absorption of moisture, alkaline and caustic to the taste. It loses all water at a red heat. *Potassii Carbonas Pura*, U. S. P., is obtained by heating the bicarbonate to redness: the resulting white anhydrous carbonate is converted into hydrous granular carbonate by solution in water and evaporation until a dry granular salt remains.

Preparation.—Potassium itself is isolated with some difficulty by distilling a mixture of its carbonate and charcoal. It rapidly oxidizes in the air, and hence is always kept below the surface of mineral naphtha, a liquid containing no oxygen.

Quantivalence.—The atom of potassium is univalent, K′.

Reactions having (*a*) Synthetical and (*b*) Analytical Interest.

(*a*) *Synthetical Reactions.*

These are actions utilized in manufacturing preparations of potassium. The word *synthesis* is from σύνθεσις (*sūnthĕsis*), a putting together, as opposed to analysis, from ἀναλύω (*analuo*), I resolve.

Hydrate of Potassium. Caustic Potash.

First Synthetical Reaction.—Boil together, for a few minutes, in a test-tube, five or six grains of carbonate of potassium (K_2CO_3) and a like quantity of slaked lime (Ca2HO) with a small quantity of water. Set the mixture aside in the test-tube rack till all solid matter has subsided.

This liquid is a solution of caustic potash, or hydrate of potassium (KHO). Made of a prescribed strength, it forms the *Liquor Potassæ*, B. P. (5.84 per cent.), and U. S. P. (5.8 per cent.).

The mixture is known to be boiled long enough when a little of the clear liquid, poured into another test-tube and warmed, gives no effervescence on the addition of an acid (sulphuric, hydrochloric, or acetic)—a test whose mode of action will be explained hereafter.

Best method of expressing decompositions.—This will be easy of comprehension if what has already been stated concerning symbols and formulæ on pages 27 to 40, has been carefully and thoughtfully considered. The best means of showing on paper the action which occurs when chemical substances attack each other is by the employment either of equations or diagrams. In an *equation* the formulæ of the salts used are written on one line, the sign of addition (+) intervening; the sign of equality (=) follows, and then the formulæ of the salts produced also separated by a plus sign (+). Thus:—

$$K_2CO_3 + Ca2HO = 2KHO + CaCO_3.$$

In this reaction (the operation just performed) the metals of the two salts change places: from K_2CO_3 and Ca2HO there are produced

$CaCO_3$ and KHO (two molecules); from carbonate of potassium and hydrate of calcium there result carbonate of calcium (the insoluble portion) and hydrate of potassium (in solution).

In constructing a *diagram*, or pictorial illustration, of a chemical reaction, first the formulæ of the salts used are written under each other on the left side of a leaf of a note-book; secondly, on the right are written the formulæ of the salts produced; thirdly, the paths which may be supposed to be taken by the respective elements are indicated by the use of brackets and lines, as follows:—



It will be noticed that the only important data required in making either equationary or diagrammatic notes of decompositions are the symbolic formulæ of the various compounds employed or produced. These formulæ are, in this manual, given whenever necessary. (Chemists obtain them in the first instance by the help of quantitative analysis.)

Note on Nomenclature.—Hydrates are bodies indirectly or directly derived from water by one-half of its hydrogen becoming displaced by an equivalent quantity of another radical. Thus, a piece of potassium thrown on to water (HHO) instantly liberates hydrogen, hydrate of potassium (KHO) being formed. The temperature produced at the same time is sufficiently high to cause ignition of the hydrogen, which burns with a purple flame (owing to the presence of a little vapor of potassium), while the hydrate of potassium remains dissolved in the bulk of the water. Water might be termed hydrate of hydrogen.

Explanation.—With regard to the groups of atoms represented by the symbols CO_3 and HO, only a few words need be said here. The former (CO_3) is the grouping (root or radical) found in all carbonates; it is termed the carbonic radical, and is as characteristic of carbonates as potassium (K) is of potassium salts. HO (hydroxyl) is characteristic of all hydrates. CO_3 is a bivalent root, HO univalent; hence CO_3 is found united with two univalent atoms, as in carbonate of potassium, K_2CO_3, or with one bivalent atom, as in carbonate of calcium, $CaCO_3$; and HO is found united in single proportion with univalent atoms as in hydrate of potassium, KHO, or in double proportion with bivalent atoms as in hydrate of calcium, Ca2HO. The quantivalence of a metal has only to be learnt, and the formulæ of its carbonate and hydrate are ascertained without seeing the formula of either. The formulæ of all other metallic salts are constructed on the same principle. But, beyond committing to memory the formulæ and quantivalence of the various groupings characteristic of carbonates, hydrates, nitrates, sulphates, acetates, etc. (see the following Table), special attention should not at present

be devoted to the subject of the constitution of salts, but restricted to what may be called the metallic or basylous side of salts. The formulæ and quantivalence of the chief acidulous groupings referred to and the symbols and quantivalence of allied elementary bodies are included in the following table:—

Formulæ and Quantivalence of Acidulous Radicals.

All chlorides contain	Cl	Univalent radicals.
" bromides "	Br	
" iodides "	I	
" cyanides "	NC	
" hydrates "	HO	
" nitrates "	NO_3	
" chlorates "	ClO_3	
" acetates "	$C_2H_3O_2$	
" oxides "	O	Bivalent radicals.
" sulphides "	S	
" sulphites "	SO_3	
" sulphates "	SO_4	
" carbonates "	CO_3	
" oxalates "	C_2O_4	
" tartrates "	$C_4H_4O_6$	Trivalent radicals.
" citrates "	$C_6H_5O_7$	
" phosphates "	PO_4	
" borates "	BO_3	

Radicals.—The above elements and compounds are termed *radicals*, each being the common *root* (*radix*) in a series of salts. Why compound radicals (as NO_3, SO_4, PO_4, etc.) differ in quantivalence cannot well be explained. Their constituent atoms doubtless always exert the same amount of attractive force, nearly but not quite all this force being exerted in retaining the atoms in one group, and the remainder probably determining the quantivalence. Some of the compound radicals are obtainable in the free state, others have yet to be proved capable of isolated existence.*

Pure Solution of Potash.—Solution of potash generally contains a trace of alumina dissolved from the lime by the hot alkali, but not enough to interfere with the use of the liquid in medicine. If the solution is required for analytical purposes, it may be obtained free from alumina by avoiding the employment of heat, in the manner suggested by Redwood. Half a gallon is made by mixing half a pound of slaked lime with about three pints of water, placing the mixture in a half-gallon bottle (Winchester quart), and adding to it, in small quantities at a time, a solution of half a pound of carbonate of potassium dissolved in the other pint of water, shaking the mixture well for several minutes after each addition. The whole is now set on one side till clear; and then, if a small quantity poured into a

* A few modern authors term these roots *radicles*, a form of the word more usefully expressive of little roots or rootlets.

test-tube and warmed does not effervesce on the addition of hydrochloric acid, the solution is fit for use. If effervescence (carbonic acid gas) occurs, the mixture must be again well shaken. If the lime be good and recently slaked, and the bottle violently shaken once every half-hour, the decomposition will be complete in about ten or twelve hours.

Liquor Potassæ is officially directed to be made as follows:—

Dissolve 1 pound of carbonate of potassium in one gallon of water; heat the solution to the boiling-point in a clean iron vessel, gradually mix with it 12 ounces of slaked lime, and continue the ebullition for ten minutes with constant stirring. Then remove the vessel from the fire; and when by the subsidence of the insoluble matter the supernatant liquor has become perfectly clear, transfer it by means of a siphon or by decantation to a green-glass bottle furnished with an air-tight stopper, and add distilled water, if necessary, to make it correspond with the tests of *specific gravity* and *neutralizing-power*. The method of applying these tests will be explained in subsequent sections.

Solid Potash.—Solution of potash evaporated to dryness in a silver or clean iron vessel and the residue fused and poured into moulds constitutes *Potassa Caustica*, B. P.; *Potassa*, U. S. P. It often contains chloride and sulphates, detected by nitrate of silver and a barium salt, as described subsequently in connection with hydrochloric and sulphuric acids. *Potassa cum Calce*, U. S. P., is a grayish-white powder, made by rubbing together equal weights of solid potash and quicklime.

Sulphurated Potash.

Second Synthetical Reaction.—Into a test-tube put a few grains of carbonate of potassium previously mixed with half its weight of sulphur. Heat the mixture gradually until it ceases to effervesce. The resulting fused mass poured on a slab and quickly bottled is the *Potassa Sulphurata*, Sulphurated Potash, of B. P., or the *Potassii Sulphuretum*, U. S. P.

$$\underset{\text{Carbonate of potassium.}}{3K_2CO_3} + \underset{\text{Sulphur.}}{4S_2} = \underset{\text{Hyposulphite of potassium.}}{K_2S_2O_3} + \underset{\text{Sulphite of potassium.}}{2K_2S_3} + \underset{\text{Carbonic acid gas.}}{3CO_2}$$

As met with in pharmacy this salt is not a single definite chemical compound, but a mixture of several, in short, its chemical character is well indicated by its vague name. When fresh, and if carefully prepared with the official proportions of dry ingredients, it is of the color of liver (whence the old name "liver of sulphur"), and consists, as shown by Watts, of the salts mentioned in the foregoing equation, together with a little undecomposed carbonate of potassium, with perhaps higher sulphides of potassium (K_2S_4 and K_2S_5); but rapidly absorbing oxygen from the air it soon becomes green and yellow, sulphite (K_2SO_3) and sulphate of potassium (K_2SO_4) are formed, and ultimately a useless mass of a dirty-white

color results, consisting of sulphate and hyposulphite, with generally some carbonate of potassium and free sulphur. Moreover, if overheated in manufacture the hyposulphite $4(K_2S_2O_3)$ is decomposed into sulphate $3(K_2SO_4)$ and sulphide (K_2S_3) of potassium. Recently made, "about three-fourths of its weight are dissolved by rectified spirit." It is occasionally employed in the form of ointment.

In preparing large quantities of sulphurated potash, the test-tube is replaced by an earthenware vessel termed a *crucible* (from *crux*, a cross, for originally a cross was impressed upon the melting-pot as used by alchemists and goldsmiths; others derive the word from crux an instrument of torture, the sense here being symbolical).

Heating Crucibles.—Crucibles of a few ounces' capacity may be heated in an ordinary grate-fire. Larger ones require a stove with a good draught—that is, a *furnace*. Even the smaller ones are more conveniently and quickly heated in a furnace. Half-ounce or one ounce experimental porcelain crucibles may be heated in a spirit- or gas-flame; the air gas-flame already described being generally the most suitable.

Acetate of Potassium.

Third Synthetical Reaction.—Place ten or twenty grains or more of carbonate of potassium in a small dish, and *saturate* (*satur*, full) with acetic acid; that is, add acetic acid so long as effervescence is thereby produced; the resulting liquid is a strong solution of acetate of potassium.

Evaporate most of the water, stirring with a glass rod* to promote the evolution of vapor; a white salt remains which fuses on the further application of heat: this is the official Acetate of Potassium (*Potassæ Acetas*, B. P., and *Potassii Acetas*, U. S. P.). If fused in the open vessel the acetate is liable to become slightly charred and discolored; this is prevented by transferring the solid residue to a test-tube or florence flask before finally fusing. It forms a white deliquescent foliaceous satiny mass, neutral to test-paper, and wholly soluble in spirit. A ten per cent. solution in water forms the "Solution of Acetate of Potash," B. P.

$$\underset{\text{Carbonate of potassium.}}{K_2CO_3} + \underset{\text{Acetic acid.}}{2HC_2H_3O_2} = \underset{\text{Acetate of potassium.}}{2KC_2H_3O_2} + \underset{\text{Water.}}{H_2O} + \underset{\text{Carbonic acid gas.}}{CO_2}$$

Explanation of Formulæ.—The formula for one molecule of acetic acid (the acetate of hydrogen) is $HC_2H_3O_2$, and one of acetate of potassium $KC_2H_3O_2$. The grouping, $C_2H_3O_2$, is characteristic of all

* Glass rod is usually purchased in the form of long sticks. The pieces may be cut to convenient lengths of from 6 to 12 inches (*vide* p. 16), sharp ends being rounded off by holding in a flame for a few minutes.

acetates; it is univalent, and may be shortly, though less instructively, written $\overline{A}$.

Explanation of Process.—When two molecules of acetic acid ($2HC_2H_3O_2$) and one of carbonate of potassium (K_2CO_3) react, two molecules of acetate of potassium ($2KC_2H_3O_2$) and one of carbonic acid (H_2CO_3) are produced, the latter at once splitting up into water (H_2O) and carbonic acid gas (CO_2), as already shown in the equation.

Diagram of the Reaction.—The nature of the above operation is indicated by an *equation;* it (and all succeeding reactions) should be expressed in the student's note-book as a *diagram*, similar to that just given in connection with the first synthetical reaction. In constructing a diagram, a little reflection concerning the formulæ of the bodies produced will show how the symbols in the formulæ of the bodies employed are to be arranged on the right-hand side of the brackets.

Evaporation of water from a liquid is best conducted in wide shallow vessels rather than in narrow deep ones, as the steam can thus quickly diffuse into the air and be rapidly conveyed away; hence a small round-bottomed basin is far more suitable than a test-tube for such operations. On the manufacturing scale, iron, or iron lined with enamel, or semiporcelain, copper, tinned copper, or solid tin pans are used. Up to 12 or 18 inches diameter, pans, basins, or dishes, made of Wedgwood ware or porcelain composition, may be employed.

Note.—The above reaction has a general as well as a special synthetical interest. It represents one of the commonest methods of forming salts, namely, the saturation of an acid with a carbonate. Carbonates added to acetic acid yield acetates, to nitric acid, nitrates, to sulphuric acid, sulphates. Many illustrations of this general process occur in pharmacy.

Bicarbonate of Potassium.

Fourth Synthetical Reaction.—Make a *strong* solution of carbonate of potassium by heating in a test-tube a mixture of several grains of the salt with rather less than an equal weight of water. Through the cooled solution pass carbonic acid gas, slowly but continuously; after a time a white crystalline precipitate of Acid Carbonate or Bicarbonate of Potassium ($KHCO_3$), *Potassii Bicarbonas*, U. S. P., the Bicarbonate of Potash of the British Pharmacopœia (*Potassii Bicarbonas*, B. P.), will be formed.

K_2CO_3	+	H_2O	+	CO_2	=	$2KHCO_3$
Carbonate of potassium.		Water.		Carbonic acid gas.		Bicarbonate of potassium.

The carbonic acid gas necessary for this operation is to be prepared from marble, though it might be obtained from any carbonate. Thus the previous synthetical reaction could be made available for

this purpose, the carbonic gas evolved on the addition of the acetic acid to the carbonate of potassium being conducted into a strong solution of more carbonate of potassium by a glass tube bent and fitted as described when treating of oxygen gas. But motives of economy induce the use of carbonate of calcium, the form known as marble being always employed. Economy and convenience also cause hydrochloric acid to be used in preference to acetic or any other.

Generate the carbonic acid gas by adding common hydrochloric acid, diluted with twice its bulk of water, to a few fragments of marble contained in a test-tube or small flask, and conduct the gas into the solution of carbonate of potassium by a glass tube bent to a convenient angle or angles, and fitted to the test-tube by a cork in the usual way. The tube may be replenished with marble or acid or both when the evolution of gas is becoming slow. In working on any larger quantity than a few grains of the carbonate a wide delivery tube should be employed, or the end of the narrow tube occasionally cleared from any bicarbonate that may have been deposited in it. The more economical official arrangements of the apparatus employed in this process will be described under the corresponding sodium salt.

Deposition of the Bicarbonate explained.—Bicarbonate of potassium is to a certain extent soluble in water; but as it is less so than the carbonate of potassium, and as a *saturated* solution of the latter has been used, the precipitation of a part of the bicarbonate inevitably occurs. In other words, the quantity of water present is sufficient to keep the carbonate, but insufficient to retain the equivalent quantity of bicarbonate in solution.

Properties.—Prepared on the large scale, bicarbonate of potassium occurs in colorless, non-deliquescent, right rhombic prisms; it has a saline, feebly alkaline, non-corrosive taste.

Effervescing Solution of Potash.—A solution of 30 grains of bicarbonate of potassium in one pint of water, charged with 7 times its bulk (often less) of carbonic acid gas by pressure, constitutes the ordinary "potash-water," the so-called *Liquor Potassæ Effervescens*, B. P.

Notes on Nomenclature.—The prefix *bi-* in the name "bicarbonate of potassium," serves to recall the fact that to a given amount of potassium this salt contains *twice* as much carbonic radical as the carbonate. The salt is really a "carbonate of potassium and hydrogen" ($KHCO_3$); it is intermediate between carbonate of potassium (K_2CO_3) and carbonate of hydrogen, or true carbonic acid (H_2CO_3); it is "acid carbonate of potassium" or "hydric potassium carbonate;" chemically, though not physically, it is an acid salt.

Salts whose specific names end in the syllable "*ate*" (carbon*ate*, sulph*ate*, etc.) are in general conventionally so termed when they

contain an acidulous radical, or the characteristic elements of an acid, whose name ends in "*ic*," and from which acid they have been or may be formed. Thus the syllable "*ate*," in the words sulph*ate*, nitr*ate*, acet*ate*, carbon*ate*, etc., indicates that the respective salts contain a radical whose name ended in *ic*, the previous syllables, sulph-, nitr-, acet-, carbon-, indicating what that radical was—the sulphuric, nitric, acetic, or carbonic. Occasionally a letter or syllable is dropped from or added to a word to render the name more euphonious; thus the sulphuric radical forms sulphates, not sulphurates.

Citrate of Potassium.

Fifth Synthetical Reaction.—Dissolve a few grains or more of citric acid ($H_3C_6H_5O_7$) in water, and add carbonate (bicarbonate, U. S. P.) of potassium until it no longer causes effervescence, and the solution after well stirring is neutral or faintly acid to test paper. The resulting liquid is a solution of citrate of potassium ($K_3C_6H_5O_7$) *Liquor Potassii Citratis*, U. S. P.). Evaporated to dryness, in an open dish, a pulverulent or granular residue is obtained, which is the official *Potassii Citras*, U. S. P., a white deliquescent powder.

$$\underset{\text{Carbonate of potassium.}}{3K_2CO_3} + \underset{\text{Citric acid.}}{2H_3C_6H_5O_7} = \underset{\text{Citrate of potassium.}}{2K_3C_6H_5O_7} + \underset{\text{Water.}}{3H_2O} + \underset{\text{Carbonic acid gas.}}{3CO_2}$$

Citrates.—The citric radical or group of elements, which with three atoms of hydrogen forms a molecule of citric acid, and with three of potassium citrate of potassium, is a trivalent grouping; hence the three atoms of potassium in a molecule of the citrate. The full chemistry of citric acid and other citrates will be subsequently described.

Nitrate of potassium (KNO_3) (*Potassii Nitras*, U. S. P.) and *Sulphate of potassium* (K_2SO_4) (*Potasii Sulphas*, U. S. P.) could obviously also be made by saturating nitric acid (HNO_3), and sulphuric acid (H_2SO_4), respectively, by carbonate of potassium. Practically they are not made in that way—the nitrate occurring, as already stated, in nature, and the sulphate as a by-product in many operations. Both salts will be hereafter alluded to in connection with nitric acid.

Tartrate of Potassium.

Sixth Synthetical Reaction.—Place a few grains of carbonate of potassium in a test-tube with a little water, heat to the boiling-point, and then add acid tartrate of potassium ($KHC_4H_4O_6$ or $KH\overline{T}$) till there is no more effervescence, and the solution is neutral to test-paper; a solution of neutral tartrate of potassium ($K_2\overline{T}$) results, the *Potassii*

Tartras of the United States Pharmacopœia. Crystals (4- or 6-sided prisms) may be obtained on concentrating the solution by evaporation and setting the hot liquid aside. Larger quantities are made in the same way, 20 of acid tartrate and 9 of carbonate (with 50 of water) being about the proportions necessary for neutrality.

$$\underset{\text{Acid tartrate of potassium.}}{2KHC_4H_4O_6} + \underset{\text{Carbonate of potassium.}}{K_2CO_3} = \underset{\text{Neutral tartrate of potassium.}}{2K_2C_4H_4O_6} + \underset{\text{Water.}}{H_2O} + \underset{\text{Carbonic acid gas.}}{CO_2}$$

Tartrates.—$C_4H_4O_6$ are the elements characteristic of all tartrates; they form a bivalent grouping; hence the formula of the hydrogen tartrate, or tartaric acid, is $H_2C_4H_4O_6$; that of the potassium tartrate $K_2C_4H_4O_6$; of the intermediate salt, the acid potassium tartrate (cream of tartar), $KHC_4H_4O_6$. If the acid tartrate of one metal and the carbonate of another react, a neutral dimetallic tartrate results, as seen in Rochelle salt ($KNaC_4H_4O_6$), the Soda Tartrate of the British Pharmacopœia. (*Potassii et Sodii Tartras*, U. S. P.)

Acid salts (*e. g.* $KHC_4H_4O_6$), that is, salts intermediate in composition between a normal or neutral salt (*e. g.* $K_2C_4H_4O_6$) and an acid (*e. g.* $H_2C_4H_4O_6$) will frequently be met with. All acidulous radicals, except those which are univalent, may be concerned in the formation of acid salts.

Iodide of Potassium.

Seventh Synthetical Reaction.—To a solution of potash, heated in a test-tube, flask, or evaporating-basin, according to quantity, add a small quantity of solid iodine. The deep color of the iodine disappears entirely. This is due to the formation of the colorless salts, iodide of potassium (KI) and iodate of potassium (KIO_3), which remain dissolved in the liquid. Continue the addition of iodine so long as its color, after a few minutes' warming and stirring, disappears. When the whole of the potash in the solution of potash has been converted into the salts mentioned, the slight excess of iodine remaining in the liquid will color it, and thus show that this stage of the operation is completed.

$$\underset{\text{Hydrate of potassium.}}{6KHO} + \underset{\text{Iodine.}}{3I_2} = \underset{\text{Iodide of potassium.}}{5KI} + \underset{\text{Iodate of potassium.}}{KIO_3} + \underset{\text{Water.}}{3H_2O}$$

Separation of the Iodide from the Iodate.—Evaporate the above solution to dryness. If both salts were required, the solid mixture might be digested in spirits of wine, which dissolves the iodide, but not the iodate. But the iodide only is used in medicine. Mix the residue, therefore (re-

serving a grain or two for a subsequent experiment), with about a twelfth of its weight of charcoal, and gently heat in a test-tube or crucible until slight deflagration ensues.*

$$\underset{\text{Iodide of potassium.}}{2KIO_3} + \underset{\text{Carbon.}}{3C_2} = \underset{\text{Iodide of potassium.}}{2KI} + \underset{\text{Carbonic oxide.}}{6CO}$$

Under these circumstances the iodide remains unaffected, but the iodate loses all its oxygen, and is thus also reduced to the state of iodide. Treat the mass with a little water, and filter to separate excess of charcoal; a solution of pure iodide of potassium results. It may be used as a reagent or evaporated to a small bulk, and set aside to crystallize.

This is the process mentioned in the British and United States Pharmacopœias (*Potassii Iodidum*). "Solution of Iodate of Potassium," is also official as a test-liquid.

Properties. — Iodide of Potassium crystallizes in small cubical crystals, very soluble in water, less so in spirit. One part in ten of water forms "Solution of Iodide of Potassium," B. P.

The addition of charcoal in the above process is simply to facilitate the removal of the oxygen of the iodate of potassium. Iodate of potassium (KIO_3) is analogous in constitution, and in composition, so far as the atoms of oxygen are concerned, to chlorate of potassium ($KClO_3$), which has already been stated to be more useful than any other salt for the actual preparation of oxygen gas itself. Hence the removal of the oxygen of the iodate might be accomplished by heating the residue without charcoal. In that case the liberated oxygen would be detected on inserting the incandescent extremity of a strip of wood into the mouth of the test-tube in which the mixture of iodide and iodate had been heated. The charcoal, however, burns out the oxygen more quickly, and thus economizes heat and time.

Note.—The formula of iodide of potassium (KI) shows that the salt contains potassium and iodine in atomic proportions. A reference to the table of atomic weights at the end of the volume, and a rule-of-three sum, would therefore show what weight of salt is producible from any given weight of iodine.

Detection of Iodate in Iodide of Potassium.—Iodate of potassium remaining as an impurity in iodide of potassium

* Deflagration means violent burning, from *flagratus*, burnt (*flagro*, I burn), and *de*, a prefix augmenting the sense of the word to which it may be attached. Paper thrown into a fire simply burns, nitre deflagrates. *De*-tonate (*detono*) is a precisely similar word, meaning to explode with violent noise.

If, in the operation of heating iodate of potassium with charcoal, excess of the latter be employed, slight incandescence rather than deflagration occurs; if the charcoal be largely in excess, the reduction of the iodate to iodide of potassium is effected without visible deflagration or even incandescence.

may be detected by adding to a solution of the latter salt some tartaric acid, shaking, and then adding mucilage of starch; blue "iodide of starch" is formed if a trace of iodate be present, but not otherwise. The tartaric acid liberates iodic acid (HIO_3) from the iodate of potassium and hydriodic acid (HI) from the iodide of potassium; neither acid alone attacks starch, but by reaction on each other the two give rise to free iodine which then forms the blue color. This experiment should be tried on a sample of pure iodide of potassium and on a grain or two of the impure iodide reserved from the previous experiment.

$$HIO_3 + 5HI = 3H_2O + 3I_2.$$

Note on Nomenclature.—The syllable *ide* attached to the syllable *iod*, in the name "iodide of potassium," indicates that the element *iodine* is combined with the potassium. An iod*ate*, as already explained, is a salt containing the characteristic elements of iod*ic* acid and all iodic compounds. Salts one of whose names ends in *ide* are those which are, or may be, formed from elements. The names of salts which are, or may be, formed from compounds include other syllables, *ate* being one (see page 59). The only other syllable is *ite*, which is included in the names of salts which are, or may be, formed from acids and radicals whose names end in *ous:* thus hyposulph*ite* of sodium, etc. To recapitulate: A salt, whose name ends in *ate* contains a compound acidulous radical whose name ends in *ic;* a salt whose name ends in *ite* contains a compound acidulous radical whose name ends in *ous;* a salt whose name ends in *ide* contains an element for its acidulous radical. Thus sulph*ide* relates to sulphur, sulph*ite* to the sulphurous radical, sulph*ate* to the sulphuric radical, and so on with other "ides," "ites," or "ates."

Bromide of Potassium (*Potassii Bromidum*, B. P.).—This salt is identical in constitution with iodide of potassium, and may be made in exactly the same way, bromine being substituted for iodine. The formula of bromic acid is $HBrO_3$. It will be noticed that the following equations are similar in character to those showing the preparation of iodide of potassium.

$$\underset{\text{Hydrate of potassium.}}{6KHO} + \underset{\text{Bromine.}}{3Br_3} = \underset{\text{Bromide of potassium.}}{5KBr} + \underset{\text{Bromate of potassium.}}{KBrO_3} + \underset{\text{Water.}}{3H_2O}$$

$$\underset{\text{Bromate of potassium.}}{2KBrO_3} + \underset{\text{Carbon.}}{3C_2} = \underset{\text{Bromide of potassium.}}{2KBr} + \underset{\text{Carbonic oxide.}}{6CO}$$

Potassii Bromidum, U. S. P., is made by decomposing solution of bromide of iron (FeI_2) by solution of pure carbonate of potassium (K_2CO_3), evaporating, and crystallizing.

Manganates of Potassium.

Eighth Snythetical Reaction.—Place a fragment of solid caustic potash (KHO), with about the same quantity of

chlorate of potassium ($KClO_3$), and of black oxide of manganese (MnO_2), on a piece of platinum foil.* Hold the foil by a small pair of forceps or tongs in the flame of a blow-pipe for a few minutes until the fused mixture has become dark green. This color is that of *manganate of potassium* (K_2MnO_4).

$$\underset{\text{Hydrate of potassium.}}{6KHO} + \underset{\text{Chlorate of potassium.}}{KClO_3} + \underset{\text{Black oxide of manganese.}}{3MnO_2} = \underset{\text{Manganate of potassium.}}{3K_2MnO_4} + \underset{\text{Chloride of potassium.}}{KCl} + \underset{\text{Water.}}{3H_2O}$$

Ninth Synthetical Reaction.—Permanganate of Potassium ($K_2Mn_2O_8$) (*Potassii Permanganas*, U. S. P.), which is purple, is obtained, or rather a solution of it, on placing the foil and its adherent mass in water, and boiling for a short time.

$$\underset{\text{Manganate of potassium.}}{3K_2MnO_4} + \underset{\text{Water.}}{2H_2O} = \underset{\text{Permanganate of potassium.}}{K_2Mn_2O_8} + \underset{\text{Hydrate of potassium.}}{4KHO} + \underset{\text{Black oxide of manganese.}}{MnO_2}$$

On the large scale, the potash set free in the reaction is neutralized by sulphuric or carbonic acid, and the solution evaporated to the crystallizing point. Further details will be given in connection with manganese.

Solutions of manganate or permanganate of potassium and of sodium so readily yield their oxygen to organic matter, that they are used on the large scale as disinfectants, under the name of "Condy's Disinfecting Fluids."

Synthetical Reactions bringing under consideration the remaining official compounds (namely, bichromate, arsenite, chlorate, cyanide, ferrocyanide, and ferridcyanide of potassium) are deferred at present.

(*b*) *Reactions having Analytical Interest* (*Tests*).

Note.—These are reactions utilized in searching for small quantities of a substance (in the present instance of potassium) in a solution. They are best performed in test-tubes or other small vessels. Each should be expressed, in the form of an equation or diagram, in the student's note-book. *All previous or future equations given in this volume should be transferred to the note-book in the form of diagrams similar to that given on page* 54.

First Analytical Reaction.—To a solution of any salt of

* The foil may be 1 inch broad by 2 long. No ordinary flame will melt, or common chemical substance attack platinum; hence the same piece may be used in experiments over and over again. Metals form a fusible alloy with platinum, and phosphorus rapidly attacks it, hence such substances, as well as mixtures likely to yield them, should be heated in a small porcelain crucible.

potassium (chloride,* for example) add solution of perchloride of platinum ($PtCl_4$), and stir the mixture with a glass rod; yellow double chloride of platinum and potassium ($PtCl_4 2KCl$) will be precipitated.†

Explanation.—The precipitate is, practically, insoluble in water. It is for this reason that a very small quantity of any soluble potassium salt (or, rather, of the potassium in that salt) is thrown out of solution by perchloride of platinum.

Precaution.—Only chloride of potassium forms this characteristic compound; hence, if the potassium salt in the solution is known not to be a chloride, or if its composition is unknown, a few drops of hydrochloric acid must be added, otherwise some of the perchloride of platinum will be utilized for its chlorine only, the platinum being wasted. Thus, if nitrate of potassium (KNO_3) be present, a few drops of hydrochloric acid enable the potassium to assume the form of chloride when the perchloride of platinum is added, nitric acid (HNO_3) being set free.

Memoranda.—Experiments with such expensive reagents as perchloride of platinum are economically performed in watch-glasses, drops of the liquids being operated on. When the precipitate is long in forming, it is sometimes of an orange-yellow tint. If iodide of potassium happen to be the potassium salt under examination, some iodide of platinum (PtI_4) will also be formed, giving a red color to the solution, and a larger quantity of the *precipitant* (that is, the precipitating agent) be required.

Note on Nomenclature.—When distinct molecules of salts unite and form a single crystalline compound, the product is termed a *double* salt. The double chloride of potassium and platinum is such a body.

Acid Tartrate of Potassium.

Second Analytical Reaction.—To a solution of any salt of potassium add some strong solution of tartaric acid ($H_2C_4H_4O_6$), and shake or well stir the mixture; a white granular precipitate of acid tartrate of potassium ($KHC_4H_4O_6$) will be formed.

Limits of the Test.—Acid tartrate of potassium is soluble in about 180 parts of cold and in 6 parts of boiling water. Hence, in applying the tartaric test for potassium, the solutions must not be hot. Even if cold, no percipitate will be obtained if the solutions are very dilute. This test, therefore, is of far less value than the first mentioned. The

* A few fragments of carbonate of potassium, two or three drops of hydrochloric acid, and a small quantity of water, give a solution of chloride of potassium at once, $K_2CO_3+2HCl=2KCl+H_2O+CO_2$.

† By *precipitation* (from *præcipito*, to throw down suddenly) is simply meant the formation of particles of solid in a liquid, no matter whether the solid, the *precipitate*, subsides or floats.

acid tartrate of potassium is less soluble in diluted alcohol than in water; so that the addition of spirit of wine renders the reaction somewhat more delicate.

Cream of Tartar.—The precipitate is the *Bitartrate or Acid Tartrate of Potassium*, though the official preparation is not formed in the above manner; on the contrary, the acid is derived from the salt, which occurs naturally in the juice of many plants.

Memorandum.—When the tartaric acid is added to the salt of potassium, and the acid tartrate formed, the acid whose chief elements were previously with the potassium is set free; and in such acid solutions the acid tartrate is somewhat soluble. To prevent loss on this account, acid tartrate of sodium, a salt tolerably soluble in water, may be used as a test instead of tartaric acid (Plunkett). The sodium uniting with the acidulous radical, thus gives a neutral instead of an acid solution. But this advantage is of less importance from the fact that more water is introduced by the saturated solution of acid tartrate of sodium than by a saturated solution of tartaric acid.

Third Analytical Reaction.—The *flame-test.* Dip the looped end of a platinum wire into a solution containing a potassium salt, and introduce the loop into a spirit-flame, the flame of a mixture of gas and air, a blowpipe flame, or other slightly colored flame. A light violet or lavender tint will be communicated to the flame, an effect highly characteristic of salts of potassium.

Fourth Analytical Fact.—Salts of potassium are not volatile. Place a fragment of carbonate, nitrate, or any other potassium salt, on a piece of platinum foil, and heat the latter in the flame of a lamp; the salt may fuse to a transparent liquid and flow freely over the foil, water also if present will escape as steam, and black carbon be set free if the salt happen to be of vegetable origin; but the potassium compound itself will not be vaporized. This is a valuable negative property, as will be evident when the analytical reactions of ammonium come under notice.

QUESTIONS AND EXERCISES.

70. Name the sources of Potassium.

71. Give the source, formula, and characters of Carbonate of Potassium.

72. Distinguish between synthetical and analytical reactions.

73. How is the official *Liquor Potassæ* prepared?

74. What is the systematic name of Caustic Potash?

75. State the chemical formula of Caustic Potash.

76. Construct an equation or diagram expressive of the reaction between carbonate of potassium and slaked lime.

77. Define a *hydrate.*
78. What group of atoms is characteristic of all carbonates?
79. Define the term *radical.*
80. How is "Sulphurated Potash" made, and of what salts is it a mixture?
81. What is the formula of the acetic radical—the radical of all acetates?
82. Draw a diagram showing the formation of Acetate of Potassium.
83. Give a general process for the conversion of carbonates into other salts.
84. What is the difference between Carbonate and Bicarbonate of Potassium? How is the latter prepared?
85. What is the relation between salts whose specific names end in the syllable "*ate*," and acids ending in "*ic*"?
86. Draw out diagrams or equations descriptive of the formation of Tartrate of Potassium from the Acid Tartrate, and Citrate from the Carbonate of Potassium.
87. Distinguish between a normal and an acid salt.
88. How is Iodide of Potassium made? Illustrate the process by either diagrams or equations.
89. Describe the appearance and chemical properties of iodide of potassium.
90. How much Iodide of Potassium is producible from 1000 grains of Iodine? Ans. 1307 grains.
91. Give a method for the detection of iodate in iodide of potassium. Explain the reaction.
92. Has the syllable "*ide*" any general signification in chemical nomenclature?
93. What is the difference between sulphides, sulphites, and sulphates?
94. Mention the chemical relations of Bromide to Iodide of Potassium.
95. Describe the formation of Permanganate of Potassium, giving equations or diagrams.
96. How do manganate and permanganate of potassium act as disinfectants?
97. Enumerate the tests for potassium, explaining by diagrams or equations the various reactions which occur.

SODIUM.

Symbol Na. Atomic weight 23.

Formula Na_2. Probable molecular weight 46.

Memoranda.—Most of the sodium salts met with in Pharmacy are directly obtained from carbonate of sodium, which is now manufactured on an enormous scale from chloride of sodium (common salt, sea-salt or bay-salt, or rock-salt), the natural source of the sodium salts. When pure, salt (*Sodii Chloridum*, B. P. and U. S. P.) occurs "in small white crystalline grains, or transparent cubic crys-

tals, free from moisture;" the best varieties commonly contain a little chloride of magnesium and sometimes other impurities. Besides the direct and indirect use of carbonate of sodium, or carbonate of soda, as it is commonly called in medicine, it is largely used for household cleansing-purposes under the name of "soda," and in the manufacture of soap. Nitrate of sodium also occurs in nature, but is valuable for its nitric constituents rather than its sodium. Sodium is a constituent of about forty chemical or Galenical preparations of the Pharmacopœias.

Sodium is prepared by a process similar to that for potassium, but with less difficulty. Its atom is univalent, Na′.

Reactions having (*a*) Synthetical and (*b*) Analytical Interest.

(*a*) *Reactions having Synthetical Interest.*

Hydrate of Sodium. Caustic Soda.

First Synthetical Reaction.—The formation of solution of hydrate of sodium or caustic soda, NaHO (*Liquor Sodæ*, B. P. and U. S. P.). This operation resembles that of making solution of potash already described.

The practical student should refer to the remarks made concerning solution of potash, applying them to solution of soda. He may perform the corresponding experiments or omit them, as he considers he does or does not clearly comprehend all they are designed to teach.

Na_2CO_3	+	Ca2HO	=	2NaHO	+	$CaCO_3$
Carbonate of sodium.		Hydrate of calcium.		Hydrate of sodium.		Carbonate of calcium.

Pure Solution of Soda, free from any trace of alumina, may be prepared by shaking in a Winchester quart, once every 20 or 30 minutes for 5 or 6 hours, 14 ozs. of crystals of carbonate of sodium and 8 ozs. of good recently slaked lime. The official *Liquor Sodæ* is made from 28 ounces of crystals of carbonate of sodium, 12 of slaked lime, and 1 gallon of water, under precisely similar circumstances to those detailed for *Liquor Potassæ* (p. 56). If the solution be evaporated to dryness, and the residue fused and poured into moulds, solid hydrate of sodium (*Soda Caustica*, B. P., *Soda*, U. S. P.) is obtained. Common and cheap caustic soda is now largely employed in manufactures. It is a by-product in the preparation of carbonate of sodium, and, though highly useful as a chemical agent, is too impure for use in medicine.

Action of Sodium on Water.—Sodium, like potassium, decomposes water with production of hydrate of sodium and hydrogen, but, unless the sodium is confined to one spot, by placing it on a small floating piece of filter-paper, the action is not sufficiently intense to cause ignition of the escaping hydrogen. When the latter does ignite, it burns with a yellow flame, due to the presence of a little vapor of sodium.

Second Synthetical Reaction.—The reaction of sulphur and carbonate of sodium at a high temperature resembles that of sulphur and carbonate of potassium; but, as the product is not used in medicine, the experiment may be omitted. It is mentioned here to draw attention to the close resemblance of the potassium salts to those of sodium.

Acetate of Sodium.

Third Synthetical Reaction.—Add the powder or fragments of carbonate of sodium (Na_2CO_3) to some strong acetic acid in a test-tube or evaporating-basin as long as effervescence occurs, and then evaporate some of the water.* When the solution is cold, crystals of acetate of sodium ($NaC_2H_3O_2,3H_2O$) (*Sodii Acetas*, U. S. P.) will be deposited. A ten per cent. solution in distilled water forms the "Solution of Acetate of Soda," B. P.

$$\underset{\text{Carbonate of sodium.}}{Na_2CO_3} + \underset{\text{Acetic acid.}}{2HC_2H_3O_2} = \underset{\text{Acetate of sodium.}}{2NaC_2H_3O_2} + \underset{\text{Water.}}{H_2O} + \underset{\text{Carbonic acid gas.}}{CO_2}$$

Bicarbonate of Sodium.

Fourth Synthetical Reaction.—The action of carbonic acid (H_2CO_3), or carbonic acid gas (CO_2) and water (H_2O), on carbonate of sodium (Na_2CO_3). This resembles that of carbonic acid on carbonate of potassium, but is applied in a different manner. The result is bicarbonate of sodium ($NaHCO_3$) (*Sodii Bicarbonas Venalis*, U. P. S.).

$$\underset{\text{Carbonate of sodium.}}{Na_2CO_3} + \underset{\text{Water.}}{H_2O} + \underset{\text{Carbonic acid gas.}}{CO_2} = \underset{\text{Bicarbonate of sodium.}}{2NaHCO_3}$$

Process.—Heat crystals of carbonate of sodium in a porcelain crucible until no more steam escapes. Mix the product, in a mortar, with two-thirds its weight of crystals, and place the powder in a test-tube or small bottle into which carbonic acid gas may be conveyed by a tube passing through a cork and terminating at the bottom of the vessel. To generate the carbonic acid gas fill a test-tube having a small hole in the bottom (or a similar piece of glass tubing, of which one end is plugged by a grooved cork) with fragments of marble, insert a cork and delivery-tube, and connect the latter with the similar tube of the

* The "water" alluded to occurs in the acid, which, though commonly termed "acetic acid," is really a solution of that acid in water.

vessel containing the carbonate of sodium by a piece of India-rubber tubing. Now plunge the tube of marble into a test-glass, or other vessel, containing a mixture of one part hydrochloric acid and two parts water, and loosen the cork of the carbonate-of-sodium tube until carbonic acid gas, generated in the marble tube, may be considered to fill the whole arrangement; then replace the cork tightly and set the apparatus aside. As the gas is absorbed by the carbonate of sodium, hydrochloric acid rises into the marble tube, generates fresh gas, which, in its turn, drives back the acid liquid, and thus prevents the production of any more gas until further absorption has occurred. When the salt is wholly converted into bicarbonate ($NaHCO_3$), it will be found to have become damp through the liberation of water from the crystallized carbonate (Na_2CO_3, $10H_2O$). (It would be inconveniently moist, even semi-fluid, if a part of the carbonate had not previously been rendered anhydrous.) The *Sodii Bicarbonas*, U. S. P., is the commercial bicarbonate purified from any carbonate or traces of other salts by introducing it into a percolator and passing water through it till the washings cease to precipitate a solution of sulphate of magnesium, the bicarbonate of sodium is then removed from the percolator and dried on bibulous paper in a warm place.

A *crystal* of carbonate of sodium is carbonate of sodium plus water; on heating it, more or less of the water is evolved, and *anhydrous* carbonate of sodium is partially or wholly produced (*Sodii Carbonas Exsiccata*, U. S. P.).

$$\underset{\text{Crystallized carbonate of sodium.}}{Na_2CO_3,10H_2O} \quad - \quad \underset{\text{Water.}}{10H_2O} \quad = \quad \underset{\text{Dried carbonate of sodium.}}{Na_2CO_3}$$

Note on Nomenclature.—*Anhydrous* bodies (from ἀ, *a*, and ὕδωρ, *hudōr*, i. e. without water) are compounds from which water has been taken, but whose essential chemical properties are unaltered. Salts containing water are *hydrous* bodies; of these the larger portion are crystalline, and their water is then termed *water of crystallization*. Non-crystalline *hydrous* compounds were formerly spoken of as *hydrated* substances; *hydrates* are, however, a distinct class of bodies, salts derived from water by one-half of its hydrogen becoming displaced by an equivalent quantity of another radical. *Anhydrides* are compounds from which the elements of water have been removed, their essential chemical (acid) properties being thereby greatly altered. (For illustrations, see Index, "Anhydrides.")

Water of Crystallization.—The water in crystallized carbonate of sodium is in the solid condition, and, like ice and other fusible substances, requires heat for its liquefaction. Many salts (freezing-

mixtures), when dissolved in water, give a very cold solution. This is because they and their solid water, if they have any, are then converted into liquids which absorb heat from surrounding media. Take away from water some of its heat, the result is ice. Give to ice (at 32° F.) more heat than it contains already, the result is water (still at 32° F.). (Heat thus taken into a substance without increasing its temperature is said to become *latent*—from *latens*, hiding; it is no longer discoverable by the sense of touch or the thermometer. The term *latent* gives a somewhat incorrect idea, however, of the process; for our knowledge of the extent and readiness with which one form of force is convertible into another renders highly probable the assumption that heat is in these cases converted into motion, the latter enabling the particles of a solid to take up the new positions demanded by their liquid condition.) The only apparent difference between ice and the water in such crystals as carbonate of sodium is that ice is solid water in the free, and water of crystallization solid water in the combined state. The former can only exist at and below freezing, the latter at ordinary temperatures. In chemical formulæ, the symbols representing water are usually separated by a comma from those representing salts. The crystals of acetate of sodium (of the third reaction) contain water in this loose state of combination—water of crystallization ($NaC_2H_3O_2,3H_2O$).

"*Soda-water.*"—A solution of bicarbonate of sodium in water charged with carbonic acid gas under pressure constitutes the official *Liquor Sodæ Effervescens*, B. P., and, like the "potash-water" of the shops, is a true medicine, an antacid. Ordinary "soda-water," however, is in many cases simply a solution of carbonic acid gas in water, and would be more appropriately termed "aërated water": any medicinal effect it may possess is due to the sedative influence of its carbonic acid gas on the coats of the stomach. At common temperatures water dissolves about its own volume of carbonic acid gas, both being under equal pressure. One pint of the official soda-water contains 30 grains of bicarbonate of sodium and a pint of carbonic acid gas; but the solution is under a pressure of seven atmospheres, so that seven pints of the gas at ordinary atmospheric pressure are required for the quantity mentioned.

Solubility of Gases in Water.—Whatever the weight and volume of a gas dissolved by a liquid at ordinary atmospheric pressure, that weight is doubled by double pressure, the two volumes of gas thereby being reduced to one, trebled at treble pressure, the three volumes of gas being reduced to one, quadrupled at quadruple pressure, the four volumes of gas being reduced to one, and so on. This is a general law regarding the solubility of gases in liquids under given temperatures. An average bottle of "soda-water" contains about four times the weight of carbonic acid gas which can exist in it without artificial pressure, so that on removing its cork three times its bulk escape, its own bulk remaining dissolved.

Bicarbonate of sodium may also be medicinally administered in the form of lozenge (*Trochisci Sodii Bicarbonatis*, U. S. P.).

Tartrate of Potasium and Sodium.

Fifth Synthetical Reaction.—To some hot strong solution of carbonate of sodium in a test-tube or larger vessel add acid tartrate of potassium till no more effervescence occurs (about three parts to four will be required); when the solution is cold, crystals of double tartrate of potassium and sodium (*Soda Tartarata*, B. P., *Potassii et Sodii Tartras*, U. S. P.), the old *Rochelle Salt*, will be deposited. ($KNaC_4H_4O_6,4H_2O$). The crystals are usually halves of right rhombic prisms.

$$\underset{\text{Carbonate of sodium.}}{Na_2CO_3} + \underset{\text{Acid tartrate of potassium.}}{2KHC_4H_4O_6} = \underset{\text{Double tartrate of potassium and sodium.}}{2KNaC_4H_4O_6} + \underset{\text{Water.}}{H_2O} + \underset{\text{Carbonic acid gas.}}{CO_2}$$

Formulæ of Tartrates.

Tartaric acid	$HH\ C_4H_4O_6$
Acid tartrate of potassium . . .	$KH\ C_4H_4O_6$
Tartrate of potassium and sodium .	$KNaC_4H_4O_6$

Very close analogy will be noticed in the constitution of these salts. When the other tartrates come under notice it will be found they also have a similar constitution.

Hypochlorite of Sodium.

Sixth Synthetical Reaction.—Pass chlorine (*vide* page 24) into a solution of carbonate of sodium. The result is a bleaching and disinfecting liquid, which, when made of prescribed strength (12 ounces of carbonate in 36 of water, charged by the washed chlorine from 15 fluidounces of hydrochloric acid and 4 ounces of black oxide of manganese), is the Solution of Chlorinated Soda (*Liquor Sodæ Chloratæ*) of the British Pharmacopœia. It is said to contain chloride of sodium (NaCl) and hypochlorite of sodium (NaClO), with some undecomposed bicarbonate of sodium.

$$\underset{\text{Blk. oxide of manganese.}}{MnO_2} + \underset{\text{Hydrochloric acid.}}{4HCl} = \underset{\text{Chloride of manganese.}}{MnCl_2} + \underset{\text{Water.}}{2H_2O} + \underset{\text{Chlorine.}}{Cl_2}$$

$$\underset{\text{Carbonate of sodium.}}{Na_2CO_3} + \underset{\text{Chlorine.}}{Cl_2} = \underset{\text{Chlorinated soda.}}{NaCl,NaClO} + \underset{\text{Carbonic acid gas.}}{CO_2}$$

Liquor Sodæ Chlorinatæ, U. S. P., is made by decomposing solution of carbonate of sodium by solution of chlorinated lime, sp. gr. 1.045.

$$\underset{\text{Carbonate of sodium.}}{2Na_2CO_3} + \underset{\text{Chlorinated lime.}}{CaCl_2,Ca2ClO} = \underset{\text{Chlorinated soda.}}{2(NaCl,NaClO)} + \underset{\text{Carbonate of calcium.}}{2CaCO_3}$$

Other Sodium Compounds.

Synthetical Reactions portraying the chemistry of the remaining official compounds (namely, nitrate, sulphate, hyposulphite, borate, arseniate, and valerianate of sodium) are deferred until the several acidulous radicals of these salts have been described.

Phosphate of Sodium.—The preparation and composition of this salt will be most usefully studied after bone-ash, the source of it and other phosphates, has been described. Bone-ash is phosphate of calcium (see page 94).

The official Citro-Tartrate (*Sodæ Citro-tartras Effervescens*, B. P.) is a mixture of bicarbonate of sodium (17 parts), citric acid (6), and tartaric acid (8), heated (to 200° or 220°) until the particles aggregate to a granular condition. When required for medicinal use, a dose of the mixture is placed in water; escape of carbonic acid gas at once occurs, and an effervescing liquid results.

Soda Powders (*Pulveres Effervescentes*, U. S. P.) are formed of 30 grains of bicarbonate of sodium and 25 of tartaric acid, wrapped separately in papers of different color. When mixed with water, tartrate of sodium results, a little bicarbonate also remaining.

In the manufacture of Carbonate of Sodium from chloride, the latter is first converted into sulphate, the sulphate is then roasted with coal and limestone, and the resulting *black-ash* lixiviated (*lixivia*, from *lix*, lye—water impregnated with alkaline salts: hence *lixiviation*, the operation of washing a mixture with the view of dissolving out salts). The lye, evaporated to dryness, yields crude carbonate of sodium (soda-ash). This process will be further described in connection with Carbonates.

Deliquescence and Efflorescence.—The carbonates of sodium and potassium, chemically closely allied, are readily distinguished physically. Carbonate of potassium quickly absorbs moisture from the air and becomes damp, wet, and finally fluid—it is *deliquescent* (*deliquescens*, melting away). Carbonate of sodium, on the other hand, yields some of its water of crystallization to the air, the crystals becoming white, opaque, and pulverulent—it is *efflorescent* (*efflorescens*, blowing as a flower).

Analogy of Sodium salts to Potassium salts.—Other synthetical reactions might be described similar to those given under potassium, and thus citrate, iodide, bromide, iodate, bromate, chlorate, manganate, and permanganate of sodium, and many other salts be formed. But enough has been stated to show how chemically analogous sodium is to potassium. Such analogies will constantly present themselves. In few departments of knowledge are order and method more perceptible; in few is there as much natural law, as much *science*, as in chemistry.

Substitution of Potassium and Sodium salts for each other.—Sodium salts being cheaper than potassium salts, the former may sometimes be economically substituted. That one is employed rather

than the other, is often merely a result due to accident or fashion. But it must be borne in mind that in some cases a potassium salt will crystallize more readily than its sodium analogue, or that a sodium salt is stable when the corresponding potassium salt has a tendency to absorb moisture, or one may be more soluble than the other, or the two may have different medicinal effect. For these or similar reasons, a potassium salt has come to be used in medicine or trade, instead of the corresponding sodium salt, and *vice versâ*. Whenever the acidulous portion only is to be utilized, the least expensive salt of the class would nearly always be selected.

(*b*) *Reactions having Analytical Interest.*

1. *The chief analytical reaction* for sodium is the *flame-test.* When brought into contact with a flame in the manner described under potassium (page 66), an intensely yellow color is communicated to the flame by any salt of sodium. This is highly characteristic—indeed, almost too delicate a test; for if the point of the wire be touched by the fingers, enough salt (which is contained in the moisture of the hand) adheres to the wire to communicate a very distinct sodium reaction. These statements should be experimentally verified, the chloride, sulphate, or any other salt of sodium being employed.

2. *Precipitant of Sodium.*—Sodium is the only metal whose common salts are all soluble in water. Hence no ordinary reagent can be added to a solution containing a sodium salt which shall give a precipitate containing the sodium. A neutral or alkaline solution of a sodium salt gives, however, a granular precipitate of antimoniate of sodium ($Na_2H_2Sb_2O_7$, $6H_2O$) if well stirred or shaken with a solution of *antimoniate of potassium* ($K_2H_2Sb_2O_7$), but the reagent precipitates other metals, and is liable to decompose and become useless, and hence is seldom employed.

Antimoniate of potassium is made by adding, gradually, finely powdered metallic antimony to nitrate of potassium fused in a crucible so long as deflagration continues. The resulting mass is boiled with a large quantity of water, the solution filtered and preserved in a well-stoppered bottle; for the carbonic gas in the air is rapidly absorbed by the solution, antimonic acid being deposited.

3. Sodium salts, like those of potassium, are not volatile. Prove this fact by the means described when treating of the effect of heat on potassium salts (p. 66).

QUESTIONS AND EXERCISES.

98. How is the official solution of soda prepared? Give a diagram or equation.

99. Explain the action of sodium or potassium on water. What colors do these elements respectively communicate to flame?

100. How much bicarbonate of sodium can be obtained from 2240 pounds of crystallized carbonate of sodium? Ans. 1316 lbs.

101. Acetate of sodium: give formula, process, and equation.

102. Give a diagram showing the formation of bicarbonate of sodium.

103. Why is a mixture of dried and undried carbonate of sodium employed in the preparation of the bicarbonate?

104. State the difference between anhydrous and crystallized carbonate of sodium.

105. Define the terms *anhydrous, hydrous, hydrate, anhydride.*

106. What do you understand by *water of crystallization?*

107. What is the nature of "Soda-water?"

108. How many volumes of gas (reckoned as at ordinary atmospheric pressure) are contained in any given volume of the British official "Soda-water?"

109. What is the general law regarding the solubility of gases in liquids under pressure?

110. What is the systematic name of Rochelle salt, and how is the salt prepared?

111. What is the relation of Rochelle salt to cream of tartar and tartaric acid?

112. Give the mode of preparation and composition of solution of chlorinated soda, and express the process by a diagram.

113. How is the granular effervescing Citro-tartrate of Sodium prepared?

114. Define *Deliquescence, Efflorescence,* and *Lixiviation.*

115. What is the general relation of potassium salts to those of sodium?

116. How are sodium salts analytically distinguished from those of potassium?

AMMONIUM.

Symbol NH_4 or Am. Atomic weight 18.

Memoranda.—The elements nitrogen and hydrogen, in the proportion of one atom to four (NH_4), are those characteristics of all the compounds about to be studied, just as potassium (K) and sodium (Na) are the characteristic elements of the potassium and sodium compounds. Ammonium is a univalent nucleus, root, or radical, like potassium or sodium; and the ammonium compounds closely resemble those of potassium or sodium. In short, if, for an instant, potassium or sodium be imagined to be compounds, the analogy between these

three series of salts is complete. Yet ammonium never having been isolated, its existence remains a matter of assumption.

Source.—The source of nearly all the ammoniacal salts met with in commerce is ammonia-gas (NH_3) obtained in distilling coals in the manufacture of ordinary illuminating gas. It is doubtless derived from the nitrogen of the plants from which the coal has been produced.

Ammonia.—When this gas (NH_3) comes into contact with water (H_2O), in the process of washing and cooling coal-gas, hydrate of ammonium (NH_4HO, or AmHO) is believed to be formed, the analogue of hydrate of potassium (KHO) or sodium (NaHO). The grounds for this belief are the observed analogy of the well-known ammoniacal salts to those of potassium and sodium, the similarity of action of solution of potash, soda, and ammonia on salts of most metals, and the existence of crystals of an analogous sulphur salt (NH_4HS).

Chloride of Ammonium.—The "ammoniacal liquor" of the gas-works is usually neutralized by hydrochloric acid, by which *chloride of ammonium* (sal-ammoniac) is produced.

$$NH_4HO + HCl = NH_4Cl + H_2O;$$

and from this salt, purified, the others used in pharmacy are directly or indirectly made. Chloride of ammonium (*Ammonii Chloridum*, B. P. and U. S. P.) occurs "in colorless, inodorous, translucent fibrous masses, tough, and difficult to powder, soluble in water [1 in 10 is the 'Solution of Chloride of Ammonium,' B. P.] and in rectified spirit." Chloride of ammonium generally contains slight traces of oxychloride of iron, tarry matter, and possibly chlorides of compound ammoniums (*vide* "Artificial Alkaloids" in Index).

Sulphate of Ammonium $(NH_4)_2.SO_4$, results when "ammoniacal liquor" is neutralized by oil of vitriol. It is largely used as a constituent of artificial manure in England, and when purified by recrystallization is employed in pharmacy (*Ammonii Sulphas*, U. S. P.).

Volcanic Ammonia.—The purest form of ammonia is that met with in volcanic districts, and obtained as a by-product in the manufacture of borax; the crude boracic acid as imported contains about 10 per cent. of ammonium salts, chiefly sulphate, and double sulphates of ammonium with magnesium, sodium, and manganese (Howard).

Reactions having (*a*) General (*b*) Synthetical, and (*c*) Analytical Interest.

Ammonium-Amalgam. (?)

(*a*) *General Reaction.*—To forty or fifty grains of dry mercury in a *dry* test-tube, add one or two small pieces of sodium (freed from adhering naphtha by gentle pressure with a piece of filter-paper), and amalgamate by gently warming the tube. To this amalgam, when cold, add some fragments of chloride of ammonium and a strong solution

of the same salt. The sodium amalgam soon begins to swell and rapidly increase in bulk, probably overflowing the tube. The light spongy mass produced is the so-called ammonium-amalgam, and the reaction is usually adduced as evidence of the existence of ammonium; the sodium of the amalgam unites with the chlorine of the chloride of ammonium, while the ammonium is supposed to form an amalgam with the mercury. As soon as formed the amalgam gives off hydrogen and ammonia gases; this decomposition is complete after some minutes, and a globule of mercury alone remains.

(*b*) *Reactions having Synthetical Interest.*

Hydrate of Ammonium. Ammonia.

First Synthetical Reaction.—Heat a few grains of sal-ammoniac with about an equal weight of hydrate of calcium (slaked lime) damped with a little water in a test-tube; ammonia gas is given off, and may be recognized by its well-known odor. It is very soluble in water. Pass a delivery-tube, fitted to the test-tube as described for the preparation of oxygen and hydrogen, into a second test-tube, at the bottom of which is a little water; again heat; solution of ammonia will be thus formed.

$2NH_4Cl$	+	$Ca2HO$	=	$CaCl_2$	+	$2H_2O$	+	$2NH_3$
Chloride of ammonium.		Hydrate of calcium.		Chloride of calcium.		Water.		Ammonia gas.

Ammonia gas is composed of one atom of nitrogen with three atoms of hydrogen; its formula is NH_3; two volumes of it contain one volume of nitrogen combined with three atoms or volumes of hydrogen. Its constituents have therefore in combining suffered condensation to one-half their normal bulk. Its conversion into hydrate of ammonium may be thus shown:—

NH_3	+	H_2O	=	NH_4HO or AmHO
Ammonia gas.		Water.		Hydrate of ammonium (ammonia).

Solutions of Ammonia, prepared by this process on a large scale and in suitable apparatus, are met with in pharmacy—the one (sp. gr. 0.891) containing 32.5 per cent., the other (sp. gr. 0.959), 10 per cent., by weight, of ammonia gas, NH_3, or 66.9 and 20.6 of ammonia, NH_4HO (*Liquor Ammoniæ Fortior* and *Liquor Ammoniæ*, B. P. One part, *by measure*, of the former, and two of water form the latter). On the large scale, bottles are so arranged in a series as to condense all the ammonia evolved during the operation. *Aqua Ammoniæ Fortior*, U. S. P., sp. gr. 0.900, contains 26 per cent. of ammonia gas. *Aqua Ammoniæ*, U. S. P., has a sp. gr. of 0.960.

Note.—When water is mixed with strong solution of ammonia, expansion occurs. Thus, calculating from the stated specific gravities of the official solutions, 3000 parts by measure of the *Liquor Ammoniæ* weigh 2877 parts (959 × 3); whereas 1000 parts by measure of the *Liquor Ammoniæ Fortior* (weighing 891 parts) and 2000 measures of water (weighing 2000) weigh 2891 parts. Apparently 1000 volumes of the strong solution of ammonia with 2000 volumes of water yield 3000 volumes of mixture, and 14 parts by weight, or 15 volumes to spare, total 3015 volumes—an expansion of about half of one (.5) per cent.

Acetate of Ammonium.

Second Synthetical Reaction.—To acetic acid and water in a test-tube add powdered commercial carbonate (acid carbonate and carbamate) of ammonium until effervescence ceases; the resulting liquid, made of prescribed strength, is the official solution of Acetate of Ammonium ($NH_4C_2H_3O_2$) (*Liquor Ammonii Acetatis*, U. S. P.).

$$\underset{\text{Acid carbonate and carbamate of ammonium.}}{(NH_4HCO_3)_2NH_4NH_2CO_2} + \underset{\text{Acetic acid.}}{4HC_2H_3O_2} = \underset{\text{Acetate of ammonium.}}{4NH_4C_2H_3O_2} + \underset{\text{Water.}}{2H_2O} + \underset{\text{Carbonic acid gas.}}{3CO_2}$$

Carbonates of Ammonium.

Commercial carbonate of ammonium is made by heating a mixture of chalk and sal-ammoniac; chloride of calcium ($CaCl_2$) is produced, ammonia gas (NH_3) and water (H_2O) escape, and the ammoniacal carbonate distils, or rather sublimes,* in cakes (*Ammonii Carbonas*, B. P. and U. S. P.). The best form of apparatus to employ is a retort with a short wide neck and a cool receiver. On the large scale the retort is usually iron and the receiver earthenware or glass; on the small scale glass vessels are employed. The salt is purified by resublimation at a low temperature; 150° F. is said to be sufficient.

This salt, the empirical formula of which is $N_4H_{16}C_3O_8$, is probably a mixture of two molecules of acid carbonate or bicarbonate of ammonium ($2NH_4HCO_3$) and one of a salt termed carbamate of ammonium ($NH_4NH_2CO_2$). The latter belongs to an important class of salts known as carbamates, but it is the only one of interest to the pharmacist. Cold water extracts it from the commercial carbonate of ammonium, leaving the acid carbonate of ammonium undissolved, if the amount of liquid used be very small. In water carbamate soon changes into neutral carbonate of ammonium,

$$NH_4NH_2CO_2 + H_2O = (NH_4)_2CO_3 \text{ or } Am_2CO_3;$$

* *Sublimation* (from *sublimis*, high). Vaporization of a solid substance by heat, and its condensation on an upper and cooler part of the vessel or apparatus in which the operation is performed.

so that an aqueous solution of commercial carbonate of ammonium contains both acid carbonate and neutral carbonate of ammonium. If to such a solution some ordinary solution of ammonia be added, a solution of *neutral carbonate of ammonium* is obtained; and this is the common reagent always found on the shelves of the analytical laboratory.

$$AmHCO_3 + AmHO = Am_2CO_3 + H_2O.$$

Neutral carbonate of ammonium is the salt formed on adding strong solution of ammonia to the commercial carbonate in preparing a pungent mixture for toilet smelling-bottles; but it is unstable, and on continued exposure to air is reduced to a mass of crystals of the acid carbonate or bicarbonate of ammonium. Bicarbonate of ammonium (NH_4HCO_3) is also produced on passing carbonic acid gas into an aqueous solution of commercial carbonate.

According to Divers, the sublimed product of the first distillation of chalk and sal-ammoniac is a mixture of carbamate and carbonate of ammonium, the latter losing some ammonia gas on redistillation, and carbamate with bicarbonate forming the resulting commercial salt. Dr. Divers considers that the salt now met with in trade contains one molecule of acid carbonate to one of carbamate, and not two of the former to one of the latter, as was the case when the analyses were made from which the foregoing formulæ were deduced.

Sal Volatile (*Spiritus Ammoniæ Aromaticus*, B. P. and U. S. P.) is a spirituous solution of ammonia (AmHO), neutral carbonate of ammonium (Am_2CO_3), and the oils of nutmeg and lemon (and lavender, U. S. P.). Fetid spirit of ammonia (*Spiritus Ammoniæ Fœtidus*, B. P.) is an alcoholic solution of the volatile oil of assafœtida mixed with solution of ammonia. "Solution of Carbonate of Ammonia," B. P., is formed by dissolving half an ounce of the salt in ten ounces of water. *Spiritus Ammoniæ*, U. S. P., is an alcoholic solution of ammonia.

Citrate, Phosphate, and Benzoate of Ammonium.

Third Synthetical Reaction.—To solution of citric acid ($H_3C_6H_5O_7$ or $H_3\overline{Ci}$) add solution of ammonia (AmHO) until the liquid is neutral to test-paper; the product is Solution of Citrate of Ammonium ($Am_3\overline{Ci}$) *Liquor Ammoniæ Citratis*, B. P.).

Phosphate of Ammonium (Am_2HPO_4) (*Ammoniæ Phosphas*, B. P.) and *Benzoate of Ammonium* ($AmC_7H_5O_2$) (*Ammonii Benzoas*, U. S. P.) are also made by adding solution of ammonia to phosphoric acid (H_3PO_4) and benzoic acid ($HC_7H_5O_2$) respectively, evaporating (keeping the ammonia in slight excess by adding more of its solution), and setting aside for crystals to form. The official Solution of Acetate of Ammonium could be made in the same way; but, when prepared with Carbonate of Ammonium, the liquid remains charged with carbonic acid, and has a less vapid flavor.

$$\underset{\text{Citric acid.}}{H_3C_6H_5O_7} + \underset{\text{Ammonia.}}{3AmHO} = \underset{\text{Citrate of ammonium.}}{Am_3C_6H_5O_7} + \underset{\text{Water.}}{3H_2O}$$

$$\underset{\text{Phosphoric acid.}}{H_3PO_4} + \underset{\text{Ammonia.}}{2AmHO} = \underset{\text{Phosphate of ammonium.}}{Am_2HPO_4} + \underset{\text{Water.}}{2H_2O}$$

$$\underset{\text{Benzoic acid.}}{HC_7H_5O_2} + \underset{\text{Ammonia.}}{AmHO} = \underset{\text{Benzoate of ammonium.}}{AmC_7H_5O_2} + \underset{\text{Water.}}{H_2O}$$

Phosphate of ammonium occurs in transparent colorless prisms, soluble in water, insoluble in spirit; benzoate in crystalline plates, soluble in water and in spirit.

Ammonii Iodidum, U. S. P., is made by decomposing the two bodies iodide of potassium and sulphate of ammonium, which give iodide of ammonium and sulphate of potassium; the latter salt is separated by adding alcohol to the cooled solution, when, by reason of its insolubility in alcohol, it crystallizes out, and the separated solution of iodide of ammonium is then evaporated to dryness.

Bromide of Ammonium (*Ammonii Bromidum*, B. P. and U. S P.) will be noticed in connection with Hydrobromic Acid and other Bromides.

Oxalate of Ammonium.

Fourth Synthetical Reaction.—To a nearly boiling solution of 1 part of oxalic acid in about 8 of water add carbonate of ammonium until the liquid is neutral to test-paper, filter while hot, and set aside for crystals ($(NH_4)_2C_2O_4,H_2O$) to form. The mother-liquor is useful as a reagent in analysis: 1 of the salt in 40 of water constitutes "Solution of Oxalate of Ammonia," B. P.

$$\underset{\text{Oxalic acid.}}{2H_2C_2O_4} + \underset{\text{Carbonate of ammonium.}}{N_4H_{16}C_3O_8} = \underset{\text{Oxalate of ammonium.}}{2(NH_4)_2C_2O_4} + \underset{\text{Carbonic acid gas.}}{3CO_2} + \underset{\text{Water.}}{2H_2O}$$

Sulphydrate of Ammonium.

Fifth Synthetical Reaction.—Pass sulphuretted hydrogen gas (H_2S) through a small quantity of solution of ammonia in a test-tube, until a portion of the liquid no longer causes a white precipitate in solution of sulphate of magnesium (Epsom salt); the product is solution of sulphydrate (or sulphide) of ammonium (NH_4HS), the "Solution of Sulphide of Ammonium" of the British Pharmacopœia, a most valuable chemical reagent, as will presently be apparent.

$$NH_4HO + H_2S = NH_4HS + H_2O.$$

"*Solution of Sulphide of Ammonium*," B. P., is made by passing the gas prepared in the apparatus described below into 3 fluidounces of solution of ammonia (*Liquor Ammoniæ*) so long as the gas continues to be absorbed, then adding 2 more ounces of solution of ammonia, and preserving the solution in a well-stoppered bottle.

Sulphuretted hydrogen is a compound of noxious odor; hence the above operation, and many others, described further on, in which this gas is indispensable, can only be performed in the open air, or in a fume-cupboard, a chamber so contrived that deleterious gases and vapors shall escape into a chimney in connection with the external air. In the above experiment, the small quantity of gas required can be made in a test-tube, after the manner of hydrogen itself. To two or three fragments of sulphide of iron (FeS), add water and then sulphuric acid; the gas is at once evolved, and may be conducted by a tube into the solution of ammonia.

$$FeS + H_2SO_4 = H_2S + FeSO_4.$$

The iron remains dissolved in the water in the state of sulphate of iron.

Crystals of sulphydrate of ammonium (NH_4HS) may be obtained on bringing ammonia gas (NH_3) and sulphuretted hydrogen (H_2S) together at a low temperature. They are soluble in water without decomposition.

Sulphuretted-hydrogen Apparatus.—As no heat is necessary in making sulphuretted hydrogen, the test-tube of the foregoing operation may be advantageously replaced by a bottle, especially when larger quantities of the gas are required. In analytical operations, the gas should be purified by passing it through water contained in a second bottle.

The most convenient arrangement for experimental use is prepared as follows: Two common wide-mouth bottles are selected, the one having a capacity of about half a pint, the other a quarter pint; the former may be called the generating-bottle, the latter the wash-bottle. Fit two corks to the bottles. Through each cork bore two holes by a round file or other instrument, of such a size that glass tubing of about the diameter of a quill pen shall fit them tightly. Through one of the holes in the cork of the generating-bottle pass a funnel-tube, so that its extremity may nearly reach the bottom of the bottle. Such "funnel-tubes" may be purchased at the usual shops; or, if the student has access to a table-blowpipe, and the advantage of a tutor to

direct his operations, they may be made by himself. To the other hole adapt a piece of tubing, 6 inches long, and bent in the middle to a right angle. A similar "elbow-tube" is fitted to one of the holes in the cork of the wash-bottle, and another elbow-tube, one arm of which is long enough to reach to near the bottom of the wash-bottle, fitted to the other hole. Removing the corks, two or three ounces of water are now poured into each bottle, an ounce or two of sulphide of iron put into the generating-bottle, and the corks replaced. The elbow-tube of the generating-bottle is now attached by a short piece of India-rubber tubing to the long-armed elbow-tube of the wash-bottle, so that gas coming from the generator may pass through the water in the wash-bottle. The delivery-tube of the wash-bottle is then lengthened by attaching to it, by India-rubber tubing, a straight piece of glass tubing, three or four inches long. The apparatus is now ready for use. Strong sulphuric acid is poured down the funnel-tube in small quantities at a time, until brisk effervescence is established, and more added from time to time as the evolution of gas becomes slow. The gas passes through the tubes into the wash-bottle, where, as it bubbles up through the water, any trace of sulphuric acid, or other matter mechanically carried over, is arrested, and thence flows out at the delivery-tube into any vessel or liquid that may be placed there to receive it. The generator must be occasionally dismounted, and the sulphate of iron washed out.

Luting (*lutum*, mud).—If the corks of the above apparatus are sound, and tube-holes well made, no escape of gas will occur. If rough corks have been employed, or the holes are not cylindrical, linseed-meal lute may be rubbed over the defective parts. The lute is prepared by mixing linseed-meal with water to the consistence of dough. A neat appearance may be given to the lute by gently rubbing a well-wetted finger over its surface.

(*c*) *Reactions having Analytical Interest* (*Tests.*)

First Analytical Reaction.—To a solution of any salt of ammonium (the chloride, for example) in a test-tube add solution of caustic soda (or solution of potash, or a little slaked lime); ammonia gas is at once evolved, recognized by its well-known odor.

$$NH_4Cl + NaHO = NH_3 + H_2O + NaCl.$$

Though ammonium itself cannot exist in the free state, its compounds are stable. Ammonia is easily expelled from those compounds by action of the stronger alkalies, caustic potash, soda, or lime. As a matter of exercise, the student should here draw out equations in which acetate ($NH_4C_2H_3O_2$), sulphate (Am_2SO_4), nitrate (NH_4NO_3) or any other ammoniacal salt not already having the odor of ammonia, is supposed to be under examination; also representing the use of the other hydrates, potash (KHO) or slaked lime (Ca2HO).

The *odor* of ammonia gas is perhaps the best means of recognizing its presence; but the following tests are also occasionally useful. Into the test-tube in which the ammonia gas is evolved insert a glass rod moistened with hydrochloric acid (that is, with the solution of hydrochloric acid gas, conveniently termed hydrochloric acid, the *Acidum Hydrochloricum* of the Pharmacopœias); white fumes of chloride of ammonium will be produced.

$$NH_3 + HCl = NH_4Cl.$$

Hold a piece of moistened red litmus paper in a tube in which ammonia gas is present; the red color will be changed to blue.

Test-papers.—Litmus (B. P.) is a blue vegetable pigment, prepared from various species of *Roccella* lichen, exceedingly sensitive to the action of acids, which turn it red. When thus reddened, alkalies (potash, soda, and ammonia) and other soluble hydrates readily turn it blue. The student should here test for himself the delicacy of this action by experiments with paper soaked in solutions of litmus and dipped into very dilute solutions of acids, acid salts ($KHC_4H_4O_6$ *e. g.*), alkalies, and such neutral salts as nitrate of potassium, sulphate of sodium, or chloride of ammonium.

Tincture of Litmus.—1 ounce of litmus is macerated for two days in 10 fluidounces of proof spirit, and the solution poured off from insoluble matter.

Blue litmus paper is unsized white paper steeped in tincture of litmus and dried by exposure to the air. *Red litmus paper* is unsized white paper steeped in tincture of litmus which has been previously reddened by the addition of a very minute quantity of sulphuric acid, and dried by exposure to the air.

Turmeric paper, similarly prepared from tincture of turmeric (1 of turmeric root or rhizome to 6 of rectified spirit, macerated for seven days), is occasionally useful as a test for alkalies, which turn its yellow to brown; acids do not affect it.

Second Analytical Reaction.—To a few drops of a solution of an ammonium salt add a drop or two of hydrochloric acid and a like small quantity of solution of perchloride of platinum ($PtCl_4$); a yellow crystalline precipitate of the double chloride of platinum and ammonium ($PtCl_4 2NH_4Cl$)

will be produced, similar in appearance to the corresponding salt of potassium, the remarks concerning which (p. 65) are equally applicable to the precipitate under notice.

Third Analytical Reaction.—To a moderately strong solution of an ammonium salt add a strong solution of tartaric acid, and shake or well stir the mixture; a white granular precipitate of acid tartrate of ammonium will be formed.

For data from which to draw out an equation representing this action, see the remarks and formulæ under the analogous salt of potassium (p. 65).

Fourth Analytical Fact.—Evaporate a few drops of a solution of an ammonium salt to dryness, or place a fragment of a salt in the solid state on a piece of platinum foil, and heat in a flame; the salt is readily *volatilized*. As already noticed, the salts of potassium and sodium are *fixed* under these circumstances, a point of difference of which advantage will frequently be taken in analysis. A porcelain crucible may often be advantageously substituted for platinum foil in experiments on volatilization.

A wire-triangle may be used in supporting crucibles. It is made by placing three (5 or 6 inch) pieces of wire in the form of a triangle and then twisting each pair of ends together through half the length of the wires. A piece of tobacco-pipe stem (about 2 inches) is sometimes placed in the centre of each wire before twisting, the transference of any metallic matter to the sides of the crucible being thus prevented.

Practical Analysis.

With regard to those experiments which are useful rather as means of detecting the presence of potassium, sodium, and ammonium, than as illustrating the preparation of salts, the student should proceed to apply them to certain solutions of any of the salts of potassium, sodium, and ammonium, with the view of ascertaining which metal is present; that is, proceed to practical analysis.* A little thought

* Such solutions are prepared in educational laboratories by a tutor. They should, under other circumstances, be mixed by a friend, as it is not desirable to know previously what is contained in the substance about to be analyzed.

The analysis of solutions containing only one salt serves to impress the memory with the characteristic tests for the various metals and other radicals, and familiarize the mind with chemical principles. Medical students seldom have time to go further than this. More thorough analytical and general chemical knowledge is only acquired

will enable him to apply these reactions in the most suitable order and to the best advantage for the contemplated purpose; but the following arrangements are perhaps as good as can be devised:—

DIRECTIONS FOR APPLYING THE FOREGOING ANALYTICAL REACIONS TO THE ANALYSIS OF AN AQUEOUS SOLUTION OF A SALT OF ONE OF THE METALS, POTASSIUM, SODIUM, AMMONIUM.

Add caustic soda to a small portion of the solution to be examined, and warm the mixture in a test-tube; the odor of ammonia gas at once reveals the presence of an ammonium salt.

If ammonium be not present, apply the perchloride-of-platinum test; a yellow precipitate proves the presence of potassium.

(It will be observed that potassium can only be detected in the absence of ammonium, salts of the latter radical giving similar precipitates.)

The flame-test is sufficient for the recognition of sodium.

DIRECTIONS FOR APPLYING THE FOREGOING ANALYTICAL REACTIONS TO THE ANALYSIS OF AN AQUEOUS SOLUTION OF SALTS OF ONE, TWO, OR ALL THREE OF THE ALKALI METALS.

Commence by testing a small portion of the solution for an ammonium salt. If present, make a memorandum to that effect, and then proceed to get rid of the ammoniacal compound to make way for the detection of potassium: advantage is here taken of the volatility of ammonium salts and the fixity of those of potassium and sodium. Evaporate the original solution to dryness in a small basin, transfer the solid residue to a porcelain crucible, and heat the latter to a low redness, or until dense white fumes (of ammoniacal salts) cease to escape. This operation should be conducted in a fume-cupboard, to avoid contamination of the air of the apartment. When the cru-

by working on such mixtures of bodies as are met with in actual practice, beginning with solutions which may contain any or all the members of a group. Hence in this manual, two Tables of short directions for analyzing are given under each group. Pharmaceutical students should follow the second Table.

cible is cold, dissolve out the solid residue with a small quantity of hot water, and test the solution for potassium by the perchloride-of-platinum test, and for sodium by the flame test.

If ammonium is proved to be absent, the original solution may, of course, be at once tested for potassium and sodium.

Flame-test.—The violet tint imparted to flame by potassium salts may be seen when masked by the intense yellow color due to sodium, if the flame be observed through a piece of dark-blue glass, a medium which absorbs the yellow rays of light.

Note on Nomenclature.—The operations of *evaporation* and heating to redness, or *ignition*, are frequently necessary in analysis, and are usually conducted in the above manner. If vegetable or animal matter be also present, carbon is set free, and ignition is accompanied by *carbonization;* the material is said to *char.* When all carbonaceous matter is burnt off, the crucible being slightly inclined and its cover removed to facilitate combustion, and mineral matter, or *ash*, alone remains, the operation of *incineration* has been effected.

Note on the Classification of Elements.—The compounds of potassium, sodium, and ammonium have many analogies. Their carbonates, phosphates, and most other salts are soluble in water. The atoms of the radicals themselves are univalent—that is, displace or are displaced by one atom of hydrogen. In fact, they constitute by their similarity in properties a distinct group or family. All the elements thus naturally fall into classes—a fact that should constantly be borne in mind, and evidence of which should always be sought. It would be impossible for the memory to retain the details of chemistry without a system of classification and leading principles. Classification is also an important feature in the art as well as in the science of chemistry; for without it practical analysis could not be undertaken. The classification adopted in this volume is founded, as far as possible, on the quantivalence of the elements, but chiefly on their analytical relations.

QUESTIONS AND EXERCISES.

117. Why are ammoniacal salts classed with those of potassium and sodium?

118. Mention the sources of the ammonium salts.

119. Describe the appearance and other characters of Chloride of Ammonium.

120. Give the formula of Sulphate of Ammonium.

121. Adduce evidence of the existence of ammonium.

122. How are the official Solutions of Ammonia prepared? Give diagrams.
123. How is the official Solution of Acetate of Ammonium prepared?
124. What is the composition of commercial Carbonate of Ammonium?
125. Define *sublimation.*
126. What ammoniacal salts are contained in *Spiritus Ammoniæ Aromaticus?*
127. Give diagrams or equations illustrating the formation of Citrate, Phosphate, and Benzoate of Ammonium.
128. Give the formula of Oxalate of Ammonium.
129. Show how hydrate of ammonium may be converted into sulphydrate.
130. Describe the preparation of Sulphuretted Hydrogen gas.
131. Enumerate and explain the tests for ammonium.
132. How is potassium detected in a solution in which ammonium has been found?
133. Give equations illustrating the action of hydrate of sodium on acetate of ammonium; hydrate of potassium on sulphate of ammonium; and hydrate of calcium on nitrate of ammonium.
134. What are the effects of acids and alkalies on litmus and turmeric?
135. Describe the analysis of an aqueous liquid containing salts of potassium, sodium, and ammonium.
136. What meanings are commonly assigned to the terms *evaporation, ignition, carbonization,* and *incineration?*
137. Write a short article descriptive of the analogies of potassium, sodium, and ammonium, and their compounds.

BARIUM, CALCIUM, MAGNESIUM.

These three elements have many analogies. Their atoms are bivalent.

BARIUM.

Symbol Ba. Atomic weight 137.

The analytical reactions only of this metal are of interest to the general student of pharmacy. The chloride ($BaCl_2$) (Chloride of Barium, B. P. and U. S. P., and "Solution of Chloride of Barium," 1 in 10 of water, B. P.) and nitrate ($Ba2NO_3$) are the soluble salts in common use in analysis; and these and others are made by dissolving the native carbonate ($BaCO_3$), *Barii Carbonas*, U. S. P., the mineral *witherite*, in acids, or by heating the other common natural compound of barium, the sulphate, *heavy white* or *heavy spar* ($BaSO_4$), with coal—

$$BaSO_4 + C_4 = 4CO + BaS,$$

and dissolving the resulting sulphide in acids. When the nitrate is strongly heated, it is decomposed, the oxide of barium or *baryta* (BaO) remaining. Baryta, on being moistened, assimilates the elements of water with great avidity, and yields hydrate of barium, (Ba2HO). The latter is tolerably soluble, giving *baryta-water;* and from this solution crystals of hydrate of barium are obtained on evaporation.

The operations above described may all be performed in test-tubes and small porcelain crucibles heated by the gas-flame. Quantities of 1 oz. to 1 lb. require a coke-furnace.

Peroxide of barium (BaO_2) is formed on passing air over heated baryta. By the action of dilute hydrochloric acid it yields solution of *peroxide of hydrogen* (H_2O_2) or *oxygenated water.*

Quantivalence.—The atom of barium is bivalent, Ba″.

Reactions having Analytical Interest (Tests).

First Analytical Reaction.—To the solution of any soluble salt of barium (nitrate or chloride, for example) add dilute sulphuric acid; a white precipitate is obtained. Set the test-tube aside for two or three minutes, and when some of the precipitate has fallen to the bottom pour away most of the supernatant liquid, add strong nitric acid, and boil; the precipitate is insoluble.

The production of a white precipitate by sulphuric acid, insoluble even in hot nitric acid, is highly characteristic of barium. The name of this precipitate is sulphate of barium; its formula is $BaSO_4$.

Antidotes.—In cases of poisoning by soluble barium salts, any sulphates, such as those of magnesium and sodium (Epsom salt, Glauber's salt, alum), would be obvious antidotes.

Second Analytical Reaction.—To a barium solution add solution of the yellow chromate of potassium (K_2CrO_4); a pale yellow precipitate ($BaCrO_4$) falls. Add acetic acid to a portion of the chromate of barium; it is insoluble. Add hydrochloric or nitric acid to another portion; it is soluble.

"*Neutral Chromate.*"—The red chromate (or bichromate) of potassium ($K_2CrO_4.CrO_3$) must not be used in this reaction, or the barium will be only imperfectly precipitated; for the red salt gives rise to the formation of free acid, in which chromate of barium is to some extent soluble:—

$$K_2CrO_4, CrO_3 + 2BaCl_2 + H_2O = 2BaCrO_4 + 2KCl + 2HCl.$$

Yellow chromate is obtained on adding carbonate of potassium, in small quantities at a time, to a hot solution of the red chromate until effervescence ceases; a little more red chromate is then added to insure decomposition of any slight excess of carbonate of potassium.

$$K_2CrO_4, CrO_3 + K_2CO_3 = 2K_2CrO_4 + CO_2.$$

For analytical purposes solution of a neutral chromate is still more readily prepared by simply adding solution of ammonia to solution of red chromate of potassium, until the liquid turns yellow, and, after stirring, smells of ammonia.

$$K_2CrO_4, CrO_3 + 2NH_4HO = 2KNH_4CrO_4 + H_2O.$$

Other Analytical Reactions.—To a barium solution add a soluble carbonate (carbonate of ammonium (Am_2CO_3) will generally be rather more useful than others); a white precipitate of carbonate of barium ($BaCO_3$) results.——To more of the solution add an alkaline phosphate or arseniate (phosphate of sodium (Na_2HPO_4) is the most common of these chemically analogous salts, but phosphate of ammonium (Am_2HPO_4) or arseniate (Am_2HAsO_4) will subsequently have the preference); white phosphate of barium ($BaHPO_4$), insoluble in pure water but slightly soluble in aqueous solutions of some salts, or arseniate of barium ($BaHAsO_4$), both soluble even in acetic and other weak acids, are precipitated.——To another portion add oxalate of ammonium ($Am_2C_2O_4$); white oxalate of barium (BaC_2O_4) is precipitated, soluble in strong acids, and sparingly so in acetic acid.——The silico-fluoride of barium ($BaSiF_6$) is insoluble, and falls readily if an equal volume of spirit of wine be added to the solution under examination after the addition of hydrofluosilicic acid (H_2SiF_6.) ——Barium salts, moistened with hydrochloric acid, impart a greenish-color to flame.

Mem.—Good practice will be found in writing out equations descriptive of each of the foregoing reactions.

QUESTIONS AND EXERCISES.

138. What is the quantivalence of barium?

139. Write down the formulæ of oxide, hydrate, chloride, nitrate, carbonate, and sulphate of barium; and state how these salts are prepared.

140. Describe the preparation of peroxide of hydrogen.

141. Which of the tests for barium are most characteristic? Give an equation of the reactions.

142. Name the antidote in cases of poisoning by soluble barium salts, and explain its action.

CALCIUM.

Symbol Ca. Atomic weight 40.

Calcium compounds form a large proportion of the crust of our earth. Carbonate of calcium is met with as chalk, marble, limestone, calc-spar, etc., the sulphate, as gypsum or plaster of Paris ("Plaster of Paris, native sulphate of calcium—$CaSO_4$, $2H_2O$—deprived of water by heat."—B. P.), and alabaster, the silicate in many minerals, the fluoride of calcium as fluor-spar. The phosphate is also a common mineral. The element itself is only isolated with great difficulty. The atom of calcium is bivalent, Ca″.

Reactions having Synthetical Interest.

Chloride of Calcium.

First Synthetical Reaction.—To some hydrochloric acid add carbonate of calcium (chalk, or, the purer form, white marble, *Marmor Album*, B. P. and U. S. P.) ($CaCO_3$) until effervescence ceases, filter; solution of chloride of calcium ($CaCl_2$), the most common soluble salt of calcium, is formed.

$CaCO_3$	+	$2HCl$	=	$CaCl_2$	+	H_2O	+	CO_2
Carbonate of calcium.		Hydrochloric acid.		Chloride of calcium.		Water.		Carbonic acid gas.

This solution contains carbonic acid, and will give a precipitate of carbonate of calcium on the addition of lime-water. It may be obtained quite neutral by well boiling before filtering off the excess of marble. It is a serviceable test-liquid in analytical operations.

Solution of chloride of calcium evaporated to a syrupy consistence readily yields crystals. These are extremely deliquescent. The solution, evaporated to dryness, and the white residue strongly heated, gives solid anhydrous chloride of calcium in a porous form. The resulting agglutinated lumps (*Calcii Chloridum*, B. P. and U. S. P.) are much used for drying gases, and for freezing certain liquids from water. The salt is soluble in alcohol. One part in ten of water constitutes a useful test-liquid, "Solution of Chloride of Calcium," B. P. Four parts in five of water forms the "Solution (saturated) of Chloride of Calcium," B. P.

Marble often contains ferrous carbonate ($FeCO_2$), which in the above process becomes converted into ferrous chloride, rendering the chloride of calcium impure:—

$FeCO_3$	+	$2HCl$	=	$FeCl_2$	+	H_2O	+	CO_2
Ferrous carbonate.		Hydrochloric acid.		Ferrous chloride.		Water.		Carbonic acid gas.

If absolutely pure chloride of calcium be required, a few drops of the solution should be poured into a test-tube or

test-glass, diluted with water, and examined for iron (by adding sulphydrate of ammonium, which gives a black precipitate with salts of iron), and, if the latter is present, hypochlorite of calcium (in the form of chlorinated lime) and slaked lime should be added to the remaining bulk of the liquid, and the whole boiled for a few minutes, whereby iron (as ferric hydrate) is thus precipitated; on filtering, a pure solution of chloride of calcium is obtained:—

$4FeCl_2$	+	$Ca2ClO$	+	$4CaH_2O_2$	+	$2H_3O$
Ferrous chloride.		Hypochlorite of calcium.		Hydrate of calcium.		Water.

$$= 2(Fe_26HO) + 5CaCl_2$$

Ferric hydrate. Chloride of calcium.

This is the official process, and may be imitated on the small scale after adding a minute piece of iron to a fragment of the marble before dissolving in acid.

The names, formulæ, and reactions of these compounds of iron will be best understood when that metal comes under treatment.

Oxide of Calcium (Quick Lime).

Second Synthetical Reaction.—Place a small piece of chalk in a strong grate-fire or furnace and heat until a trial fragment, chipped off from time to time and cooled, no longer effervesces on the addition of acid; caustic lime, CaO (*Calx*, B. P. and U. S. P.), remains.

$CaCO_3$	=	CaO	+	CO_2
Carbonate of calcium (chalk).		Oxide of calcium (lime).		Carbonic acid gas.

Note.—Etymologically considered, this action is anylytical (*ἀναλύω*, *analuo*, I resolve) and not synthetical (*σύνθεσις*, *sūnthesis*, a putting together); but conventionally it is synthetical, and not analytical; for in this, the usual sense, and the sense in which the words are used throughout this book, synthesis is the application of chemical action with the view of producing something, analysis the application of chemical action with the view of finding out the composition of a substance. In the etymological view of the matter there is scarcely an operation performed either by the analyst or by the manufacturer but includes both analysis and synthesis.

Lime-kilns.—On the large scale the above operation is carried on in what are termed *lime-kilns* (*Kiln*, Saxon, *cyln*, from *cylene*, a furnace).

Hydrate of Calcium (Slaked Lime).

Slaked Lime.—When cold, add to the lime about half its weight of water, and notice the evolution of steam and

other evidence of strong action; the product is *slaked* lime or hydrate of calcium (Ca2HO) (*Calcis hydras*, B. P.), with whatever slight natural impurities the lime might contain. The slaking of hard or "stony" lime may be accelerated by using hot water.

CaO	+	H_2O	=	Ca2HO
Lime.		Water.		Hydrate of calcium (slaked lime).

Lime-water.—Place the hydrate of calcium in about a hundred times its weight of water: in a short time a saturated solution, known as *lime-water* (*Liquor Calcis*, B. P. and U. S. P.), results. It contains about 16 grains of hydrate of calcium (Ca2HO), equivalent to about 11 or 12 grains of lime (CaO), in one pint.

Strong Solution of Lime.—Slaked lime is much more soluble in aqueous solution of sugar than in pure water. The *Liquor Calcis Saccharatus*, B. P., is such a solution, containing 2 ounces of sugar and 188 grains of hydrate of calcium (Ca2HO), equivalent to 142 grains of lime (CaO), in 1 pint. It is a more efficient precipitant of hydrates and carbonates than lime-water. The official process is as follows: Mix 1 ounce of lime and 2 of sugar by trituration in a mortar. Transfer the mixture to a bottle containing 1 pint of water, and, having closed this with a cork, shake it occasionally for a few hours. Finally separate the clear solution with a siphon and keep it in a stoppered bottle.

Solutions of hydrate of calcium absorb carbonic acid gas on exposure to air, a semicrystalline precipitate of carbonate being deposited. When the saccharated solution is heated, there is precipitated a compound of three molecules of lime with one of sugar.

Carbonate of Calcium.

Third Synthetical Reaction.—To a solution of chloride of calcium add excess of carbonate of sodium, or about 5 parts of dry chloride to 13 of carbonate; a white precipitate of carbonate of calcium (*Calcii Carbonas Præcipitata*, U. S. P.), ($CaCO_3$) results. If the solutions of the salts be made hot before admixture, and the whole set aside for a short time, the particles aggregate to a greater extent than when cold water is used, and the product is finely granular or slightly crystalline. The official variety is thus prepared.

$CaCl_2$	+	Na_2CO_3	=	$CaCO_3$	+	2NaCl
Chloride of calcium.		Carbonate of sodium.		Carbonate of calcium.		Chloride of sodium.

Collect and purify this *Precipitated Chalk* by pouring the mixture into a paper cone supported by a funnel, and,

when the liquid has passed through the filter, pour water over the precipitate three or four times until the whole of the chloride of sodium is washed away. This operation is termed *washing a precipitate*. When dry (*vide* Index, "Drying precipitates") the precipitate is fit for use.

Filtering-paper, or *bibulous-paper* (from *bibo*, to drink), is simply good unsized paper made from the best white rags—white blotting-paper, in fact, of unusually good quality. Students' or analysts' filters, on which to collect precipitates, are round pieces of this paper, from three to six inches in diameter, twice folded, and then opened out so as to form a hollow cone. Square pieces are rounded by scissors *after* folding. The cone is supported by a glass or earthenware funnel.

Washing-bottle.—Precipitates are best washed by a fine jet of water directed on to the different parts of the filter. A common narrow-necked bottle of about half-pint capacity is fitted with a cork; two holes are bored through the cork, the one for a glass tube reaching to the bottom of the bottle within, and externally bent to a slightly acute angle, the other for a tube bent to a slightly obtuse angle, the inner arm terminating just within the bottle. The outer arms may be about 3 inches in length. The extremity of the outer arm continuous with the long tube should be previously drawn out to a fine capillary opening by holding the original tube, before cutting, in a flame, and, when soft, gently pulling the halves away from each other until the heated portion is reduced to the thinness of a knitting-needle. The tube is now cut at the thin part by a file, and the sharp edges rounded off by placing in a flame for a second or two. The outer extremity of the shorter tube should also be made smooth in the flame. The apparatus being put together, and the bottle nearly filled with water, air, blown through the short tube by the lungs, forces water out in a fine stream at the capillary orifice.

Decantation.—Precipitates may also be washed by allowing them to settle, pouring off the supernatant liquid, agitating with water, again allowing to settle, and so on. This is washing by *decantation* (*de*, from, *canthus*, an edge). If a stream of liquid flowing from a basin or other vessel exhibits any tendency to run down the outer side of the vessel, it should be guided by a glass rod placed against the point whence the stream emerges.

If the vessel be too large to handle with convenience, the wash-water may be drawn off by a *siphon*. A siphon is a tube of glass, metal, gutta-percha, or India-rubber, bent into the form of a V or U, filled with water, and inverted; one end immersed in the wash-water, and the other allowed to hang over the side of the vessel; so long as the outer orifice of the instrument is below the level of the liquid in the vessel, so long will that liquid flow from within outwards until the vessel be empty.*

* *The nature of the action of a syphon* is simple. The column of water in the outer limb is longer, and therefore heavier, than the column of similar area in the inner limb. (The length of the inner limb must be reckoned from the surface of the liquid, the portion

Prepared carbonate of calcium (*Creta Præparata*, B. P. and U. S. P.) is merely washed chalk (*Creta*, B. P. and U. S. P.) or *whiting*, only that in Pharmacy fashion demands that the chalk be in little conical lumps, about the size of thimbles, instead of in the larger rolls characteristic of "whiting." Wet whiting pushed, portion by portion, through a funnel, and each separately dried, gives the conventional *Creta Præparata*. Its powder is amorphous.

Testa Præparata, U. S. P., is powdered oyster-shell, similarly treated. It is an inferor kind of prepared chalk.

Phosphate of Calcium.

Fourth Synthetical Reaction.—Digest bone-ash (bones burnt in an open crucible with free access of air till all animal and carbonaceous matter has been removed—impure phosphate of calcium (*Os Ustum*, B. P.)) with nearly twice its weight of hydrochloric acid (diluted with three or four times its bulk of water) in a test-tube or larger vessel; the phosphate is dissolved.

$$\underset{\text{Phosphate of calcium (impure).}}{Ca_3 2PO_4} + \underset{\text{Hydrochloric acid.}}{4HCl} = \underset{\text{Acid phosphate of calcium.}}{CaH_4 2PO_4} + \underset{\text{Chloride of calcium.}}{2CaCl_2}$$

Dilute with water, filter, boil, and when cold add excess of solution of ammonia; the phosphate of calcium, now pure (*Calcis Phosphas*, B. P.; *Calcii Phosphas Precipitata*, U. S. P.), is reprecipitated as a light white amorphous powder. After well washing, the precipitate should be dried over *a water-bath* (*vide* Index), or at a temperature not exceeding 512°, to prevent undue aggregation of the particles.

$$\underset{\text{Acid phosphate of calcium.}}{CaH_4 2PO_4} + \underset{\text{Chloride of calcium.}}{2CaCl_2} + \underset{\text{Ammonia.}}{4AmHO} = \underset{\text{Phosphate of calcium (pure).}}{Ca_3 2PO_4} + \underset{\text{Chloride of ammonium.}}{4AmCl} + \underset{\text{Water.}}{4H_2O}$$

Bone-ash or bone-earth contains small quantities of carbonate and sulphide of calcium. These are decomposed in the above process by the acid, chloride of calcium being formed; on boiling the mixture, carbonic acid gas and sul-

below the surface playing no part in the operation). Being heavier, it naturally falls by gravitation, the liquid in the shorter limb instantly following, because pressed upwards by the air. The air, be it observed, exerts a similar amount of pressure on the liquid in the outer limb: in short, atmospheric pressure causes the retention of liquid in the instrument, while gravitation determines the direction of the flow.

phuretted hydrogen gas are evolved. Any carbonaceous or siliceous matter, etc., is removed by filtration. In bones the phosphate of calcium is always accompanied by a small quantity of an allied substance, phosphate of magnesium; a trace of fluoride of calcium (CaF_2) is also present.

Bone-black, or *Animal Charcoal* (*Carbo Animalis*, B. P. and U. S. P.), is the residue obtained on subjecting dried bones (*Os*, U. S. P.) to a red heat without access of air. The operation may be imitated by heating a few fragments of bone in a covered porcelain crucible in a fume-chamber until smoke and vapor cease to be evolved. Purified Animal Charcoal (*Carbo Animalis Purificatus*, B. P. and U. S. P.) is obtained by digesting animal charcoal (16 parts) in hydrochloric acid (10 parts) and water (20 parts) in a warm place for a day or two, filtering, thoroughly washing, drying over a water-bath, and igniting the product in a closely covered crucible. The reaction is the same as that just described; that is to say, the acid removes the phosphate of calcium from the carbon of animal charcoal by forming soluble acid phosphate and chloride of calcium.

Wood Charcoal (*Carbo Ligni*, B. P. and U. S. P.) is wood similarly ignited without access of air.

Decolorizing power of Animal Charcoal.—Animal charcoal, in small fragments, is the material employed in decolorizing solutions of common brown sugar with the view of producing white lump sugar. Its power and the nearly equal power of an equivalent quantity of the purified variety may be demonstrated on solution of litmus or logwood.

Phosphate of Sodium.—Phosphate of calcium is converted into phosphate of sodium (*Sodii Phosphas*, U. S. P.) ($Na_2HPO_4,12H_2O$) as follows: Mix, in a mortar, 3 ounces of ground bone-earth with 1 fluidounce of sulphuric acid; set aside for twenty-four hours to promote reaction; mix in about 3 ounces of water, and put in a warm place for two days, a little water being added to make up for that lost by evaporation; stir in another 3 ounces of water, warm the whole for a short time, filter, and wash the residual sulphate of calcium on the filter to remove adhering acid phosphate of calcium; concentrate the *filtrate* (the liquid portion), which is a solution of acid phosphate of calcium, to about 3 ounces, filter again, if necessary, add solution of (about $4\frac{1}{2}$ ounces of crystals of) carbonate of sodium to the hot filtrate until a precipitate (a phosphate of calcium,

$CaHPO_4$), ceases to form, and the fluid is faintly alkaline; filter, evaporate, and set aside to crystallize.

Phosphate of sodium occurs "in transparent colorless rhombic prisms, terminated by four converging planes, efflorescent, tasting like common salt." One part in ten of water constitutes "Solution of Phosphate of Soda," B. P. This is an official as well as the ordinary process. The following equations show the two decompositions which occur during the operations:—

$$\underset{\text{Phosphate of calcium}}{Ca_3 2PO_4} + \underset{\text{Sulphuric acid.}}{2H_2SO_4} = \underset{\text{Acid phosphate of calcium.}}{CaH_4 2PO_4} + \underset{\text{Sulphate of calcium.}}{2CaSO_4}$$

$$\underset{\text{Acid phosphate of calcium.}}{CaH_4 2PO_4} + \underset{\text{Carbonate of sodium.}}{Na_2CO_3} = \underset{\text{Phosphate of sodium.}}{Na_2HPO_4} + \underset{\text{Water.}}{H_2O}$$

$$+ \underset{\text{Carbonic acid gas.}}{CO_2} + \underset{\text{Phosphate of calcium.}}{CaHPO_4}$$

Ordinary phosphate of sodium (Na_2HPO_4, $12H_2O$) effloresces rapidly in the air until nearly half its water has escaped, when it has a permanent composition represented by the formula Na_2HPO_4, $7H_2O$.

Hypochlorite of Calcium.

Fifth Synthetical Reaction.—Pass chlorine, generated as already described, into damp slaked lime contained in a piece of wide tubing, open at the opposite end to that in which the delivery-tube is fixed. (A test-tube, the bottom of which has been accidentally broken, is very convenient for such operations.) The product is ordinary *bleaching-powder*, said to be a mixture of hypochlorite and chloride of calcium, commonly called *chloride of lime*, *Calx chlorata*, B. P. (*Calx Chlorinata*, U. S. P.).

$$\underset{\text{Black oxide of manganese.}}{MnO_2} + \underset{\text{Hydrochloric acid.}}{4HCl} = \underset{\text{Chloride of manganese.}}{MnCl_2} + \underset{\text{Water.}}{2H_2O} + \underset{\text{Chlorine.}}{Cl_2}$$

$$\underset{\text{Hydrate of calcium.}}{2CaH_2O_2} + \underset{\text{Chlorine.}}{2Cl_2} = \underset{\text{Water.}}{2H_2O} + \underset{\text{Hypochlorite of calcium.}}{CaCl_2O_2} , \underset{\text{Chloride of calcium.}}{CaCl_2}$$

Chlorinated lime, exposed to air and moisture, as in disinfecting the air of sick rooms, slowly yields hypochlorous acid ($HClO$). Free hypochlorous acid soon breaks up into water, chloric acid ($HClO_3$), and free chlorine. Chloric acid is also unstable, decomposing into oxygen, water, chlorine, and perchloric acid ($HClO_4$). The small quantity of hypochlorous acid, diffused through an apartment when

bleaching-powder is exposed thus, yields fourteen-fifteenths of its chlorine in the form of chlorine gas—one of the most efficient of known disinfectants.

Bleaching-liquor.—Digest chlorinated lime in water, in which the bleaching compound is soluble, filter from the undissolved lime, and test the bleaching-powers of the clear liquid by adding a few drops to a decoction of log-wood slightly acidulated. One pound of this bleaching-powder, shaken several times during three hours, with 1 gallon of water, forms Solution of Chlorinated Lime (*Liquor Calcis Chloratæ*, B. P.).

Gummate of Calcium.

Gummate of Calcium is the only official calcium salt that remains to be noticed. This compound is, in short, *arabin*, the ordinary Gum-Acacia, or Gum-Arabic (*Acaciæ Gummi*, B. P., and U. S. P.), a substance too well known to need description. A solution of gum-arabic in water (*Mucilago Acaciæ*, B. P. and U. S. P.) yields a white precipitate of oxalate of calcium on the addition of solution of oxalate of ammonium. Or a piece of gum burnt to an ash in a porcelain crucible yields a calcareous residue, which, dissolved in dilute acids, affords characteristic reactions with any of the following analytical reagents for calcium. The gummic radical may be precipitated as opaque gelatinous gummate of lead by the addition of solution of oxyacetate of lead (*Liquor Plumbi Subacetatis*, B. P.) to an aqueous solution of gum. These statements may be experimentally verified by the practical student.

Tragacanth (*Tragacantha*, B. P. and U. S. P.) is usually considered to be a mixture of soluble gum or arabin and a variety of calcium gum insoluble in water, termed *bassorin:* Guibourt thought it to be gelatinoid. With water a gelatinous mucilage is formed (*Mucilago Tragacanthæ*, B. P. and U. S. P.).

Reactions having Analytical Interest (Tests).

First Analytical Reaction.—Add sulphuric acid, highly diluted, to a calcium solution contained in a test-tube or small test-glass; sulphate of calcium ($CaSO_4$, $2H_2O$) is formed, but is *not* precipitated, it being, unlike sulphate of barium, slightly soluble in water.

Solution of Sulphate of Calcium.—A quarter of an ounce of that (dried) form of sulphate of calcium known as plaster of Paris ($CaSO_4$)

digested in one pint of water for a short time, with occasional shaking, and the mixture filtered, yields the official test-liquid termed "Solution of Sulphate of Lime," B. P. About 400 parts of the solution contain 1 of sulphate of calcium.

Second Analytical Reaction.—Add yellow chromate of potassium (K_2CrO_4) to a calcium solution slightly acidified with acetic acid; chromate of calcium ($CaCrO_4$) is probably formed, but it is *not* precipitated. Barium is precipitated by the chromic radical.

These two negative reactions are most valuable in analysis, as every precipitant of calcium is also a precipitant of barium; but the above two reagents are precipitants of barium only. Hence calcium, which when alone can be readily detected by the following reactions, cannot by any reaction be detected in the presence of barium. But by the sulphuric or chromic test barium is easily removed, and then either of the following reagents will throw down the calcium.

Other Analytical Reactions.—Add carbonate of ammonium, phosphate of sodium, arseniate of ammonium, and oxalate of ammonium to calcium solutions as described under the analytical reactions of barium, and write out descriptive equations. The precipitates correspond in appearance to those of barium; their constitution is also identical, hence their correct formulæ can easily be deduced. Of these precipitants oxalate of ammonium is that most commonly used as a reagent for calcium salts, barium being absent. The oxalate of calcium is insoluble in acetic, but soluble in hydrochloric or nitric acids.——Calcium compounds impart a reddish color to the flame.

QUESTIONS AND EXERCISES.

143. Enumerate some of the common natural compounds of calcium.

144. Explain, by an equation, the action of hydrochloric acid on marble. What official compounds result?

145. Why is chloride of calcium used as a desiccator for gases?

146. How would you purify Chloride of Calcium which has been made from ferruginous marble? Give diagrams.

147. Write a few lines on the chemistry of the lime-kiln.

148. In what sense is the conversion of chalk into lime an analytical action?

149. What occurs when lime is slaked?

150. To what extent is lime soluble in water? to what in syrup?

151. Describe the preparation of the official Precipitated Carbonate of Calcium; in what does it differ from Prepared Chalk?

152. In what does filtering-paper differ from other kinds of paper?
153. Explain the construction of "a washing bottle" for cleansing precipitates by water.
154. Define *decantation*.
155. Describe the construction and manner of employment of a siphon.
156. Explain the mode of action of a siphon.
157. What is the difference between Bone, Bone-earth, and Precipitated Phosphate of Calcium?
158. How is "Bone-earth" purified for use in medicine?
159. Explain the action of hydrochloric acid on Animal Charcoal in the conversion of *Carbo Animalis* into *Carbo Animalis Purificatus*.
160. What is the chemical difference between *Carbo Animalis* and *Carbo Ligni?*
161. Give equations showing the conversion of Phosphate of Calcium into Phosphate of Sodium.
162. Write a short article on the manufacture, composition, and uses of "bleaching-powder."
163. How may calcium be detected in Gum-Arabic?
164. State the chemical nature of Tragacanth.
165. To what extent is sulphate of calcium soluble in water?
166. Can calcium be precipitated from an aqueous solution containing barium?
167. Barium being absent, what reagents may be used for the detection of calcium? Which is the chief test?

MAGNESIUM.

Symbol Mg. Atomic weight 24.

Source.—Magnesium is abundant in nature in the form of magnesian or mountain limestone, or *dolomite*, a double carbonate of magnesium and calcium in common use as a building-stone (*e. g.* the Houses of Parliament, and the School of Mines in London), and *magnesite*, a tolerably pure carbonate of magnesium, though too "stony" for direct use in medicine, even if very finely powdered. Chloride of magnesium and sulphate of magnesium (Epsom salt) also occur in sea-water and the water of many springs. Metallic magnesium may be obtained from the chloride by the action of sodium. It burns readily in the air, emitting a dazzling light due to the white heat to which the resulting particles of magnesia (MgO) are exposed. The chloride employed as a source of the metal is obtained by dissolving the carbonate in hydrochloric acid, adding some chloride of ammonium, evaporating to dryness, heating the residue in a flask (on the small scale a large test-tube or Florence flask) until the chloride of ammonium is all volatilized and the chloride of magnesium remains as a clear fused liquid. The latter is poured on to a clean earthenware slab. The chloride of ammonium prevents reaction between chloride of magnesium and water in the last stages of the

operation and consequent formation of oxide (or oxychloride) of magnesium and hydrochloric acid gas.

Quantivalence.—The atom of magnesium is bivalent, Mg″.

Reactions having Synthetical Interest.

Sulphate of Magnesium.

First Synthetical Reaction.—To a few drops of sulphuric acid and a little water in a test-tube (or to larger quantities in larger vessels), add carbonate of magnesium (preferably the native carbonate *magnesite*, $MgCO_3$) until effervescence ceases, subsequently boiling to aid in the expulsion of the carbonic acid gas. The filtered liquid is a solution of sulphate of magnesium ($MgSO_4$), crystals of which, *Epsom salt* ($MgSO_4$, $7H_2O$) (*Magnesii Sulphas*, U. S. P.), may be obtained on evaporating most of the water, and setting the concentrated solution aside to cool. This is an ordinary manufacturing process. Instead of magnesite, *dolomite*, the common magnesian limestone ($CaCO_3$, $MgCO_3$) may be employed, any iron being removed by evaporating the solution (filtered from the sulphate of calcium produced) to dryness, gently igniting to decompose sulphate of iron, dissolving in water, filtering from oxide of iron, and crystallizing.

$MgCO_3$	+	H_2SO_4	=	$MgSO_4$	+	H_2O	+	CO_2
Carbonate of magnesium.		Sulphuric acid.		Sulphate of magnesium.		Water.		Carbonic acid gas.

Sulphate of magnesium readily crystallizes in large, colorless, transparent, rhombic prisms; but, from concentrated solutions, the crystals are deposited in short thin needles, a form more convenient for manipulation, solution, and general use in medicine.

Iron may be detected in sulphate of magnesium by adding the common alkaline solution of chlorinated lime or chlorinated soda to an aqueous solution of the salt; brown hydrate of iron ($Fe_2$6HO) being precipitated. Sulphydrate of ammonium will also give a black precipitate if iron be present.

Carbonates of Magnesium.

Second Synthetical Reaction.—To solution of sulphate of magnesium add solution of carbonate of sodium and boil; the resulting precipitate is *light* carbonate of magnesium (*Magnesiæ Carbonas Levis*, B. P., *Magnesii Carbonas*, U. S. P.), a white, partly amorphous, partly minutely crystalline mixture of carbonate and hydrate of magnesium ($3MgCO_3$, Mg2HO, $4H_2O$). A denser, slightly granular

precipitate of similiar chemical composition (*Magnesiæ Carbonas*, B. P.) is obtained on mixing strong solutions of the above salts, evaporating to dryness, then removing the sulphate of sodium by digesting the residue in hot water, filtering, washing, and drying the precipitate.

$$\underset{\text{Sulphate of magnesium.}}{4MgSO_4} + \underset{\text{Carbonate of sodium.}}{4Na_2CO_3} + \underset{\text{Water.}}{H_2O} = \underset{\text{Official carbonate of magnesium.}}{3MgCO_3, Mg2HO} + \underset{\text{Sulphate of sodium.}}{4Na_2SO_4} + \underset{\text{Carbonic acid gas.}}{CO_2}$$

The official proportions for the light carbonate are 10 of sulphate of magnesium and 12 of crystals of carbonate of sodium, each dissolved in 80 of cold water, the solutions mixed, boiled for 15 minutes, the precipitate collected on a filter, well washed, drained, and dried over a water-bath. The heavier carbonate is made with the same proportions of salts, each dissolved in 20 instead of 80 of water, the mixture evaporated quite to dryness, and the residue washed by decantation or filtration until all sulphate of sodium is removed (shown by a white precipitate—sulphate of barium—ceasing to form on the addition of solution of chloride or nitrate of barium to a little of the filtrate).

Third Synthetical Reaction.—Pass carbonic acid gas, generated as described on page 61, into a mixture of water and carbonate of magnesium contained in a test-tube. After some time, separate undissolved carbonate by filtration; the filtrate contains carbonate of magnesium dissolved by carbonic acid. When of a strength of about 13 grains in one ounce, the solution constitutes "*Fluid Magnesia*" (*Liquor Magnesiæ Carbonatis*, B. P.).

Officially, 1 pint is directed to be made from freshly prepared carbonate. The latter is obtained by adding a hot solution of 2 ounces of sulphate of magnesium in half a pint of water to one of 2½ ounces of crystals of carbonate of sodium in another half pint of water, boiling the mixture for a short time (to complete decomposition), filtering, thoroughly washing the precipitate, placing the latter in 1 pint of distilled water, and transmitting carbonic acid gas through the liquid (say, at the rate of three or four bubbles per second) for an hour or two, then leaving the solution in contact with the gas under slight pressure for twenty-four hours, and, finally, filtering from undissolved carbonate, and, after passing in a little more gas, keeping in a well-corked bottle. Slight pressure is best created by placing the carbonate and water in a bottle fitted with a cork and tubes as for a wash-bottle (p. 81 or 93), conveying the gas by a tube which reaches to the bottom, and allowing excess of gas to flow out by the upper tube, the external end of which is continued to the bottom of a common phial containing about an inch of mercury.

The phial should be loosely plugged with cotton-wool, to prevent loss of metal by spurting during the flow of the gas through it. (Each inch in depth of mercury through which the gas escapes corresponds to about half-a-pound pressure on every square inch of surface within the apparatus.)

Heat a portion of the solution; true carbonate of magnesium containing combined water ($MgCO_3,3H_2O$) is precipitated. The water in this compound is probably in the state of water of crystallization, for a salt having the same composition is deposited in crystals by the spontaneous evaporation of the solution of carbonate of magnesium. The official "carbonate" ($3MgCO_3,Mg2HO,4H_2O$) is another of these very common *hydrous* compounds.

Exposed to cold, the solution of "fluid magnesia" sometimes affords large thick crystals ($MgCO_3,5H_2O$), which, in contact with the air, lose water, become opaque, and then have the composition of those deposited by evaporation ($MgCO_3,3H_2O$).

Liquor Magnesii Citratis, U. S. P., is a solution of carbonate of magnesium and bicarbonate of potassium in excess of citric acid and syrup of citric acid.

Oxide of Magnesium (Magnesia).

Fourth Synthetical Reaction.—Heat light dry carbonate of magnesium in a porcelain crucible over a lamp (or in a larger earthen crucible in a furnace) till it ceases to effervesce on adding, to a small portion, water and acid; the residue is light magnesia (MgO) (*Magnesia Levis*, B. P.). The same operation on the heavy carbonate yields heavy magnesia (MgO) (*Magnesia*, B. P). Both are sometimes spoken of as "calcined magnesia" (*Magnesia*, U. S. P.) A given weight of the official light magnesia occupies three and a half times the bulk of the weight of heavy magnesia.

$3MgCO_3,Mg2HO$	=	$4MgO$	+	H_2O	+	$3CO_2$
Official carbonate of magnesium.		Oxide of magnesium.		Water.		Carbonic acid gas.

A trace only of magnesia is dissolved by pure water. Moisten a grain or two of magnesia with water, and place the paste on a piece of red litmus-paper; the wet spot, after a time, becomes blue, showing that the magnesia is slightly soluble.

Reactions having Analytical Interest (Tests).

First Analytical Reaction.—Add solution of hydrate or carbonate of ammonium to a magnesian solution (sulphate for example) and boil the mixture in a test-tube; the precipitation of part only of the magnesium as hydrate (Mg2HO) or carbonate ($MgCO_3$) occurs. Add now to a

small portion of the mixture of precipitate and liquid a considerable excess of solution of chloride of ammonium; the precipitate is dissolved.

This is an important reaction, especially as regards carbonate of magnesium, the presence of chloride of ammonium enabling the analyst to throw out from a solution barium and calcium by an alkaline carbonate, magnesium being retained. The cause of this reaction is the tendency of magnesium to form soluble double salts with potassium, sodium, or ammonium. In analysis, the chloride of ammonium should be added before the carbonate, as it is easier to prevent precipitation than to redissolve a precipitate once formed.

Second Analytical Reaction.—To some of the solution resulting from the last reaction, add solution of phosphate of sodium or ammonium; phosphate of magnesium and ammonium ($MgNH_4PO_4$) is precipitated.——3*d*. To another portion add arseniate of ammonium; arseniate of magnesium and ammonium ($MgNH_4AsO_4$) is precipitated.

Note.—Barium and calcium are also precipitated by alkaline phosphates and arseniates. The other precipitants of magnesium are also precipitants of barium and calcium. In other words, there is no *direct* test for magnesium. Hence the analyst always removes any barium or calcium by an alkaline carbonate, as above indicated; the phosphate of sodium or arseniate, or phosphate of ammonium, then become very delicate tests of the presence of magnesium. In speaking of magnesium tests, the absence of barium and calcium salts is to be understood.

QUESTIONS AND EXERCISES.

168. Name the natural sources of the various salts of magnesium.
169. Give a process for the preparation of Epsom salt.
170. Draw diagrams illustrative of the formation of sulphate of magnesium from *magnesite* and from *dolomite*.
171. Show by an equation the process for the preparation of the official Carbonate of Magnesium.
172. What circumstances determine the two different states of aggregation of the *Magnesiæ Carbonas* and *Magnesiæ Carbonas Levis?*
173. What are the relations of *Magnesia* and *Magnesia Levis* to the official Carbonates of Magnesium?
174. How much denser is the one than the other?
175. Is magnesia soluble in water?
176. How is "Fluid Magnesia" prepared?
177. Mention the effects of heat and cold on "Fluid Magnesia."
178. How much magnesia (MgO) can be obtained from 100 grains of Epsom Salt?

179. Calculate the amount of official Carbonate of Magnesium which will yield 100 grains of magnesia.

180. Can magnesium be detected in presence of barium and calcium?

181. Describe the analysis of an aqueous liquid containing salts of barium, calcium, and magnesium.

182. How may magnesium be precipitated from solutions containing ammoniacal salts?

Quantivalence.

On reviewing the foregoing statements regarding compounds of the three univalent radicals, potassium, sodium, and ammonium, and the three bivalent elements, barium, calcium, and magnesium, the doctrine of quantivalence will be more clearly understood, and its usefulness more apparent. Quantivalence, or the value of atoms, is, in short, in chemistry, closely allied to value in commercial barter. A number of articles, differing much in weight, appearance, and general characters, may be of equal money value; and if these be regarded, for convenience, as having a sort of unit of value, others worth double as much might be termed bivalent, three times as much trivalent, and so on. In like manner, chemical radicals, no matter whether elementary, like potassium (K), iodine (I), or sulphur (S), or compound, like those of nitrates (NO_3), sulphates (SO_4), or acetates ($C_2H_3O_2$), have a given chemical value in relation to each other, and are exchangeable for, and will unite with each other to an extent determined by that value.

Most chemical salts apparently, though probably not really, have two parts, a basylous and an acidulous, the one quantivalently balancing the other. The formulæ of the chief of these radicals and their quantivalence are given below. Examples of formulæ of salts containing univalent, bivalent, and trivalent radicals are also appended.

Quantivalence of Common Radicals.

Univalent Radicals, or Monads.		Bivalent Radicals, or Dyads.		Trivalent Radicals, or Triads.	
Acidulous.	Basylous.	Acidulous.	Basylous.	Acidulous.	Basylous.
H	H	O	Ca	PO_4	As
Cl	K	SO_4	Mg	BO_3	Sb
I	Na	CO_3	Zn	$C_6H_5O_7$	Bi
HO	NH_4	C_2O_4	Cu	AsO_3	Fe^{iii}(ic) or Fe^{vi}_2(ic)
NO_3	Ag	$C_4H_4O_6$	Hg(ic)	AsO_4	
$C_2H_3O_2$	Hg(ous)	S	Fe(ous)	$C_4H_3O_5$	

Note.—The hydrogen (H) in the basylous parts of salts has entirely different functions to the hydrogen (H) in the acidulous part.

The latter gives compounds commonly termed *hydrides* (*e. g.* CuH_2); in the former the element is the basylous radical of acids (*e. g.* HCl, H_2SO_4). In compound radicals, *e. g.* $C_2H_3O_2$ or NH_4, the properties of hydrogen are no longer apparent: the chemical force resident with the atoms of such radicals seems to be mainly exerted in binding those atoms together.

Examples of Formulæ containing Univalent, Bivalent, and Trivalent Radicals.

The reader will find instructive practice in writing twenty or thirty imaginary formulæ of salts by placing in juxtaposition acidulous and basylous radicals, as in the following examples. Just as in a pair of scales a 2-lb. weight must be balanced by two 1-lb. weights, or a 4-lb. weight by two 2-lb. weights, or by one 3-lb. and one 1-lb. weight, so a bivalent radical unites with a bivalent radical or with two univalent radicals, a quadrivalent radical with two bivalent radicals, or with one trivalent and one univalent radical, and so on.

(R = any basylous Radical.) (*R* = any acidulous Radical.)

General formula.	*Examples.*
R′*R*′	KI, NaCl, $NH_4C_2H_3O_2$, $AgNO_3$.
R″*R*′$_2$	$CaCl_2$, Zn2$C_2H_3O_2$, Pb2NO_3($BaNO_3C_2H_3O_2$).
R‴*R*′$_3$	Bi3NO_3, AsH_3, $SbCl_3$.
R′$_2$*R*″	K_2CO_3, Na_2SO_4, $H_2C_4H_4O_6$.
R′R*R*″	$KHCO_3$, $NaHSO_4$, $KHC_4H_4O_6$.
R′$_3$*R*‴	Am_3PO_4, $K_3C_6H_5O_7$, H_3AsO_3.
R′$_2$R′*R*‴	Na_2HPO_4, Na_2HAsO_4.
R″*R*″	$CaCO_3$, MgO, $CuSO_4$, HgO, $FeSO_4$.
R″$_3$*R*‴$_2$	$Ca_3$2PO_4. $Ca_3$2$C_6H_5O_7$.
R″R′*R*‴	$MgAmPO_4$, $CuHAsO_3$.
R‴*R*″*R*	$BiONO_3$.
R‴$_2$*R*″$_2$*R*″	$Bi_2O_2CO_3$.
R‴$_2$*R*″$_3$	As_2O_3, Sb_2O_3.
R‴*R*‴	$BiC_6H_5O_7$.
R‴$_2$*R*′$_6$	Fe_2Cl_6, $Fe_2$6NO_3, $Fe_2$6$C_2H_3O_2$.
R‴$_2$*R*″$_3$	Fe_2O_3, $Fe_2$3SO_4.

Quadrivalent Radicals or Tetrads, Quinquivalent Radicals or Pentads, and Sexivalent Radicals or Hexads, are known.

EXERCISE.

183. Write an exposition of the doctrine of Quantivalence within the limits of a sheet of note paper.

DIRECTIONS FOR APPLYING THE FOREGOING ANALYTICAL REACTIONS TO THE ANALYSIS OF AN AQUEOUS SOLUTION OF A SALT OF ONE OF THE METALS, BARIUM, CALCIUM, MAGNESIUM.

Add yellow chromate of potassium to a portion of the solution to be examined; a precipitate indicates barium.

If no barium is present, add chloride and carbonate of ammonium, and boil; a precipitate indicates calcium.

If barium and calcium are proved to be absent, add chloride of ammonium, ammonia, and then either phosphate of sodium or arseniate of ammonium; a white granular precipitate indicates magnesium.

Ammonia is here added to yield the necessary elements to ammonio-magnesian phosphate or ammonio-magnesian arseniate, both of which are highly characteristic precipitates; and chloride of ammonium is added to prevent a mere partial precipitate of the magnesium by the ammonia.

DIRECTIONS FOR APPLYING THE FOREGOING ANALYTICAL REACTIONS TO THE ANALYSIS OF AN AQUEOUS SOLUTION OF ONE, TWO, OR ALL THREE OF THE METALS, BARIUM, CALCIUM, MAGNESIUM.

Add chromate of potassium to the solution; barium, if present, is precipitated. Filter, if necessary, and add to the *filtrate* (that is, the liquid which has run through the filter) chloride, hydrate, and carbonate of ammonium, and boil; calcium, if present, is precipitated. Filter, if requisite, and add phosphate of sodium; magnesium, if present, is precipitated.

Note.—Red chromate of potassium must not be used in these operations, or a portion of the barium will remain in the liquid and be thrown down with, or in place of, the carbonate of calcium (*vide* p. 88). The yellow chromate must not contain carbonate of potassium, or calcium will be precipitated with, or in place of, barium. The absence of carbonate is proved by the non-occurrence of effervescence on the addition of hydrochloric acid to a little of the solution of the chromate, previously made hot in a test-tube. If the yellow chromate has been prepared by adding excess of ammonia to solution of red chromate of potassium, its addition to the liquid to be analyzed must be preceded by that of solution of chloride of ammonium; the precipitation of a portion of the magnesium (by the free ammonia in the yellow chromate) is thus prevented, for chloride of ammonium solution is a good solvent of hydrate (and carbonate) of magnesium.

TABLE OF SHORT DIRECTIONS FOR APPLYING THE FOREGOING ANALYTICAL REACTIONS TO THE ANALYSIS OF AN AQUEOUS SOLUTION OF SALTS CONTAINING ANY OR ALL OF THE METALLIC ELEMENTS HITHERTO CONSIDERED.

To the solution add AmCl, AmHO, Am_2CO_3; boil and filter.

Precipitate Ba Ca. Wash, dissolve in $HC_2H_3O_2$, add K_2CrO_4, and filter.		Filtrate Mg Am Na K. Add Am_2HPO_4, shake, filter.	
Precipitate Ba	Filtrate Ca. Test by $Am_2C_2O_4$.	Precipitate Mg.	Filtrate Am Na K. Evap. to dryness, ignite, dissolve residue in water. Test for K by $PtCl_4$. Test for Na by flame. Test orig. sol. for Am.

Note 1.—The analysis of solutions containing the foregoing metals is commenced by the addition of chloride of ammonium (AmCl) and ammonia (AmHO), simply as a precautionary measure, the former compound preventing partial precipitation of magnesium, the latter neutralizing acids. The carbonate of ammonium (Am_2CO_3) is the important group-reagent—the precipitant of barium and calcium.

Note 2.—In the above, and in subsequent charts of analytical processes, the leading precipitants will be found to be ammonium salts. These, being volatile, can be got rid of towards the end of the operations, and thus the detection of potassium and sodium be in no way prevented—an advantage which could not be had if such salts as chromate of potassium or phosphate of sodium were the group-precipitants employed.

Note 3.—Acetic, and not hydrochloric or nitric, acid is used in dissolving the barium and calcium carbonates, because chromate of barium, on the precipitation of which the detection of barium depends, is soluble in the stronger acids, and therefore could not be thrown down in their presence.

Note on Classification.—The compounds of barium, calcium, and magnesium, like those of the alkali metals, have many analogies; the carbonates, phosphates, and arseniates of each are insoluble, which sufficiently distinguishes them from the members of the class first studied. They possess, moreover, well-marked differences, so that their separation from each other is easy. The solubility of their hydrates in water marks their connection with the alkali metals; the slightness of that solubility, diminishing as we advance further and further from the alkalies, baryta being most and magnesia least

soluble in water, points to their connection with the next class of metals, the hydrates of which are insoluble in water. These considerations must not, however, be over-valued. Though the solubility of their hydrates places barium nearest and magnesium furthest from the alkali metals, the solubility of their sulphates gives them the opposite order, magnesium-sulphate being most soluble, calcium-sulphate next, strontium-sulphate third (strontium is a rarer element, which will be mentioned subsequently), and barium-sulphate insoluble in water. These elements are sometimes spoken of as the metals of the alkaline earths.

Note.—In connection with the bivalence of the metals Barium, Calcium, and Magnesium, it is interesting to note that just as bivalent acidulous radicals give salts containing two atoms of univalent basylous radicals (K_2SO_4, $NaHSO_4$, H_2CO_3, $KNaC_4H_4O_6$), so bivalent basylous radicals yield salts containing two atoms of univalent acidulous radicals, as seen in acetonitrate of barium, $BaC_2H_6O_2NO_3$, a salt which is a definite compound, and not a mere mixture of acetate with nitrate of barium. A very large number of such salts is known.

Distillation.

The water with which, in analysis, solution of a salt or dilution of a liquid is effected should be pure. Well or river-water (*Aqua*, U. S. P.) is unfit for the purpose, because containing alkaline and earthy salts (about 20 to 60 grains per gallon), derived from the soil through which the water percolates, and rain-water is not unfrequently contaminated with the dust and debris which fall on the roofs whence it is usually collected. Such water is purified by *distillation*, an operation in which the water is by ebullition converted into steam, and the steam condensed again to water in a separate vessel, the fixed earthy and other salts remaining in the vessel in which the water is boiled. On the large scale, ebullition is effected in metal boilers having a hood or head in which is a lateral opening through which passes the steam; on the small scale, either a common glass flask is employed, into the neck of which, by a cork, is inserted a glass tube bent to an acute angle, or a *retort* is used, a sort of long-necked Florence flask, dextrously bent near the body by the glass-worker to an appropriate angle (hence the name *retort*, from *retorqueo*, to bend back). *Condensation* is effected by surrounding the lateral steam-tube with cold water. In large stills the steam-tube, or *condensing-worm*, is usually a metal (tin) pipe, twisted into a spiral form for the sake of compactness, and so fixed in a tub that a few inches of one end of the pipe may pass through and closely fit a hole bored near the bottom of the tub. Cold water is kept in contact with the exterior of the pipe, provision being made for a continuous supply to the bottom, while the water heated by the condensing steams runs off from the top of the column. The condenser for a flask or retort may be a simple glass tube of any size, placed within a second much wider tube (a common long, narrow lamp-glass answers very well for experimental operations), the tube being connected at the extremities of the wider by bored corks; a stream of

water passes into one end of the inclosed space (the end furthest from the retort), through a small glass tube inserted in the cork, and out at the other through a similar tube. The common (Liebig's) form of laboratory condenser is a glass tube three-fourths of an inch wide and a yard long, surrounded by a shorter tin or zinc tube two inches in diameter, and having at each extremity a neck, through which the glass tube passes. The ends of the necks of the tin tube, and small portions of the glass tube near them, are connected by means of a strip of sheet caoutchouc carefully bound round. An aperture near the lower part of the tin tube provides for the admission of a current of cold water, and a similar aperture near the top allows the escape of heated water. The inner tube may thus constantly be surrounded by cold water, and heated vapors passing through it be perfectly cooled and condensed.

In distilling several gallons of water for analytical or medicinal purposes (*Aqua Destillata*, B. P. and U. S. P.), the first two or three pints should be rejected, because likely to contain ammoniacal and other volatile impurities.

Rectification is the process of redistilling a distilled liquid. *Rectified spirit* is spirit of wine thus treated.

Dry or *destructive distillation* is distillation in which the condensed products are directly formed by the decomposing influence of the heat applied to the dry or non-volatile substances in the retort or still.

EXERCISE.

184. Write from memory two or three paragraphs descriptive of *distillation*.

ZINC, ALUMINIUM, IRON.

These three elements are classed together for analytical convenience rather than for more general analogies.

ZINC.

Symbol Zn. Atomic weight 65.

Source.—Zinc is tolerably abundant in nature as sulphide (ZnS) or *blende*, and carbonate ($ZnCO_3$) or *calamine* (from *calamus*, a reed, in allusion to the appearance of the mineral). The ores are roasted to expel sulphur, carbonic acid gas, and some impurities, and the resulting oxide distilled with charcoal, when the metal vaporizes and readily condenses. Zinc is a brittle metal, but at a temperature somewhat below 300° F. is malleable, and may be rolled into thin sheets. Above 400° it is again brittle, and may then be pulverized. At 773° F. it melts, and at a bright red heat is volatile.

Uses.—Its use as a metal is familiar; alloyed with nickel it yields german silver; with twice its weight of copper forms common brass, and as a coating on iron (the so-called *galvanized* iron) greatly

retards the formation of rust. Most of the salts of zinc are prepared, directly or indirectly, from the metal (*Zincum*, B. P. and U. S. P.).

Quantivalence.—The atom of zinc is bivalent, Zn″.

Molecular Weight.—Some remarks on this point will be made under Mercury.

Reactions having (*a*) Sythetical and (*b*) Analytical Interest.

(*a*) *Synthetical Reactions.*

Sulphate of Zinc.

First Synthetical Reaction.—Heat zinc (4 pts.) with water (20 pts.) and sulphuric acid (3 fl. pts.) in a test-tube (or larger vessel) until gas ceases to be evolved; solution of sulphate of zinc ($ZnSO_4$) results. Filter and concentrate the solution in an evaporating dish; on cooling, colorless, transparent, prismatic crystals of Sulphate of Zinc ($ZnSO_4,7H_2O$) are deposited (*Zinci Sulphas*, B. P. and U. S. P.).

$$\underset{\text{Zinc.}}{Zn_2} + \underset{\text{Sulphuric acid.}}{2H_2SO_4} + \underset{\text{Water.}}{xH_2O} = \underset{\text{Sulphate of Zinc.}}{2ZnSO_4} + \underset{\text{Water.}}{xH_2O} + \underset{\text{Hydrogen.}}{2H_2}$$

Zinc does not displace hydrogen from the sulphuric acid alone, nor from the water alone, yet the mixture affords hydrogen. The probable explanation is that as sulphuric acid combines with several different quantities of water to form definite hydrous compounds (H_2SO_4, H_2O; $H_2SO_4, 2H_2O$; etc), it is one of these that is decomposed with elimination of hydrogen. At present we can only say that an unknown (x) amount of water is required in the reaction.

Note.—This reaction affords hydrogen and sulphate of zinc; it also gives electricity. Of several methods of evolving hydrogen, it is the most convenient; of the two or three means of preparing sulphate of zinc it is that most commonly employed; and of the many reactions which may be utilized in the development of dynamic electricity it is at present the cheapest and most manageable. The apparatus in which the reaction is effected differs according to the requirements of the operator; if the sulphate of zinc alone is wanted, an open dish is all that is necessary, the action being, perhaps, accelerated by heat; if hydrogen, a closed vessel and delivery-tube; if electricity, square vessels called cells and certain complementary materials, forming altogether what is termed a battery. In each operation for one product the other two are commonly wasted. It would not be difficult for the operator, as a matter of amusement, to construct an apparatus in which all three products should be collected.

Purification.—Impure sulphate of zinc may be purified in the same manner as impure chloride (see next reaction).

Sulphate of zinc is isomorphous with sulphate of magnesium, and, like that salt, loses six-sevenths of its water of crystallization at 212° F.

Chloride of Zinc.

Second Synthetical Reaction.—Dissolve zinc in hydrochloric acid mixed with half its bulk of water; the resulting solution contains chloride of zinc. Evaporate the liquid till no more steam escapes; Chloride of Zinc ($ZnCl_2$) in a state of fusion remains, and, on cooling, is obtained as a white opaque solid (*Zinci Chloridum*, B. P. and U. S. P.). It is soluble in water, alcohol, or ether.

$$\underset{\text{Zinc.}}{Zn_2} + \underset{\text{Hydrochloric acid.}}{4HCl} = \underset{\text{Choloride of zinc.}}{2ZnCl_2} + \underset{\text{Hydrogen.}}{2H_2}$$

This reaction is analogous to that previously described. The Burnett deodorizing or disinfecting liquid is solution of chloride of zinc.

Purification of Chloride or Sulphate of Zinc.—Zinc sometimes contains traces of iron or lead; and these, like zinc, are dissolved by most acids, with formation of soluble salts; they may be recognized in the liquids by applying the tests described hereafter to a little of the solution in a test-tube (p. 114). Should either be present in the above solution, a little chlorine water is added to the liquid till the odor of chlorine is permanent, and then the whole well shaken with some hydrate of zinc or the common official "carbonate" of zinc (really hydrato-carbonate—see next page). In this way iron is precipitated as ferric hydrate, and lead as peroxide:—

$$\underset{\text{Ferrous chloride.}}{*2FeCl_2} + \underset{\text{Chlorine.}}{Cl_2} = \underset{\text{Ferric chloride.}}{*Fe_2Cl_6}$$

$$\underset{\text{Ferric chloride.}}{Fe_2Cl_6} + \underset{\text{Carbonate of zinc.}}{3ZnCO_3} + \underset{\text{Water.}}{3H_2O} = \underset{\text{Ferric hydrate.}}{Fe_2 6HO} + \underset{\text{Chloride of zinc.}}{3ZnCl_2} + \underset{\text{Carbonic acid gas.}}{3CO_2}$$

$$\underset{\text{Chloride of lead.}}{PbCl_2} + \underset{\text{Chlorine.}}{Cl_2} + \underset{\text{Carbonate of zinc.}}{2ZnCO_3} = \underset{\text{Peroxide of lead.}}{PbO_2} + \underset{\text{Chloride of zinc.}}{2ZnCl_2} + \underset{\text{Carbonic acid gas.}}{2CO_2}$$

In the British Pharmacopœia the presence of impurities in the zinc is assumed, and the process of purification just described incorporated with the process of preparation of *Zinci Chloridum*, *Liquor Zinci Chloridi*, and *Zinci Sulphas*. In the purification of the sulphate of zinc, the action of chlorine on any ferrous sulphate will result in the formation of ferric sulphate as well as ferric chloride:—

$$6FeSO_4 + Cl_6 = 2(Fe_2 3SO_4) + Fe_2Cl_6;$$

* It will be noticed that the iron is represented, in these equations, as exerting both bivalent and trivalent activity; this will be alluded to when iron comes under consideration.

carbonate of zinc will then give chloride as well as sulphate of zinc, and thus the whole quantity of sulphate of zinc be slightly contaminated by chloride. On evaporating and crystallizing, however, the chloride of zinc will be retained in the mother-liquor.

For *Liquor Zinci Chloridi*, B. P., 1 pound of zinc is placed in a mixture of 44 fluidounces of hydrochloric acid and 20 of water, the mixture ultimately warmed until no more gas escapes, filtered into a bottle, chlorine water added until the liquid after shaking smells fairly of chlorine, about half an ounce or somewhat more of carbonate of zinc shaken up with the solution until a brown precipitate (of ferric hydrate or peroxide of lead, or both) appears, the whole filtered and the filtrate evaporated to 40 fluidounces. One fluidounce contains 366 grains of chloride of zinc. If there is reason to believe that neither iron nor lead is present in the zinc, the treatment of chlorine, water, and carbonate of zinc may be omitted. The *Liquor Zinci Chloridi*, U. S. P., is prepared by a somewhat similar process, nitric acid, however, is used instead of chlorine water; the solution contains 375 grains of chloride of zinc in one fluidounce.

Carbonate of Zinc.

Third Synthetical Reaction.—To solution of any given quantity of sulphate of zinc in twice its weight of water (in a test-tube, evaporating basin, or other large or small vessel), add about an equal quantity of carbonate of sodium, also dissolved in twice its weight of water, and boil; the resulting white precipitate is so-called Carbonate of Zinc (*Zinci Carbonas*, B. P., *Zinci Carbonas Precipitata*, U. S. P.), a mixture of carbonate ($ZnCO_3$) and hydrate ($Zn2HO$), in the proportion of one molecule of the former and two of the latter, together with a molecule of water (H_2O). It may be washed, drained, and dried in the usual manner. It is used in the arts under the name of *zinc-white*, and frequently in medicine in the form of ointment (*Ceratum Zinci Carbonatis*, U. S. P.).

$$\underset{\text{Sulphate of zinc.}}{3ZnSO_4} + \underset{\text{Water.}}{2H_2O} + \underset{\text{Carbonate of sodium.}}{3Na_2CO_3} = \underset{\text{Official carbonate of zinc.}}{ZnCO_3,2ZnH_2O_2} + \underset{\text{Carbonic acid gas.}}{2CO_2} + \underset{\text{Sulphate of sodium.}}{3Na_2SO_4}$$

Acetate of Zinc.

Fourth Synthetical Reaction.—Collect in a filter the precipitate obtained in the last reaction, wash with distilled water, and dissolve a portion in strong acetic acid; the resulting solution contains acetate of zinc ($Zn2C_2H_3O_2$), and, on evaporating, and setting aside for a day, yields

lamellar pearly crystals ($Zn2C_2H_3O_2,2H_2O$). This is the process for *Zinci Acetas*, B. P.

$$\underset{\text{Official carbonate of zinc.}}{ZnCO_3,2ZnH_2O_2} + \underset{\text{Acetic acid.}}{6HC_2H_3O_2} = \underset{\text{Acetate of zinc.}}{3(Zn2C_2H_3O_2)} + \underset{\text{Water.}}{5H_2O} + \underset{\text{Carbonic acid gas.}}{CO_2}$$

The U. S. P. process consists in digesting oxide of zinc in acetic acid, heating the mixture to boiling point, filtering while hot, and setting aside the clear solution to crystallize.

Oxide of Zinc.

Fifth Synthetical Reaction.—Dry the remainder of the precipitated carbonate (by placing the open filter on a plate over a dish of water kept boiling), and then heat it in a small crucible till it ceases to effervesce on the addition of water and acid to trial samples taken out of the crucible from time to time; the product is Oxide of Zinc (*Zinci Oxidum*, B. P. and U. S. P.), much used in the form of ointment (*Unguentum Zinci*, B. P., and *Unguentum Zinci Oxidi*, U. S. P.).

$$\underset{\text{Official carbonate of zinc.}}{ZnCO_3,\ 2ZnH_2O_2} = \underset{\text{Oxide of zinc.}}{3ZnO} + \underset{\text{Water.}}{2H_2O} + \underset{\text{Carbonic acid gas.}}{CO_2}$$

Note.—This oxide is yellow while hot, and of a very pale yellow or slight buff tint when cold, not actually white like the oxide prepared by the combustion of zinc in air. The latter variety occurs in commerce under the name of Hubbuck's oxide of zinc. Its preparation can only be practically accomplished on the large scale, but the chief features of the action may be observed by heating a piece of zinc in a small porcelain crucible till it burns; flocks escape from the crucible, float about in the air, and slowly fall. These are the old *Flores Zinci*, *Lana Philosophica*, or *Nihilum Album*.

Valerianate of Zinc.

Sixth Synthetical Reaction.—Valerianate of Zinc ($Zn2C_5H_9O_2$) (*Zinci Valerianas*, B. P.) is prepared by mixing strong solutions of sulphate of zinc and valerianate of sodium, cooling, separating the white pearly crystalline matter, evaporating at 200° to a low bulk, cooling, again separating the lamellar crystals, washing the whole product with a small quantity of cold distilled water, draining and drying by exposure to air at ordinary tempera-

tures. Valerianate of zinc is soluble in ether, alcohol, or hot water.

$$\underset{\text{Sulphate of zinc.}}{ZnSO_4} + \underset{\text{Valerianate of sodium.}}{2NaC_5H_9O_2} = \underset{\text{Sulphate of sodium.}}{Na_2SO_4} + \underset{\text{Valerianate of zinc.}}{Zn2C_5H_9O_2}$$

Note.—The compounds of zinc described in the above six reactions are the only ones mentioned in the British Pharmacopœia; the processes are also those of that work. *Sulphide and Hydrate of Zinc* are mentioned in the following analytical paragraphs. The formula of *Sulphite of Zinc* is $ZnSO_3,3H_2O$.

(*b*) *Reactions having Analytical Interest* (*Tests*).

First Analytical Reaction.—To solution of a zinc salt (sulphate for example) in a test-tube, add solution of sulphydrate of ammonium (NH_4HS); white sulphide of zinc (ZnS) is precipitated, insoluble in acetic, but soluble in the stronger acids.

Note.—This is the only white sulphide that will be met with. Its formation, on the addition of the sulphydrate of ammonium, is therefore highly characteristic of zinc. If the zinc salt contains iron or lead as impurities, the precipitate will have a dark appearance, the sulphides of those metals being black. Hydrate of aluminium, which is also white and precipitated by sulphydrate of ammonium, is the only substance sulphide of zinc is likely to be mistaken for, and *vice versâ*; but, as will be seen immediately, there are good means of distinguishing these from each other.

Second Analytical Reaction.—To solution of a zinc salt add solution of ammonia; white hydrate of zinc (Zn2HO) is precipitated. Add excess of ammonia; the precipitate is redissolved.

This reaction at once distinguishes a zinc salt from an aluminium salt, hydrate of aluminium being insoluble in ammonia.

Other Analytical Reactions.—The fixed alkali-hydrates afford a similar reaction to that just mentioned, the hydrate of zinc redissolving if the alkali is free from carbonate.——Carbonate of ammonium yields a white precipitate of carbonate and hydrate, soluble in excess.——The fixed alkaline carbonates give a similar precipitate, which is not redissolved if the mixed solution and precipitate be well boiled.——Ferrocyanide of potassium precipitates white ferrocyanide of zinc (Zn_2FeCy_6).

Sulphate of magnesium, which is isomorphous with and indistinguishable in appearance from sulphate of zinc, is not precipitated from its solutions either by ferrocyanide of potassium or sulphydrate of ammonium.

Antidotes.—There are no efficient chemical means of counteracting the poisonous effects of zinc. Large doses, fortunately, act as powerful emetics. If vomiting has not occurred, or apparently to an insufficient extent, solution of carbonate of sodium (common washing salt) immediately followed by white of egg and demulcents may be administered.

QUESTIONS AND EXERCISES.

185. Give the sources and uses of metallic zinc.
186. Explain by a diagram what occurs when zinc is dissolved in dilute sulphuric acid.
187. How may solutions of Chloride of Sulphate of Zinc be purified from salts of iron? Give equations descriptive of the reactions.
188. State the formula of Carbonate of Zinc, and illustrate by a diagram the reaction which takes place in its production.
189. Give an equation showing the formation of Acetate of Zinc.
190. In what respect does Oxide of Zinc, resulting from the ignition of the carbonate, differ from that produced during the combustion of the metal?
191. How is Valerianate of Zinc prepared?
192. What are the properties of Valerianate of Zinc.
193. Name the more important tests for zinc.
194. How would you distinguish, chemically, between solutions of Sulphate of Zinc and Alum?
195. Describe the treatment in cases of poisoning by salts of zinc.
196. Give reactions distinguishing Sulphate of Zinc from Sulphate of Magnesium.

ALUMINIUM.

Symbol Al. Atomic weight 27.5.

Note.—In the formulæ of aluminium salts, it will be observed that to one atom of metal there are three atoms of other univalent radicals; hence, apparently, the atom of aluminium is trivalent, Al‴. But possibly it is quadrivalent; for one molecule of aluminium compounds includes two atoms of the metal, three-fourths only of whose power may be supposed to be exerted in retaining the other constituents of the molecule, the remaining fourth enabling the aluminium atoms themselves to keep together. This is graphically shown in the following formula of chloride of aluminium (Al_2Cl_6) from Frankland's "Lecture Notes for Chemical Students," which represents each



aluminium atom as a body having four arms or bonds, three of which are engaged in grasping the arms of univalent chlorine atoms, while

the fourth grasps the corresponding arm of its brother aluminium atom. Such graphic formulæ, as they are called, are useful in facilitating the acquirement of hypotheses regarding the constitution of chemical substances, especially if the error be avoided of supposing that they are pictures either of the position or absolute power of atoms in a molecule, or indeed, the true representation of a molecule at all; for on this point man knows little or nothing.

Source.—Aluminium is very abundant in nature, chiefly as silicate, in clays, slate, marl, granite, basalt, and a large number of minerals. The sapphire and ruby are almost pure oxide of aluminium. The metal is obtained from the double chloride of aluminium and sodium, by the action of metallic sodium, the source of the chloride being the mineral *bauxite*.

Aluminium-bronze is an alloy of ten parts of aluminium with ninety of copper.

Alum (*Alumen*, B. P. and U. S. P.), a double sulphate of aluminium and ammonium ($Al_2 3SO_4$, Am_2SO_4, $24H_2O$), may be obtained from aluminous schist (from σχιστὸς, *schistos*, divided) a sort of pyritous slate or shale, by exposure to air; oxidation and chemical change produce sulphate of aluminium, sulphate of iron, and silica, from the silicate of aluminium and bisulphide of iron (iron pyrites) originally present in the shale. The sulphate of aluminium and sulphate of iron are dissolved out of the mass by water, and sulphate or chloride of ammonium added; on concentrating the liquid, alum cyrstallizes out, while the more soluble iron salt remains in the mother-liquor.

Alum is also prepared by directly decomposing the silicate of aluminium in the calcined shale of the coal-measures by hot sulphuric acid, ammonia being added from time to time until a solution strong enough to crystallize is obtained. The liquid well agitated during cooling deposits *alum-flour*, which is afterwards recrystallized.

Alums.—There are several *alums*, iron or chromium replacing aluminium, and potassium or sodium taking the place of ammonium, all crystallizing in an eight-sided form, the octahedron—a sort of double pyramid. These are, apparently, alike in chemical constitution, and their general formula (M = either metal) is $M'''_2 3SO_4$, M'_2SO_4, $24H_2O$. The alum of the manufacturer commonly occurs in colorless, transparent, octahedral crystals, massed in lumps, which are roughly broken up for trade purposes, but still exhibit the faces of octahedra.

Sulphate of Aluminium ($Al_2 3SO_4$, $9H_2O$), or *Alum Cake*, prepared from natural silicates in the manner just described, is a common article of trade, serving most of the manufacturing purposes for which alum was formerly employed. In the United States Pharmacopœia (*Aluminii Sulphas*) it is directed to be made by dissolving hydrate of aluminium in diluted sulphuric acid with subsequent removal of water by evaporation.

$$Al_2 6HO + 3H_2SO_4 = Al_2 3SO_4 + 6H_2O.$$

The hydrate of aluminium is to be prepared by the addition of solution of alum to solution of carbonate of sodium, the precipitated hydrate being collected on a filter and well washed.

$$Al_2 3SO_4, Am_2SO_4 + 3Na_2CO_3 + 3H_2O = Al_2 6HO + Am_2SO_4 + 3Na_2SO_4 + 3CO_2.$$

Preparation of Alum.—Prepare alum by heating a small quantity of powdered pipeclay (silicate of aluminium) with about twice its weight of sulphuric acid for some time, dissolving out the resulting sulphate of aluminium and excess of sulphuric acid by water, and adding only ammonia to the clear-filtered solution until, after well stirring, the excess of acid is neutralized. (If too much ammonia be added the hydrate of aluminium precipitated when the ammonia is first poured in will not be redissolved on well mixing the whole. Perhaps the readiest indication of neutrality in this and similar cases is the presence of a little precipitate after stirring and warming the mixture.) On evaporating the clear solution, crystals of alum are obtained.

The *Ammonio-ferric Alum* of American pharmacy (*Ferri et Ammonii Sulphas*, U. S. P.) is made by adding sulphate of ammonium to a hot solution of persulphate of iron, and setting the liquid aside to crystallize. It forms pale violet octahedral crystals, expressed by the formula $Fe_4 3SO_4, (NH_4)_2SO_4, 24H_2O$. *Aluminii et Potassii Sulphas* (U. S. P.) is potassium alum, the sulphate of aluminium and potassium ($Al_2 3SO_4$, K_2SO_4, $24H_2O$).

Dried Alum (*Alumen Exsiccatum*, B. P. and U. S. P.) is alum from which the water of crystallization has been expelled by heat, the temperature not exceeding 400°. By calculation from the molecular weight of alum, it will be found that the salt contains between 47 and 48 per cent. of water. At temperatures above 400° alum is decomposed, sulphate of ammonium and sulphuric anhydride escaping, and pure *alumina* (Al_2O_3) remaining. Dried alum rapidly reabsorbs water from the atmosphere. It is almost useless as a medicinal preparation.

Roche alum, or *Rock alum* (*roche*, French, rock), is the name of an impure native variety of alum containing iron. The article sold under this name is an artificial mixture of common alum with oxide of iron.

Reactions having Analytical Interest.

First Analytical Reaction.—To a solution of an aluminium salt (alum, for example, which contains sulphate of aluminium) add sulphydrate of ammonium (NH_4HS); a gelatinous white precipitate of hydrate of aluminium falls:—

$$Al_2 3SO_4 + 6AmHS + 6H_2O = Al_2 6HO + 3Am_2SO_4 + 6H_2S.$$

Second Analytical Reaction.—To solution of alum add ammonia, NH_4HO; hydrate of aluminium falls: add excess of ammonia; the precipitate is insoluble.

Principle of Dyeing by help of Mordants.—The precipitated hydrate of aluminium, or alumina, has great affinity for vegetable coloring-matters, and also for the fibre of

cloth. Once more perform the above experiment, but before adding the ammonia introduce some decoction of logwood, solution of cochineal, or other similar colored liquid, into the test-tube. Add now the ammonia, and set the tube aside for the alumina to fall; the latter takes down with it all the coloring principle. In dye-works the fabrics are passed through liquids holding the alumina but weakly in solution, and then through the coloring solutions; from the first bath the fibres abstract alumina, and from the second the alumina abstracts coloring matter. Some other metallic hydrates, notably those of tin and iron, resemble alumina in this property; they are all termed *mordants* (from *mordens*, biting); the substances they form with coloring-matters have the name of *lakes*.

Third Analytical Reaction.—To the alum add solution of potash; again hydrate of aluminium falls. Add excess of potash, and agitate; the precipitate dissolves.

Alumina may be precipitated from this solution by neutralizing the potash with hydrochloric acid, and adding ammonia until, after shaking, the mixture has an ammoniacal smell, or by adding solution of chloride of ammonium to the potash liquid. But the former way is the better; for it is difficult to know when a sufficiency of the chloride of ammonium has been poured in, whereas reaction with blue and red litmus-paper at once enables the operator to know when excess of hydrochloric acid or ammonia has been added.

Alkaline carbonates, phosphates, arseniates, and salts of other acidulous radicals also decompose solutions of aluminium salts and produce insoluble compounds of that metal, with the several acidulous radicals (except the carbonic), but the resulting precipitates are of no special interest.

QUESTIONS AND EXERCISES.

197. What is there remarkable about the quantivalence of aluminium?

198. Practically what is the quantivalence of the atom of aluminium?

199. Enumerate the chief natural compounds of aluminium.

200. Write down a formula which will represent either of the Alums.

201. Which *alum* is official, and commonly employed in the arts?

202. State the source, and explain the formation of alum.

203. What is the crystalline form of alum? Work a sum showing

how much Dried Alum is theoretically producible from 100 pounds of alum? Ans. 52 lbs. 6 ozs.

204. Show by figures how ordinary ammonium alum is capable of yielding 11.356 per cent. of alumina.

205. Why are aluminium compounds used in dyeing?

206. How are salts of aluminium analytically distinguished from those of zinc?

IRON.

Symbol Fe. Atomic weight 56.

Sources.—Compounds of iron are very abundant in nature. *Magnetic Iron Ore*, or *Loadstone* (*Lodestone* or *Leadstone*, from the Saxon *lædan*, to lead, in allusion to its use, or rather of magnets made from it, in navigation), is the chief ore from which Swedish iron is made; it is a mixture of ferrous and ferric oxide (FeO,Fe_2O_3). Much of the Russian iron is made from *Specular Iron Ore* (from *speculum*, a mirror, in allusion to the lustrous nature of the crystals of this mineral). This and *Red Hæmatite* (from αἷμα, *haima*, blood, so named from the color of its streak) an ore raised in Lancashire, are composed of ferric oxide only (Fe_2O_3). *Brown Hæmatite*, an oxyhydrate, is the source of much of the French iron. *Spathic Iron Ore* (from *spatha*, a slice, in allusion to the lamellar structure of the ore) is a ferrous carbonate ($FeCO_3$). An impure ferrous carbonate forms the *Clay Ironstone*, whence most of the English iron is derived. The chief Scotch ore is also an impure carbonate, containing much bituminous matter; it is known as *Black Band*. *Iron Pyrites* (from πῦρ, *pur*, fire, in allusion to the production of sparks when sharply struck) (FeS_2) is a yellow lustrous mineral, of use only for its sulphur. Ferrous carbonate ($FeCO_3$), chloride ($FeCl_2,4H_2O$), and sulphate ($FeSO_4,7H_2O$) sometimes occur in springs, the water of which is hence termed *chalybeate* (*chalybs*, steel).

Process.—Iron is obtained from its ores by processes of roasting, and reduction of the resulting impure oxide with coal or charcoal in the presence of chalk, the latter uniting with the sand, clay, etc., to form a fusible slag. The *cast iron* thus produced is converted into *wrought iron* (*Ferrum*, U. S. P) by burning out the 4 or 5 per cent. of carbon, silicon, and other impurities present, by oxidation in a furnace, an operation which is termed *puddling*. *Steel* is wrought iron impregnated with from one to two per cent. of carbon by strongly heating in charcoal. The official variety of the metal (*Ferrum*, B. P.), the condition in which it is most easily employed for conversion into its compounds, is "wrought iron in the form of wire or nails free from oxide." In the form of a fine powder (see 17 Reac.) metallic iron is employed as a medicine.

Properties.—The specific gravity of pure iron is 7.844, of the best bar iron 7.7; its color is bluish-white or gray. Bar iron requires the highest heat of a wind-furnace for fusion, but below that temperature assumes a pasty consistence, and in that state two pieces may be joined or *welded* (Germ. *wellen*, to join) by the pressure of blows from a hammer. A little sand thrown on to the hot metal facilitates

this operation by forming with the superficial oxide of iron a fusible slag, which is dispersed by the blows: the purely metallic surfaces are thus better enabled to come into thorough contact and enter into perfect union. Iron is highly ductile, and of all common metals possesses the greatest amount of tenacity. At a high temperature it burns in the air, forming oxide of iron. *Rust of iron* is chiefly red oxide of iron, with a little ferrous oxide and carbonate; it is produced by action of the moist carbonic acid of the air and subsequent oxidation. Steam passed over scrap iron heated to redness gives hydrogen gas and black oxide of iron.

Quantivalence.—Iron combines with other elements and radicals in two proportions; those salts in which the atom of iron appears to possess inferior affinities (in which the other radicals are in the less amount) are termed *ferrous*, the higher being *ferric* salts. In the former the iron exerts bivalent (Fe''), in the latter trivalent activity (Fe''' or Fe_2^{VI}).

The atom of iron is also sometimes considered to be sexivalent, on account of the analogy of its compounds with those of chromium, which is sexivalent, if the formula of its fluoride (CrF_6) be correct, and because the composition of *ferrate of potassium* (K_2FeO_4), a deep-purple salt obtained on passing chlorine through a concentrated solution of potash in which fresh ferric hydrate is suspended, is best explained on the assumption of the sexivalence of its iron.

Why the quantivalence of the atom of iron should vary is not at present known.

The Nomenclature of Iron Salts.—For educational and descriptive purposes the two classes of iron compounds are very conveniently spoken of as *ferrous* and *ferric*, the syllable "*ferr*" common to all indicating their allied ferruginous character, the syllable *ous* and *ic* indicating the lower and higher class respectively—functions fulfilled by these two syllables in other similar cases (sulphurous and sulphuric, mercurous and mercuric). Officially the iron salts are known by other names, thus, *Sulphate of Iron* (*Ferri Sulphas*), and *Phosphate of Iron* (*Ferri Phosphas*), names which are chemically inexplicit, for there are two sulphates, and two phosphates, and the terms do not define which salt is intended. Consistency and uniformity would demand that the names Ferrous Sulphate, Ferrous Phosphate, or similar terms should be employed. Practically, however, the old names cause no confusion, inasmuch as only one sulphate, phosphate, etc., are used in medicine; moreover, the higher salts usually have the prefix *per* attached (as persulphate, perchloride). These names are already well known, can be easily rendered in Latin, and then admit of simple abbreviations and adaptations such as are employed in prescriptions, advantages not possessed by the more rational terms. While, therefore, the comprehension of the chemistry of iron is rendered simple and intelligible by the use of the terms ferrous and ferric, the employment of older and less definite names may very well be continued in pharmacy as being practically more convenient.

Reactions having (*a*) Synthetical and (*b*) Analytical Interest.

(*a*) *Synthetical Reactions.*

FERROUS SALTS.

Green Sulphate of Iron. Ferrous Sulphate.

First Synthetical Reaction.—Place iron (small tacks) in sulphuric acid diluted with eight times its bulk of water (in a test-tube, basin, or other vessel of any required size), accelerating the action by heat until effervescence ceases.

$$\underset{\text{Iron.}}{Fe_2} + \underset{\substack{\text{Sulphuric}\\\text{acid.}}}{2H_2SO_4} = \underset{\substack{\text{Ferrous}\\\text{sulphate.}}}{2FeSO_4} + \underset{\text{Hydrogen.}}{2H_2}$$

The solution contains what is generally known as Sulphate of Iron, that is, Ferrous Sulphate, the lower of the two sulphates, and will yield crystals of that substance ($FeSO_4,7H_2O$) (*Ferri Sulphas*, B. P. and U. S. P.) on cooling or on further evaporation; or if the hot concentrated solution be poured into alcohol, the mixture being well stirred, the sulphate is at once thrown down in minute crystals (*Ferri Sulphas Granulata*, B. P.). At a temperature of 400° F. ferrous sulphate loses six-sevenths of its water, and becomes the *Ferri Sulphas Exsiccata*, B. P. and U. S. P.

Other Sources of Ferrous Sulphate.—In the laboratory, ferrous sulphate is often obtained as a by-product in making sulphuretted hydrogen,

$$FeS + H_2SO_4 = H_2S + FeSO_4.$$

In manufactories it occurs as a by-product in the decomposition of aluminous shale, as already noticed (p. 116).

Ten grains of granulated sulphate of iron dissolved in one ounce of water constitutes "Solution of Sulphate of Iron," B. P. "The solution should be recently prepared."

Notes.—Ferrous sulphate is sometimes termed *green vitriol.* Vitriol (from *vitrum*, glass) was originally the name of any transparent crystalline substance, but afterwards restricted to the sulphates of zinc, iron, and copper, which were, and still are, occasionally known as white, green, and blue vitriol. *Copperas* (probably originally *Copper-rust*, a term applied to verdigris and other green incrustations of copper) is another name for this sulphate of iron, sometimes distinguished as *green copperas*, sulphate of copper being blue copperas. Solid sulphate of iron is a constituent of *Pilula Aloes et Ferri*, B. P.

Ferrous sulphate, when exposed to the air, gradually turns brown

through absorption of oxygen, ferric oxysulphate (Fe_2O2SO_4) being formed. The latter is not completely dissolved by water, owing to the formation of a still lower insoluble oxysalt ($Fe_4O_5SO_4$) and soluble ferric sulphate $5(Fe_2O2SO_4) = Fe_4O_5SO_4 + 3(Fe_2 3SO_4)$.

Iron heated with undiluted sulphuric acid gives sulphurous acid gas and ferrous sulphate :—

$$Fe_2 + 4H_2SO_4 = SO_2 + FeSO_4 + 2H_2O.$$

Carbonate of Iron. Ferrous Carbonate.

Second Synthetical Reaction.—To solution of ferrous sulphate, boiling, in a test-tube, add a solution of carbonate of ammonium (Am_2CO_3, etc.) in recently boiled water; a white precipitate of ferrous carbonate ($FeCO_3$) is thrown down, rapidly becoming light green, bluish-green, and, after a long time, red, through absorption of oxygen, evolution of carbonic acid gas, and formation of ferric oxyhydrate.

$FeSO_4$	+	Am_2CO_3	=	$FeCO_3$	+	Am_2SO_4
Ferrous sulphate.		Carbonate of ammonium.		Ferrous carbonate.		Sulphate of ammonium.

Saccharated Carbonate of Iron.—The above precipitate, rapidly washed with hot well-boiled distilled water, and the moist powder mixed with sugar and quickly dried—in short, all possible precautions taken to avoid exposure to air—forms the saccharated carbonate of iron (*Ferri Carbonas Saccharata*, B. P.).

The official proportions are two ounces of the sulphate and one ounce and a quarter of the carbonate, each dissolved in half a gallon of hot water; the solutions are mixed and set aside in a deep well-covered pan, the supernatant liquid poured off when the precipitate has subsided, the pan again filled up with boiling water, the liquid once more poured away, the precipitate transferred to a calico filter, drained, gently pressed, and while still somewhat moist rubbed in a mortar with one ounce of sugar, and finally dried over a water-bath.

Carbonate of Iron, mixed with a fourth its weight of Confection of Roses (Honey and Sugar, U. S. P.), forms the *Pilula Ferri Carbonatis*, B. P. and U. S. P.

Notes.—The *Subcarbonate of Iron* (*Ferri Subcarbonas*, U. S. P.) is precipitated on mixing solutions of sulphate of iron and carbonate of sodium. On washing and drying it is converted into reddish-brown oxyhydrate of iron, water being absorbed and carbonic acid gas being eliminated. This oxyhydrate of iron is best made by precipitating solution of persulphate of iron by solution of soda, and washing and drying the product (see page 127).

Saccharated ferrous carbonate is said to be more easily dissolved in the stomach than any other iron preparation. It is so unstable and prone to oxidation, that it must be washed in water containing no dissolved air and mixed with the sugar (which protects it from oxidation) as quickly as possible. In making the official compound mixture of iron (*Mistura Ferri Composita*, B. P. and U. S. P.),

"Griffith's mixture," the various ingredients, including the carbonate of potassium, should be placed in a bottle of the required size, space being left for the crystals or solution of ferrous sulphate, which should be added last, the bottle immediately filled up with rose-water, and securely corked; oxidation is thus prevented to the greatest possible extent. *Pilulæ Ferri Compositæ*, U. S. P., is made from myrrh, carbonate of sodium, sulphate of iron and syrup: carbonate of iron is gradually formed.

$$\underset{\text{Ferrous sulphate.}}{FeSO_4} + \underset{\text{Carbonate of potassium.}}{K_2CO_3} = \underset{\text{Ferrous carbonate.}}{FeCO_3} + \underset{\text{Sulphate of potassium.}}{K_2SO_4}$$

Arseniate of Iron. Ferrous Arseniate.

Third Synthetical Reaction, by which the lower arseniate of iron, ferrous arseniate (*Ferri Arsenias*, B. P.) ($Fe_3 2AsO_4$), partially oxidized, is formed. This will be noticed again under Arsenicum.

Phosphate of Iron. Ferrous Phosphate.

Fourth Synthetical Reaction.—To solution of ferrous sulphate in a test-tube add a little solution of acetate of sodium, then solution of phosphate of sodium; the lower phosphate of iron, ferrous phosphate ($Fe_3 2PO_4$), is precipitated (*Ferri Phosphas*, B. P. and U. S. P.).

$$\underset{\text{Ferrous sulphate.}}{3FeSO_4} + \underset{\text{Phosphate of sodium.}}{2Na_2HPO_4} + \underset{\text{Acetate of sodium.}}{2NaC_2H_3O_2} = \underset{\text{Ferrous phosphate.}}{Fe_3 2PO_4} + \underset{\text{Sulphate of sodium.}}{3Na_2SO_4} + \underset{\text{Acetic acid.}}{2HC_2H_3O_2}$$

Officially, solutions of 3 ounces of sulphate of iron in a quart of water, and $2\frac{1}{2}$ ounces of phosphate and 1 of acetate of sodium in another quart of water, are well mixed, filtered, the precipitate well washed, and, to prevent oxidation as much as possible, dried at a temperature not exceeding 120° F. These proportions will be found to accord with the molecular weights of the crystalline salts, multiplied as indicated in the foregoing equation. $3(FeSO_4, 7H_2O)=834$; $2(Na_2HPO_4, 12H_2O)=716$; $2(NaC_2H_3O_2, 3H_2O)=272$.

The use of the acetate of sodium (not mentioned in the U. S. P. formula) is to insure the occurrence of acetic acid in the solution, where otherwise would be free sulphuric acid. Sulphuric acid is a solvent of ferrous phosphate; acetic acid is not. It is impossible to prevent the separation of sulphuric acid, if only ferrous sulphate and phosphate of sodium be employed. Ferrous phosphate is white, but soon oxidizes and becomes slate-blue.

The above reaction also occurs in making *Syrupus Ferri Phosphatis*, B. P. The precipitate should be well washed, or red ferric acetate may be developed after a time.

Sulphide of Iron. Ferrous Sulphide.

Fifth Synthetical Reaction.—In a gas- or spirit-flame strongly heat sulphur with about twice its weight of iron filings in a test-tube (or in an earthen crucible in a furnace); ferrous sulphide (FeS) is formed. When cold, add water to a small portion, and then a few drops of sulphuric acid; sulphuretted hydrogen gas (H_2S), known by its odor, is evolved.

$$FeS + H_2SO_4 = FeSO_4 + H_2S.$$

Sticks of sulphur pressed against a white-hot bar of cast iron give the purest form of ferrous sulphide. The liquid sulphide thus formed is allowed to drop into a vessel of water (Sulphide of Iron, B. P.; Ferri Sulphuretum, U. S. P.).

Green Iodide of Iron. Ferrous Iodide.

Sixth Synthetical Reaction.—Place a piece of iodine, about the size of a pea, in a test-tube with a small quantity of water, and add a few iron filings, small nails, or iron wire. On gently warming, or merely shaking if longer time be allowed, the iodine disappears, and, on filtering, a clear light green solution of iodide of iron (FeI_2) is obtained.

The official Ferri Iodidum is formed by gently warming a mixture of 3 parts of iodine, $1\frac{1}{2}$ of fine iron wire, and 12 of distilled water in an iron vessel. When combination is nearly complete (as shown by indications of a sea-green tint), boil for a short time until the whiteness of the froth proves that the iodine has entirely disappeared. The solution is then filtered and evaporated in a clean bright iron saucepan, ladle, or dish until a drop taken out on the end of an iron wire stirrer solidifies on cooling. The liquid is poured out on a clean smooth slab, broken up and preserved in a glass-stoppered bottle. Solid iodide of iron has a crystalline fracture, is "green with a tinge of brown; inodorous, deliquescent, and almost entirely soluble in water, forming a slightly green solution which gradually deposits a colored sediment and acquires a red color."

The solid iodide contains about 18 per cent. of water of crystallization, and a little oxide of iron. It is deliquescent and liable to absorb oxygen from the air with formation of insoluble ferric oxyiodide or hydrato-iodide. Iodide of iron thus spoilt may be purified by re-solution in water, addition of a little more iodine and some iron, warming, filtering, and evaporating as before.

Ferrous bromide ($FeBr_2$), occasionally used in medicine, could be made, as might be expected, in the same way as the iodide.

FERRIC SALTS.

Anhydrous Perchloride of Iron. Ferric Chloride.

Seventh Synthetical Reaction.—Pass chlorine (generated as usual, from black oxide of manganese and hydrochloric acid in a flask) through sulphuric acid contained in a small bottle, and thence by the ordinary narrow glass tubing to the bottom of a test-tube containing twenty or thirty small iron tacks (or a Florence flask containing 2 or 3 ounces of iron tacks), the latter kept hot by a gas-flame; the higher chloride of iron, ferric chloride, or the perchloride* of iron (Fe_2Cl_6) is formed and condenses in the upper part of the tube or flask as a mass of small dark iridescent crystals. When a tolerably thick crust of the salt is formed, break off the part of the glass containing it, being careful that the remaining corroded tacks are excluded, and place it in ten or twenty times its weight of water; the resulting solution, poured off from any pieces of glass, is a pure neutral solution of hydrous ferric chloride, and will be serviceable in performing analytical reactions.

Precaution.—The above experiment must be conducted in the open air, or in a cupboard having a draught outwards.

Anhydrous Ferrous Chloride.—In breaking up the tube, small scales of a light buff color will be observed adhering to the nails; they are crystals of ferrous chloride ($FeCl_2$).

Note.—Solution of ferric chloride evolves some hydrochloric acid on boiling, while a darker-colored solution of ferric oxychloride remains.

Green Chloride of Iron. Hydrous ferrous Chloride. Solution of Hydrous Ferric Chloride.

Eighth Synthetical Reaction.—Dissolve iron tacks, in a test-tube, in hydrochloric acid; hydrogen escapes, and the solution on cooling, or on evaporation and cooling, deposits *crystallized ferrous chloride* ($FeCl_2,4H_2O$).

Through a portion of the solution of ferrous chloride pass chlorine gas; the ferrous chloride becomes *ferric chloride.*

The excess of chlorine dissolved by the liquid in this experiment may be removed by ebullition; but the ferric chloride is slightly de-

* The prefixes *per* and *hyper* used here and elsewhere are from ὑπὲρ, *hyper*, over and above, and simply mean "the highest" of several. Thus perchloride, the highest *chloride.*

composed at the same time, for the reason just stated. The free chlorine may also be carried off by passing a current of air through the liquid for some time.

Hydrous Ferric Chloride (another process).

Ninth Synthetical Reaction.—To another portion of the solution of ferrous chloride, in a test-tube, add a little more hydrochloric acid; heat the liquid, and continue to drop in nitric acid until the black color it first produces disappears; the resulting reddish-brown liquid is also solution of ferric chloride.

$$\underset{\text{Ferrous chloride.}}{6FeCl_2} + \underset{\text{Nitric acid.}}{2HNO_3} + \underset{\text{Hydrochloric acid.}}{6HCl} = \underset{\text{Ferric chloride.}}{3Fe_2Cl_6} + \underset{\text{Nitric oxide.}}{2NO} + \underset{\text{Water.}}{4H_2O}.$$

The black color is due to solution of nitric oxide gas (NO) in a portion of the ferrous salt; it is decomposed by heat.

This is the process for producing the *Liquor Ferri Perchloridi Fortior*, B. P., 2 ounces of iron, 12 fluidounces of hydrochloric acid, 9 fluidrachms of nitric acid, and 8 ounces of water being employed, and the product boiled down to 10 fluidounces. Practically it is impossible so to apportion the acids that a solution shall result containing neither excess of acid nor of metal, nor contain ferric nitrate. For most medicinal purposes, however, solution of perchloride of iron containing hydrochloric acid is said to be unobjectionable. The *Liquor Ferri Chloridi*, U. S. P., is a similar solution, but not quite so strong.

Diluted with 3 volumes of water this strong solution gives the *Liquor Ferri Perchloridi*, B. P.—or with 3 volumes of rectified spirit the *Tinctura Ferri Perchloridi*, B. P. The *Tinctura Ferri Chloridi*, U. S. P., is a similar solution.

Note.—The spirit in the tincture is unnecessary, useless, and deleterious; for it acts neither as a special solvent nor as a preservative, the offices usually performed by alcohol (*Tincturæ et Succi*, B. P. and U. S. P.); but, unless the liquid contain excess of acid, decomposes the ferric chloride and causes the formation of an insoluble oxychloride of iron. Even if the tincture be acid, it slowly loses color, ferrous chloride and chlorinated ethereal bodies being formed. A *Liquor*, of similar strength, is doubtless destined to displace the tincture altogether.

Solution of ferric chloride evaporated yields a mass of yellow crystals (*Ferri Chloridum*, U. S. P.) containing $Fe_2Cl_6,12H_2O$, or, rarely, red crystals having the formula $Fe_2Cl_6,5H_2O$. An old method of making solution of ferric chloride is to dissolve ferric oxide or hydrate in hydrochloric acid; but from the varying character of trade specimens of the ingredients, the liquid is more likely to contain excess or deficiency of iron than the proper proportion.

Persulphate of Iron. Ferric Sulphate.

Tenth Synthetical Reaction.—Dissolve about three-quarters of an ounce of ferrous sulphate and a sixth of its weight of sulphuric acid in an ounce and a half of water in an evaporating dish, heat the mixture and drop in nitric acid until the black color it first produces disappears; the resulting liquid, when made of a certain prescribed strength, is the solution of ferric sulphate, or higher sulphate, "Solution of Persulphate of Iron" of the British Pharmacopœia, a heavy dark-red liquid, sp. gr. 1.441. *The Liquor Ferri Tersulphatis*, U. S. P., is the same preparation, but slightly stronger (sp. gr. 1.320). *Liquor Ferri Subsulphatis*, U. S. P. (Monsel's solution), is a similar fluid, made with less acids, probably containing, therefore, ferric oxysulphate and ferric oxynitrate (sp. gr. 1.552).

$$\underset{\text{Ferrous sulphate.}}{6FeSO_4} + \underset{\text{Sulphuric acid.}}{3H_2SO_4} + \underset{\text{Nitric acid.}}{2HNO_3} = \underset{\text{Ferric sulphate.}}{3(Fe_2 3SO_4)} + \underset{\text{Nitric oxide.}}{2NO} + \underset{\text{Water.}}{4H_2O}.$$

The black color, as in the previous reaction, is due to a compound of ferrous salt with nitric oxide ($2FeSO_4+NO$).

Note.—In all the reactions in which iron passes from ferrous to ferric condition the element assumes different properties, the chief being an alteration from bivalent to trivalent activity.

Acetate of Iron. Ferric Acetate.

Eleventh Synthetical Reaction.—To a strong solution of ferric sulphate (from which free nitric acid has been removed by evaporating to dryness and redissolving in water) add an *alcoholic* solution of acetate of potassium ($KC_2H_3O_2$), and well shake the mixture; a crystalline precipitate of sulphate of potassium (K_2SO_4) falls, and ferric acetate ($Fe_2 6C_2H_3O_2$) remains in solution, forming, when filtered, and of definite strength, the *Tinctura Ferri Acetatis*, B. P. The preparation is unstable.

$$\underset{\text{Ferric sulphate.}}{Fe_2 3SO_4} + \underset{\text{Acetate of potassium.}}{6KC_2H_3O_2} = \underset{\text{Sulphate of potassium.}}{3K_2SO_4} + \underset{\text{Ferric acetate.}}{Fe_2 6C_2H_3O_2}$$

The official proportions are 2½ fluidounces of "Solution of Persulphate of Iron" with 8 fluidounces of rectified spirit, mixed with a solution of 2 ounces of acetate of potassium in 10 fluidounces of spirit, the whole well shaken frequently during an hour, filtered, and the precipitated sulphate of potassium washed by pouring on spirit until the filtrate measures 1 pint. A solution four times this strength, made from ferric hydrate and glacial acetic acid, is stable: it is diluted with spirit as wanted (J. Deane and T. Jeaffreson).

Perhydrate of Iron. Ferric hydrate.

Twelfth Synthetical Reaction.—Pour a portion of the solution of ferric sulphate into excess of solution of soda (ammonia, U. S. P.); moist ferric hydrate is precipitated (*Ferri Peroxidum Humidum*, B. P., *Ferri Oxidum Hydratum*, U. S. P.).

$$\underset{\text{Ferric sulphate.}}{Fe_2 3SO_4} + \underset{\text{Soda.}}{6NaHO} = \underset{\text{Ferric hydrate.}}{Fe_2 6HO} + \underset{\text{Sulphate of sodium.}}{3Na_2SO_4}$$

Either of the other alkalies (potash or ammonia) will produce a similar reaction; but soda is cheapest and most convenient.

Ferric hydrate is an antidote to arsenic if administered directly the poison has been taken.

It converts the soluble arsenic (As_2O_3) into insoluble ferrous arseniate:—

$$2(Fe_2 6HO) + AS_2O_3 = Fe_3 2AsO_4 + 5H_2O + Fe2HO.$$

Dried ferric hydrate (then become an oxyhydrate—$Fe_4O_4 4HO$) (*Ferri Peroxidum Hydratum*, B. P.) has no action on arsenic. Even the moist recently prepared hydrate ($Fe_2 6HO$) ceases to react with arsenic as soon as it has become converted into an oxyhydrate ($Fe_4O_3 6HO$), a change which occurs though the hydrate be kept under water (W. Procter, Jr.). According to T. and H. Smith this decomposition occurs gradually, but in an increasing ratio; so that after four months the power of the moist mass is reduced to one-half, and after five months to one-fourth. Now mere loss of water is not usually followed by any alteration of the essential chemical properties of a compound. It would seem, therefore, that ferric hydrate (two molecules) ($Fe_4 12HO$) probably suffers, on standing, actual decomposition into oxyhydrate ($Fe_4O_3 6HO$) and water ($3H_2O$), and does not merely lose water already existing in it as water. Ferric hydrate is also far more readily soluble in hydrochloric acid, tartaric acid, citric acid, and acid tartrate of potassium, than ferric oxyhydrate. Any formula exhibiting ferric hydrate ($Fe_2 6HO$) as a combination of ferric oxide and water ($Fe_2O_3, 3H_2O$) is, apparently, for these and other reasons, incorrect.

Peroxyhydrate of Iron. Ferric Peroxyhydrate.

Collect the precipitate on a filter, wash, and dry on a plate over hot water; ferric oxyhydrate (*Ferri Peroxidum Hydratum*, B. P.) ($Fe_2O_2 2HO$) remains. When rubbed to powder it is fit for use in medicine.

$$Fe_2 6HO = Fe_2O_2 2HO + 2H_2O.$$

This oxyhydrate further decomposes when heated to low redness, ferric oxide (Fe_2O_3) remaining.

$$Fe_2O_2 2HO = Fe_2O_3 + H_2O.$$

Peroxide of Iron. Ferric oxide.

The six univalent atoms of the HO, the characteristic elements of all hydrates, are thus, by two successive steps, split up into water and oxygen. But between the hydrate and oxide there obviously may be another oxyhydrate, in which only 2HO is displaced by O″, and such a compound is well known; it is a variety of brown iron ore. The other oxyhydrate, $Fe_2O_2$2HO, is also native (needle iron ore), as well as being the *Ferri Peroxidum Hydratum*, B. P.

"Ferri Peroxidum Humidum"	Fe'''_2 6HO
A variety of brown iron ore	Fe'''_2 O″ 4HO
"Ferri Peroxidum Hydratum" (needle ore) .	Fe'''_2 $O''_2$2HO
Ferric oxide	Fe'''_2 O''_3

The moist ferric hydrate, as already stated, when kept for some months, even under water, loses the elements of water, and is converted into an oxyhydrate having the formula $Fe_4H_6O_9$ (limonite or brown hæmatite), which is either a compound of the above oxyhydrates (Fe_2O4HO)+($Fe_2O_2$2HO), or is a definite intermediate oxyhydrate ($Fe_4O_3$6HO).

By ebullition with water for seven or eight hours, ferric hydrate is decomposed into water and an oxyhydrate having the formula $Fe_4H_2O_7$ (Saint-Giles), which is either a mixture of the official oxyhydrate ($Fe_2O_2$2HO) with ferric oxide (Fe_2O_3), or a definite intermediate body ($Fe_4O_5$2HO). The relation of these bodies to each other will be apparent from the following Table, in which, for convenience, the formulæ of ferric hydrate and oxide are doubled.

Ferric hydrate (B. P.) (as stalactite) . . .	Fe_4 12HO
Kilbride mineral (?)	Fe_4 O10HO
Brown iron ore (Huttenrode and Raschau) .	Fe_4 $O_2$8HO
Old ferric hydrate (limonite)	Fe_4 $O_3$6HO
Ferric oxyhydrate (B. P.) (gothite)	Fe_4 $O_4$4HO
Boiled ferric hydrate (turgite)	Fe_4 $O_5$2HO
Ferric oxide (red hæmatite)	Fe_4 O_6

The English official ferric oxyhydrate ($Fe_2O_2$2HO), termed in the British Pharmacopœia *Hydrated Peroxide of Iron*, under the assumption that it is a compound of ferric oxide and water (Fe_2O_3, H_2O), was formerly made by mixing solutions of ferrous sulphate and carbonate of sodium and exposing the resulting ferrous carbonate to the air until it was nearly all converted into ferric oxyhydrate; hence its old name, still sometimes seen on old bottles, of *Ferri Carbonas* and *Ferri Subcarbonas*.

Ferric Oxide (another process.)

Thirteenth Synthetical Reaction.—Roast a crystal or two of ferrous sulphate in a small crucible until fumes cease to be evolved; the residue is a variety of ferric oxide (Fe_2O_3) or peroxide of iron, known in trade as *red oxide of iron*, *colcothar*, *crocus*, *rouge* (mineral), or *Venetian red*

It has sometimes been used in pharmacy in mistake for the official oxyhydrates (*vide* 12th Synthet. Reac.), from which it differs not only in composition but in the important respect of being almost insoluble in acids.

The Scale Compounds of Iron.

Fourteenth Synthetical Reaction.—Repeat the twelfth reaction, introducing a little solution of citric or tartaric acid, or acid tartrate of potassium, before adding to the alkali (soda, potash, or ammonia), and notice that now no precipitation of ferric hydrate occurs. This experiment serves to illustrate, not the manufacture of a scale compound, but the chemistry of the manufacture. The effect is due to the formation of double compounds, termed Ammonio-Citrate, Potassio-Citrate, Ammonio-Tartrate, Potassio-Tartrate, and similar Sodium compounds of Iron, which remain in solution along with the secondary product—sulphate of the alkali metal. Such ferric compounds, made with certain prescribed proportions of recently prepared ferric hydrate (from which all alkaline sulphate has been washed), and the respective acids (tartaric or citric) or acid salts (acid tartrate of posassium), etc., and the solutions evaporated to a syrupy consistence and spread on flat plates till dry, form the scale preparations known as *Ferri et Ammonii Citras*, U. S. P., *Ferri Citras*, U. S. P. (also *Liquor Ferri Citratis*, U. S. P.), *Ferri et Ammonii Tartras*, U. S. P., and *Ferri Potassio-tartras*, or rather, *Ferrum Tartaratum*, B. P., *Ferri et Potassii Tartras*, U. S. P. A mixture of citrate of iron and ammonium with citrate of strychnia yields, on evaporation, *Ferri et Strychniæ Citras*, U. S. P. A mixture of ferric citrate with citrate of ammonium and citrate of quinine yields, by similar treatment, the well-known scales of *Ferri et Quiniæ Citras*, B. P. and U. S. P.

Specimens of these substances may be prepared by attending to the following details. It is essential, first, that the ferric hydrate be thoroughly washed, or an insoluble oxysulphate will be formed; second, that the ferric hydrate be rapidly washed, or an insoluble ferric oxyhydrate will be produced; thirdly, that the whole operation be conducted quickly, or reduction to green ferrous salt will occur; and, fourthly, that the solutions of the salts be not evaporated at a higher temperature than that stated, or decomposition will take place.

In the pharmacopœial processes for the three scale compounds, the ferric hydrate is in each case freshly made from solution of ferric sulphate by precipitation with solution of ammonia :—

$Fe_2 3SO_4$	+	$6AmHO$	=	$Fe_2 6HO$	+	$3Am_2SO_4$
Ferric sulphate.		Hydrate of ammonium.		Ferric hydrate.		Sulphate of ammonium.

the solution of ferric sulphate being made of a definite strength from a known weight of ferrous sulphate. The reason for adopting this course is that ferric hydrate is unstable and cannot be weighed, because it cannot be dried without decomposing and becoming insoluble, as explained under the 12th reaction. This definite solution of ferric sulphate (*Liquor Ferri Persulphatis*, B. P., *Liquor Ferri Tersulphatis*, U. S. P.) is made by adding six fluidrachms of sulphuric acid to half a pint of water, warming, dissolving eight ounces of crystals of sulphate of iron in the liquid, pouring in nitric acid (six fluidrachms or rather more) slightly diluted until the mixture turns from a black to a reddish color, and ruddy nitrous vapors cease to be produced; the whole should measure eleven fluidounces, being diluted or further evaporated, as the case may be, to this bulk.

$$6FeSO_4 + 3H_2SO_4 + 2HNO_3 = 3(Fe_2 3SO_4) + 2NO + 4H_2O$$

Ferri et Ammonii Citras, U. S. P.—Ferric hydrate is dissolved in solution of citric acid, ammonia added, and the whole evaporated to dryness.

To prepare the ferric hydrate, dilute eight fluidounces of the above solution of ferric sulphate with about a quart of water; pour this into two or three pints of water containing excess of solution of ammonia—about 5 fluidounces of "Strong Solution of Ammonia," or 15 ounces of "Solution of Ammonia." (If the opposite course were adopted, the alkaline liquid poured into the ferric solution, the precipitate would contain ferric oxysulphate, or hydrato-sulphate, which interferes with the brilliancy of the scales.) Thoroughly stir the mixture (it will smell strongly of ammonia, if enough of the latter has been added), allow the precipitate to subside, pour away the supernatant liquid, add more water, and repeat the washing until a little of the liquid tested for by-product (sulphate of ammonium) by solution of chloride or nitrate of barium ceases to give a white precipitate (sulphate of barium). Collect the ferric hydrate on a filter, drain, and place, while still moist, in a solution of four ounces of citric acid in eight of water, placed in an evaporating basin, over a water-bath, stir frequently, until the whole, or nearly the whole, of the hydrate has dissolved. To the solution, when cold, add nearly two fluidounces of strongest (or five and a half of weak) solution of ammonia, filter, evaporate over a water-bath to the consistence of syrup, spread thinly on panes of glass, and dry (at a temperature not exceeding 100° F.). The product scales off the glass in deep-red transparent laminæ.

Ferri et Quiniæ Citras, B. P. and U. S. P.—Ferric hydrate and pure quinia are dissolved in solution of citric acid, ammonia added, and the whole evaporated to dryness. The product contains citrate of iron, citrate of quinia, and citrate of ammonium.

The ferric hydrate is obtained from four and a half fluidounces of the solution of ferric sulphate, with all the precautions described in the previous paragraph, a proportionate quantity of ammonia being employed.

While the ferric hydrate is being washed, prepare the quinia by dissolving one ounce of the ordinary sulphate of quinia in eight ounces of distilled water, acidified with sufficient sulphuric acid to dissolve the sulphate (about 12 fluidrachms of the official "diluted sulphuric acid"), and to the clear liquid add solution of ammonia, well mixing the product by stirring, until the whole of the quinia is precipitated (that is, until the mixture, after thorough agitation, smells of ammonia). Collect the precipitate on a filter, let it drain, and wash away adhering solution of sulphate of ammonium by passing through it about a pint and a half of distilled water.

(It will be observed that the principle involved in the preparation of quinia from its sulphate is identical with that which obtains in the precipitation of alumina, ferric hydrate, or hydrate of zinc, etc. A soluble sulphate—or, indeed, any common soluble salt—has its acidulous constituent removed by the superior affinity of the basylous radical in ammonia, or other alkali, an insoluble precipitate and a new soluble sulphate being formed. The latter is washed away, leaving the former pure. In such manipulations, when economy has to be practised, soda is the alkali generally employed. Ammonia, however, has the advantage of showing the moment when its work of removing an acidulous radical is completed; for the salts which ammonium forms with such acidulous radicals as SO_4, Cl, NO_3, and $C_2H_3O_2$ are inodorous, while it itself has a powerful odor; so long, therefore, as the salt to be decomposed is not wholly attacked, the addition of ammonia does not give an ammoniacal odor to the mixture, the ammonia, as such, being, in fact destroyed; but when the work is accomplished, the quantity of ammonia last added remains as ammonia, and communicates its natural smell to the liquid.)

The ferric hydrate and quinia being now washed and drained, dissolve the former, and afterwards the latter, in a solution of three ounces of citric acid in five of distilled water, the acid liquid being warmed over a water-bath, and portions of the precipitates stirred in as fast as solution is effected. "Let the solution cool, then add in small quantities at a time twelve fluidrachms of solution of ammonia diluted with two fluidounces of distilled water, stirring the solution briskly, and allowing the quinia which separates with each addition of ammonia to dissolve (in the acid) before the next addition is made. (Excess of ammonia must be avoided or the quinia will be precipitated.) Filter the solution, evaporate to the consistence of a thin syrup, and then dry in thin layers on flat porcelain or glass plates at a temperature of 100°. Remove the dry salt in flakes, and keep it in a stoppered bottle." Long-continued exposure to sunlight causes opacity in the scales, and renders them difficultly soluble (Wood).

Ferri et Strychniæ Citras, U. S. P., is prepared by mixing a solution containing five grains of strychnia and five grains of citric acid with a solution containing five hundred grains of citrate of iron

and ammonium, evaporating the mixture at a temperature not exceeding 140° to a syrupy consistence, and scaling in the usual way by spreading it upon plates of glass.

Ferrum Tartaratum, B. P.; *Ferri et Potassii Tartras*, U. S. P. —Ferric hydrate is dissolved in solution of acid tartrate of potassium, and the whole evaporated to dryness.

The ferric hydrate obtainable from five and a half fluidounces of the official solution of ferric sulphate by the action of ammonia, in the manner detailed in the previous paragraphs, is mixed (in a mortar), while still moist but well drained, with two ounces of acid tartrate of potassium. The whole is set aside for twenty-four hours, with occasionally rubbing to promote contact and reaction of the molecules (otherwise somewhat sluggish in attacking each other), and then heated in a dish over a water-bath to a temperature not exceeding 140° F.; a pint of distilled water is then added, and the mixture kept warm until nothing more will dissolve. Filter, evaporate at a temperature not exceeding 140° (greater heat causes decomposition), and when the mixture has the consistence of syrup, spread on panes of glass and dry (in any warm and light place shown by a thermometer to be not hotter than 140°). Remove the dry salt in flakes, and keep it in well-closed bottles.

Ferri et Ammonii Tartras, U. S. P., is made by saturating solution of acid tartrate of ammonium with ferric hydrate, evaporating, and scaling. The acid tartrate is prepared by exactly neutralizing half of any quantity of tartaric acid by carbonate of ammonium, and then adding the other half.

The foregoing are the only official scale preparations of iron. Many others of similar character might be formed. The *Citrate* dissolves slowly in cold but readily in warm water. None crystallize or give other indications of definite chemical composition. Their properties are only constant so long as made with unvarying proportions of constituents. Their want of chemical compactness, the loose state in which the iron is combined, precludes their recognition as well-defined chemical compounds, yet possibly enables them to be more readily assimilated as medicines than some of the more definite ferrous and ferric salts.

Wine of Iron, or "Steel" wine (*Vinum Ferri*, B. P.), made by digesting iron wire in sherry wine, probably contains tartrate of potassium and iron and other iron salts, formed by action of the metal on the acid tartrate of potassium and tartaric, citric, malic, and acetic acids present in the wine. *Vinum Ferri Citratis*, B. P., is a solution of ammonio-citrate of iron in orange wine.

Black Hydrate of Iron. Ferro-ferric Hydrate.

Ferri Oxidum Magneticum, B. P.

Fifteenth Synthetical Reaction.—To two-thirds of a small quantity of a solution of ferrous sulphate add a little sulphuric acid; warm, and gradually add nitric acid, as described in the tenth reaction, care being taken not to allow

one drop more nitric acid than necessary to fall into the test-tube. Add the other third of ferrous sulphate, shake, and pour the liquid into excess of an alkali; black (at first brown) hydrate of iron, or ferroso-ferric hydrate ($Fe_3 8HO = Fe2HO, Fe_2 6HO$), is produced.

$$\underset{\text{Ferric sulphate.}}{Fe_2 3SO_4} + \underset{\text{Ferrous sulphate.}}{FeSO_4} + \underset{\text{Soda.}}{8NaHO} = \underset{\text{Blk. hydrate of iron.}}{Fe_3 8HO} + \underset{\text{Sulphate of sodium.}}{4Na_2SO_4}$$

It is so readily attracted by a magnet, even when moist, as to collect round the latter when immersed in the supernatant liquid. Hence the B. P. name, *Ferri Oxidum Magneticum.*

In this process the nitric acid oxidizes the hydrogen of the sulphuric acid, the sulphuric radical uniting with the ferrous sulphate, whose iron is at the same time altered from the ferrous to the ferric condition, ferric sulphate being formed. If too much nitric acid be employed, the second portion of ferrous sulphate will also be converted into ferric salt, and the solution, on the addition of alkali, yield only red ferric hydrate. This result may be avoided by evaporating the solution of ferric sulphate nearly to dryness, thus boiling off excess of nitric acid, or by pouring first the ferric and then the ferrous liquid into the alkali and thoroughly stirring the mixture; any nitric acid is then neutralized and rendered incapable of oxidizing the ferrous sulphate subsequently added.

Black hydrate of iron is decomposed by heat, yielding, in a closed vessel, oxyhydrates, and, finally, black oxide of iron or ferroso-ferric oxide. Heated in the air it absorbs oxygen and gives ferric oxide. The black *forge-scales*, which collect near the blacksmith's anvil, have the composition of ferroso-ferric oxide; the black magma formed on exposing a mixture of iron and water to the air is ferroso-ferric hydrate; but these varieties are apt to contain particles of metal, and, hence, give hydrogen gas when dissolved in acids—a character which distinguishes them from the official preparation.

If a dried specimen of the black hydrate of iron be required, the mixture should be well boiled and then set aside for an hour or two to favor aggregation of the particles, the mixture filtered, and the precipitate washed until the washings contain no trace of sulphate (indicated by a white precipitate with chloride of barium). Black hydrate of iron absorbs oxygen even at the temperature of the water-bath; it should consequently be dried at 120°, a temperature at which only slight oxidation occurs.

Pernitrate of Iron. Ferric Nitrate.

Sixteenth Synthetical Reaction.—Place a few iron tacks in dilute nitric acid and set aside; solution of ferric nitrate, or pernitrate of iron, is formed ($Fe_2 6NO_3$).

$$\underset{\text{Iron.}}{Fe_2} + \underset{\text{Nitric acid.}}{8HNO_3} = \underset{\text{Ferric nitrate.}}{Fe_2 6NO_3} + \underset{\text{Water.}}{4H_2O} + \underset{\text{Nitric oxide.}}{2NO}$$

This solution, made with care, and of a prescribed strength, forms the *Liquor Ferri Pernitratis*, B. P. (sp. gr. 1.107) and U. S. P. (sp. gr. 1.065). The process is as follows: Four and a half fluidounces of nitric acid are diluted with sixteen ounces of distilled water, and one ounce of iron wire, free from rust, dissolved in the mixture, the latter being kept cool to avoid violence of action. The liquid is finally filtered and diluted to thirty fluidounces.

Reduced Iron.

Seventeenth Synthetical Reaction.—Pass hydrogen gas (dried by passing over pieces of chloride of calcium contained in a tube, or through sulphuric acid in a wash bottle) into a small quantity of ferric oxyhydrate or oxide ("subcarbonate," U. S. P.) contained in a tube arranged horizontally (a test-tube, the bottom of which has been accidentally broken, answers very well), the oxide being kept hot by a gas-flame; oxygen is removed from the oxide by the hydrogen, steam escapes at the open end of the tube, and after a short time, when moisture ceases to be evolved, metallic iron, in a minute state of division, remains.

$$\underset{\text{Ferric oxide.}}{Fe_2O_3} + \underset{\text{Hydrogen.}}{3H_2} = \underset{\text{Iron.}}{Fe_2} + \underset{\text{Water.}}{3H_2O}$$

While still hot throw the iron out into the air; it takes fire and falls to the ground as oxide.

If the ferric oxide is reduced in a gun-barrel heated by a strong furnace, the particles of iron aggregate to some extent, and, when cold, are only slowly oxidized in dry air. This latter form of reduced iron is *Fer réduit*, or *Quevenne's Iron, the Ferri pulvis*, or *Ferrum Redactum*, B. P. and U. S. P.—"a fine grayish-black powder, strongly attracted by the magnet, and exhibiting metallic streaks when rubbed with firm pressure in a mortar." It is often administered in the form of lozenges (*Trochisci Ferri Redacti*, B.P.) gum and sugar protecting the iron from oxidation as well as forming a vehicle for its administration.

Note.—The spontaneous ignition of the iron in the above experiment is an illustration of the influence of minute division on chemical affinity. The action is the same as occurs whenever iron rusts, and the heat evolved and amount of oxide formed is not greater from a given quantity of iron; but the surface exposed to the action of the oxygen of the air is, in the case of this variety of reduced iron, so enormous compared with the weight of the iron, that heat cannot be conducted away sufficiently fast to prevent elevation of temperature to a point at which the whole becomes incandescent. In the slow rusting of iron, escape of heat occurs, but is not ob-

served, because spread over a length of time; in the spontaneous ignition of reduced iron the whole is evolved at one moment.

Ferric Pyrophosphate.

Eighteenth Synthetical Reaction.—To solution of pyrophosphate of sodium add solution of persulphate of iron; a yellowish-white precipitate of ferric pyrophosphate ($Fe_4 3P_2O_7$, $9H_2O$) separates. This precipitate, dissolved in solution of citrate of ammonium, and evaporated, yields apple-green scales (*Ferri pyrophosphas*, U. S. P., containing forty-eight per cent. of anhydrous pyrophosphate).

(*b*) *Reactions having Analytical Interest* (*Tests*).

(The iron occurring as a ferrous salt.)

First Analytical Reaction.—Pass sulphuretted hydrogen (H_2S) through a solution of a ferrous salt (*e.g.*, ferrous sulphate) slightly acidulated by hydrochloric acid; no precipitate occurs.

This is a valuable negative fact, as will be evident presently.

Second Analytical Reaction.—Add sulphydrate of ammonium (NH_4HS) to solution of a ferrous salt; a black precipitate of ferrous sulphide (FeS) falls.

$$FeSO_4 + 2AmHS = FeS + Am_2SO_4 + H_2S.$$

Third Analytical Reaction.—Add solution of ferrocyanide of potassium (yellow prussiate of potash), $K_4Fe''Cy_6$, or K_4Fcy'''', to solution of a ferrous salt; a precipitate ($K_2Fe''Fcy$) falls, at first white, but rapidly becoming blue, owing to absorption of oxygen.

Fourth Analytical Reaction.—To solution of a ferrous salt add ferridcyanide of potassium (red prussiate of potash), $K_6Fe'''_2Cy_{12}$, or K_6Fdcy; a precipitate (Fe''_3Fdcy) resembling Prussian blue (Turnbull's blue) is thrown down.

Other Analytical Reactions.—The precipitates produced from ferrous solutions on the addition of alkaline carbonates, phosphates, and arseniates, as already described in the synthetical reactions of ferrous salts, are characteristic, and hence have a certain amount of analytical interest, but are inferior in this respect to the four reactions above mentioned.

Note.—The alkalies (solution of potash, soda, or ammonia) are incomplete precipitants of ferrous salts, and are

therefore almost useless as tests. To solution of a ferrous salt add ammonia (NH_4HO); on filtering and testing with sulphydrate of ammonium, iron will still be found in the solution. To another portion of the ferrous solution add a few drops of nitric acid and boil; this converts the ferrous into ferric salt, and now alkalies will wholly remove the iron, as already twice seen during the performance of the synthetical experiments.

In actual analysis, the separation of iron as ferric hydrate is an operation of frequent performance. This is always accomplished by the addition of alkali, and, if the iron occurs as a ferrous salt, by previous ebullition with a little nitric acid. Ferrocyanide and ferridcyanide of potassium are the tests used in distinguishing ferrous from ferric salts.

(The iron occurring as a ferric salt.)

Sixth Analytical Reaction.—Through a ferric solution (ferric chloride, *e. g.*) pass sulphuretted hydrogen; a white precipitate of the sulphur of the sulphuretted hydrogen falls, and the ferric is reduced to a ferrous salt, the latter remaining in solution. This reaction is of frequent occurrence in practical analysis.

$$2Fe_2Cl_6 + 2H_2S = 4FeCl_2 + 4HCl + S_2.$$

Seventh Analytical Reaction.—Add sulphydrate of ammonium to a ferric solution; the latter is reduced to the ferrous state, and black ferrous sulphide (FeS) is precipitated as in the second analytical reaction, sulphur being set free.

Eighth Analytical Reaction.—To a ferric solution add ferrocyanide of potassium (K_4FeCy_6, or K_4Fcy''''); a precipitate of prussian blue, the common pigment, occurs ($Fe'''_4 3Fe''Cy_6$, or $Fe'''_4 Fcy''''_3$). (*Ferri Ferrocyanidum*, U. S. P.)

Ninth Analytical Reaction.—To a ferric solution add solution of ferridcyanide of potassium; no precipitate occurs, but the liquid is darkened to a greenish or olive hue, according to the strength.

Tenth Analytical Reaction.—This is the production of a red precipitate of ferric hydrate, on the addition of alkalies to ferric salts, and is identical with the twelfth synthetical reaction.

Note.—This reaction illustrates the conventional character of the terms synthesis and analysis. It is of equal importance to the manu-

facturer and the analyst, and is synthetical or analytical according to the intention with which it is performed.

Other ferric reactions have occasional analytical interest. In neutral ferric solutions the tannic acid in aqueous infusion of galls occasions a bluish-black inky precipitate, the basis of ordinary writing ink.——(The *Mistura Ferri Aromatica* of the British Pharmacopœia, made by digesting metallic iron in an infusion of various vegetable substances, contains tannate, or rather tannates of iron: it is commonly known in Ireland by the name of Heberden's Ink, after the physician by whom it was first used. It contains about 1 grain of iron in 1 pint.)——*Sulphocyanide of Potassium* (KCyS) causes the formation of ferric sulphocyanate, which is of deep blood-red color.——There is no ferric carbonate; alkaline carbonates cause the precipitation of ferric hydrate, while carbonic acid gas escapes.

Note.—Cyanogen (NC, or Cy′), ferrocyanogen (FeC_6N_6, or $FeCy_6$, or simply Fcy''''), and ferridcyanogen (Fe_2Cy_{12}, or $Fdcy^{VI}$), are radicals which play the part of non-metallic elements, just as ammonium in its chemical relations resembles the metallic elements. They will be again referred to.

Memorandum.—The reader must on no account omit to write out equations or diagrams expressive of each of the reactions of iron, analytical as well synthetical. It is presumed that this has already been done immediately after each reaction has been performed.

DIRECTIONS FOR APPLYING THE FOREGOING ANALYTICAL REACTIONS TO THE ANALYSIS OF AN AQUEOUS SOLUTION OF SALTS CONTAINING ONE OF THE METALS, ZINC, ALUMINIUM, IRON.

Add solution of ammonia gradually:—

A dirty-green precipitate indicates iron in the state of a ferrous salt.

A red precipitate indicates iron in the state of a ferric salt.

A white precipitate, insoluble in excess, indicates the presence of an aluminium salt.

A white precipitate, soluble in excess, shows zinc.

These results may be confirmed by the application of some of the other tests to fresh portions of the solution.

TABLE OF SHORT DIRECTIONS FOR APPLYING THE FOREGOING ANALYTICAL REACTIONS TO THE ANALYSIS OF AN AQUEOUS SOLUTION OF SALTS OF **ONE, TWO, OR ALL THREE** OF THE METALS, ZINC, ALUMINIUM, IRON.

Boil about half a test-tubeful of the solution with a few drops of nitric acid. This insures the conversion of ferrous into ferric salts, and enables the next reagent (ammonia) *completely* to precipitate the iron. Add excess of ammonia, and shake the mixture. Filter.

Precipitate Al Fe.* Dissolve in HCl, add excess of KHO, stir, filter.		Filtrate Zn. Test by AmHS. (white ppt.).
Ppt. Fe (red ppt.).	Filtrate Al. Neutralize by HCl, and add excess of AmHO† (white ppt.).	

Note I.—If iron is present, portions of the original solution must be tested by ferridcyanide of potassium for ferrous, and by ferrocyanide for ferric salts; dark-blue precipitates with both indicate both salts.

Note II.—If no ferrous salt is present, ebullition with nitric acid is unnecessary. It is, perhaps, therefore advisable always to determine this point by previously testing a little of the original solution with ferridcyanide; if no blue precipitate occurs, the nitric acid treatment may be omitted.

CHART FOR ALL METALS HITHERTO CONSIDERED.

The following Table (*vide* p. 141) is perhaps the best, but not the only adaptation of the ordinary reactions to systematic analysis. It is little else than the addition of the analytical scheme for the

* The aluminium precipitate ($Al_2 6HO$) is white, the iron ($Fe_2 6HO$) red. If the precipitate is red, iron must be and aluminium may be present; if white, iron is absent, and further operation on the precipitate unnecessary.

† Alumina, when in small quantity, is sometimes prevented from being precipitated by ammonia through the presence of organic matter derived from the filter paper by action of the potash. In cases of doubt, therefore, before adding ammonia boil the liquid with a little nitric acid, which destroys any organic matter.

third group to that of the first two groups. As before, analysis is commenced by the addition of chloride of ammonium (NH_4Cl) to prevent partial precipitation of magnesium, and ammonia (NH_4HO) to neutralize any acid. The latter would attack the chief group-precipitant, sulphydrate of ammonium (NH_4HS), preventing its useful action, and causing a precipitation of the sulphur it commonly contains.

Note.—When a test gives no reaction, absence of the body sought for may be fairly inferred. If group-tests (that is, tests which precipitate a group of substances) give no reaction, the analyst is saved the trouble of looking for either member of the respective groups.

TABLE OF SHORT DIRECTIONS FOR THE ANALYSIS OF AN AQUEOUS SOLUTION OF SALTS OF ANY OR ALL OF THE METALLIC ELEMENTS HITHERTO CONSIDERED.

Add AmCl; AmHO; AmHS; stir, filter.

<table>
<tr><td colspan="3">Precipitate
Fe Al Zn.
Wash, dissolve in HCl,* boil (to remove H_2S), filter (to remove S), add KHO, stir, filter.</td><td colspan="4">Filtrate
Ba Ca Mg Am Na K.
Add Am_2CO_3, boil, filter.</td></tr>
<tr><td rowspan="2">Ppt.
Fe
(test orig. sol. by K_4Fcy and K_6Fdcy).</td><td colspan="2">Filtrate
Al Zn.
Neutralize with HCl.
Add AmHO, stir, filter.</td><td colspan="2">Ppt.
Ba Ca
Dissolve in $HC_2H_3O_2$,
Add K_2CrO_4, filter.</td><td colspan="2">Filtrate
Mg Am Na K
Add Am_2HPO_4, stir, filter.</td></tr>
<tr><td>Ppt.
Al
(white).</td><td>Filtrate
Zn
Add AmHS.
(white ppt.).</td><td>Ppt.
Ba
(yellow).</td><td>Filtrate
Ca
Add $Am_2C_2O_4$
(white ppt.).</td><td>Ppt.
Mg
(white).</td><td>Filtrate
Am Na K.
Evap., ignite, dissolve.
Na by flame; K by $PtCl_4$;
orig sol. for Am.</td></tr>
</table>

* Add, also, a few drops of HNO_3 if Fe be present—*i. e.*, if the ppt. be black. (*Vide* notes on pp. 136 and 139.)

QUESTIONS AND EXERCISES.

207. Name the chief ores of iron.

208. How is the metal obtained from the ores?

209. What is the chemical difference between cast iron, wrought iron, and steel?

210. Explain the process of welding.

211. What is the nature of chalybeate waters?

212. Illustrate by formulæ the difference between ferrous and ferric salts.

213. Under what different circumstances may the atom of iron be considered to exert bivalent, trivalent, and sexivalent activity?

214. Write a paragraph on the nomenclature of iron salts.

215. Give a diagram of the official process for the preparation of ferrous sulphate.

216. In what respects do Sulphate of Iron, Granulated Sulphate of Iron, and dried Sulphate of Iron differ?

217. How is ferrous sulphate obtained on the large scale?

218. Mention the chemical names of white, green, and blue vitriol.

219. Why does ferrous sulphate become brown by prolonged exposure to air?

220. Give a diagram showing the formation of Ferrous Carbonate

221. Describe the action of atmospheric oxygen on ferrous carbonate: can the effect be prevented?

222. In what order would you mix the ingredients of *Mistura Ferri Composita*, and why?

223. Write out an equation illustrative of the formation of the Phosphate of Iron.

224. Why is acetate of sodium used in the preparation of ferrous phosphate?

225. Which four compounds of iron may be formed by the direct union of their elements?

226. Give the official method for the preparation of Solution of Ferric Chloride.

227. Of what use is the spirit in Tincture of Perchloride of Iron?

228. How may Ferrous be converted into Ferric Sulphate?

229. What is the formula of Ferric Acetate? and how is it prepared for use in pharmacy?

230. Express, by formulæ, the difference between *Ferri Peroxidum Humidum*, B. P., and *Ferri Peroxidum Hydratum*, B. P.

231. How does Ferric Hydrate act as an antidote to arsenic?

232. What are the properties of anhydrous ferric oxide?

233. What are the general characters and mode of production of the medicinal scale preparations of iron?

234. In what state is the iron in *Vinum Ferri*, B. P.?

235. What other form of Wine of Iron is official in Great Britain?

236. Give equations illustrating the chief steps in the artificial production of the so-called Magnetic Oxide of Iron.

237. How is precipitated magnetic oxide of iron distinguished from the varieties made directly from the metal?

238. Why is magnetic oxide of iron officially directed to be dried at a temperature not exceeding 120° Fahr.?

239. Give a diagram showing the formation of Ferric Nitrate.

240. Work out a sum showing how much anhydrous ferric oxide will yield, theoretically, one hundred-weight of iron. Ans. 160 lbs.

241. What are the properties of anhydrous ferric oxide?

242. Give the characteristic tests for iron, distinguishing between ferrous and ferric reactions, and illustrating each by an equation or a diagram:—

a. Sulphydrate of ammonium.
b. Ferrocyanide of potassium.
c. Ferridcyanide of potassium.
d. Caustic alkalies.
e. Sulphocyanate of potassium.

243. Describe the action of ammonia on salts of iron, aluminium, and zinc respectively.

244. What precautions must be used in testing for calcium in the presence of iron?

245. How is magnesium detected in the presence of zinc?

246. How is aluminium detected in the presence of magnesium?

247. Draw up a scheme for the analysis of an aqueous liquid containing salts of iron, barium, and potassium.

248. How may zinc, magnesium, and ammonium be consecutively removed from aqueous solution?

ARSENICUM, ANTIMONY.

These two elements resemble metals in appearance and in the character of some of their compounds; but they are still more closely allied to the non-metals, especially to phosphorus and nitrogen. They are quinquivalent (As^{v}, Sb^{v}), as seen in arsenic anhydride (As_2O_5) and pentachloride of antimony ($SbCl_5$), but usually exert trivalent activity only (As^{III}, Sb^{III}), as seen in the hydrogen and other compounds (AsH_3, $AsCl_3$, $AsBr_3$, AsI_3). A few preparations of these elements are used in medicine; but all are more or less powerful poisons, and hence have considerable toxicological interest. The iodide (*Arsenici Iodidum*, U. S. P.) is made by cautiously fusing together atomic proportions of arsenicum and iodine. It is an orange-red crystalline solid soluble in water. The *Liquor Arsenici et Hydrargyri Iodidi*, U. S. P., is made by dissolving iodide of arsenicum and red iodide of mercury in water, in the proportion of 1 grain of each of the solids to 104 grains of water.

Arsenicum is an exception to the rule that the atomic weights (taken in grains, grammes, or other weight) of elements, under similar circumstances of temperature and pressure, give equal volumes of vapor, the equivalent weight (75) of arsenicum only occupying half such a volume. Hence, while the molecular weights (that is, double the atomic weights) of oxygen ($O_2 = 32$), hydrogen ($H_2 = 2$), nitrogen ($N_2 = 28$), etc., give a similar bulk of vapor at any given

temperature and pressure, the double atomic weight of arsenicum, ($As_2 = 150$), at the same temperature and pressure, only affords half this bulk. It would appear, therefore, that the molecule of arsenicum contains four atoms, and that its formula is As_4. As with sulphur, however, arsenicum, in the state ordinarily known to us, may be abnormal, and a variety yet be found in which the molecular weight is double (instead of quadruple) the atomic weight.

From observed analogy between the two metals, the molecular constitution of antimony is probably similar to that of arsenicum.

ARSENICUM.

Symbol As. Atomic weight 75.

Sources.—Arsenical ores are frequently met with in nature, the commonest being the arsenio-sulphide of iron (FeSAs). This mineral is roasted in a current of air, the oxygen of which, combining with the arsenicum, forms common white arsenic (As_2O_3) (*Acidum Arseniosum*, B. P. and U. S. P.) which is condensed in chambers or long flues. It commonly "occurs as a heavy white powder, or in sublimed masses, which usually present a stratified appearance, caused by the existence of separate layers, differing from each other in degrees of opacity." *Realgar* (red algar) is the red native sulphide (As_2S_2), and orpiment (*auripigmentum*, the golden pigment) the yellow native sulphide (As_2S_3) of arsenicum.

Reactions having (*a*) Synthetical and (*b*) Analytical Interest.

(*a*) *Reactions having Synthetical Interest.*

Alkaline Solution of Arsenic.

First Synthetical Reaction.—Boil a grain or two of powdered arsenic (As_2O_3) in water containing an equal weight of carbonate of potassium, and, if necessary, filter. The solution, colored with compound tincture of lavender, and containing 4 grains of arsenic per ounce, forms the *Liquor Arsenicalis*, B. P., or *Liquor Potassii Arsenitis*, U. S. P. (*Fowler's Solution.*)

Note.—This official solution does not generally contain arsenite of potassium; for the arsenic does not decompose the carbonate of potassium, or only after long boiling. From concentrated solutions carbonic acid gas is more quickly eliminated.

Arsenious Acids and other Arsenites.

When arsenic (As_2O_3) is dissolved in excess of solutions of potash or soda, arsenites are formed having the formulæ KH_2AsO_3 and

NaH_2AsO_3. Boiled with excess of arsenic, one molecule of these salts combines with one of arsenic. The usual character of such compounds is that of oily alkaline liquids. Arsenic or arsenious anhydride (the so-called arsenious acid), when dissolved in water, yields true arsenious acid (H_3AsO_3), the arsenite of hydrogen.

$$\underset{\text{Arsenious anhydride.}}{As_2O_3} + \underset{\text{Water.}}{3H_2O} = \underset{\text{Arsenious acid.}}{2H_3AsO_3}$$

Acid Solution of Arsenic.

Second Synthetical Reaction.—Boil arsenic with dilute hydrochloric acid. Such a solution made with prescribed proportions of acid and water, and containing 4 grains of arsenic (As_2O_3) per ounce, forms the *Liquor Arsenici Hydrochloricus*, B. P. (*Liquor Arsenici Chloridi*, U. S. P.) (*De Valangin's Solution* contained a grain and a half per ounce.)

Note.—No decomposition occurs in this experiment. The liquid is simply a solution of arsenic in dilute hydrochloric acid. These two solutions may be preserved for analytical operations.

Mem.—The practical student should boil arsenic in water also, and thus have an acid, alkaline, and aqueous solution for analytical comparison.

Arsenicum.

Third Synthetical Reaction.—Place a grain or less of arsenic at the bottom of a narrow test-tube, cover it with about half an inch or an inch of small fragments of dry charcoal, and hold the tube, nearly horizontally, in a flame, the mouth being loosely covered by the thumb. At first let the bottom of the tube project slightly beyond the flame, so that the charcoal may become nearly red-hot; then heat the bottom of the tube. The arsenic will sublime, become deoxidized by the charcoal, carbonic oxide being formed, and arsenicum deposited in the cool part of the tube as a dark mirror-like metallic incrustation.

There is a characteristic odor, resembling garlic, emitted during this operation, probably due to a partially oxidized trace of arsenicum which escapes from the tube; for arsenic alone does not give this odor; moreover, arsenicum being a freely oxidizable element, its vaporous particles could scarcely exist in the air in an entirely unoxidized state.

Metallic arsenicum (*Arsenicum*, U. S. P.) may be obtained in large quantities by the above process if the operation be conducted in vessels of commensurate size. But performed with great care, in narrow tubes, using not charcoal alone, but *black flux* (a mixture of charcoal and carbonate of potassium obtained by heating acid tar-

trate of potassium in a test-tube or other closed vessel till no more fumes are evolved), the reaction has considerable analytical interest, the garlic odor and the formation of the mirror-like ring being highly characteristic of arsenicum. Compounds of mercury and antimony, however, give sublimates which may be mistaken for arsenicum.

Arsenic Acid and other Arseniates.

Fourth Synthetical Reaction.—Boil a grain or two of arsenic with a few drops of nitric acid until red fumes cease to be evolved; evaporate the solution in a small dish to dryness, to remove excess of nitric acid; dissolve the residue in water: the product is Arsen'ic acid (H_3AsO_4).

Arsenic acid, when strongly heated, loses the elements of water, and arsenic anhydride remains (As_2O_5).

Arsenic anhydride readily absorbs water and becomes arsenic acid (H_3AsO_4). Arsenic acid is readily reduced to arsenious by the action of reducing agents such as sulphurous acid, $H_3AsO_4 + H_2SO_3 = H_3AsO_3 + H_2SO_4$.

Salts analogous to arsenic acid, the arseniate of hydrogen, are termed *arseniates*, and have the general formula R'_3AsO_4. The ammonium arseniate (Am_3HAsO_4) may be made by neutralizing arsenic acid with ammonia. Its solution in water forms a useful reagent. ——Arsenic acid is used as an oxidizing agent in the manufacture of the well-known dye, magenta.

Arsenite and arseniate of sodium are used in the cleansing operations of the calico-printer.

Pyroarseniate and Arseniate of Sodium.

Fifth Synthetical Reaction.—Fuse a minute fragment of common white arsenic (As_2O_3) with nitrate of sodium ($NaNO_3$) and dried carbonate of sodium (Na_2CO_3) in a porcelain crucible, and dissolve the mass in water; solution of arseniate of sodium (Na_2HAsO_4) results.

As_2O_3	$+ 2NaNO_3$	$+ Na_2CO_3$	$= Na_4As_2O_7$	$+ N_2O_3$	$+ CO_2$
Arsenic.	Nitrate of sodium.	Carbonate of sodium.	Pyroarseniate of sodium.	Nitrous anhydride.	Carbonic acid gas.

The official proportions (B. P) are 10 of arsenic to 8½ of nitrate of sodium and 5½ of dried carbonate, each powdered, the whole well mixed, fused in a crucible at a red heat till effervescence ceases, and the liquid poured out on a slab. The product is pyroarseniate of sodium ($Na_4As_2O_7$). Dissolved in water, crystallized, and dried, the salt has the formula $Na_2HAsO_4, 7H_2O$ (*Sodii Arsenias*, U. S. P.).

$$Na_4As_2O_7 + 15H_2O = 2(Na_2HAsO_4, 7H_2O).$$

Heated to 300° F. the crystals lose all water. A solution of 4 grains of the anhydrous salt (Na_2HAsO_4) in 1 ounce of water forms the *Liquor Sodii Arseniatis*, U. S. P. The anhydrous salt is used

in this preparation because the crystallized is of somewhat uncertain composition. The fresh crystals are represented by the formula Na_2HAsO_4, $12H_2O$ (= 53.7 per cent of water); these soon effloresce and yield a stable salt having the formula Na_2HAsO_4, $7H_2O$ (= 40.4 per cent. of water). To avoid the possible employment of a mixture of these bodies, the invariable anhydrous salt is officially used, constancy in the strength of a powerful preparation being thereby secured.

The student will find useful practice in verifying the above numbers representing the centesimal proportion of water in the two arseniates of sodium. This will readily be accomplished if what has already been stated respecting a symbol representing a number as well as a name, and the remarks concerning molecular weight, be remembered.

The shape of each of the two varieties of arseniate of sodium (Na_2HAsO_4, $12H_2O$, and Na_2HAsO_4, $7H_2O$) is identical with that of the corresponding phosphate of sodium (Na_2HPO_4, $12H_2O$, and Na_2HPO_4, $7H_2O$); the structure of the molecule of the 12-arseniate is the same as that of 12-phosphate, and the 7-arseniate as that of the 7-phosphate; the two former are isomorphous, the two latter are isomorphous. This is only one instance of the strong analogy of arsenicum and its compounds with phosphorus and its corresponding compounds. The preparation and characters of the next substance, arseniate of iron, will remind the learner of phosphate of iron.

Arseniate of Iron. Ferrous Arseniate.

Sixth Synthetical Reaction.—To solution of arseniate of sodium add a little acetate of sodium and then solution of ferrous sulphate, a precipitate of ferrous arseniate occurs (Fe_32AsO_4) (*Ferri Arsenias*, B. P.). On the large scale 4 parts of dried arseniate and 3 of acetate dissolved in 40 of water, mixed with 9 of sulphate in 60 of water, may be employed. The precipitate should be collected on a calico filter, washed, squeezed, and dried at a low temperature (100° F.) over a wash-bath to avoid excessive oxidation.

$$\underset{\text{Arseniate of sodium.}}{2Na_2HAsO_4} + \underset{\text{Acetate of sodium.}}{2NaC_2H_3O_2} + \underset{\text{Ferrous sulphate.}}{3FeSO_4} = \underset{\text{Ferrous arseniate.}}{Fe_32AsO_4} + \underset{\text{Sulphate of sodium.}}{3Na_2SO_4} + \underset{\text{Acetic acid.}}{2HC_2H_3O_2}.$$

The use of the acetate of sodium is to insure the occurrence of acetic acid in solution, where otherwise would be free sulphuric acid. Sulphuric acid is a solvent of ferrous arseniate; acetic acid is not. It is impossible to prevent the separation of sulphuric acid, if only ferrous sulphate and arseniate of sodium be employed. At the instant of precipitation ferrous arseniate is white, but rapidly becomes of a green or greenish-blue color, owing to absorption of oxygen and formation of a ferroso-ferric arseniate. It is a tasteless amorphous powder, soluble in acids.

The *Hydride* and *Sulphides* of *Arsenicum*, and the *Arsenites* and *Arseniates of Copper* and of *Silver* are mentioned in the following analytical paragraphs :—

(*b*) *Reactions having Analytical Interest* (*Tests*).

First Analytical Reaction.—Cut or break off portions of the tube containing the sublimate of arsenicum obtained in the third synthetical reaction, put them into a test-tube and heat the bottom of the latter, holding it nearly horizontally, and partially covering the mouth with the finger or thumb; the arsenicum (As_2) will absorb oxygen from the air in the tube, and the resulting arsenious anhydride (As_2O_3) be deposited on the cool part of the tube in characteristic octahedral (ὀκτώ, *okto*, eight; ἕδρα, *hedra*, side) crystals, more or less perfect.

Microscopic Test.—Prove that the crystals are identical in form with those of common white arsenic, by heating a grain or less of the latter in another test-tube, examining the two sublimates by a good lens or compound microscope.

Notes.—The production of arsenicum and its subsequent oxidation are test-reactions perhaps not quite so delicate as some that follow, requiring more material for their satisfactory performance; yet the form of the crystals is charateristic. no other volatile body being likely to be mistaken for them; and in toxicological cases it is desirable to obtain the arsenicum in a similar state to that in which probably it originally exerted its effects; the processes alluded to are therefore of considerable importance. Moreover, arsenicum, ready for sublimation to crystalline arsenic, is easily obtained from solution by the following reaction :—

Second Analytical Reaction.—Place a thin piece of copper, about a quarter inch wide and half inch long, in a solution of arsenic, acidified by hydrochloric acid, and boil (nitric acid must not be present, or the copper itself will be dissolved); arsenicum is deposited on the plate in a metallic condition, an equivalent portion of copper going into solution. Pour off the supernatant liquid from the copper, wash the latter once or twice with water, dry the piece of metal by holding in the fingers and passing through a flame, and finally place it at the bottom of a clean dry narrow test-tube; sublime as described in the last reaction, again noticing the form of the resulting crystals.

This is commonly known as Reinsch's test for arsenicum. The tube may be reserved for subsequent comparison with an antimonial sublimate (p. 160).

Note.—Copper itself frequently contains arsenicum, a fact that may not, perhaps, much trouble an operator so long as he is performing experiments in practical chemistry merely for educational purposes; but when he engages in the analysis of bodies of unknown composition, he must assure himself that neither his apparatus nor materials already contain the element of which he is in search.

The detection of arsenicum in metallic copper is best accomplished by distilling a mixture of a few grains of the sample with five or six times its weight of ferric hydrate or chloride (free from arsenicum) and excess of hydrochloric acid. The arsenicum is thus volatilized in the form of chloride of arsenicum, and may be condensed in water and detected by sulphuretted hydrogen (5th Analytical Reaction) or Reinsch's test. The ferric chloride solution is, if necessary, freed from any trace of arsenicum by evaporating once or twice to dryness with excess of hydrochloric acid (Odling).

Third Analytical Reaction — Marsh's test. — Generate hydrogen in the usual way from water by zinc and sulphuric acid, a bottle of about four or six ounces capacity being used, and a funnel-tube and short delivery-tube passing through the cork in the usual manner (described on page 81). Dry the escaping hydrogen (except in rough experiments, when it is unnecessary) by adapting to the delivery-tube, by a pierced cork, a short piece of wider tubing containing fragments of chloride of calcium. To the opposite end of the drying-tube fit a piece of narrow tubing ten or twelve inches long, made of hard German glass, and having its aperture narrowed by drawing out in the flame of the blowpipe. When the hydrogen has been escaping at such a rate and for a sufficient number of minutes as to warrant the operator in concluding that all the air originally existing in the bottle has been expelled, set light to the jet, and then pour eight or ten drops of the aqueous solution of arsenic, or three or four drops of the acid or alkaline solution of arsenic, previously prepared, into the funnel-tube, washing the liquid into the generating-bottle with a little water. The arsenic is at once reduced to the state of arsenicum, and the latter combines with some of the hydrogen to form hydride of arsenicum or arseniuretted hydrogen gas (AsH_3). Immediately hold a piece of earthenware or porcelain (the lid of a porcelain crucible, if at hand) in the hydrogen jet at the extremity of the delivery-tube; a brown spot of condensed arsenicum is deposited. Collect several of these spots, and retain them for future comparison with antimonial spots (p. 160).

The separation of arsenicum in the flame is due to the decomposition of the arseniuretted hydrogen by the heat of combustion. The cool porcelain at once condenses the arsenicum, and thus prevents its oxidation to white arsenic, which would otherwise take place at the outer edge of the flame.

Hold a small beaker or wide test-tube over the flame for a few minutes; a white film of arsenic (As_2O_3) will be slowly deposited, and may be further examined in contrast with a similar antimonial film (p. 160).

During these experiments the effect produced by the arsenical vapors on the color of the hydrogen-flame will have been noticed; they give it a dull livid bluish tint. This is characteristic.

Apply the flame of a gas-lamp to the middle of the hard delivery-tube; the arseniuretted hydrogen, as before, is decomposed by the heat, but the liberated arsenicum (As_2) immediately condenses in the cool part of the tube beyond the flame, forming a dark metallic mirror. The tube may be removed and kept for comparison with an antimonial deposit.

Note I.—Zinc, like copper, frequently itself contains arsenicum. When a specimen free from arsenicum is met with, it should be reserved for analytical experiments, or a quantity of guaranteed purity should be purchased of the chemical-apparatus maker. Sulphuric acid is more easily obtained free from arsenic.

Note II.—In delicate and important applications of Marsh's test, magnesium may be substituted for zinc with safety, as arsenicum has not yet been, nor is it likely to be, found in magnesium. Magnesium in rods is convenient for this purpose, and may be obtained from most dealers in chemicals.

Note III.—Arseniuretted hydrogen is decomposed by strong sulphuric acid; hence chloride of calcium is used in drying the gas.

Fourth Analytical Reaction — Fleitmann's test.—Generate hydrogen by heating to near the boiling-point a strong solution of caustic soda or potash and some pieces of zinc. Drop into the test-tube a little arsenical solution, and spread over the mouth of the tube a cap of filter-paper moistened with one drop of solution of nitrate of silver. Again heat the tube, taking care that the liquid itself shall not spirt up on to the cap; the arsenic is reduced to arsenicum, the latter uniting with the hydrogen as in Marsh's test; and the arseniuretted hydrogen passing up through the cap reacts on the nitrate of silver, causing the production of a purplish-black spot.

$$AsH_3 + 3H_2O + 6AgNO_3 = H_3AsO_3 + 6HNO_3 + 3Ag_2.$$

Note.—This reaction is particularly valuable, enabling the analyst to quickly distinguish arsenicum in the presence of its sister element antimony, which, although it combines with the hydrogen evolved from dilute acid and zinc, does not combine with the hydrogen evolved from solution of alkali and zinc, and therefore does not give the effect just described.

Fifth Analytical Reaction.—To a solution of chloride of tin in strong hydrochloric acid add a very small quantity of any arsenical solution. Arsenicum then separates, especially on the application of heat, giving the mixture a yellowish and then brownish hue or grayish-brown turbidity, or even a sediment of gray-brown flocks, according to the amount present. Much water prevents the reaction; its presence, therefore, must be avoided as much as possible; indeed a liquid saturated by hydrochloric acid gas gives best results. Arsenic in sulphuric or hydrochloric acids or in tartar emetic, etc., may be detected by this method. Nitrates, such as subnitrate of bismuth, must first be heated with sulphuric acid to remove the nitric radical before applying this reduction test for arsenicum. The stannous is converted to stannic salt during the reaction.

Distinction between Arsenious and Arsenic combinations.—The above tests are those of arsenicum, whether existing in the arsenious or arsenic condition, though from the latter the element is not generally eliminated so quickly as from the former. Of the following reactions, that with nitrate of silver at once distinguishes arsenious acid and other arsenites from arsenic acid and other arseniates.

Mem.—The exact nature of all these analytical reactions will be more fully evident if traced out by diagrams or equations.

Sixth Analytical Reaction.—Through an acidified solution of arsenic pass sulphuretted hydrogen; a yellow precipitate of sulphide of arsenicum or arsenious sulphide (As_2S_3) quickly falls. Add an alkaline hydrate or sulphydrate to a portion of the precipitate; it readily dissolves. The precipitate consequently would not be obtained on passing sulphuretted hydrogen through an alkaline solution of arsenic. To another portion of the precepitate, well drained, add *strong* hydrochloric acid; it is insoluble, unlike sulphide of antimony.

Note I.—The only other metal which gives a yellow sulphide in an acid solution by action of sulphuretted hydrogen is cadmium; but this sulphide is insoluble in alkaline liquids.

Note II.—A trace of sulphide of arsenicum is sometimes met with in sulphur (distilled from arsenical pyrites). It may be detected by digesting the sulphur in solution of ammonia, filtering, and evaporating to dryness; a yellow residue of sulphide of arsenicum is obtained if that substance be present.

Seventh Analytical Reaction.—Through an acidified solution of arsenic acid, or any other arseniate, pass sulphuretted hydrogen; a yellow precipitate of arsenic sulphide (As_2S_5) slowly falls. This also is soluble in alkaline hydrates and sulphydrates.

Chemical Analogy of Sulphur and Oxygen.—The solubility of arsenious and arsenic sulphide in alkaline solutions is good evidence of the close chemical analogy between them and the corresponding oxygen compounds of arsenicum. The potassium arsenite and sulph-arsenite, arseniate and sulph-arseniate, have the composition represented by the following formulæ:—

K_3AsO_3 $\quad$ K_3AsO_4
K_3AsS_3 $\quad$ K_3AsS_4;

and the corresponding ammonium and sodium salts have a similar composition:—

$$6AmHS + As_2S_3 = 2Am_3AsS_3 + 3H_2S$$
$$6AmHS + As_2S_5 = 2Am_3AsS_4 + 3H_2S.$$

Eighth Analytical Reaction.—To an aqueous solution of arsenic add two or three drops of solution of sulphate of copper, and then cautiously add diluted solution of ammonia, drop by drop, until a green precipitate is obtained. The production of this precipitate is characteristic of arsenicum. To a portion of the mixture add an acid; the precipitate dissolves. To another portion add alkali; the precipitate dissolves. These two experiments show the advantage of testing a suspected arsenical solution by litmus paper before applying this reaction; if acid, cautiously adding alkali, if alkaline, adding acid, till neutrality is obtained. (Or a special copper reagent may be used; see a note to the Eleventh Analytical Reaction, p. 153.)

The precipitate is arsenite of copper ($Cu''HAsO_3$) or *Scheele's Green.* More or less pure, or mixed with acetate or, occasionally, carbonate of copper, it is very largely used as a pigment under many names, such as Brunswick Green and Schweinfurth Green, by painters, paper-stainers, and others.

Ninth Analytical Reaction.—Apply the test just described to a solution of arsenic acid or other arseniate; a somewhat similar precipitate of arseniate of copper is obtained.

Tenth Analytical Reaction.—Repeat the eighth reaction, substituting nitrate of silver for sulphate of copper: in this case *yellow* arsenite of silver (Ag_3AsO_3) falls, also soluble in acids and alkalies.

Eleventh Analytical Reaction.—Apply the test to a solution of arsenic acid or other arseniate; a *chocolate*-colored precipitate of arseniate of silver (Ag_3AsO_4) falls.

Copper and Silver Reagents for Arsenicum.—The last four reactions may be performed with increased delicacy and certainty of result, if the copper and silver reagents be previously prepared in the following manner: To solution of pure sulphate of copper (about 1 part in 20 of water) add ammonia until the blue precipitate at first formed is nearly, but not quite, redissolved; filter and preserve the liquid as an arsenicum reagent, labelling it *solution of ammonio-sulphate of copper* (B. P.). Treat solution of nitrate of silver (about 1 part in 40) in the same way, and label it *solution of ammonio-nitrate of silver* (B. P.). The composition of these two salts will be referred to subsequently.

Arsenious and Arsenic Compounds.—While many reagents may be used for the detection of arsenicum, only nitrate of silver, as already stated, will readily indicate in which state of oxidation the arsenicum exists; for the two sulphides and the two copper precipitates, though differing in composition, resemble each other in appearance, whereas the two silver precipitates differ in color as well as in composition.

Soluble arseniates also give insoluble arseniates with barium, calcium, zinc, and some other metallic solutions.

Antidote.—In cases of poisoning by arsenic or arsenical preparations, the most effective antidote is recently precipitated moist ferric hydrate (*Ferri Peroxidum Humidum*, B. P., *Ferri Oxidum Hydratum*, U. S. P.). It is perhaps best administered in the form of a mixture of solution of perchloride of iron (*Liquor* or *Tinctura*) with carbonate of sodium—two or three ounces of the former to about one ounce of the crystals of the latter. Instead of the carbonate of sodium, about a quarter of an ounce of calcined magnesia may be used. These quantities will render at least 10 grains of arsenic insoluble. Emetics should also be given, and the stomach-pump applied as quickly as possible.

The above statements regarding the antidote for arsenic may be verified by mixing the various substances together, filtering, and proving the absence of arsenicum in the filtrate by applying some of the foregoing tests.

Mode of Action of the Antidote.—The action of the carbonate of sodium or the magnesia is to precipitate ferric hydrate (Fe_26HO)—chloride of sodium (NaCl) or magnesium ($MgCl_2$) being formed,

which are harmless, if not beneficial, under the circumstances. The reaction between the ferric hydrate and the arsenic results in the formation of insoluble ferrous arseniate.

$$\underset{\text{Ferric hydrate.}}{2(Fe_2 6HO)} + \underset{\text{Arsenic.}}{As_2O_3} = \underset{\text{Ferrous arseniate.}}{Fe_3 2AsO_4} + \underset{\text{Water.}}{5H_2O} + \underset{\text{Ferrous hydrate.}}{Fe2HO}$$

As already stated, dried ferric hydrate (then become an oxyhydrate, $Fe_4O_4 4HO$) *Ferri Peroxidum Hydratum*, B. P.) has no action on arsenic. Even the moist recently prepared hydrate ($Fe_2 6HO$) ceases to react with arsenic as soon as it has become converted into an oxyhydrate ($Fe_4O_3 6HO$), a change which occurs though the hydrate be kept under water (Procter). According to T. and H. Smith this decomposition occurs gradually, but in an increasing ratio; so that after four months the power of the moist mass is reduced to one-half, and after five months to one-fourth.

QUESTIONS AND EXERCISES.

249. What is the formula of a molecule of arsenicum?

250. In what form does arsenicum occur in nature?

251. Describe the characters of white arsenic.

252. Name the official preparations of arsenicum.

253. What proportion of arsenic (As_2O_3) is contained in *Liquor Arsenicalis*, B. P., and *Liquor Arsenici Hydrochloricus*, B. P.?

254. By what method may arsenic be reduced to arsenicum?

255. Give the formulæ of arsenious and arsenic acids and anhydrides.

256. Explain, by diagrams, the reactions which occur in converting arsenic into Arseniate of Sodium by the process of the British Pharmacopœia.

257. Why is anhydrous instead of crystallized arseniate of sodium employed in the preparation of *Liquor Sodæ Arseniatis*, B. P.?

258. In the preparation of Arseniate of Iron from ferrous sulphate and arseniate of sodium, why is acetate of sodium included?

259. Describe the manipulations necessary in distinguishing arsenic by its crystalline form.

260. How is Reinsch's test for arsenicum applied, and under what circumstances may its indications be fallacious?

261. Give the details of Marsh's test for arsenicum, and the precautions to be observed in its performance. Explain the reactions by diagrams.

262. What peculiar value has Fleitmann's test for arsenicum?

263. Describe the conditions under which sulphuretted hydrogen becomes a trustworthy test for arsenicum.

264. How may a trace of sulphide of arsenicum be detected in sulphur?

265. How are the salts of copper and silver applied as reagents for the detection of arsenicum?

266. How are arsenites distinguished from arseniates?

267. Mention the best antidote in cases of poisoning by arsenic, explain the process by which it may be most quickly prepared, and describe its action.

268. What light does the action of arsenic on ferric hydrate throw on the constitution of the latter substance?

ANTIMONY.

Symbol Sb (stibium). Atomic weight 122.

Source and Uses.—Antimony occurs in nature chiefly as sulphide, Sb_2S_3. The *crude* or *black antimony* of pharmacy is this native sulphide freed from earthy impurities by fusion: it has a striated, crystalline, lustrous fracture; subsequently powdered it forms the grayish-black crystalline *Antimonium nigrum*, B. P., *Antimonii sulphuretum*, U. S. P. The metal is easily obtained from the sulphide by roasting, and then reducing with charcoal and carbonate of sodium. Metallic antimony is an important constituent of *Type-metal*, *Britannia metal* (tea and coffee pots, spoons, etc.), and the best varieties of *Pewter*. The old *pocula emetica*, or everlasting emetic cups, were made of antimony; wine kept in them for a day or two acquired a variable amount of emetic quality. The metal is not used in making the antimonial preparations of the Pharmacopœia, the sulphide alone being, directly or indirectly, employed for this purpose.

Antimony has very close chemical analogies with arsenicum. Its atom, in the official salts, exerts trivalent activity (*e. g.*, $SbCl_3$), but sometimes it is quinquivalent (*e. g.*, $SbCl_5$).

Reactions having (*a*) Synthetical and (*b*) Analytical Interest.

(*a*) *Reactions having Synthetical Interest.*

Chloride of Antimony. Antimonious Chloride.

First Synthetical Reaction.—Boil half an ounce or less of sulphide of antimony with four or five times its weight of hydrochloric acid in a dish in a fume-chamber or the open air; sulphuretted hydrogen is evolved and solution of chloride of antimony, $SbCl_3$, obtained.

Sb_2S_3	+	$6HCl$	=	$2SbCl_3$	+	$3H_2S$
Sulphide of antimony.		Hydrochloric acid.		Chloride of antimony.		Sulphuretted hydrogen.

This solution, cleared by subsidence, is what is commonly known as *Butter of antimony* (*Liquor Antimonii Chloridi*, B. P.). If pure sulphide has been used in its preparation the liquid is nearly colorless; but much of that met with in veterinary pharmacy is simply a by-product in the generation of sulphuretted hydrogen from

native sulphide of antimony and hydrochloric acid, and is more or less brown from the presence of chloride of iron. It not unfrequently darkens in color on keeping; this is due to absorption of oxygen from the air and conversion of light-colored ferrous into dark-brown ferric chloride or oxychloride.

True butter of antimony ($SbCl_3$) is obtained on evaporating the above solution to a low bulk, and distilling the residue. The butter condenses (as a white crystalline semi-transparent mass in the neck of the retort; at the close of the operation it may be easily melted and run down in a bottle, which should be subsequently well stoppered.

Pentachloride of antimony ($SbCl_5$), or *antimonic chloride*, is a fuming liquid, obtained on passing chlorine over the lower chloride.

Oxychloride of Antimony. Antimonious Oxychloride.

Second Synthetical Reaction.—Pour the solution of chloride of antimony produced in the last reaction into several ounces of water; a white precipitate of oxychloride of antimony ($2SbCl_3, 5Sb_2O_3$) falls, some chloride of antimony remaining in the supernatant acid liquid.

This is the old *pulvis Algarothi*, *pulvis angelicus*, or *mercurius vitæ*. On standing under water it gradually becomes crystalline.

$12SbCl_3$	+	$15H_2O$	=	$2SbCl_3,5Sb_2O_3$	+	$30HCl$
Chloride of antimony.		Water.		Oxychloride of antimony.		Hydrochloric acid.

Oxide of Antimony. Antimonious Oxide.

Well wash the precipitate with water, by decantation (*vide* p. 93), and add solution of carbonate of sodium; the chloride remaining with the oxide is thus decomposed, and oxide of antimony (Sb_2O_3) alone remains. This is *Antimonii Oxidum*, B. P. and U. S. P. It is of a light buff or grayish-white color, or quite white if absolutely free from iron, insoluble in water, soluble in hydrochloric acid, fusible at a low red heat. The moist oxide of antimony may be well washed and employed for the next reaction, or dried over a water-bath. At temperatures above 212° oxygen is absorbed, and other oxides of antimony formed. The presence of the latter is detected on boiling the powder in solution of acid tartrate of potassium, in which oxide of antimony (Sb_2O_3) is soluble, but *antimonic anhydride* (Sb_2O_5) and the double oxide or so-called *antimonious anhydride* (Sb_4O_8) insoluble.

$2SbCl_3,5Sb_2O_3$	+	$3Na_2CO_3$	=	$6Sb_2O_3$	+	$6NaCl$	+	$3CO_2$
Oxychloride of antimony.		Carbonate of sodium.		Oxide of antimony.		Chloride of sodium.		Carbonic acid gas.

The higher oxide of antimony (Sb_2O_5), termed antimonic oxide or anhydride, corresponding with arsenic anhydride, is obtained on decomposing the pentachloride by water, or on boiling metallic antimony with nitric acid. The variety obtained from the chloride differs in saturating-power from that obtained from the metal, and is termed metantimonic acid (*μετὰ, meta,* beyond.)

Tartar Emetic.

Third Synthetical Reaction.—Mix the moist oxide of antimony obtained in the previous reaction with about an equal quantity of cream of tartar (6 of the latter to 5 of the dry oxide) and sufficient water to form a paste; set aside for a day to facilitate complete combination; boil the product with water, and filter; the resulting liquid contains the double tartrate of antimony and potassium ($KSbC_4H_4O_7$), potassio-tartrate of antimony, tartrated antimony, or tartar emetic (emetic, from ἐμέω, *emeō*, I vomit; tartar from Τάρταρος, *tartaros*, see Index).

$$\underset{\text{Acid tartrate of potassium.}}{2KHC_4H_4O_6} + \underset{\text{Oxide of antimony.}}{Sb_2O_3} = \underset{\text{Tartar emetic.}}{2KSbC_4H_4O_7} + \underset{\text{Water.}}{H_2O}$$

On evaporation the salt is obtained in colorless transparent triangular-faced crystals of the above composition, with a molecule of water of crystallization, forming the *Antimonium Tartaratum*, B. P. ($KSbC_4H_4O_7, H_2O$) the *Antimonii et Potassii Tartras*, U. S. P.

The formula for tartar emetic is apparently inconsistent with the general formula for tartrates ($R'R'C_4H_4O_6$); this will be subsequently fully explained in connection with Tartaric Acid. The salt appears to be an oxytartrate ($KSbC_4H_4O_6O$).

Tartar emetic is soluble in water, and slightly so in proof spirit. Dissolved in sherry wine it forms the official *Vinum Antimoniale*, B. P., and *Vinum Antimonii*, U. S. P. It may be externally applied as an ointment, *Unguentum Antimonii Tartarati*, B. P. (*Unguentum Antimonii*, U. S. P.).

Sulphurated Antimony. Oxysulphide of Antimony.

Fourth Synthetical Reaction.—Boil a few grains of sulphide of antimony with solution of soda (potash, U. S. P.) in a test-tube (or larger quantities in larger vessels, 10 ounces of sulphide to 4½ pints of the official solution of soda for 2 hours, frequently stirring, and occasionally replacing water lost by evaporation), and filter; into the

filtrate, before cool, stir diluted sulphuric acid until the liquid is slightly acid to test-paper; a brownish-red precipitate of oxysulphide of antimony, the *Antimonium Sulphuratum*, B. P. and U. S. P., falls; filter, wash, and dry over a water-bath. It is a mixture of sulphide of antimony (Sb_2S_3) with a small and variable amount of oxide (Sb_2O_3). The oxide results from the double decomposition of sulphide of antimony and soda.

Antimonii Oxysulphuretum.—The United States Pharmacopœia in another preparation orders carbonate of sodium instead of the caustic alkali, and directs that only that precipitate be retained which separates from the alkaline liquid on cooling.

If a small quantity of sulphur be boiled with the sulphide of antimony in solution of soda, the precipitate on the addition of sulphuric acid will be bright orange-red, on account of the presence of a higher sulphide having a yellow color (Sb_2S_5).

There are some of the many varieties of *mineral kermes*, so called from their similarity in color to the *insect kermes*. Kermes is the name, now obsolete, of the *Coccus Ilicis*, a sort of cochineal-insect, full of reddish juice, and used for dyeing from the earliest times.

Explanation of process.—The sulphides and oxides of antimony, like those of arsenicum, react with the sulphides and oxides of certain metals to form soluble salts (Na_3SbS_3 and Na_3SbO_3).

$$\underset{\text{Sulphide of antimony.}}{2Sb_2S_3} + \underset{\text{Soda.}}{6NaHO} = \underset{\text{Sulph-antimonite of sodium.}}{2Na_3SbS_3} + \underset{\text{Oxide of antimony.}}{Sb_2O_3} + \underset{\text{Water.}}{3H_2O}$$

$$\underset{\text{Oxide of antimony.}}{Sb_2O_3} + \underset{\text{Soda.}}{6NaHO} = \underset{\text{Antimonite of sodium.}}{2Na_3SbO_3} + \underset{\text{Water.}}{3H_2O}$$

In the hot solutions of these salts sulphide and oxide of antimony are soluble, and are reprecipitated in an indefinite state of combination, partially, on cooling, or wholly on the addition of acid. The acid also decomposes the oxysalt with precipitation of oxide, and the sulphur-salt with precipitation of orange sulphide of antimony. The acid is added to the liquid before much oxysulphide has deposited (that is, before the solution is cool), in order to insure uniformity of product.

$$\underset{\text{Sulph-antimonite of sodium.}}{2Na_3SbS_3} + \underset{\text{Sulphuric acid.}}{3H_2SO_4} = \underset{\text{Sulphate of sodium.}}{3Na_2SO_4} + \underset{\text{Sulphide of antimony.}}{Sb_2S_3} + \underset{\text{Sulphuretted hydrogen.}}{3H_2S}$$

$$\underset{\text{Antimonite of sodium.}}{2Na_3SbO_3} + \underset{\text{Sulphuric acid.}}{3H_2SO_4} = \underset{\text{Sulphate of sodium.}}{3Na_2SO_4} + \underset{\text{Oxide of antimony.}}{Sb_2O_3} + \underset{\text{Water.}}{3H_2O}$$

The oxide and sulphide mentioned in these equations, together with excess of sulphide of antimony originally dissolved by the alkaline

liquid, are all precipitated when the acid is added, and form the *Sulphurated Antimony* of the Pharmacopœia, "an orange-red powder, readily dissolved by caustic soda, also by hydrochloric acid with the evolution of sulphuretted hydrogen and the separation of a little sulphur." Its antimony is detected by dissolving the precipitate in hydrochloric acid, or in solution of acid tartrate of potassium, and passing sulphuretted hydrogen through the liquid, as described in the first analytical reaction.

These four synthetical reactions illustrate the official processes for the respective substances. The solution of chloride of antimony is only used in the preparation of oxide; the oxide, besides its use in the preparation of tartar emetic, is mixed with twice its weight of phosphate of calcium (purified bone-earth) to form *Pulvis Antimonialis*, B. P.

The *sulphides* and *hydride* of antimony are incidentally mentioned in the following analytical paragraphs.

(*b*) *Reactions having Analytical Interest* (*Tests*).

First Analytical Reaction.—Through an acidified antimonial solution pass sulphuretted hydrogen; an orange precipitate of amorphous sulphide of antimony falls. It has the same composition as the crystalline black sulphide (Sb_2S_3), into which, indeed, it is quickly converted by heat. Like sulphide of arsenicum, it is soluble in alkaline solutions. Collect a portion on a filter and, when well drained, add *strong* hydrochloric acid; it dissolves—unlike sulphide of arsenicum.

A higher sulphide of antimony (Sb_2S_5) corresponding to the higher sulphide of arsenicum, exists. It is formed on passing sulphuretted hydrogen through an acidified solution of the higher chloride ($SbCl_5$), or on boiling black sulphide of antimony and sulphur with an alkali, and decomposing the resulting filtered liquid by an acid.

Note.—The arsenious and antimonious compounds only are employed in medicine. The arseniates and antimoniates are sometimes useful in analysis, and the antimonic chloride in chemical research. The higher compounds of both elements are noticed here chiefly to draw attention to the close analogy existing between arsenicum and antimony, an analogy carried out in the numerous other compounds of these elements.

Second Analytical Reaction.—Dilute two or three drops of the solution of chloride of antimony with water; a precipitate of oxychloride occurs, the formation of which has

been explained under the similar synthetical reaction. The occurrence of this precipitate distinguishes antimony from arsenicum, but is a reaction that cannot be fully relied upon in analysis, because requiring the presence of too much material and the observance of too many conditions. Add a sufficient quantity of hydrochloric acid to dissolve the precipitate, and boil a piece of copper in the solution as directed in the corresponding test for arsenicum (*vide* page 148); antimony is deposited on the copper. Wash, dry, and heat the copper in a test-tube as before; the antimony, like the arsenicum, is volatilized off the copper and condenses on the side of the tube as white oxide, but the sublimate, from its low degree of volatility, condenses close to the copper, and, moreover, is destitute of crystalline character, is amorphous (α, *a*, without; μορφή, *morphē*, shape).

Shake out the copper and boil water in the tube for several minutes. Do the same with the arsenical sublimate similarly obtained. The deposit of arsenic slowly dissolves, and may be recognized in the solution by ammonio-nitrate of silver; the antimonial sublimate is insoluble.

Third Analytical Reaction.—Perform the experiments described under Marsh's test for arsenicum (pp. 149, 150), carefully observing all the details there mentioned, but using a few drops of solution of chloride of antimony or tartar emetic instead of the arsenical solution. Antimoniuretted hydrogen, or hydride of antimony (SbH_3), is formed and decomposed in the same way as arseniuretted hydrogen.

To one of the arsenicum spots on the porcelain lid (p. 149) add a drop of solution of "chloride of lime" (bleaching-powder); it quickly dissolves. Do the same with an antimony spot; it is unaffected.

Heat more quickly causes the volatilization of an arsenicum than an antimony spot; sulphydrate of ammonium more readily dissolves the antimony than the arsenicum.

Boil water for several minutes in the beaker or wide test-tube containing the arsenious sublimate (page 150); it slowly dissolves and may be recognized in the solution by the yellow precipitate given on the addition of solution of ammonio-nitrate of silver. The antimonial sublimate, similarly treated, gives no corresponding reaction.

Pass a slow current of sulphuretted hydrogen through the delivery-tube removed from the hydrogen-apparatus (page 150), and, when the air may be considered to have been expelled from the tube, gently heat that portion containing the deposit of arsenicum; the latter will be converted into a *yellow* sublimate of sulphide of arsenicum. Remove the tube from the sulphuretted-hydrogen apparatus, and repeat the experiment with a similar antimony deposit; it is converted into *orange* sulphide of antimony, which, moreover, owing to inferior volatility, condenses nearer to the flame than sulphide of arsenicum.

Pass dry hydrochloric acid gas through the two delivery-tubes. This is accomplished by adapting first one tube and then the other by a cork to the test-tube containing a few lumps of common salt, on which a little sulphuric acid is poured during the momentary removal of the cork. The sulphide of antimony dissolves and disappears; the sulphide of arsenicum is unaffected.

Thorough perception of the chemistry of arsenicum and antimony will be obtained on constructing equations or diagrams descriptive of each of the foregoing reactions.

Antidote.—The introduction of poisonous doses of antimonials into the stomach is fortunately quickly followed by vomiting. If vomiting has not occurred, or apparently to an insufficient extent, any form of tannic acid may be administered (infusion of tea, nutgalls, cinchona, oak-bark, or other astringent solutions or tinctures), an insoluble tannate of antimony being formed, and absorption of the poison consequently somewhat retarded. The stomach-pump must be as quickly as possible applied.

Recently precipitated moist ferric hydrate is also, according to T. and H. Smith, a perfect absorbent of antimony from its solutions, the chemical actions being probably, they say, similar to that which takes place between ferric hydrate and arsenious anhydride. It may be given in the form of a mixture of perchloride of iron with either carbonate of sodium or magnesia.

These statements may be verified by mixing together the various substances, filtering, and testing the filtrate for antimony in the usual manner.

DIRECTIONS FOR APPLYING THE FOREGOING REACTIONS TO THE ANALYSIS OF AN AQUEOUS SOLUTION OF SALTS OF ONE OF THE ELEMENTS ARSENICUM AND ANTIMONY.

Acidify the liquid with hydrochloric acid, and pass through it sulphuretted hydrogen:—

A *yellow* precipitate indicates arsenicum.

An *orange* precipitate indicates antimony.

The result may be confirmed by the application of other tests.

DIRECTIONS FOR APPLYING THE FOREGOING REACTIONS TO THE ANALYSIS OF AN AQUEOUS SOLUTION OF SALTS OF BOTH ARSENICUM AND ANTIMONY.

Acidify a small portion of the liquid with hydrochloric acid, and pass through it sulphuretted hydrogen.

Note I. If the precipitate by sulphuretted hydrogen is unmistakably orange, antimony may be put down as present, and arsenicum only further sought by the application of Fleitmann's test to the solution of the sulphides in aqua regia* freed from sulphur by boiling, or, better, to the original solution.

Note II. Sulphide of antimony is far less readily soluble than sulphide of arsenicum in solution of carbonate of ammonium. But this fact possesses limited analytical value; for the color of the sulphides is already sufficient to distinguish the one from the other when they are unmixed; and when mixed, much sulphide of antimony will prevent a little sulphide of arsenicum from being dissolved by the alkaline carbonate, while much sulphide of arsenicum will carry a little sulphide of antimony into the solution. When the proportions are, apparently, from the color of the precipitate, less wide, solution of carbonate of ammonium will be found useful in roughly separating the one sulphide from the other. On filtering and neutralizing the alkaline solution by an acid, the yellow sulphide of arsenicum is reprecipitated. The orange sulphide of antimony will remain on the filter.

Note III. Solution of bisulphite of potassium is said by Wöhler to be a good reagent for separating the sulphides of arsenicum and antimony, the former being soluble, the latter insoluble in the liquid.

Note IV. Another reagent for separating the sulphides of arsenicum and antimony is *strong* hydrochloric acid. As little water as possible must be present. On boiling, the sulphide of antimony dissolves, while the sulphide of arsenicum remains insoluble. The liquid

* *Aqua regia* is a mixture of two parts hydrochloric and one part nitric acid. It was so called, from its property of dissolving gold, the "king" of metals.

slightly diluted, filtered, more water added, and sulphuretted hydrogen again transmitted, gives orange sulphide of antimony. The process should previously be tried on the precipitated mixed sulphides. The presence of arsenicum may be confirmed by the application of Fleitmann's test to the original solution.

Note V. If the precipitate by sulphuretted hydrogen is unmistakably yellow, arsenicum may be put down as present, and any antimony detected by the previous or one of the following two processes. These two processes are rather long, and require much care in their performance, but are useful, because a small quantity of antimony in much arsenicum, or *vice versâ*, may be detected by their means.

First Process.—Generate hydrogen and pass it through a small wash-bottle containing solution of acetate of lead, to free the gas from any trace of sulphuretted hydrogen it may possess, and then through a dilute solution of nitrate of silver contained in a test-tube. When the apparatus is in good working order, pour into the generating-bottle the solution to be examined, adding it gradually to prevent violent action. After the gas has been passing for five or ten minutes, examine the contents of the nitrate-of-silver tube; arsenicum, if present, will be found in the solution in the state of arsenious acid,

$$AsH_3 + 3H_2O + 6AgNO_3 = H_3AsO_3 + 6HNO_3 + 3Ag_2;$$

while antimony, if present, will be found in the black precipitate that has fallen, according to the following equation:—

$$SbH_3 + 3AgNO_3 = SbAg_2 + 3HNO_3.$$

The arsenious radical may be detected in the clear, filtered, supernatant liquid, which still contains much nitrate of silver, by cautiously neutralizing with a very dilute solution of ammonia, or by adding a few drops of solution of ammonio-nitrate of silver, yellow arsenite of silver being produced. The antimony may be detected by washing the black precipitate, boiling it in an open dish with solution of tartaric acid, filtering, acidulating with hydrochloric acid, and passing sulphuretted hydrogen through the solution—the orange sulphide of antimony being precipitated (Hofmann).

Second process.—Obtain the metallic deposit in the middle of the delivery-tube as already described under Marsh's test. Act on the deposit by sulphuretted hydrogen gas, and then by hydrochloric acid gas as detailed in the third

analytical reaction of antimony (p. 160). If both arsenicum and antimony are present, the deposit, after the action of sulphuretted hydrogen, will be found to be of two colors, the yellow sulphide of arsenicum being usually further removed from the heated portion of the tube than the orange sulphide of antimony. Moreover, subsequent action of hydrochloric acid gas causes disappearance of the antimonial deposit, which is converted into chloride of antimony and carried off in the stream of gas.

The chief objection to this process is the liability of the operator mistaking sulphur, deposited from the sulphuretted hydrogen gas by heat, for sulphide of arsenicum. But the presence or absence of arsenicum is easily confirmed by applying Fleitmann's test to the original solution, while the process is most useful for the detection of a small quantity of salt of antimony when mixed with much arsenical compounds.

The laboratory student may now proceed to the analysis of aqueous solutions of salts of any of the metallic elements hitherto considered. The method followed may be that for the separation of the previous three groups, sulphuretted hydrogen being first passed through the solution to throw out arsenicum and antimony. The whole scheme of analysis is given on the next page. Three or four solutions should be examined before proceeding to the last group of metals.

Learners who have no opportunity of working at practical analysis will gain much knowledge by endeavoring not to remember, but to understand these methods of separating elements from each other in a solution containing several compounds.

TABLE OF SHORT DIRECTIONS FOR THE ANALYSIS OF AN AQUEOUS SOLUTION OF SALTS OF ANY OR ALL OF THE METALLIC ELEMENTS HITHERTO CONSIDERED.

Acidify with HCl, and pass H_2S through the solution; filter.

Precipitate	Filtrate
As Sb Wash, separate by carb. ammon.; or by strong HCl; or dissolve in a few drops HCl and HNO_3, and examine as described pages 162 and 163.	Fe Al Zn Ba Ca Mg K Na Am. Add AmHO;* AmHS; stir; filter.

Precipitate†	Filtrate
Fe Al Zn Wash, dissolve in HCl, boil with HNO_3 (p. 139), add KHO, stir, filter.	Ba Ca Mg K Na Am. Add Am_2CO_3, boil, filter.

Precipitate	Filtrate
Fe. Examine orig. solution for ferrous or ferric state.	Al Zn. Neut. by HCl, add AmHO, stir, filter.

Precipitate	Filtrate
Ba Ca. Dissolve in $HC_2H_3O_2$, add K_2CrO_4, filter.	Mg K Na Am. Add Am_2HPO_4, shake, filter.

Precipitate	Filtrate
Al	Zn
Ba	Ca
Mg	Am Na K (page 85).

* It is not usually necessary to add NH_4Cl, the HCl with some of the NH_4HO commonly giving sufficient NH_4Cl.

† Much time may sometimes be saved by carefully remembering the color of the various hydrates and sulphides precipitated. Thus, if the AmHS precipitate is white, iron cannot be present, and AmHO, for Al and Zn may be at once added to the hydrochloric solution of the precipitate. The group-tests in this table are H_2S, AmHS, and Am_2CO_2.

QUESTIONS AND EXERCISES.

269. What is the composition and source of the *Black Antimony* of pharmacy?

270. In what alloys is metallic antimony a characteristic ingredient?

271. What is the quantivalence of antimony as far as indicated by the formulæ of the official preparations?

272. By a diagram show how "Butter of Antimony" is prepared.

273. Write out equations or diagrams expressive of the reactions which occur in converting chloride of antimony into oxide.

274. What is the formula of Tartar Emetic?

275. Explain the official process for the preparation of Oxysulphide of Antimony (*Antimonium Sulphuratum*, B. P.) by aid of diagrams.

276. Give a comparative statement of the tests for arsenicum and antimony.

277. How is antimony detected in the presence of arsenicum?

278. How may arsenicum and iron be distinguished analytically?

279. Describe a method by which antimony, magnesium, and iron may be separated from each other.

280. Draw out an analytical chart for the examination of an aqueous liquid containing salts of arsenicum, zinc, calcium, and ammonium.

COPPER, MERCURY, LEAD, SILVER.

These metals, like arsenicum and antimony, are precipitated from acidified solutions by sulphuretted hydrogen, in the form of sulphides; but the sulphides, unlike those of arsenicum and antimony, are insoluble in alkalies. The atom of copper is usually bivalent, Cu″; mercury bivalent in the mercuric salts, Hg″, and univalent in the mercurous salts, Hg′; lead sometimes quadrivalent, Pb‴′, but generally exerting only bivalent activity, Pb″; and silver univalent, Ag′.

COPPER.

Symbol Cu. Atomic weight 63.5.

Source.—The commonest ore of this metal is *copper pyrites*, a double sulphide of copper and iron, raised in Cornwall; Australia and Russia supply *malachite*, a mixed carbonate and hydrate; much ore is also imported from South America. It is smelted in enormous quantities at Swansea, South Wales, a locality peculiarly fitted for the operation on account of its proximity to the coal-fields, and its position as a sea-coast town—these advantages at all times insuring cheap fuel and freightage to the different metallurgical establishments.

Alchemy.—The alchemists termed this metal *Venus*, perhaps on account of the beauty of its lustre, and gave it her symbol ♀, a compound hieroglyphic also indicating a mixture of gold ☉ and a certain hypothetical substance called acrimony ✠, the corrosive nature of which was symbolized by the points of a Maltese cross. To this day the blue show-bottle in the shop-window of the pharmacist is occasionally ornamented by such a symbol, indicative, possibly, of the fact that the blue liquid in the vessel is a preparation of copper.

Coinage.—The material of British copper coinage is now a bronze mixture composed in 100 parts by weight of 95 copper, 4 tin, and 1 zinc, the same as in the copper coinage of France. The penny is coined at the rate of 48 pence in one pound avoirdupois, of 7000 grains, or 453.6 grammes; the halfpenny at 80 in the pound avoirdupois, and the farthing at 160. British bronze coins are a legal tender in payments to the amount of 1*s.*

Metallic Copper (*Cuprum*, B. P. and U. S. P.) in the form of fine wire, about No. 25, is used in preparing *Spiritus Ætheris Nitrosi*, B. P. and U. S. P. *Copper Foil*, B. P., is "pure metallic copper, thin and bright."

Quantivalence.—Copper forms two classes of salts; in one the atom is bivalent (Cu''), in the other exerts univalent activity (Cu_2''). The former are of primary importance, the latter being for the most part unstable and wanting in technical interest. Their compounds are distinguished as cupric and cuprous; but those of the higher class only have general interest, and will be almost exclusively alluded to in the following paragraphs. Cuprous iodide (Cu_2I_2) will subsequently be referred to as a convenient form in which to remove iodine from solution, and the formation of cuprous oxide (Cu_2O), under given circumstances, as an indicator of the presence of sugar in a liquid.

Reactions having (*a*) Synthetical and (*b*) Analytical Interest.

(*a*) *Synthetical Reactions.*

The processes for the following salts include the only synthetical copper-reactions having any medical or pharmaceutical interest: 1, cupric oxide, the black oxide of copper, by heating a piece of copper to low redness on a piece of earthenware in an open fire; 2, cupric sulphate, the common sulphate of copper, by boiling black oxide of copper and about an equal weight of sulphuric acid in water, filtering, and setting aside the solution so that crystals may form on cooling; and, 3, the preparation of solution of ammonio-sulphate of copper (see p. 153; also p. 168).

$$\underset{\text{Copper.}}{Cu_2} + \underset{\text{Oxygen.}}{O_2} = \underset{\text{Cupric oxide.}}{2CuO}$$

$$\underset{\text{Cupric oxide.}}{CuO} + \underset{\text{Sulphuric acid.}}{H_2SO_4} = \underset{\text{Cupric sulphate.}}{CuSO_4} + \underset{\text{Water.}}{H_2O}$$

Sulphate of Copper (*Cupri Sulphas*, B. P. and U. S. P.) ($CuSO_4$, $5H_2O$), *blue vitriol*, *bluestone*, or *cupric sulphate*, is the only copper salt of much importance in Pharmacy. It is a by-product in silver-refining ($2Ag_2SO_4 + Cu_2 = 2CuSO_4 + 2Ag_2$). It is also formed by roasting copper pyrites. In the latter operation the sulphide of iron and sulphide of copper are oxidized to sulphates; but the low red heat employed decomposes the sulphate of iron, while the sulphate of copper is unaffected; it is purified by crystallization from a hot aqueous solution, though frequently much sulphate of iron remains in the crystals. Sulphate of copper results on dissolving in diluted sulphuric acid the black oxide (CuO) obtained in annealing copper plates; it may also be prepared by boiling copper with three times its weight of sulphuric acid ($2H_2SO_4 + Cu = CuSO_4 + SO_2 + 2H_2O$), diluting, filtering, evaporating, and crystallizing.

Anhydrous Sulphate of Copper ($CuSO_4$), is a yellowish-white powder prepared by depriving the ordinary blue crystals of sulphate of copper of their water of crystallization by exposing to a temperature of about 400° F. It is used in testing alcohol and similar liquids for water, becoming blue if the latter be present.

Verdigris (from *verde-gris*, Sp. green-gray) is a Subacetate (*Cupri Subacetas*, U. S. P.) or Oxyacetate of Copper (B. P.) ($Cu_2O2C_2H_3O_2$), obtained by exposing alternate layers of copper and fermenting refuse grape-husks to the action of air. Digested with twice its weight of acetic acid and a little water, the mixture being evaporated to dryness and the residue dissolved in water, it forms the official Solution of Acetate of Copper ($Cu2C_2H_3O_2$).

The modes of forming *cupric sulphide*, *hydrate*, *oxide*, *ferrocyanide*, and *arsenite*, as well as the precipitation of *metallic copper*, are incidentally alluded to in the following analytical paragraphs.

(*b*) *Reactions having Analytical Interest* (*Tests.*)

First Analytical Reaction.—Pass sulphuretted hydrogen through an acidified solution of a copper salt (sulphate, for example); black cupric sulphide (CuS) falls.

Second Analytical Reaction.—Add sulphydrate of ammonium to an aqueous copper solution; cupric sulphide is again precipitated, insoluble in excess.

Note.—Cupric sulphide is not altogether insoluble in sulphydrate of ammonium if free ammonia or much ammoniated salt be present; it is quite insoluble in the fixed alkaline sulphides.

Third Analytical Reaction.—Immerse a piece of iron or steel, such as the point of a penknife or a piece of wire, in

a few drops of a copper solution; the copper is deposited, of characteristic color, an equivalent quantity of iron passing into solution.

By this reaction copper may be recovered on the larger scale from waste solutions, old hoop or other scrap iron being thrown into the liquors.

Fourth Analytical Reaction.—Add ammonia to a cupric solution; cupric hydrate (Cu2HO) of a light-blue color is precipitated. Add excess of ammonia; the precipitate is redissolved, forming a blue solution of ammonio-salt of copper, so deep in color as to render ammonia an exceedingly delicate test for this metal.

An ammonio-sulphate of copper may be obtained in large crystals by adding strongest solution of ammonia to powdered sulphate of copper until the salt is dissolved, placing the liquid in a test-glass or cylinder, cautiously pouring in twice its volume of strong alcohol or methylated spirit, taking care that the liquids do not become mixed, tying over the vessel with bladder, and setting aside for some weeks in a cool place. (Wittstein.) The constitution of ammonio-sulphate and other ammonio-salts of copper and coresponding salts of silver will be alluded to in connection with "white precipitate," the official "ammoniated mercury."

Cuprum Ammoniatum, U. S. P., is an ammonia-sulphate of copper prepared by rubbing together sulphate of copper and carbonate of ammonium until effervescence ceases, and drying the product.

Fifth Analytical Reaction.—Add solution of potash or soda to a cupric solution; cupric hydrate (Cu2HO) is precipitated, insoluble in excess. Boil the mixture in the test-tube; the hydrate is decomposed, losing the elements of water, and becoming the black anhydrous oxide (CuO).

Sixth Analytical Reaction.—Add solution of ferrocyanide of potassium (K_4Fcy) to an aqueous cupric solution; a reddish-brown precipitate of cupric ferrocyanide (Cu_2Fcy) falls. This also is a delicate test for copper.

Seventh Analytical Reaction.—To a cupric solution add solution of arsenic, and cautiously neutralize with alkali; green cupric arsenite ($CuHAsO_3$) falls.

Note.—This precipitate has been already mentioned under arsenicum. An arsenicum salt is thus a test for copper, as a copper salt is for arsenicum—a remark that may obviously be extended to most analytical reactions; for the *body acted upon characteristically by a reagent is as good a test for the reagent as the reagent is for it;* indeed it becomes a reagent when the other body is the object of search.

Antidotes.—In cases of poisoning by compounds of copper, iron filings should be administered, the action of which has just been explained (see third analytical reaction). Ferrocyanide of potassium may also be given (see sixth analytical reaction). Albumen forms, with copper, a compound insoluble in water; hence raw eggs should be swallowed, vomiting being induced or the stomach-pump applied as speedily as possible.

QUESTIONS AND EXERCISES.

281. What are the relations of copper, mercury, lead, and silver to each other and to arsenicum and antimony?
282. Name the sources of copper.
283. What proportion of copper is contained in English and French "copper" coins?
284. Give diagrams showing how Sulphate of Copper is prepared on the small and large scales.
285. Work out a sum showing how much Crystallized Sulphate of Copper may be obtained from 100 parts of sulphide?—*Ans.* 261¼.
286. How may Oxide of Copper be prepared?
287. Mention the formula of Verdigris.
288. Name a good clinical test for copper.
289. What is the analytical position of copper?
290. Mention the chief tests for copper.
291. How may copper be separated from arsenicum?
292. Why is finely divided iron an effective antidote in cases of poisoning by copper?

MERCURY.

Symbol Hg. Atomic weight 200.

Molecular weight 200 (*not* double the atomic weight).

Source.—Mercury occurs in nature as sulphide (HgS), forming the ore *cinnabar* (an Indian name expressive of something red), and is obtained from Spain, California, Eastern Hungary, China, Japan, and Peru.

Preparation.—The metal is separated by roasting off the sulphur and then distilling, or distilling with lime, which combines with and retains the sulphur.

Properties.—Mercury (*Hydrargyrum*, B. P. and U. S. P.) is a silver-white lustrous metal, liquid at common temperature. It boils at 662° F., and at —40° F. solidifies to a malleable mass of octahedral crystals. When quite free from other metals it does not tarnish, and

its globules roll freely over a sheet of white paper without leaving any streak or losing their spherical form.

Formula.—The formula of the mercury molecule is Hg and not Hg_2, because at all ordinary temperatures two volumes, which if hydrogen would weigh two parts (H_2) or oxygen thirty-two parts (O_2), in the case of mercury vapor weigh only two hundred parts (Hg); that is, only once the atomic weight, not twice. That 200, and not 100, is the atomic weight of mercury is shown by the fact that 200 is the minimum proportion relative to 1 of hydrogen in which mercury combines, and by its relations to heat. Still it is difficult to imagine an atom existing in the free state in nature; and the suggestion has been made that (as is proved to be the case with sulphur) mercury, as we know it, is in abnormal condition, and that if the weight of its vapor could be taken at a low temperature or under some other condition, its molecular weight might be found to be 400. Similar remarks may be made respecting zinc, the molecular weight of which, so far as we know, is identical with its atomic weight.

Medicinal Compounds.—The compounds of mercury used in medicine are all obtained from the metal. The metal itself, rubbed with chalk or with confection of roses and powdered liquorice-root, or with lard and suet, until globules are not visible *to the unaided eye*, is often used in medicine. The preparations are: the *Hydrargyrum cum Creta*, B. P. and U. S. P., or "Gray Powder;" *Pilula Hydrargyri*, B. P. and U. S. P., or "Blue Pill;" and *Unguentum Hydrargyri*, B. P. and U. S. P., or "Blue Ointment." There are also a Compound Ointment, a Plaster of Mercury, a Plaster of Ammoniacum and Mercury, a Liniment, and a Suppository. Their therapeutic effects are probably due to the black and red oxide which occur in them through the action of the oxygen of the air on the finely-divided metal. The proportion of oxide or oxides varies according to the age of the specimen.

Mercurous and Mercuric Compounds.—Mercury combines with other elements and radicals in two proportions: those compounds in which the other, acidulous, radicals are in the lesser amount are termed *mercurous*, the higher being *mercuric*. Thus, calomel (HgCl)* is mercurous chloride, while corrosive sublimate ($HgCl_2$) is mercuric chloride. In every pair of mercury compounds the mercuric contains *twice* as much complementary radical, in proportion to the mercury, as the mercurous.

Note on Nomenclature.—The remarks made concerning the two classes of iron salts, ferrous and ferric (p. 120), apply in the main to the two series of mercury salts. The latter are systematically distinguished in most modern works by the terms *mercurous* and *mercuric*. In the British and United States Pharmacopœias, however, which include only a few in comparison with the whole number of mercury salts, older and more strongly contrasted names are employed, thus:—

* The specific gravity of the vapor of calomel, and the fact that the salt is *not* decomposed at the temperature at which its specific gravity is taken, show that the formula of calomel is HgCl, and not Hg_2Cl_2.

Systematic names.	Official names.
Mercurous iodide	Green iodide of mercury.
Mercuric iodide	Red iodide of mercury.
Mercurous nitrate	Not mentioned in B. P.
Mercuric nitrate	Nitrate of mercury.
Mercurous sulphate . . .	Not mentioned in B. P.
Mercuric sulphate	Sulphate of mercury.
Mercurous chloride	Subchloride of mercury.
Mercuric chloride	Perchloride of mercury.
Mercurous oxide	Black oxide of mercury.
Mercuric oxide	Red oxide of mercury.

Specific Gravity.—Mercury is 13.6 times as heavy as water.

Amalgams.—The compound formed in fusing metals together is usually termed an *alloy* (*ad* and *ligo*, to bind); but if mercury is a constituent, an *amalgam* (μάλαγμα *malagma*, from μαλάσσω, *malassō*, to soften, the presence of mercury lowering the melting point of such a mixture). Most metals, even hydrogen, according to Leow, form amalgams.

Reaction having (*a*) Synthetical and (*b*) Analytical Interest.

(*a*) *Synthetical Reactions.*

The Two Iodides.

First Synthetical Reaction.—Rub together a small quantity of mercury and iodine, controlling the rapidity of combination by adding a few drops of spirit of wine, which, by evaporation, carries off heat, and thus keeps down temperature. The product is either mercuric iodide, mercurous iodide, or a mixture of the two, as well as mercury or iodine if excess of either has been employed. If the two elements have been previously weighed in single atomic proportions, 200 of mercury to 127 of iodine (about 8 to 5, or 1 ounce of mercury to 278 grains of iodine), the mercurous or green (grayish-green) iodide results (HgI (*Hydrargyri Iodidum Viride*, B. P. and U. S. P.); if in the proportion of one atom of mercury to two atoms of iodine (200 to twice 127, or about 4 to 5), the mercuric or red iodide, HgI_2, results, an iodide that is also official, but made in another way. (See page 174.) The green iodide should be made and dried (without heat) with as little exposure to light as possible.

Mercurous iodide is decomposed slowly by light, and quickly by heat, into mercuric iodide and mercury. Mercuric iodide occurring as an impurity in mercurous iodide may be detected by digesting in

ether (in which mercurous iodide is insoluble), filtering and evaporating to dryness; mercuric iodide remains. Mercuric iodide is stable, and may be sublimed in scarlet crystals without decomposition. (For details of the method by which a specimen of the crystals may be obtained, and the precautions to be observed, *vide* "corrosive sublimate," p. 176.)

Relation of Mercuric Iodide to Light.—In condensing, mercuric iodide is at first yellow, afterwards acquiring its characteristic scarlet color. This may be shown by smearing or rubbing a sheet of white paper with the red iodide, and then holding the sheet before a fire or over a flame for a few seconds. As soon as the paper becomes hot the red instantly changes to yellow, and the salt does not quickly regain its red color, even when cold, if the paper is carefully handled. But if a mark be made across the sheet by anything at hand, or the salt be pressed or rubbed in any way, the portions touched immediately return to the scarlet condition. According to Warington, this change is consequent upon rhomboidal crystals being converted into octahedra with a square base, and will serve as an excellent illustration of the influence of physical structure in causing color. The yellow modification so acts on the rays of white light shining on its particles as to absorb the violet and reflect the complementary hue, the yellow, which, entering the eye of the observer, strikes his retina, and thus conveys to the brain the impression of yellowness; and the red modification, though actually the same chemical substance, is sufficiently different in the structure of its particles to absorb the green constituent of white light and reflect the complementary ray, the red.

Illustration of the Chemical law of Multiple Proportions (p. 42). —Applying the atomic theory to the above iodides, it will at once be apparent why mercury and iodine should combine in the proportion of 200 of mercury with either 127 or 254 of iodine, and not with any intermediate quantity. For it is part of that theory that masses are composed of atoms, and that atoms are indivisible; and that the weight of the atom of mercury is to that of iodine as 200 is to 127. Mercury and iodine can only combine, therefore, in atomic proportions, atom to atom (which is the same as 200 to 127), or one atom to two atoms (which is the same as 200 to 254). To attempt to combine them in any intermediate proportion would be useless, a mere mixture of the two iodides would result. A higher proportion of mercury than 200 to 127 of iodine gives but a mixture of mercurous iodide and mercury; a higher proportion of iodine than 254 to 200 of mercury gives but a mixture of mercuric iodide and iodine. Or, for example, 200 grains of mercury, mixed with, say, 200 of iodine, would yield 139 grains of mercurous iodide, and 261 grains of mercuric iodide; for the 200 grains of mercury uniting with 127 grains of the iodine gives, for the moment, 327 grains of mercurous iodide and 73 grains of iodine still free. The 73 grains of iodine will immediately unite with 188 grains of the mercurous iodide (for if 127 of I require 327 of HgI to form HgI_2, 73 will require 188), and form 261 grains of mercuric iodide, diminishing the 327 grains of mercurous iodide to 139 grains.

Preparation of Red Iodide of Mercury by precipitation.—To a few drops of a solution of a mercuric salt (corrosive sublimate, for example), add solution of iodide of potassium, drop by drop; a precipitate of mercuric iodide, HgI_2, forms, and at first quickly redissolves, but is permanent when sufficient iodide of potassium has been added. Continue the addition of iodide of potassium; the precipitate is once more redissolved.

Note.—When first precipitated, mercuric iodide is yellowish-red, but soon changes to a beautiful scarlet. Its solubility either in solution of the mercuric salt or in solution of iodide of potassium renders the detection of a small quantity of a mercuric salt by iodide of potassium, or a small quantity of an iodide by a mercuric solution, difficult, and hence lessens the value of the reaction as a test. But the reaction has synthetical interest, the method by precipitation being that adopted in the British and United States Pharmacopœias (*Hydrargyri Iodidum Rubrum*, B. P. and U. S. P.). Mercuric iodide thus made has the same composition as that prepared by direct combination of its elements. Equivalent proportions of the two salts must be used in making the preparation ($HgCl_2 = 271$; $2KI = 332$). About 4 parts of corrosive sublimate are dissolved in 50 or 60 of water (warmth quickens solution) and 5 of iodide of potassium in 15 or 20 of water, the solutions mixed and the precipitate collected on a filter, drained, washed twice with distilled water, and dried on a plate over a water-bath. The mercury in mercuric or mercurous iodide is set free and sublimes in globules on heating either powder with dried carbonate of sodium in a test-tube; the iodine may be detected by digesting with solution of soda, filtering, and to the solution of iodide of sodium thus formed adding starch paste and acidulating with nitric acid, when blue iodide of starch results.

$HgCl_2$	+	$2KI$	=	HgI_2	+	$2KCl$
Mercuric chloride.		Iodide of potassium.		Mercuric iodide.		Chloride of potassium.

Mercuric iodide is insoluble in water, slightly soluble in alcohol, tolerably soluble in ether. Precipitated red iodide of mercury mixed with white wax, lard, and oil, forms the *Unguentum Hydrargyri Iodidi Rubri*, B. P. and U. S. P. *Donovan's Solution* contained mercuric and arsenious iodides.

The Two Nitrates.

Second Synthetical Reaction.—Mix a little nitric acid in a test-tube with four or five times its bulk of water, add a small globule of mercury, and set the tube aside for a few hours, in a cool place; solution of mercurous nitrate ($HgNO_3$) will be formed, and nitric oxide (NO) evolved. The solution may be retained for subsequent analytical operations.

$$Hg_3 + 4HNO_3 = 3HgNO_3 + 2H_2O + NO.$$

Third Synthetical Reaction.—Place mercury in strong nitric acid, and warm the mixture; mercuric nitrate is formed, and will be deposited in crystals as the solution cools. Retain the product for a subsequent experiment.

The mercuric nitrates vary somewhat in composition, according to the proportion, strength, and temperature of the acid used in their formation. A mercuric nitrate may be obtained having the formula $Hg2NO_3$.

Hg_3	+	$8HNO_3$	=	$3(Hg2NO_3)$	+	$2NO$	+	$4H_2O$
Mercury.		Nitric acid.		Mercuric nitrate.		Nitric oxide.		Water.

Mercuric Oxynitrates.—From the normal mercuric nitrate several oxynitrates may be obtained. Thus on merely evaporating a solution of mercuric nitrate, and cooling, crystals having the formula $Hg_6O_36NO_3$ are deposited. The latter, by washing with cold water, yield a *yellow* pulverulent oxynitrate, $Hg_6O_4NO_3$: mixed with lard, this has sometimes been used as an ointment. Boiled in water, the yellow gives a *brick-red* oxynitrate, $Hg_6O_52NO_3$.

The Pharmacopœial preparations of mercuric nitrate are *Liquor Hydrargyri Nitratis Acidus*, B. P. (sp. gr. 2.246; U. S. P., sp. gr. 2.165), and *Unquentum Hydrargyri Nitratis*, B. P. and U. S. P. The former (B. P.) is made by placing four ounces of mercury in five fluidounces of nitric acid diluted with an ounce and a half of water, and, when the metal is dissolved, boiling gently for fifteen minutes.

The Two Sulphates.

Fourth Synthetical Reaction.—Boil two or three grains of mercury with a few drops of strong sulphuric acid in a test-tube; sulphurous acid gas (SO_2) is evolved, and mercuric sulphate (*Hydrargyri Sulphas*, B. P.) ($HgSO_4$) results—a white heavy crystalline powder.

Hg	+	$2H_2SO_4$	=	$HgSO_4$	+	SO_2	+	$2H_2O$
Mercury.		Sulphuric acid.		Mercuric sulphate.		Sulphurous acid gas.		Water.

Between two and three ounces of mercuric sulphate may be prepared from a fluidrachm of mercury and a fluidounce of sulphuric acid boiled together in a small dish. These are the official proportions. The operation is completed and any excess of acid removed by evaporating the mixture of metal and liquid to dryness, either in the open air or in a fume-chamber, sulphuric acid vapors being excessively irritating to the mucous membrane of the nose and throat; dry crystalline mercuric sulphate remains. If residual particles of mercury are observed, the mass should be damped with sulphuric acid and again heated.

By-products.— In chemical manufactories, secondary products, such as the sulphurous gas of the above reaction, are termed *by-products*, and, if of value, are utilized. In the present case the gas has no immediate interest, and is therefore allowed to escape. When very pure sulphurous acid gas is required for experiments on the small scale, this would be the best method of making it, a delivery-tube being adapted by a cork to the mouth of a flask containing the acid and metal. The sulphate of mercury would then become the by-product.

Mercuric Oxysulphate.—Water decomposes mercuric sulphate into a soluble acid salt and an insoluble yellow oxysulphate ($Hg_3O_2SO_4$). The latter is called *Turpeth mineral*, from its resemblance in color to the powdered root of *Ipomœa turpethum*, an Indian substitute for jalap. The yellow sulphate of mercury (*Hydrargyri Sulphas Flava*, U. S. P.) was formerly official in the pharmacopœia of Great Britain, but is now seldom used.

Fifth Synthetical Reaction.—Rub a portion of the dry mercuric sulphate of the previous reaction with as much mercury as it already contains; the product, when the two have thoroughly blended, is mercurous sulphate (Hg_2SO_4): it may be retained for a subsequent experiment.

Molecular Weight.—The exact proportion of mercury to sulphate is merely a matter of calculation; for the combining proportion of a compound (if it possess any combining-power) is the sum of the combining proportions of its constituents. *In other words, the combining weight of a molecule is simply the sum of the weights of its constituent atoms*, or, more generally, *the molecular weight of a compound is the sum of the atomic weights of its elements.* In accordance with this rule (sometimes called the fourth law of chemical combination, though only a deduction from the first—p. 41), 296 of mercuric sulphate and 200 of mercury (about 3 to 2) are the exact proportions necessary to the formation of mercurous sulphate.

The Two Chlorides.

Sixth Synthetical Reaction. — Mix thoroughly a few grains of dry mercuric sulphate with about four-fifths its weight of chloride of sodium, and heat the mixture slowly in a test-tube in a fume-chamber or in the open air to leeward of the operator; mercuric chloride ($HgCl_2$), or *corrosive sublimate* (*Hydrargyri Perchloridum*, B. P., *Hydrargyri Chloridum Corrosivum*, U. S. P.), sublimes and condenses in the upper part of the tube in heavy colorless crystals or a crystalline mass. Somewhat larger quantities (in the proportion of 20 of sulphate to 16 of salt, and, *vide infra*, 1 of black oxide of manganese) may be sublimed in a pair of two-ounce or three-ounce round-bottomed galli-

pots, the one inverted over the other, and the joint luted by moist fireclay (the powdered clay kneaded with water to the consistence of dough). The luting having been allowed to dry (somewhat slowly, to avoid cracks), the pots are placed upright on a sand-tray (plate-shape answers very well), sand piled round the lower and a portion of the upper pot, and the whole heated over a good-sized gas flame for an hour or more. Red Iodide of Mercury and Calomel may be sublimed in the same way. The former requires less, the latter more, heat than corrosive sublimate.

$$\underset{\text{Mercuric sulphate.}}{HgSO_4} + \underset{\text{Chloride of sodium.}}{2NaCl} = \underset{\text{Mercuric chloride.}}{HgCl_2} + \underset{\text{Sulphate of sodium.}}{Na_2SO_4}$$

Note.—If the mercuric sulphate contain any mercurous sulphate, some calomel may be formed. This result will be avoided if 2 or 3 per cent. of black oxide of manganese be previously mixed with the ingredients, the action of which is to eliminate chlorine from the excess of chloride of sodium used in the process, the chlorine converting any calomel into corrosive sublimate. Manganate of sodium and a lower oxide of manganese are simultaneously produced.

Precaution.—The operation is directed to be conducted with care in a fume-chamber or in the open air, because the vapor of corrosive sublimate, which might possibly escape, is very acrid and highly poisonous. Its vulgar name is indicative of its properties.

Ten grains of perchloride of mercury and the same quantity of chloride of ammonium in one pint of water, form the *Liquor Hydrargyri Perchloridi*, B. P. A dilute aqueous solution of perchloride of mercury is liable to decomposition, calomel being precipitated, water formed, and oxygen gas evolved. The presence of excess of chloride of ammonium, with a portion of which the mercuric chloride forms a stable double salt, prevents the decomposition.

Seventh Synthetical Reaction.—Mix a few grains of the mercurous sulphate of the fifth reaction with about a third of its weight of chloride of sodium, and sublime in a test-tube; crystalline mercurous chloride (HgCl) or calomel (*Hydrargyri Subchloridum*, B. P., *Hydrargyri Chloridum Mite*, U. S. P.) results. Larger quantities may be prepared in the manner directed for corrosive sublimate, a somewhat higher temperature being employed; similar precautions must also be observed. The proportions are 10 of mercuric sulphate to 7 of mercury and 5 of dry chloride of sodium. "Moisten the sulphate of mercury with some of the water, and rub it and the mercury together until globules are no longer visible; add the chloride of sodium, and thoroughly mix the whole by continued tritu-

ration. When dry sublime by a suitable apparatus into a chamber of such a size that the calomel, instead of adhering to its sides as a crystalline crust, shall fall as a fine (dull-white) powder on its floor. Wash this powder with boiling distilled water until the washings cease to be darkened by a drop of sulphydrate of ammonium. Finally, dry at a heat not exceeding 212°, and preserve in a jar or bottle impervious to light."

Hg_2SO_4	+	$2NaCl$	=	$2HgCl$	+	Na_2SO_4
Mercurous sulphate.		Chloride of sodium.		Mercurous chloride.		Sulphate of sodium

The term calomel (καλὸς, *kalos*, good, and μέλας, *melas*, black) is said to relate to the use of the salt as a *good* remedy for *black* bile, but probably was simply indicative of the esteem in which black sulphide of mercury was held, the compound to which the name calomel was first applied.

Test for corrosive sublimate in calomel.—If the mercurous sulphate contains mercuric sulphate, some mercuric chloride will also be formed. Corrosive sublimate is soluble in water, calomel insoluble; the presence of the former may therefore be proved by boiling a few grains of the calomel in distilled water, filtering and testing by sulphuretted hydrogen or sulphydrate of ammonium as described hereafter. If corrosive sublimate is present, the whole bulk of the colomel must be washed with hot distilled water till the filtrate ceases to give any indications of mercury. Corrosive sublimate is more soluble in alcohol, and still more in ether, calomel insoluble. Ether in which calomel has been digested should, therefore, after filtration, yield no residue on evaporation. Calomel is converted by hydrocyanic acid into mercuric salt, with separation of metallic mercury.

Note.—The above process is that of the Pharmacopœias; but calomel may also be made by other methods. Calomel mixed with lard forms the *Unguentum Hydrargyri Subchloridi*, B. P., and with sulphurated antimony, guaiacum resin, and castor oil, the *Pilula Hydrargyri Subchloridi Composita*, B. P., *Pilula Antimonii Composita*, U. S. P., or "Plummer's Pills."

The two Oxides.

Eighth Synthetical Reaction.—Evaporate the mercuric nitrate of the third reaction to dryness in a small dish, in a fume-chamber, or in the open air if more than a few grains have been prepared, and heat the residue till no more fumes are evolved; mercuric oxide (HgO), "Red Precipitate," the Red Oxide of Mercury (*Hydrargyri Oxidum Rubrum*, B. P. and U. S. P.), remains.

$2(Hg2NO_3)$	=	$2HgO$	+	$4NO_2$	+	O_2
Mercuric nitrate.		Mercuric oxide.		Nitric peroxide.		Oxygen.

The nitric constituents of the salt may be partially economized by previously thoroughly mixing with the dry mercuric nitrate as much mercury as is used in its preparation, or as much as it already contains (ascertained by calculation from the atomic weights and the weight of nitrate under operation, as in making mercurous sulphate p. 176), and well heating the mixture. In this case the free mercury is also converted into mercuric oxide. This is the official process, the Pharmacopœial quantities being four ounces of mercury dissolved in four and a half fluidounces of nitric acid diluted with two ounces of water, the solution evaporated to dryness, the residue thoroughly mixed with four ounces of mercury, and the whole heated until acid vapors cease to be evolved. (Mercuric oxide is tested for nitrate by heating a little of the sample in a test-tube, when orange nitrous vapors are produced and are visible in the upper part of the tube, if nitrate is present).

$$\underset{\text{Mercuric nitrate.}}{Hg2NO_3} + \underset{\text{Mercury.}}{Hg} = \underset{\text{Murcuric oxide.}}{2HgO} + \underset{\text{Nitric peroxide.}}{2NO_2}$$

Mercuric oxide is an orange-red powder, more or less crystalline according to the extent to which it may have been stirred during preparation from the nitrate, much rubbing giving the crystals a pulverulent character. Mixed with yellow wax and oil of almonds it yields the *Unguentum Hydrargyri Oxidi Rubri*, B. P. (1 part in 8). A similar ointment is official in U. S. P. Mercuric oxide, in contact with oxidizable organic matter, is liable to reduction to black or mercurous oxide.

Ninth Synthetical Reaction.—To solution of corrosive sublimate in a test-tube or larger vessel add solution of potash or soda, or lime-water; yellow oxide of mercury, *Hydrargyri Oxidum Flavum*, U. S. P., or mercuric oxide (HgO), is precipitated.

$$\underset{\text{Mercuric chloride.}}{HgCl_2} + \underset{\text{Hydrate of calcium.}}{Ca2HO} = \underset{\text{Mercuric oxide.}}{HgO} + \underset{\text{Chloride of calcium.}}{CaCl_2} + \underset{\text{Water.}}{H_2O}$$

Eighteen grains of corrosive sublimate to ten ounces of lime-water form the *Lotio Hydrargyri Flava*, B. P. The precipitate only differs physically from the red mercuric oxide; the yellow is in a more minute state of division than the red. Mercuric oxide is very slightly soluble in water, but sufficiently so to communicate a decidedly metallic taste.

Tenth Synthetical Reaction.—To calomel add solution of potash or soda, or lime-water; black oxide of mercury, or mercurous oxide (Hg_2O), is produced, and may be filtered off, washed, and dried. (This reaction and the formation of a white curdy precipitate, on the addition of solution of nitrate of silver to the filtrate from the mercurous oxide, acidified by nitric acid, form sufficient evidence of

a powder being or containing calomel. The curdy precipitate is chloride of silver.)

Thirty grains of calomel to ten ounces of lime-water form the *Lotio Hydrargyri Nigra*, B. P.

$$\underset{\text{Mercurous chloride.}}{2HgCl} + \underset{\text{Hydrate of calcium.}}{Ca2HO} = \underset{\text{Mercurous oxide.}}{Hg_2O} + \underset{\text{Chloride of calcium.}}{CaCl_2} + \underset{\text{Water.}}{H_2O}$$

(*b*) *Analytical Reactions* (*Tests*).

(The mercury occurring as mercuric or mercurous salt.)

First Analytical Reaction.— The Copper Test. Deposition of mercury upon, and sublimation from copper.—Place a small piece of bright copper, about half an inch long and a quarter of an inch broad, in a solution of any salt of mercury, mercurous or mercuric, and heat in a test-tube, the copper becomes coated with mercury in a fine state of division. (The absence of any notable quantity of nitric acid must be insured, or the copper itself will be dissolved. See below.) Pour away the supernatant liquid from the copper, wash the latter once or twice by pouring water into, and then out of, the tube, remove the metal, take off excess of water by gentle pressure in a piece of filter-paper, dry the copper by passing it quickly through a flame, holding it by the fingers; finally, place the copper in a dry narrow test-tube, and heat to redness in a flame, the tube being held in a horizontal position; the mercury sublimes and condenses as a white sublimate of minute globules on the cool part of the tube outside the flame. The globules aggregate on gently pressing with a glass rod, and are especially visible where flattened between the rod and the side of the test-tube.

Notes on the Test.—This is a valuable test, for several reasons: It is very delicate when performed with care. It brings before the observer the element itself—one which from its metallic lustre and fluidity cannot be mistaken for any other. It separates the element both from mercurous and mercuric salts. Mercury can in this way be readily eliminated in the presence of most other substances, organic or inorganic.

In performing the test the presence of any quantity of nitric acid may be avoided by adding an alkali until a slight permanent precipitate appears, and then reacidifying with a few drops of acetic or hydrochloric acid; or by concentrating in an evaporating-dish after adding a little sulphuric acid.

Tests continued. (The mercury occurring as mercuric salt.)

Second Analytical Reaction.—To a few drops of a solution of a mercuric salt (corrosive sublimate, for example) add solution of iodide of potassium, drop by drop; a precipitate of mercuric iodide (HgI_2) forms, and at first quickly redissolves, but is permanent when sufficient iodide of potassium has been added. Continue the addition of iodide of potassium; the precipitate is once more redissolved.

Note.—When first precipitated, mercuric iodide is yellowish-red, soon changes to a beautiful scarlet. Its solubility either in solution of the mercuric salt or in solution of iodide of potassium renders the detection of a small quantity of a mercuric salt by iodide of potassium, or a small quantity of an iodide by a mercuric solution, difficult, and hence lessens the value of the reaction as a test.

Third Analytical Reaction.—Add a solution of mercuric salt to solution of ammonia, taking care that the mixture, after well stirring, still smells of ammonia; a white precipitate falls.

Ammoniated Mercury.

Performed in a test-tube, this reaction is a very delicate test of presence of a mercuric salt; performed in larger vessels, the ...uric salt being corrosive sublimate (3 ounces dissolved in 3 pints ...stilled water, the solution poured into 4 fluidounces of Solution ...mmonia, and the precipitate washed and dried over a water- ... it is the usual process for the preparation of "white precipi- the old "ammonio-chloride," or "amido-chloride of mercury," now known as Ammoniated Mercury (*Hydrargyrum Ammoniatum*, B. P., and U. S. P.).

Constitution of Ammoniated Mercury.—This precipitate is considered to be the chloride of mercuric ammonium ($NH_2Hg''Cl$)—that is, chloride of ammonium (NH_4Cl) in which two atoms of univalent hydrogen are replaced by one bivalent atom of mercury.

$HgCl_2$	+	$2NH_4HO$	=	$NH_2Hg''Cl$	+	NH_4Cl	+	$2H_2O$
Mercuric chloride.		Ammonia.		"White precipitate."		Chloride of ammonium.		Water.

Varieties of Ammoniated Mercury.—If the order of mixing be reversed and ammonia be added to solution of mercuric chloride, a double chloride of mercuric-ammonium and mercury results ($NH_3HgCl, HgCl_2$): it contains 76.55 per cent. of mercury. Previously to the year 1826, "white precipitate" was officially made by adding a fixed alkali to a solution of equal parts of corrosive sublimate and sal-ammoniac; this gave a double chloride of mercuric-ammonium and ammonium (NH_2HgCl, NH_4Cl), containing 65.57 per cent. of mercury. This compound is now known as "*fusible* white precipitate," because at a temperature somewhat below redness it fuses and then volatilizes. The "white precipitate" which has been

official since 1826 contains 79.52 per cent. of mercury. The true compound may be distinguished as "*infusible* white precipitate," from the fact that when heated it volatilizes without fusing. An ointment of this body is official (*Unguentum Hydrargyri Ammoniati*, B. P. and U. S. P.). Prolonged washing with water converts "white precipitate" into a yellowish compound (NH_2HgCl, HgO); hence the official preparation is seldom thoroughly freed from the chloride of ammonium which is formed during its manufacture, and which, if present in larger proportion than seven or eight per cent., gives to it the character of partial or complete fusibility.

Note.—Chloride of mercuric ammonium is only one member of a large class of similar compounds, derivable from the various salts of ammonium by displacement of atoms of hydrogen by other atoms. The composition of ammonio-nitrate of silver and ammonio-sulphate of copper, made without excess of ammonia (p. 153), is consistent with this view.

$$N\left\{\begin{matrix}H\\H\\H\\H\end{matrix}\right\}Cl \qquad N\left\{\begin{matrix}Hg''\\H\\H\end{matrix}\right\}Cl \qquad N\left\{\begin{matrix}Ag\\Am\\H\\H\end{matrix}\right\}NO_3 \qquad N_2\left\{\begin{matrix}Cu''\\Am_2\\H_2\\H_2\end{matrix}\right\}SO_4$$

Chloride of ammonium. | Chloride of mercuric ammonium. | Nitrate of argent-ammon-ammonium. | Sulphate of cupr-ammon-ammonium.

The composition of the crystals of ammonio-sulphate of copper (p. 169) is consistent with the second of the following formulæ, the first being that of sulphate of ammonium :—

$$N_2\left\{\begin{matrix}H_2\\H_2\\H_2\\H_2\end{matrix}\right\}SO_4 \qquad\qquad N_2\left\{\begin{matrix}Cu''\\Am_2\\Am_2\\H_2\end{matrix}\right\}SO_4$$

Fourth Analytical Reaction.—Pass sulphuretted hydrogen through a mercuric solution; a black precipitate of mercuric sulphide (HgS) falls.

Note.—Sulphuretted hydrogen also precipitates mercurous sulphide (Hg_2S) from mercurous solutions; and in appearance the precipitates are alike; hence this reagent does not distinguish between mercurous and mercuric salts. But in the course of systematic analysis, mercuric salts are thrown down from solution as sulphide after mercurous salts have been otherwise removed. The sulphides are insoluble in sulphydrate of ammonium.

Note.—An insufficient amount of the gas gives a white or colored precipitate of oxysulphide.

Ethiops Mineral, the *Hydrargyri Sulphuretum cum Sulphure*, is a mixture of sulphide of mercury and sulphur, obtained on triturating the elements in a mortar till globules are no longer visible. Its name is probably in allusion to its similarity in color to the skin of the Ethiop. It was formerly official.

Vermilion is mercuric sulphide prepared by heating together sulphur and mercury, and subliming the mixture (*Hydrargyri Sulphuretum Rubrum*, U. S. P.).

Tests continued. (The mercury occurring as mercurous salt.)

Fifth Analytical Reaction.—To a solution of a mercurous salt (the mercurous nitrate obtained in the second synthetical reaction, for example) add hydrochloric acid, or any soluble chloride; a white precipitate of calomel (HgCl) occurs.

This reaction was formerly official in the Dublin Pharmacopœia as a process for the preparation of calomel.

Sixth Analytical Reaction.—To solution of a mercurous salt add iodide of potassium; green mercurous iodide (HgI) is precipitated.

Seventh Analytical Reaction.—To a mercurous salt, dissolved or undissolved (calomel), add ammonia; black salt (chloride) of mercurous ammonium (NH_2Hg_2Cl) is formed.

Other tests for Mercury.

The elimination of mercury in the actual state of metal by the copper test, coupled with the production or non-production of a white precipitate on the addition of hydrochloric acid to the original solution, is usually sufficient evidence of the presence of mercury and its existence as a mercurous or mercuric salt. But other tests may sometimes be applied with advantage. Thus, metallic mercury is deposited on placing a drop of the solution on a plate of gold (sovereign or half sovereign), and touching the drop and the edge of the plate simultaneously with a key; an electric current passes, under these circumstances, from the gold to the key, and thence through the liquid to the gold, decomposing the salt, the mercury of which forms a white metallic spot on the gold, while the other elements go to the iron. This is called *the galvanic test*, and is useful for clinical purposes.——Solution of stannous chloride ($SnCl_2$) —see Index—from the readiness with which it forms stannic salts ($SnCl_4$, SnO_2, etc.), gives a white precipitate of mercurous chloride in mercuric solutions, and quickly still further reduces this mercurous chloride (and other mercury-salts) to a grayish mass of finely divided mercury; this is the old *magpie test*, probably so called from the white and gray appearance of the precipitate. The reaction may even be obtained from such insoluble mercury compounds as "white precipitate."——Confirmatory tests for mercuric and mercurous salts will be found in the action of solution of pot-

ash, solution of soda, lime-water, solution of ammonia, and solution of iodide of potassium. (*Vide* pages 180 to 183.) ——Normal alkaline carbonates produce yellowish mercurous carbonate, and brownish-red mercuric carbonate, both of them unstable.——Alkaline bicarbonates give mercurous carbonate and white (soon becoming red) mercuric oxysalt. ——Yellow chromate of potassium (K_2CrO_4) gives, with mercurous salts, a red precipitate of mercurous chromate (Hg_2CrO_4).——Mercury and all its compounds are volatile, subliming unchanged by heat: the experiment is most conveniently performed in a test-tube.

Antidote.—Albumen gives a white precipitate with solution of mercuric salts; hence the importance of administering white of egg while waiting for a stomach-pump in case of poisoning by corrosive sublimate.

QUESTIONS AND EXERCISES.

293. Name the chief ore of mercury, and describe a process for the extraction of the metal.

294. Give the properties of mercury.

295. In what state does mercury exist in "Gray Powder?"

296. What other preparations of metallic mercury itself are employed in medicine?

297. State the relation of the mercurous to the mercuric compounds.

298. Distinguish between an *alloy* and an *amalgam*.

299. State the formulæ of the two Iodides of Mercury.

300. Under what circumstances does mercuric iodide assume two different colors?

301. Illustrate the chemical law of Multiple Proportions as explained by the atomic theory, employing for that purpose the stated composition of the two iodides of mercury.

302. Write down the formulæ of Mercurous and Mercuric Nitrates and Sulphates.

303. How is Mercuric Sulphate prepared?

304. What is the formula of "Turpeth Mineral"?

305. Describe the processes necessary for the convertion of mercury into Calomel and Corrosive Sublimate, using diagrams.

306. Why is black oxide of manganese sometimes mixed with the other ingredients in the preparation of corrosive sublimate?

307. Give the chemical and physical points of difference between calomel and corrosive sublimate.

308. How may a small quantity of calomel in corrosive sublimate be detected?

309. Work out a sum showing how much mercury will be required in the manufacture of one ton of Calomel. *Ans.* 17 cwt. nearly.

310. Mention official preparations of the chlorides of mercury.
311. Give the formulæ and mode of formation of the Red, Yellow, and Black Oxides of Mercury, employing diagrams.
312. Explain the action of the chief general test for mercury.
313. How are mercurous and mercuric salts analytically distinguished?
314. Give a probable view of the constitution of *Hydrargyrum Ammoniatum*, and an equation showing how it is made.
315. What is the best temporary antidote in cases of poisoning by mercury?

LEAD.

Symbol Pb. Atomic weight 207.

Source.—The ores of lead are numerous; but the one from which the metal is chiefly obtained is the sulphide of lead (PbS), or *galena* (from γαλήνη, *galene*, tranquillity, perhaps from its supposed effect in allaying pain).

Preparation.—The ore is first roasted in a current of air; much sulphur is thus burnt off as sulphurous acid gas, while some of the metal is converted into oxide and a portion of the sulphide oxidized to sulphate. Oxidation being stopped when the mass presents certain appearances, the temperature is raised, and the oxide and sulphate, reacting on undecomposed sulphide, yield the metal and much sulphurous acid gas:—

$$2PbO + PbS = Pb_3 + SO_2$$
$$PbSO_4 + PbS = Pb_2 + 2SO_2.$$

Uses.—The uses of lead are well known. Alloyed with arsenicum it forms common *shot*, with antimony gives *type-metal*, with tin *solder*, and in smaller quantities enters into the composition of *Britannia metal*, *pewter*, and other alloys.

The salts of lead used in pharmacy and all other preparations of lead are obtained, directly or indirectly, from the metal itself. Heated in a current of air, lead combines with oxygen and forms oxide of lead (PbO) (*Plumbi Oxidum*, B. P. and U. S. P.), a yellow powder (*massicot*), or, if fused and solidified, a brighter reddish-yellow heavy mass of bright scales, termed *litharge* (from λίθος, *lithos*, a stone, and ἄργυρος, *argyros*, silver). It is from this oxide that the chief lead compounds are obtained. Oxide of lead, by further roasting in a current of air, yields *red lead* (or *minium*), Pb_3O_4, or $PbO_2 2PbO$. Both oxides are much used by painters, paper-stainers, and glass-manufacturers. *White lead* is a mixture of carbonate ($PbCO_3$) and hydrate of lead (Pb2HO) (commonly 2 molecules of the former to 1 of the latter), usually ground up with abont 7 per cent. of linseed oil; it is made by exposing lead, cast in spirals or little gratings, to the action of air, acetic fumes, and carbonic acid, the latter generated from decaying vegetable matter, such as spent tan; oxyacetate of lead slowly but continuously forms, and is as continuously decomposed by the carbonic acid with production of hydrate and carbonate,

or *dry white lead.* The grating-like masses, when ground, form the heavy white pulverulent official *Plumbi Carbonas*, B. B. and U. S. P. The latter is the active constituent of *Unguentum Plumbi Carbonatis*, B. P. and U. S. P., the old *Unguentum Cerussæ.*

Lead compounds are poisonous, producing saturnine colic, or even paralysis. These effects are termed *saturnine* from an old name of lead, *Saturn.* The alchemists called lead Saturn, first, because they thought it the oldest of the seven then known metals, and it might therefore be compared to Saturn, who was supposed to be the father of the gods; and, secondly, because its power of dissolving other metals recalled a peculiarity of Saturn, who was said to be in the habit of devouring his own children.

Quantivalence.—The atom of lead is sometimes quadrivalent (Pb''''); but in most of the compounds used in medicine it exerts bivalent activity only (Pb'').

Reactions having (*a*) Synthetical and (*b*) Analytical Interest.

(*a*) *Synthetical Reactions.*

Acetate of Lead.

First Synthetical Reaction.—Place a few grains of oxide of lead in a test-tube, add about an equal weight of water and two and a half times its weight of acetic acid, and boil; the oxide dissolves and forms a solution of acetate of lead ($Pb2C_2H_3O_2$). When cold, or on evaporation (the solution being kept faintly acid), crystals of acetate of lead ($Pb2C_2H_3O_2$, $3H_2O$) are deposited. Larger quantities are obtained by the same method.

$$\underset{\text{Oxide of lead.}}{PbO} + \underset{\text{Acetic acid.}}{2HC_2H_3O_2} = \underset{\text{Acetate of lead.}}{Pb2C_2H_3O_2} + \underset{\text{Water.}}{H_2O}$$

This is the official process for *Plumbi Acetas*, B. B. and U. S. P. The salt is vulgarly termed *Sugar of Lead*, from its sweet taste. Besides its direct use in Pharmacy, it forms three-fourths of the *Pilula Plumbi cum Opio*, B. P., is the chief constituent of *Unguentum Plumbi Acetatis*, B. P., and an ingredient in *Suppositoria Plumbi Composita, B. P.*, and *Suppositoria Plumbi* and *Suppositoria Plumbi et Opii*, U. S. P.

Subacetate or Oxyacetate of Lead.

Second Synthetical Reaction.—Boil acetate of lead with about four times its weight of water, and rather more than two-thirds its weight of oxide of lead; the resulting filtered liquid is solution of oxyacetate of lead, *Liquor Plumbi Subacetatis*, B. P. and U. S. P.

The official (B. P.) *Liquor* is made by boiling 5 ounces of acetate and $3\frac{1}{2}$ of oxide in 1 pint of distilled water for half an hour (constantly stirring), filtering, and making up for any loss by evaporation by diluting the filtrate to 1 pint.

A similar solution was used by M. Goulard, who called it *Extractum Saturni*, and drew attention to it in 1770. It is now frequently termed *Goulard's Extract.* A more dilute solution, 1 of *Liquor* and 1 of spirit in 80 of *distilled* water, is also official in the Pharmacopœias, under the name of *Liquor Plumbi Subacetatis Dilutus.* The latter is commonly known as *Goulard Water.* The stronger solution is the chief ingredient in *Unguentum Plumbi Subacetatis Compositum*, B. P., a slight modification of the old *Goulard's Cerate.* Similar preparations are official in the United States Pharmacopœia.

Oxyacetates of Lead.—The official subacetate of lead is not a definite chemical salt. It is probably a mixture of two subacetates of lead, which are well-known crystalline compounds, and which the author is disposed to regard as having a constitution similar to that he has already indicated for some other salts (see Iron, Antimony, and Bismuth). Exposed to air it absorbs carbonic acid gas, and hydrato-carbonate of lead is deposited.

B. P. { Acetate of Lead (3 molecules) . . . $Pb_3\ 6C_2H_3O_2$
Pyro-oxyacetate of lead . . . . . $Pb_3O4C_2H_3O_2$
Goulard's oxyacetate of lead . . . . $Pb_3O_2 2C_2H_3O_2$
Oxide of lead (3 molecules) . . . . . Pb_3O_3.

$$\underset{\text{Oxide of lead.}}{PbO} + \underset{\text{Acetate of lead.}}{Pb2C_2H_3O_2} = \underset{\text{Official "subacetate."}}{Pb_2O2C_2H_3O_2}$$

$$\text{or } \underset{\text{Oxide of lead.}}{3PbO} + \underset{\text{Acetate of lead.}}{3(Pb2C_2H_3O_2)} = \underset{\text{Pyro-oxyacetate.}}{Pb_3O4C_2H_3O_2} + \underset{\text{Goulard's oxyacetate.}}{Pb_3O_2 2C_2H_3O_2}$$
The official "subacetate."

Nitrate of Lead. Red Lead. Peroxide of Lead.

Third Synthetical Reaction.—Digest a few grains of red lead in nitric acid and water; nitrate of lead ($Pb2NO_3$) is formed, and remains in solution, while a puce colored peroxide of lead (PbO_2) is precipitated.

Nitrate of Lead (*Plumbi Nitras*, B. P. and U. S. P.) is more directly made by dissolving litharge (PbO) in nitric acid; but the above reaction serves to bring before the reader two other oxides of lead, namely, red lead (Pb_3O_4) and peroxide of lead (PbO_2). In the latter oxide the quadrivalent character of lead is obvious. Nitrate of lead is used officially in preparing iodide of lead; for this purpose the above mixture is filtered, the precipitate of peroxide of lead purified from adhering nitrate by passing hot water through the filter, the filtrate and washings evaporated to dryness to remove excess of nitric acid, the residual nitrate of lead redissolved by ebullition with a small quantity of hot water, and the solution set aside to crystallize, or a portion at once used for the following experiment. Nitrate of lead forms white crystals derived from octahedra.

Iodide of Lead.

Fourth Synthetical Reaction.—To a neutral solution of nitrate of lead add solution of iodide of potassium; a precipitate of iodide of lead (PbI_2) falls (*Plumbi Iodidum*, B. P. and U. S. P.). Equal weights of the salts may be used in making large quantities.

$$\underset{\text{Nitrate of lead.}}{Pb2NO_3} + \underset{\text{Iodide of potassium.}}{2KI} = \underset{\text{Iodide of lead.}}{PbI_2} + \underset{\text{Nitrate of potassium.}}{2KNO_3}$$

Iodide of lead is the chief ingredient in *Emplastrum Plumbi Iodidi*, B. P., and *Unguentum Plumbi Iodidi*, B. P. and U. S. P.

Crystals of Iodide of Lead.—Heat the iodide of lead with the supernatant liquid, and, if necessary, filter; the salt is dissolved, and again separates in golden crystalline scales as the solution cools.

Oleate of Lead (Lead Plaster).

Fifth Synthetical Reaction.—Boil together in a small dish some very finely-powdered oxide of lead, with about twice its weight of olive oil, and ten or twenty times as much water, well stirring the mixture, and from time to time replacing water that has evaporated; the product is a white mass of oleate of lead ($Pb2C_{18}H_{33}O_2$) (*Emplastrum Plumbi*, B. P. and U. S. P.), glycerine remaining in solution in the water. Larger quantities are prepared in the same manner.

$$\underset{\text{Oxide of lead.}}{3PbO} + \underset{\text{Water.}}{3H_2O} + \underset{\text{Oleate of glyceryl (olive-oil or oleine).}}{2(C_3H_53C_{18}H_{33}O_2)} = \underset{\text{Oleate of lead (lead plaster).}}{3(Pb2C_{18}H_{33}O_2)} + \underset{\text{Hydrate of glyceryl (glycerine).}}{2(C_3H_53HO)}$$

The action between the oxide of lead and olive oil is slow, requiring several hours for its completion.

The glycerine may be obtained by treating the aqueous product of the above reaction with sulphuretted hydrogen to remove a trace of lead, then digesting with animal charcoal, filtering and evaporating. But on the large scale glycerine is now usually produced as a by-product in the manufacture of candles; for its elements are found in all vegetable and animal fats. (*Vide* Index.)

Modes of forming *chloride, sulphide, chromate, sulphate, hydrate*, and other salts of lead are incidentally described in the following analytical paragraphs.

(*b*) *Reactions having Analytical Interest* (*Tests*).

First Analytical Reaction.—To a solution of lead salt (acetate, for example) add hydrochloric acid; a white precipitate of chloride of lead ($PbCl_2$) is obtained. Boil the precipitate with much water; it dissolves, but, on the solution cooling, is redeposited in small acicular crystals. Filter the cold solution, and pass sulphuretted hydrogen through it; a black precipitate (sulphide of lead, PbS) shows that the chloride of lead is soluble to a slight extent in cold water.

Note.—A white precipitate on the addition of hydrochloric acid, soluble in hot water, and blackened by sulphuretted hydrogen, sufficiently distinguishes lead salts from those of other metals, but the non-production of such a precipitate does not prove the absence of a small quantity of lead, chloride of lead being slightly soluble in cold water. Hydrochloric acid will be found to be a useful but not a delicate test for lead.

Second Analytical Reaction.—Through a dilute solution of a lead salt pass sulphuretted hydrogen; a black precipitate of sulphide of lead (PbS) occurs.

Lead in Water.—The foregoing is a very delicate test. Should a trace of lead be present in water used for drinking-purposes, sulphuretted hydrogen will detect it. On passing the gas through a pint of such water, a brownish tint, more or less deep, is produced. If the tint is scarcely perceptible, set the liquid aside for a day; the gas will become decomposed and a thin layer of sulphur be found at the bottom of the vessel, white if no lead be present, but more or less brown if it contain sulphide of lead.

Third Analytical Reaction.—To solution of a lead salt add sulphydrate of ammonium; a black precipitate of sulphide of lead falls, insoluble in excess.

Fourth Analytical Reaction.—To solution of a lead salt add solution of chromate of potassium (K_2CrO_4); a yellow precipitate of chromate of lead ($PbCrO_4$) is formed, insoluble in weak acids.

Chromes.—This reaction has technical as well as analytical interest. The precipitate is the common pigment termed *chrome yellow*, or *lemon chrome*. Boiled with lime and water, a portion of the chromic radical is removed as soluble chromate of calcium, and an oxychromate of lead, of a bright red or orange color (*orange chrome*), is produced.

Fifth Analytical Reaction.—To solution of a lead salt add dilute sulphuric acid, or solution of a sulphate; a white precipitate of sulphate of lead ($PbSO_4$) falls.

Sulphate of lead is slightly soluble in strong acids, and in solutions of alkaline salts; it is insoluble in acetic acid.

In dilute solutions this sulphuric reaction does not take place immediately; the precipitate, however, falls after a time; its appearance may be hastened by evaporating the solution nearly to dryness and then rediluting.

The white precipitate always noticed in the vessels in which diluted sulphuric acid is kept, is sulphate of lead, derived from the leaden chambers in which the acid is made; solubility in strong acid and insolubility in weak, explains its appearance.

Antidotes.—From the insolubility of sulphate of lead in water, the best *antidote* in a case of poisoning by the acetate or other soluble salt of lead, is a soluble sulphate, such as Epsom salt, sulphate of sodium or alum, vomiting being also induced, or the stomach-pump applied as quickly as possible.

Other tests for lead will be found in the reaction with *iodide of potassium* (*vide* p. 188); with *alkaline carbonates*, a white precipitate ($2PbCO_3 + Pb2HO$) insoluble in excess; with *alkalies*, a white precipitate ($Pb2HO$) more or less soluble in excess; with alkaline *phosphates*, *arseniates*, *ferrocyanides* and *cyanides*, precipitates mostly insoluble, but of no special analytical interest. Insoluble salts of lead are decomposed by solutions of potash (KHO) or soda ($NaHO$).

The metal is precipitated in a beautifully crystalline state by metallic zinc and some other metals; the *lead tree* is thus formed.——The *blowpipe-flame* decomposes solid lead compounds placed in a small cavity in a piece of charcoal, a soft malleable bead of metal being produced, and a yellowish ring of oxide deposited on the charcoal.

QUESTIONS AND EXERCISES.

316. Write down equations descriptive of the smelting of galena.
317. Mention some of the alloys of lead.
318. How is litharge produced?
319. Give the formulæ of white lead and red lead.
320. Describe the manufacture of white lead.
321. What is the quantivalence of lead?
322. Draw a diagram expressive of the formation of Acetate of Lead.
323. Describe the preparation and composition of *Liquor Plumbi Subacetatis.*
324. What is the action of nitric acid on red lead, litharge, and metallic lead?
325. How is the official Iodide of Lead prepared?

326. Describe the reaction between oxide of lead, water, and olive oil, at the temperature of boiling water, and give chemical formulæ explanatory of the constitution of the products.

327. Mention the chief tests for lead.

328. How would you search for lead in potable water?

329. What is the composition of chrome yellow?

330. State a method whereby lead, barium, and silver may be separated.

331. Name the best antidote in case of poisoning by salts of lead.

SILVER.

Symbol Ag. Atomic weight 108.

Source.—This element occurs in nature in the free state and as ore, the common variety being sulphide of silver (Ag_2S) in combination with much sulphide of lead, forming *argentiferous galena.*

Preparation.—The lead from galena (p. 185) is melted and slowly cooled; crystals of lead separate and are raked out from the still fluid mass, and thus an alloy very rich in silver is finally obtained: this is roasted in a current of air, whereby the lead is oxidized and removed as litharge, pure silver remaining. Other ores undergo various preparatory treatments according to their nature, and are then shaken with mercury, which amalgamates with and dissolves the particles of silver, the mercury being subsequently removed from the amalgam by distillation. Soils and minerals containing metallic silver are also treated in this way. An important improvement in the amalgamation process, by which the mercury more readily unites with the silver, consists in the addition of a small proportion of sodium to the mercury—a recent discovery simultaneously made in England by Crookes, and in New York by Wurtz.

Reactions having (*a*) Synthetical and (*b*) Analytical Interest.

(*a*) *Synthetical Reactions.*

Impure Nitrate of Silver.

First Synthetical Reaction.—Dissolve a silver coin in nitric acid; nitric oxide gas (NO) and nitrous anhydride (N_2O_3) are evolved, and a solution of nitrates of silver and copper obtained.

Silver Coinage.—Pure silver is too soft for use as coin, it is therefore hardened by alloying with copper. The silver money of England contains 7.5, of France 10, and of Prussia 25 per cent. of copper. One pound troy of standard silver is coined into 66 shillings, of which the metal is worth from 60*s.* to 62*s.* according to the market price of silver. The standard fineness of silver is 0.925, three alloy in 40.

The fineness of the French standard silver is 0.900 in the five-franc piece; but an inferior alloy of 0.835 is used for the lower denominations. The single-franc piece, composed of the latter alloy, is still made to weigh five grammes, the weight originally chosen for the franc as the unit of the monetary scale when the fineness of the coin was 0.900. It has now become a token, like the British shilling, of which the nominal value exceeds the metallic value. British silver coins are a legal tender in payments to the amount of 40*s.* only.

Chloride of Silver.

Second Synthetical Reaction.—To the product of the above reaction add water and hydrochloric acid or a soluble chloride; white chloride of silver (AgCl) is precipitated, copper still remaining in solution. Collect the precipitate on a filter, and wash with water; it is pure chloride of silver.

Note.—The nitrates of silver and copper may also be separated by evaporating the solution of the metals in nitric acid to dryness, and gently heating the residue, when the nitrate of copper is decomposed, but the nitrate of silver unaffected. The latter may be dissolved from the residual oxide of copper by water.

Chloride of silver may be obtained in crystals by evaporation of its solution in ammonia.

Pure Silver.

Third Synthetical Reaction.—Place the chloride of silver of the previous reaction in a dish, wet it with dilute sulphuric acid, and float a piece of sheet zinc on the mixture; metallic silver is precipitated, and after about one day wholly removed from solution. Collect the precipitate on a filter and wash with water; it is pure metallic silver, and is readily fusible into a single button.

Note.—Chloride of silver may also be reduced to a lump of the metal by fusion, in a crucible, with about half its weight of carbonate of sodium.

Pure Nitrate of Silver.

Fourth Synthetical Reaction.—Dissolve the pure silver of the previous reaction in nitric acid (3 of silver require about 2 or $2\frac{1}{2}$ of strong acid diluted with 5 of water), and remove excess of acid by evaporating the solution to dryness, slightly heating the residue; the product is pure nitrate of silver. Dissolve by heating with a small quantity of water; on the solution cooling, or on evaporation, colorless tabular crystals of nitrate of silver are obtained.

$$\underset{\text{Silver.}}{3Ag_2} + \underset{\text{Nitric acid.}}{8HNO_3} = \underset{\text{Nitric oxide.}}{2NO} + \underset{\text{Nitrate of silver.}}{6AgNO_3} + \underset{\text{Water.}}{4H_2O}$$

Notes.—The solution of pure or refined silver (*Argentum Purificatum*, B. P., *Argentum* U. S. P.) in nitric acid, evaporation, and crystallization constitute the official process for the preparation of the nitrate (*Argenti Nitras*, B. P. and U. S. P.). The salt fused, and poured into proper moulds, yields the white cylindrical sticks or rods (*Argenti Nitras Fusa*, U. S. P.) commonly termed *caustic* (from καίω, *kaio*, I burn), or *lunar caustic*. (The alchemists called silver *Diana* or *Luna*, from its supposed mysterious connection with the moon.) The specimen of nitrate of silver obtained in the above reaction, dissolved in water, will be found useful as an analytical reagent. Nitrate of silver is soluble in rectified spirit; but after a time reaction and decomposition occur.

Silver salts are decomposed when in contact with organic matter, especially in the presence of light or heat, the metal itself being liberated, or a black insoluble compound formed. Hence the value of the nitrate in the manufacture of indelible ink for marking linen; hence, too, the reason of the practice of rendering silver solutions clear by subsidence and decantation, rather than by filtration through paper; and hence the cause of those cases of actual combustion which have been known to occur in preparing pills containing oxide of silver and essential oil or other organic matter.

Oxide of Silver.

Fifth Synthetical Reaction.—To a few drops of solution of nitrate of silver add solution of potash or soda or lime-water; an olive-brown precipitate of oxide of silver (Ag_2O) occurs. The washed and dry oxide, like most silver compounds, is decomposed by heat with production of metal.

The *Argenti Oxidum*, B. P. and U. S. P., is thus made, lime-water (solution of potash U. S. P.) being the precipitant employed, soda and potash not being so readily removed by washing. Three and a half pints of lime-water will decompose half an ounce of nitrate of silver.

$$\underset{\text{Nitrate of silver.}}{2AgNO_3} + \underset{\text{Hydrate of calcium.}}{Ca2HO} = \underset{\text{Oxide of silver.}}{Ag_2O} + \underset{\text{Nitrate of calcium.}}{Ca2NO_3} + \underset{\text{Water.}}{H_2O}$$

Methods of forming several other salts of silver are incidentally mentioned in the following analytical paragraphs.

(*b*) *Reactions having Analytical Interest.* (*Tests.*)

First Analytical Reaction.—To a solution of a silver salt add hydrochloric acid or other soluble chloride; a white curdy precipitate of chloride of silver falls. Add nitric acid, and boil; the precipitate does not dissolve. Pour off

the acid and add solution of ammonia; the precipitate dissolves. Neutralize the ammoniacal solution by an acid; the chloride of silver is re-precipitated.

This is the most characteristic test for silver. The precipitated chloride is also soluble in solutions of hyposulphite of sodium or cyanide of potassium—facts of considerable importance in photographic operations.

Other analytical reagents than the above are occasionally useful.——Sulphuretted hydrogen, or sulphydrate of ammonium, gives a black precipitate, sulphide of silver (Ag_2S), insoluble in alkalies.——Solutions of potash or soda give a brown precipitate, oxide of silver (Ag_2O), converted into a fulminating compound by prolonged contact with ammonia.——Phosphate of sodium gives a pale yellow precipitate, phosphate of silver (Ag_3PO_4), soluble in nitric acid and in ammonia.——Arseniate of ammonium gives a chocolate-colored precipitate, arseniate of silver (Ag_3AsO_4), already noticed in connection with arsenic acid.——Iodide or bromide of potassium gives a yellowish-white precipitate, iodide or bromide of silver (AgI or AgBr), insoluble in acids and only slightly soluble in ammonia.——Cyanide of potassium gives a white precipitate, cyanide of silver (AgCy), soluble in excess, sparingly soluble in ammonia, insoluble in dilute nitric acid, soluble in boiling concentrated nitric acid. *Argenti cyanidum*, U. S. P., is made by distilling a mixture of ferrocyanide of potassium and diluted sulphuric acid, and passing the resulting hydrocyanic acid into a solution of nitrate of silver: $HCy + AgNO_3 = AgCy + HNO_3$ (the precipitate is well washed and dried).——Yellow chromate of potassium (K_2CrO_4) gives a red precipitate, chromate of silver (Ag_2CrO_4).——Red chromate of potassium also gives a red precipitate, acid chromate of silver (Ag_2CrO_4,CrO_3).——Many organic acids afford insoluble salts of silver.——Several metals displace silver from solution, mercury forming in this way a crystalline compound known as the silver tree, or *Arbor Dianæ*.——In the blowpipe flame, silver salts, placed on charcoal with a little carbonate of sodium, yield bright globules of metal accompanied by no incrustation as in the corresponding reaction with lead salts; the experiment may be performed with the nitrate, which first melts and then, like all nitrates, deflagrates, yielding a white metallic coating of silver which slowly aggregates to a button.

Antidotes.—Solution of common salt, sal-ammoniac, or any other inert chloride should obviously be administered where large doses of nitrate of silver have been swallowed. A quantity of sea-water or brine would convert the silver into insoluble chloride, and at the same time produce vomiting.

QUESTIONS AND EXERCISES.

332. By what process is silver obtained from argentiferous galena?

333. What weight of English silver coin will yield one pound of pure nitrate of silver?

334. How may the metal be recovered from an impure mixture of silver salts?

335. Give a diagram showing the formation of nitrate of silver from the metal.

336. Describe the reaction of lime water and nitrate of silver.

337. Mention the chief test for silver, and the precautions to be observed in order that silver salts may be distinguished from those of lead and mercury.

338. Name the antidote for silver.

DIRECTIONS FOR APPLYING SOME OF THE FOREGOING REACTIONS TO THE ANALYSIS OF AN AQUEOUS SOLUTION OF SALTS OF ONE OF THE METALS, COPPER, MERCURY (EITHER AS MERCUROUS OR MERCURIC SALT), LEAD, SILVER.

Add hydrochloric acid:—

Silver is indicated by a white curdy precipitate, soluble in ammonia.

Mercurous salts also by a white precipitate, turned black by ammonia.

Lead by a white precipitate, insoluble in ammonia. Confirm by boiling another portion of the hydrochloric precipitate in water; it dissolves.

If hydrochloric acid gives no precipitate, silver and mercurous salts are absent. Lead can only be present in very small quantity. Mercuric salts may be present. Copper may be present. Divide the liquid into three portions, and apply a direct test for each metal.

Lead is best detected by the sulphuric test; the tube being set aside for a time if the precipitate does not appear at once.

Mercury is best detected by the copper test. If present, it occurs as mercuric salt.

Copper betrays itself by the blue color of the liquid under examination. Confirm by the ammonia test.

If the above reactions are not thoroughly conclusive, confirmatory evidence should be obtained by the application of some of the other reagents for copper, mercury, lead or silver.

TABLE OF SHORT DIRECTIONS FOR APPLYING SOME OF THE FOREGOING REACTIONS TO THE ANALYSIS OF AN AQUEOUS SOLUTION OF SALTS OF ANY OR ALL OF THE METALS COPPER, MERCURY (EITHER MERCUROUS OR MERCURIC SALT, OR BOTH), LEAD, SILVER.

Add hydrochloric acid, filter, and wash the precipitate with a small quantity of cold water.

<table>
<tr><td colspan="2">Ppt.
Pb Hg(ous) Ag.
Wash with boiling water.</td><td>Filtrate
Cu Hg(ic) Pb.
Divide into three portions.
Test for
Cu by AmHO; blue sol.
Hg (mercuric) by Cu; globules.
Pb by H_2SO_4; white ppt *</td></tr>
<tr><td colspan="2">Ppt.
Hg(ous) Ag
Add AmHO.</td><td rowspan="2">Filtrate
Pb.
Add H_2SO_4, white ppt.*</td></tr>
<tr><td>Precipitate
Hg
(mercurous)
black.</td><td>Filtrate
Ag.
Add HNO_3, white ppt.</td></tr>
</table>

* Liquids containing only a small quantity of lead do not readily yield sulphate of lead on the addition of sulphuric acid. Before lead can be said to be absent, therefore, the liquid should be evaporated to dryness with one drop of sulphuric acid, and the residue digested in water; any sulphate of lead then remains as a heavy white insoluble powder.

Add hydrochloric acid.

Ppt.
Hg(ous) Pb Ag.
Add AmHO.
Hg, black ppt.
Pb, ppt. still white.
Ag, ppt. dissolved.

If HCl gave no precipitate, neither Hg, Pb, nor Ag is present.

Hg obtained here must have existed in the solution as a mercurous salt.

Sb is also precipitated by HCl, but is dissolved on adding more HCl; the Hg, Pb, and Ag precipitates are not soluble in excess of HCl.

If HCl gave no precipitate the metal is still in the liquid; pass H_2S through it.

Ppt.
Cu Hg(ic) Pb As Sb.
As, yellow ppt.
Sb, orange ppt.
Cu, Hg, Pb } black ppt.
Test original solution for
Cu by AmHO; blue sol.
Hg by Cu; globules.
Pb by H_2SO_4; white ppt.

If H_2S gave no precipitate, neither Cu, Hg, Pb, As, nor Sb is present.

If H_2S gave no precipitate the metal is still in the liquid; add AmCl, AmHO, and AmHS.

Ppt.
Fe Al Zn
Fe, black ppt.

Test original solution for ferric salt by K_4Fcy (*dark* blue ppt.); ferrous salt by K_6Fdcy (*dark* blue ppt.).

Al, Zn } white ppt.

Test original solution by AmHO.

Al, white ppt. insoluble in excess.

Zn, white ppt. soluble in excess.

If AmHS, etc., gave no precipitate, the liquid may still contain either Ba, Ca, Mg, K, Na, or Am; add successively $KCrO_4$ for Ba, $Am_2C_2O_4$ for Ca, Na_2HPO_4 for Mg.

If neither Ba, Ca, nor Mg is found, examine the original solution for Am by KHO, Na by the flame test, and K $PtCl_4$.

TABLE OF SHORT DIRECTIONS FOR APPLYING SOME OF THE FOREGOING ANALYTICAL REACTIONS TO THE ANALYSIS OF AN AQUEOUS SOLUTION OF ORDINARY SALTS OF ANY OR ALL OF THE ELEMENTS HITHERTO CONSIDERED.

Add hydrochloric acid, and filter.

Precipitate Hg(ous) Pb Ag. Wash, boil with water, filter.		Filtrate Cu Hg(ic) Pb As Sb Fe Al Zn Ba Ca Mg K Na Am. Pass H_2S through the liquid; filter.							
Precipitate Hg Ag. Add AmHO.		Filtrate Pb. Add H_2SO_4; white precipitate.	Precipitate Cu Hg Pb As Sb. Wash, digest in AmHS; filter.		Filtrate Fe Al Zn Ba Ca Mg K Na Am. Add AmHO, AmHS, and filter.				
Precipitate Hg. Black precipitate.	Filtrate Ag. Add HNO_3; white precipitate.		Precipitate Cu Hg Pb. Wash, dissolve in a few drops of HNO_3 and HCl; evap. nearly to dryness; redissolve in H_2O, divide into three, and test for Cu by AmHO; blue solution. Hg by Cu; globules. Pb by H_2SO_4; white precip.	Filtrate As Sb. Add $HC_2H_3O_2$, and boil; digest the precipitate in *strong* HCl; boil, dilute; filter.	Precipitate Fe Al Zn. Wash, dissolve in HCl, boil (with a few drops of HNO_3 if necessary, p. 137); add KHO, stir, filter.		Filtrate Ba Ca Mg K Na Am. Add Am_2CO_3; boil, filter.		
				Precip. As. Yellow.	Precipitate Fe ? Ferric or ferrous. Test original solution by yellow and red prussiate.	Filtrate Al Zn. Neutralize by HCl; add AmHO, stir, filter.	Precipitate Ba Ca. Wash, dissolve in $HC_2H_3O_2$; add K_2CrO_4, filter.		Filtrate Mg K Na Am. Add Am_2HAsO_4; stir, filter.	
				Filtrate Sb. Add H_2S. Orange precip.		Precipitate Al. White precipitate.	Filtrate Zn. Add AmHS; white precipitate.	Precip. Ba. Yellow.	Filtrate Ca. Add $Am_2C_2O_4$; white precipitate.	Precip. Mg. White.	Filtrate K Na Am. Evap. ignite. dis. in H_2O, & test for K by $PtCl_4$, yel. precip. Na by flame; yel. Am in orig. sol. by NaHO.
				Confirm by testing original solution by the H tests.							

The group-tests of this Table are HCl, H_2S, NH_4HS, and $(NH_4)_2CO_3$.

OUTLINE OF THE PRECEDING TABLES.

HCl	H_2S		AmHS	Am_2CO_3	Am_2HAsO_4	
Hg (as mercurous salt)	Cu	Insoluble in AmHS.	Zn	Ba	Mg	K
Pb	Hg (as mercuric salt)		Al	Ca		Na
Ag	Pb		Fe			Am
	As	Soluble in AmHS.				
	Sb					

The practical student should examine solutions containing the above metals until he is able to analyze with facility and accuracy. In this way he will best perceive the peculiarities of each element and their general relations to each other. As the rarer metals are not included here, the tables are not complete analytical schemes; further remarks concerning them, therefore, are for the present deferred.

QUESTIONS AND EXERCISES.

339. Give processes for the qualitative analysis of liquids containing the following substances:—

a. Antimony and Mercurous salt.
b. Lead and Calcium.
c. Silver and Mercurous salt.
d. Lead and Mercuric salt.
e. Copper and Arsenicum.
f. Arsenicum and Antimony.
g. Aluminium and Zinc.
h. Iron and Copper.
i. Magnesium, Calcium, and Potassium.
j. Silver, Antimony, Zinc, Barium, and Ammonium.

340. Enumerate the so-called group-tests.

341. Give a general sketch of the method of analyzing a solution suspected to contain two or more salts of common metals.

342. Classify the common metals according to their analytical relations.

METALS OF MINOR PHARMACEUTICAL IMPORTANCE.

Thus far has been considered, somewhat in detail, the chemistry of the common metals, salts of which are frequently used in medicine or in testing medicinal substances. These are :—

Potassium,	Barium,	Zinc,	Arsenicum,	Mercury,
Sodium,	Calcium,	Aluminium,	Antimony,	Lead,
Ammonium (?),	Magnesium,	Iron,	Copper,	Silver.

There still remain eleven metals, eight of which are mentioned in the British Pharmacopœia, namely :—

Lithium,	Chromium,	Gold,	Cadmium,
Manganese,	Tin,	Platinum,	Bismuth.

Compounds of the remaining three are sufficiently common to occasionally come under notice :—

Strontium, Cobalt, Nickel.

These eleven metals of minor pharmaceutical interest may be shortly studied, a few only of the reactions of each (just those mentioned in the following pages) being performed. When all have been thus treated, their respective positions in the analytical groups will be indicated and a tabular scheme by which an analysis of a solution containing any metal may be effected. Thus, step by step, we may learn how to analyze almost any substance that may occur, and know to what extent the presence of a rarer will interfere with the ordinary tests for a common element : additional illustrations of the working of chemical laws will be acquired, and the store of chemical and pharmaceutical facts increased. The opportunity thus afforded for improvement in habits of neatness in manipulation, precision, and classification is another and no mean reason why such experiments should be prosecuted, the direct value of which may not be considerable to medical and pharmaceutical learners.

LITHIUM.

Symbol L. Atomic weight 7.

Lithium is widely distributed in nature, but usually in minute proportions compared with other elements. A trace of it may be found in most soils and waters, a Cornish spring containing even considerable quantities as chloride.

One salt used in medicine is the *Citrate* ($L_3C_6H_5O_7$) (*Lithii Citras*, U. S. P.), occurring in white deliquesent crystals or powder, prepared by dissolving 50 grains of the *Carbonate* (L_2CO_3) and 100 of citric acid in 1 ounce of water, evaporating to a low bulk, and

setting aside in a dry place to crystallize, or at once evaporating to dryness and powdering the residue.

$$3L_2CO_3 + 2H_3C_6H_5O_7 = 2L_3C_6H_5O_7 + 3H_2O + 3CO_2$$

Carbonate of lithium. — Citric acid. — Citrate of lithium. — Water. — Carbonic acid gas.

The carbonate (*Lithii Carbonas*, U. S. P.) is a white granular powder obtained from the minerals which contain lithium; namely, lepidolite (from λεπίς, *lepis*, a scale, and λίθος, *lithos*, a stone; it has a scaly appearance), triphane (from τρεῖς, *treis*, three, and φαίνω, *phainō*, I shine), or spodumene (from σποδόω, *spodōō*, to reduce to ashes, in allusion to its exfoliation in the blowpipe-flame), and petalite (from πέταλον, *petalon*, a leaf; its character is leafy and laminated). Each contains silicate of aluminium, with fluoride of potassium and lithium in the case of lepidolite, and silicate of sodium and lithium in the others. *Liquor Lithiæ Effervescens*, B. P., is a solution of 10 grains of carbonate of lithium in 1 pint of water charged with 7 times its volume of carbonic acid gas and kept in ordinary aërated water-bottles. "Half a pint, evaporated to dryness, yields 5 grains of a white solid residue, answering to the tests for carbonate of lithium. . . . . Ten grains of the latter salt neutralized with sulphuric acid, and afterwards heated to redness, leave 14.86 grains of dry sulphate of lithium, which, when redissolved in distilled water, yields no precipitate with oxalate of ammonium or solution of lime," indicating absence of salts of calcium and aluminium. Citrate of lithium should yield by incineration 52.8 per cent. of white carbonate of lithium.

*Urate of Lithium** is more soluble than urate of sodium; hence lithium preparations are administered to gouty patients in the hope that urate of sodium, with which such systems are loaded, may be converted into urate of lithium and removed.

In chemical position lithium stands between the alkaline and the alkaline-earth metals, its hydrate, carbonate, and phosphate being slightly soluble in water. The double chloride of platinum and lithium also is soluble in water. Its atom is univalent, L′.

Analytical Reaction.—Moisten the end of a platinum wire with solution of a minute particle of solid lithium salt, and introduce it into the flame of a Bunsen burner or other slightly colored flame (spirit-lamp or blowpipe-flame); a magnificent crimson tinge is imparted.

The light emitted by ignited lithium vapor is of a purer scarlet than that given by strontium, the next element. When the flames are examined by spectral analysis (physically analyzed by a prism), the red rays are, in the case of strontium, found to be associated with blue and yellow, neither of which is present in the lithium light.

* Urates will be considered subsequently in connection with uric acid.

STRONTIUM.

Symbol Sr. Atomic weight 87.5.

Source.—Strontium is not widely distributed in nature; but the carbonate ($SrCO_3$), known as *strontianite*, and the sulphate ($SrSO_4$) known as *celestine* (from *cœlum*, the sky, in allusion to its occasional bluish color), are by no means rare minerals.

Salts of strontium are not employed in medicine. They are chiefly used by firework manufacturers in preparing red fire. The color they impart to flame is a beautiful crimson—ignited strontium vapor emitting red rays, as already explained. Nitrate of strontium ($Sr2NO_3$) is best for pyrotechnic compositions, its oxygen enabling it to burn freely when mixed with charcoal, sulphur, etc. It, or any salts, may be obtained by dissolving the carbonate in the appropriate acid, or by igniting the cheaper sulphate with coal, whereby sulphide (SrS) is produced, and dissolving this in acid.

The position of strontium among the chemical elements is between barium and calcium; its sulphate is very sparingly soluble in water. Its atom, like those of barium and calcium, is bivalent (Sr″).

Analytical Reactions (Tests).

First Analytical Reaction.—To a solution of a strontium salt ($Sr2NO_3$ or $SrCl_2$) add carbonate of ammonium; a white precipitate of carbonate of strontium ($SrCO_3$) falls.

Second Analytical Reaction.—To a solution of a strontium salt add sulphuric acid previously so diluted that it will not precipitate calcium salts or an equally dilute solution of any other sulphate; a white precipitate of sulphate of strontium ($SrSO_4$) falls. The formation of this precipitate is promoted by stirring and by setting the liquid aside for some time.

Barium is precipitated immediately under similar circumstances.

Third Analytical Reaction.—To a dilute solution of a strontium salt add yellow chromate of potassium; no precipitate falls.

Barium may be separated from strontium by chromate of potassium, that reagent at once precipitating barium from aqueous or acetic solutions.

Fourth Analytical Reaction.—Insert a fragment of a strontium salt in the blowpipe-flame, or other equally colorless flame, or hold the end of a platinum wire dipped into a strontium solution in the flame; a crimson color is imparted.

Other Analytical Reactions.—Alkaline phosphates, arseniates, and oxalates give white insoluble precipitates with

strontium as with barium and calcium.——Strontium, like calcium, but unlike barium, is not precipitated by hydrofluosilicic acid.

Cerium. Ce. At. wt. 22.—This element occurs in the mineral cerite (a silicate of iron, calcium, and the three rare metals, cerium, lanthanium, and didymium); also occasionally as impure fluoride, carbonate, and phosphate. The oxalate of cerium, a white granular powder, is the only official salt; it may be obtained from cerite by boiling the powdered mineral in strong hydrochloric acid for several hours, evaporating, diluting, and filtering to separate silica; adding ammonia to precipitate hydrates of all the metals except calcium; filtering off, washing, redissolving in hydrochloric acid, and adding oxalic acid to precipitate oxalate of cerium. The preparation will still contain oxalates of lanthanium and didymium; it is therefore strongly calcined, the resulting oxides of lanthanium and didymium dissolved out by boiling with a concentrated solution of chloride of ammonium, the residual oxide of cerium dissolved in hydrochloric acid, and oxalate of ammonium added to precipitate pure oxalate of cerium ($Ce''C_2O_4$, $3H_2O$).

Oxalate of cerium (*Cerii Oxalas*, B. P. and U. S. P.) is decomposed at a dull red heat, a salmon-colored mixture of oxides remaining; usually a little didymium is present, giving the ignited residue a reddish-brown color; it is then soluble in boiling hydrochloric acid (without effervescence; indicating, indirectly, absence of earthy and other carbonates or oxalates), and the solution gives, with excess of a saturated solution of sulphate of potassium, a crystalline precipitate of double sulphate of cerium and potassium. Alumina mixed with oxalate of cerium may be detected by boiling with solution of potash, filtering, and adding excess of solution of chloride of ammonium, when a white flocculent precipitate of hydrate of aluminium will be obtained. The oxalic radical is recognized by neutralizing the potash solution by acetic acid and adding chloride of calcium; white oxalate of calcium is then precipitated; this precipitate, though insoluble in acetic, should be wholly dissolved by hydrochloric acid.

MANGANESE.

Symbol Mn. Atomic weight 55.

Source.—Manganese is a constituent of many minerals, and as black oxide (MnO_2) (*Manganesii Oxidum Nigrum*, B. P. and U. S. P.), or *pyrolusite* (from πῦρ, *pur*, fire, and λύσις, *lusis*, a loosing or resolving, in allusion to the readiness with which it is split up by heat into a lower oxide and oxygen), occurs frequently in abundance in the southwest of England, Aberdeenshire, and most of the countries of Europe. It is met with as a steel-gray mass of prismatic crystals, or in black shapeless lumps.

The chemical position of manganese is close to iron and three other metals still to be considered—cobalt, nickel, and chromium. Its atom apparently has sexivalent affinities, as seen in manganate of potassium (K_2MnO_4); but commonly it is quadrivalent (Mn^{iv}) or bivalent (M'').

Uses.—Metallic manganese is only used in alloy with iron in the manufacture of some varieties of steel. The black oxide is an important agent in the production of chlorine, the preparation of green and red disinfecting manganates, purple glass, and black glazes for earthenware.

Reactions having either Synthetical or Analytical Interest, or both.

First Reaction.—Boil a few grains of black oxide of manganese with some drops of hydrochloric acid until chlorine ceases to be evolved; add water, and filter; the filtrate is a solution of manganous chloride ($MnCl_2$).

$$MnO_2 + 4HCl = MnCl_2 + 2H_2O + Cl_2.$$

This is the reaction commonly applied in the preparation of chlorine gas. It is also a ready method of preparing a manganous salt for analytical experiments. Coupled with the application of reagents to the filtrate, the reaction is that by which a black powder or mineral would be recognized as black oxide of manganese. Black oxide of manganese dissolves in cold hydrochloric acid, forming a dark-brown solution of a higher chloride or chlorides, $MnCl_3$, Mn_2Cl_7, or, possibly, $MnCl_4$.

Second Reaction.—Heat a particle of a manganese compound with a grain or two of carbonate and hydrate of potassium and a fragment of nitrate or chlorate of potassium on platinum foil in the blowpipe-flame; a green mass containing *manganate of potassium* (K_2MnO_4) results. Boil the foil in a little water; the green manganate dissolves and soon changes to solution of the purple *permanganate of potassium* ($K_2Mn_2O_8$).

This is a delicate analytical test for manganese.

The reaction is similar to that by which permanganate of potassium (*Potassii Permanganas*, U. S. P.) is directed to be prepared for use in volumetric analysis. *Liquor Potassii Permanganatis*, U. S. P., is a solution of 89 grains of permanganate of potassium in 1 pint of distilled water. Equations showing the exact action which occurs in making the salt according to the process of the British Pharmacopœia have already been given in connection with the compounds of potassium (*vide* p. 64). The proportions of ingredients and details of the operation are as follows:—

Reduce 3½ parts (for experiment each "part" may be ⅛th oz.) of chlorate of potassium to fine powder, and mix it with 4 of black oxide of manganese; put the mixture into a porcelain basin, and add to it 5 parts of solid caustic potash, previously dissolved in 4 parts of water. Evaporate to dryness, stirring diligently to prevent spirting. Pulverize the mass, put it into a covered Hessian or Cornish crucible, and expose it to a dull red heat (not higher) for an

hour (20 or 30 minutes for quantities of 1 or 2 ozs.), or till it has assumed the condition of a semifused mass. Allow to cool, pulverize, and boil with about 30 parts of water. Let the insoluble matter subside, decant the fluid, boil again with about 10 parts of water, again decant, neutralize the united liquors accurately with diluted sulphuric acid (or, better, carbonic acid gas), and evaporate till a pellicle forms. Set aside to cool and crystallize. Drain the crystalline mass, boil it in 6 parts of water, and strain through a funnel the throat of which is lightly obstructed by a little asbestos or gun-cotton. Let the fluid cool and crystallize, drain the dark purple slender prismatic crystals, and dry them by placing under a bell jar over a vessel containing sulphuric acid.

Instead of converting the manganate into permanganate by ebullition, by which one-third of the manganate is lost, Städelar recommends chlorine to be passed through the cold solution until the green color is entirely changed to purple.

Solutions of the manganates of potassium and sodium are in common use as disinfectants under the name of Condy's fluid. They act by oxidizing organic matter, the manganic or permanganic radical being reduced to black manganic oxide, or even a lower oxide. The reason for using asbestos instead of paper in filtering the solutions will now be understood.

The changes in color which the green mass of the above process undergoes when dropped into warm water procured for it the old name of *mineral chameleon.*

Third Reaction.—Make a borax bead by heating a fragment of the salt on the looped end of a platinum wire in the blowpipe-flame until a clear transparent globule is obtained. Place on the bead a minute portion of a manganese compound, or touch it with a drop of solution. Again fuse the borax; a bead of a violet or amethystine tint is produced.

This is a good analytical reaction. It has also synthetical interest, illustrating the use of black oxide of manganese in producing common purple-tinted glass.

Expose the bead to the reducing part of the flame, the part nearer to the blowpipe, where there are highly heated hydro-carbon gases greedy of oxygen; the color disappears.

This is owing to the reduction of the manganic compound to a manganous condition, in which it no longer possesses peculiar coloring-power. This action also illustrates the use of black oxide of manganese in glass-manufacture. Glass when first made is usually of a green tint, owing to the presence of ferrous impurities; the addition of manganic oxide to the materials converts the ferrous into ferric compounds, which have comparatively little colorific power, it itself being thereby reduced to manganous oxide, which also gives but little color. If excess of manganic oxide be added, a purple tint is produced.

Fourth Reaction.—Through a solution of a manganous salt acidified by hydrochloric acid pass sulphuretted hydrogen; no decomposition occurs. Add ammonia; the sulphydrate of ammonium thus formed causes the precipitation of a yellowish-pink or flesh-tinted precipitate of manganous sulphide (MnS) in a hydrous state.

This reaction is characteristic, sulphide of manganese being the only flesh-colored sulphide known. The salt used may be the manganous chloride obtained in the first reaction; but such crude solutions usually give a black precipitate with sulphydrate of ammonium, owing to the presence of iron. The latter element may be removed, however, on boiling the manganous solution with a little carbonate of sodium, which throws the ferric salt out of solution before the manganous. *Pure* manganous chloride may be similarly obtained on boiling the impure solution with manganous carbonate; the latter decomposes the ferric chloride with production of ferrric hydrate and more manganous chloride, and evolution of carbonic acid gas.

To the recently precipitated manganous sulphide add acetic acid; it is dissolved.

This solubility enables manganese to be separated from nickel, cobalt, and zinc, whose sulphides are insoluble in weak acetic acid. To express the fact in another way—manganese is not precipitated by sulphuretted hydrogen from a solution containing free acetic acid only.

Fifth Reaction.—To solution of manganous salt add ammonia drop by drop; a white precipitate of manganous hydrate (Mn2HO) falls. Add excess of ammonia; the precipitate is dissolved.

The fixed alkalies give a similar precipitate *insoluble* in excess. The precipitate rapidly absorbs oxygen, becomes brown, and gradually passes into a higher oxide.

Sixth Reaction.—Heat a little black oxide of manganese in a test-tube with sulphuric acid; oxygen is evolved and sulphate of manganese formed (*Manganesii Sulphas*, U. S. P.), add water, boil, filter, evaporate, and set aside to crystallize. Larger quantities are made in a similar manner.

Sulphate of manganese ($MnSO_4.5H_2O$) occurs in colorless, or pale rose-colored, transparent crystals, which, when deposited from a solution at a temperature between 68° and 86°, have the form of right rhombic prisms, and contain four molecules of water. This salt is very soluble in water. The solution is not colored by tincture of nutgall a black (a black shows iron), but affords with caustic alkalies a white precipitate (Mn2HO), which, by exposure to the air, soon absorbs oxygen, and becomes brown. Sulphydrate of ammonium throws down a flesh-colored precipitate (MnS), and ferrocyanide of potassium, a white one (Mn_2Fcy).

Many other reactions occur between manganese salts and various reagents, but are of no particular synthetical or analytical interest. A good method proposed by Crum, for detecting minute quantities of manganese, consists in adding dilute nitric acid and the puce-colored oxide or peroxide of lead to the solution, and then boiling; a red tint, due to permanganic acid, is imparted to the liquid.

COBALT.

Symbol Co. Atomic weight 58.8.

Source.—Cobalt occurs sparingly in nature as the arsenide ($CoAs_2$), or *tin-white cobalt*, and occasionally as a double arsenide and sulphide ($CoAs_2$, CoS_2), or *cobalt-glance* (from *glanz*, brightness, in allusion to its lustre).

Uses.—It chief use is in the manufactory of blue glass, the color of which is due to a compound of cobalt. Cobalt is also the coloring constituent of *smalt* (from *smelt*, a corruption of *melt*), a finely-ground sort of glass used as a blue pigment by paper-stainers and others, and employed also by laundresses to neutralize the yellowish appearance of washed linen.

The salts of cobalt may be obtained from the oxide (CoO), and the oxide from *zaffre*, a mixture of sand and roasted ore.

Quantivalence.—Cobalt often exhibits quadrivalent affinities, but still more often exerts only bivalent powers (Co″). It has analytical relations with zinc, nickel, and manganese, and may be regarded as a member of the iron group.

Analytical Reactions (Tests).

First Analytical Reaction.—Pass sulphuretted hydrogen through a solution of a salt of cobalt—the chloride ($CoCl_2$) or nitrate (Co2NO_3) for example; no decomposition occurs. Add ammonia; the sulphydrate of ammonium thus formed causes the precipitation of black sulphide of cobalt (CoS).

The moist precipitate slowly absorbs oxygen from the air, becoming converted into sulphate of cobalt ($CoSO_4$).

Second Analytical Reaction.—Add ammonia gradually to a cobalt solution; a blue precipitate of impure hydrate of cobalt (Co2HO) falls. Add excess of ammonia; the precipitate is dissolved.

A similar precipitate is given by the fixed alkalies, *insoluble* in excess.

Third Analytical Reaction.—Make a borax bead by heating a fragment of the salt on the looped end of a platinum wire in a blowpipe-flame until a clear transparent globule

is obtained. Place on the bead a minute portion of cobalt compound, or touch it with a drop of solution. Again fuse the borax; a blue bead results.

This is a delicate test for cobalt. From what has previously been said, it will be seen that this experiment has also considerable synthetical interest.

Fourth Analytical Reaction.—To a solution of a salt of cobalt add two or three drops of hydrochloric acid, then excess of solution of cyanide of potassium, and boil for ten minutes; oxygen is absorbed, and cobalticyanide of potassium ($K_6Co_2Cy_{12}$) formed. Add hydrochloric acid, and boil the mixture (in a fume-cupboard, to avoid inhalation of any hydrocyanic acid); the excess of cyanide of potassium is thus decomposed, but the cobalticyanide is unaffected. Now add excess of solution of potash; the cobalticyanide of potassium is decomposed, the hydrate of cobalt formed remaining dissolved in the alkaline liquid.

Nickel under similar circumstances is precipitated, the reaction thus affording means of separating these closely allied metals from each other.

Other reactions between a cobalt solution and different reagents may be performed, and various precipitates obtained; but these have no special analytical interest.

Invisible Ink.—The salts of cobalt containing water of crystallization are light red, the anhydrous more or less blue. Prove this by writing some words on paper with a solution of chloride of cobalt sufficiently dilute for the characters to be invisible when dry; hold the sheet before a fire or over a flame; the letters at once become visible, distinct and of a blue color. Breathe on the words, or set the sheet aside for a while; the characters are once more invisible, owing to absorption of moisture. Hence solution of chloride of cobalt forms one of the so-called *sympathetic inks*.

NICKEL.

Symbol Ni. Atomic weight 58.8.

Nickel is, chemically, closely allied to cobalt, the ores of the two metals being commonly associated in nature. Indeed it is from *speiss*, an arsenio-sulphide of nickel obtained in the manufacture of smalt, a pigment of cobalt already mentioned, that most of the nickel met with in commerce is obtained. It is much used in the preparation of the white alloy known as German or nickel silver.

Quantivalence.—Nickel exerts bivalent activity (Ni″) in its ordinary compounds. Its salts and their solutions are usually green. They are chiefly made, directly or indirectly, from the metal itself.

Analytical Reactions (Tests).

First Analytical Reaction.—Pass sulphuretted hydrogen through a solution of a salt of nickel—chloride ($NiCl_2$), nitrate ($Ni2NO_3$), or sulphate ($NiSO_4$); no decomposition occurs. Add ammonia; the sulphydrate of ammonium thus formed causes the precipitation of black sulphide of nickel (NiS).

Note.—When sulphide of nickel is precipitated by the direct addition of the common yellow solution of sulphydrate of ammonium, which always contains sulphur, there is much difficulty in filtering the mixture, owing to the slight solubility of the sulphide of nickel in the reagent and the formation of some sulphate of nickel ($NiSO_4$), oxygen being absorbed from the air by the sulphide. This may be avoided by warming the mixture and using freshly-made sulphydrate of ammonium, in which the sulphide of nickel is insoluble; or, where practicable, the salt of nickel may be precipitated from an ammoniacal solution by sulphuretted hydrogen.

Second Analytical Reaction.—Add ammonia drop by drop to a nickel solution; a pale-green precipitate of hydrate of nickel (Ni2HO) falls. Add excess of ammonia; the precipitate dissolves.

A similar precipitate is given by the fixed alkalies, *insoluble* in excess.

Third Analytical Reaction.—Nickel salts color a borax bead, when hot, a reddish-yellow tint; the reaction is not very serviceable analytically.

Fourth Analytical Reaction.—To a solution of a salt of nickel add solution of cyanide of potassium; cyanide of nickel ($NiCy_2$) is precipitated. Add excess of solution of cyanide of potassium; the precipitate is dissolved with formation of double cyanide of nickel and potassium ($NiCy_2$,2KCy). Next add hydrochloric acid, and boil the mixture (in a fume-cupboard), adding a little hydrochloric acid from time to time until all smell of hydrocyanic acid has disappeared. Lastly, add excess of solution of potash; hydrate of nickel is precipitated.

This reaction serves for the separation of nickel from cobalt. On adding excess of hydrochloric acid to a solution containing the two metals, together with cyanide of potassium, a precipitate of cyanide of nickel and cobalticyanide of nickel occurs. By ebullition with excess of hydrochloric acid the cyanide of nickel is decomposed,

chloride of nickel going into solution. On then adding excess of potash hydrate of nickel is precipitated. The cobalticyanide of nickel is not decomposed by the acid; but it is by the alkali, its cobalt going into solution and its nickel remaining insoluble as hydrate.

After filtering off the nickel, cobalt is detected in the filtrate by evaporating to dryness and testing the residue with borax in the blowpipe-flame.

Other reactions between a nickel solution and various reagents give, in many cases, insoluble precipitates which, from their green color, are occasionally useful in distinguishing nickel from allied elements.

CHROMIUM.

Symbol Cr. Atomic weight 52.5.

Source.—The chief ore of chromium is chrome ironstone, a mixture of the oxides of the metals (FeO, Cr_2O_3), occurring chiefly in the United States and Sweden. In constitution it seems to resemble magnetic iron ore (FeO, Fe_2O_3).

Preparation of Red Chromate of Potassium.—On roasting the powdered ore with carbonate of potassium and nitre, yellow chromate of potassium (K_2CrO_4) is obtained; the mass, treated with acid, yields red or bichromate (K_2CrO_4, CrO_3) (*Potassii Bichromas*, U. S. P.); from this salt other chromates are prepared, and by reduction, as presently explained, the salts of chromium itself. The yellow and orange chromates of lead are largely used as pigments.

Note on Constitution.—Red chromate of potassium is a somewhat abnormal salt, containing, probably, neutral chromate associated with chromic anhydride. The value of chromates as chemical reagents is alluded to in connection with chromate of barium (p. 88). Heated strongly in a crucible, red chromate of potassium splits up into yellow chromate, glistening oxide of chromium, and oxygen.

Quantivalence.—Chromium stands in close chemical relation to iron, aluminium, and manganese. Its atom is sexivalent if the formula of the fluoride (CrF_6) be correct. Like iron and aluminium, it is trivalent, as seen in chromic chloride (Cr_2Cl_6), but sometimes exerts only bivalent activity, as in chromous chloride ($CrCl_2$).

Passage of Chromium from the Acidulous to the Basylous Side of Salts.—Through an acidified solution of red chromate of potassium pass sulphuretted hydrogen; sulphur is deposited, and a green salt of chromium remains in solution—chloride (Cr_2Cl_6) if hydrochloric acid be used, and sulphate ($Cr_2 3SO_4$) if sulphuric be the acid employed. Boil the liquid to expel excess of sulphuretted hydrogen, filter, and reserve the solution for subsequent experiments.

Alcohol, sugar, or almost any substance which is tolerably liable to oxidation, will answer as well as sulphuretted hydrogen.

Sulphate of chromium ($Cr_2 3SO_4$), like sulphate of aluminium ($Al_2 3SO_4$), unites with alkaline sulphates to form *alums*, which resemble common alum both in crystalline form and, as far as we know, in internal structure: they are of a purple color.

Reactions.

Chromium as *Chromic Acid*, or other *Chromate*.—This is the state in which chromium will usually be met with, the most common salt being the red chromate or bichromate of potassium. Mix four volumes of a cold, saturated aqueous solution of red chromate of potassium with five of oil of vitriol; on cooling, *chromic anhydride* (CrO_3), *Acidum Chromicum*, U. S. P., separates in crimson needles. After well draining, the crystals may be freed from adhering sulphuric acid by washing once or twice with nitric acid: the latter may be removed by passing dried and slightly warmed air through a tube containing the crystals. In contact with moisture chromic anhydride takes up water and forms solution of true chromic acid (H_2CrO_4). Chromic anhydride is a powerfully corrosive oxidizing agent. It melts between 356° and 374°.

The oxygen in chromic acid and other chromates, and in manganates, permanganates, black oxide of manganese and puce colored oxide of lead is in a physically different state to that in peroxide of hydrogen, peroxide of barium, and similar compounds. On bringing chromic acid or the above acidified solution of red chromate of potassium into contact with solution of peroxide of hydrogen, a strong effervescence of oxygen ensues. According to Schönbein and Brodie the oxygen of chromic acid is in the negative or ozonic state, while that of peroxide of hydrogen is in the positive or antozonic condition. Both are equally active, but neutralize each other, forming neutral or ordinary oxygen.

In the analytical examination of solutions containing chromates, the chromium will always come out in the state of green chromic hydrate along with ferric hydrate and alumina, the prior treatment by sulphuretted hydrogen reducing the molecule to the lower state, thus:—

$$K_2CrO_4, CrO_3 + 8HCl + 3H_2S = Cr_2Cl_6 + 2KCl + 7H_2O + S_3.$$

Chromium having been found in a solution, its condition as chromate may be ascertained by applying to the original solution salts of barium, mercury, lead, and silver. (See the various paragraphs relating to those metals.)

$Ba2NO_3$	gives yellow	$BaCrO_4$	with chromates.
Hg_22NO_3	"	red	Hg_2CrO_4	"
$AgNO_3$	"	"	Ag_2CrO_4	"
"	"	"	Ag_2CrO_4,CrO_3	with bichromates.
$Pb2C_2H_3O_2$	"	yellow	$PbCrO_4$	with both.

Nitrate of barium does not completely precipitate bichromates, bichromate of barium being soluble in water; the chromate of barium is insoluble in water or acetic acid, but soluble in hydrochloric or nitric acid. Mercurous nitrate does not wholly precipitate bichromates: mercuric nitrate or chloride only partially precipitates chromates, and does not precipitate bichromates. The mercurous chromate is insoluble, or nearly so, in diluted nitric acid. Acetate of lead precipitates chromates and bichromates, acetic acid being set free in the latter case. The silver chromates are soluble in acids and alkalies.

A delicate reaction for dry chromates will be found in the formation of *chlorochromic anhydride* (CrO_2Cl_2). A small portion of the chromate is placed in a test-tube with a fragment of dry chloride of sodium and a drop or two of oil of vitriol, and the mixture heated; red irritating fumes of chlorochromic *anhydride* are evolved, and condense in dark red drops on the side of the tube.

Large quantities of pure distilled chlorochromic anhydride are obtained by the same reaction, the operation being conducted in a retort, with thoroughly dry materials, for the compound is decomposed by water. It may be regarded as chromic anhydride in which an atom of oxygen is displaced by an equivalent quantity (two atoms) of chlorine. It is not used in medicine, but is of interest to the chemical student as being an illustration of a large class of similar bodies—*chloro-acidulous* or *chloro-anhydro compounds.*

Analytical Reactions of Chromium Salts (Tests).

First Analytical Reaction.—To solution of a salt of chromium (chloride, sulphate, or chrome alum) add sulphydrate of ammonium; a bulky green precipitate of chromic hydrate (Cr_26HO), containing a large quantity of water (7 molecules, $7H_2O$), is precipitated.

$$Cr_2Cl_6 + 6AmHS + 6H_2O = Cr_26HO + 6AmCl + 6H_2S.$$

Second Analytical Reaction.—To solution of a chromium salt add ammonia; chromic hydrate is precipitated, insoluble in excess.

Third Analytical Reaction.—To solution of a chromium salt add solution of potash or soda drop by drop; chromic hydrate is precipitated. Add excess of the fixed alkali;

the precipitate is dissolved. Well boil the solution; the chromic hydrate is reprecipitated.

Iron, Chromium, and Aluminium Salts, chemically so alike, may be separated by this reaction. Ferric hydrate is insoluble in solutions of the fixed alkalies, cold or hot; chromium hydrate soluble in cold but not in hot; hydrate of aluminium in both. To a solution containing all three metals, therefore, add potash or soda, stir, and filter; the iron is thrown out: boil the filtrate, and filter: the chromium is thrown out: neutralize the filtrate by acid, and then add ammonia; the aluminium is thrown out. The three hydrates are insoluble in ammonia, and may therefore be easily separated from the hydrates of the somewhat analogous metals zinc, cobalt, nickel, and manganese.

Fourth Analytical Reaction.—Add a salt of chromium (either of the above precipitates of chromic oxide or the dry residue of the evaporation of a few drops of a solution of a chromium salt) to a few grains of nitre and carbonate of sodium on platinum foil, and fuse the mixture in the blowpipe-flame; a yellow mass of chromate of potassium and sodium ($KNaCrO_4$) is formed. Dissolve the mass in water, add acetic acid to decompose excess of carbonate, and apply the reagents for chromates.

This is a delicate and useful reaction if carefully performed.

TIN.

Symbol Sn. Atomic weight 118.

Source.—The chief ore of tin is stannic oxide (SnO_2), occurring in veins under the name of *tinstone*, or in alluvial deposits as *stream-tin*. The principal mines are those of Cornwall.

Preparation.—The metal is obtained by reducing the roasted and washed ore by charcoal or anthracite* coal at a high temperature, and is purified by slowly heating, when the pure tin, fusing first, is run off, a somewhat less fusible alloy of tin with small quantities of arsenicum, copper, iron, or lead remaining. The latter is known as *block tin;* the former heated till brittle and then hammered or let fall from a height splits into prismatic fragments resembling starch or basalt, and is named *dropped* or *grain tin*. Good tin emits a crackling noise in bending, termed the cry of tin, caused by the friction of its crystalline particles on each other.

Uses.—Tin is an important constituent of such alloys as pewter, Britannia metal, solder, speculum-metal, bell-metal, gun-metal, and

* *Anthracite* (from ἄνθραξ, *anthrax*, a burning coal) or *stone coal* differs from the ordinary *bituminous* or *caking coal*, in containing less volatile matter, and, therefore, in burning without flame. It gives a higher temperature, and from its non-caking properties is, in furnace operations, more manageable than bituminous coal.

bronze. It is very ductile, and may be rolled into plates or leaves, known as *tin foil*, varying from $\frac{1}{250}$ to $\frac{1}{1000}$ of an inch in thickness. Common tin foil, however, usually contains a large proportion of lead. The reflecting surface of most *looking-glasses* is an amalgam of tin and mercury, produced by carefully sliding a plate of glass over a sheet of tin foil on which mercury has been rubbed, and then excess of mercury poured. *Pins* are made of brass wire on which tin is deposited. *Tin plate*, of which common utensils are made, is iron alloyed with tin by dipping the cleansed sheet into melted tin. *Tin tacks* are in reality tinned iron tacks; a tin nail would be too soft to drive into wood. Tin may be granulated by melting and triturating briskly in a hot mortar, by shaking melted tin in a box on the inner sides of which chalk has been rubbed, or, in thin little bells or corrugated fragments (Granulated Tin, B. P.), by melting in a ladle and, as soon as fluid, pouring from the height of a few feet into water.

The chemical position of tin among the metals is close to that of arsenicum and antimony. Its atom is quadrivalent and bivalent. The two classes of salts are termed stannic and stannous respectively. They are all made directly or indirectly from the metal itself.

Reactions having (*a*) Synthetical and (*b*) Analytical Interest.

(*a*) *Synthetical Reactions.*

Chloride of Tin. Stannous Chloride.

First Synthetical Reaction.—Warm a fragment of tin with hydrochloric acid; hydrogen escapes and solution of stannous chloride ($SnCl_2$) is formed. It may be retained for future experiments.

One ounce of tin dissolved in three fluidounces of hydrochloric acid and one of water, and the resulting solution diluted to five fluidounces, constitutes the "Solution of Chloride of Tin," B. P.

Solid stannous chloride.—By evaporation of the above solution stannous chloride is obtainable in crystals ($SnCl_2 2H_2O$). It is a powerful reducing agent, even a dilute solution precipitating gold, silver, and mercury from their solutions, converting ferric and cupric into ferrous and cuprous salts, and partially deoxidizing arsenic, manganic, and chromic acids. It absorbs oxygen from the air, and is decomposed when added to a large quantity of water unless some acid be present. It is used as a mordant in dyeing and calico-printing.

Perchloride of Tin. Stannic Chloride.

Second Synthetical Reaction.—Through a portion of the solution of the stannous chloride of the previous reaction pass chlorine gas; solution of stannic chloride ($SnCl_4$) is formed. Or add hydrochloric acid to the stannous solution, boil, and slowly drop in nitric acid until no more

fumes are evolved; again stannic chloride results. Reserve the solutions for subsequent experiments.

Stannic Oxide, or Anhydride, and Stannates.

Third Synthetical Reaction.—Boil a fragment of tin with nitric acid, evaporate to dryness, and strongly calcine the residue; white stannic anhydride (SnO_2) is produced. Heat the stannic anhydride with excess of solid caustic potash or soda; stannate of the alkali metal (K_2SnO_3 or Na_2SnO_3) results. Dissolve the stannate in water, and add hydrochloric acid; white, gelatinous *stannic acid* (H_2SnO_3) is precipitated. Stannic acid is also obtained on adding an alkali to solution of stannic chloride; it is soluble in excess of acid or alkali.

The product of the action of nitric acid on tin is also an acid, but from its insolubility in hydrochloric and other acids, is different from ordinary stannic acid. It is termed *metastannic acid* (from μετά, *meta*, beyond), and probably has a composition expressed by the formula $H_{10}Sn_5O_{15}$. It is also produced on gently heating stannic acid:—

$$\underset{\text{Stannic acid.}}{5H_2SnO_3} = \underset{\text{Metastannic acid.}}{H_{10}Sn_5O_{15}}$$

Metastannates may be formed; their general formula is $M_2H_8Sn_5O_{15}$. Both acids yield buff-colored stannic oxide or anhydride (SnO_2) when strongly heated; it is employed in polishing plate under the name of *putty powder*. *Stannate of sodium* ($Na_2SnO_3,4H_2O$) is used as a mordant by dyers and calico-printers under the name of *tin preparе liquor*.

(*b*) *Reactions having Analytical Interest* (*Tests*).

STANNOUS SALTS.

First Analytical Reaction.—Through a solution of a stannous salt (stannous chloride, for example, see previous page) pass sulphuretted hydrogen; brown stannous sulphide (SnS) is precipitated. Pour off the supernatant liquid, add ammonia to the moist precipitate (to neutralize acid), and lastly yellow sulphydrate of ammonium; the precipitate is dissolved.

Aqueous solution of sulphydrate of ammonium becomes yellow when a day or two old, and then contains excess of sulphur, that element having become displaced by oxygen absorbed from the air; hence, in the above reaction, the stannous sulphide (SnS), in dissolving, becomes stannic sulphide (SnS_2); for the latter is precipitated on decomposing the alkaline liquid by an acid.

Second Analytical Reaction.—To solution of a stannous salt add solution of potash or soda; white stannous hydrate falls (Sn2HO). Add excess of the alkali; the precipitate dissolves. Boil the solution; some of the tin is reprecipitated as black stannous oxide (SnO).

Ammonia gives a similar precipitate, insoluble in excess. The alkaline carbonates do the same, carbonic acid gas escaping.

STANNIC SALTS.

Third Analytical Reaction.—Through solution of a stannic salt (stannic chloride, for example, see page 214) pass sulphuretted hydrogen gas; yellow stannic sulphide (SnS_2) is precipitated. Pour off the supernatant liquid, and to the moist precipitate add ammonia (to neutralize acid), and then sulphydrate of ammonium; the precipitate dissolves.

Note.—In precipitating stannic sulphide the presence of too much hydrochloric acid must be avoided; the formation of the precipitate is also facilitated if the solution be warmed. Stannic sulphide, like the sulphide of arsenicum and antimony, dissolves in a solution of alkaline sulphide, with formation of definite crystallizable salts.

Anhydrous stannic sulphide, prepared by sublimation, has a yellow or orange lustrous appearance, and is used by decorators as *bronzing-powder*. It is sometimes termed *mosaic gold.*

Fourth Analytical Reaction.—To solution of a stannic salt add potash or soda; white stannic acid falls (H_2SnO_3). Add excess of the alkali; the precipitate dissolves. Boil the precipitate; no reprecipitation occurs—a fact enabling stannic to be distinguished from stannous salts.

Ammonia gives a similar precipitate, soluble, but not readily, in excess. The fixed-alkaline carbonates do the same, carbonic acid gas escaping; after a time the stannic salt is again deposited, probably as stannate of the alkali metal. Carbonate of ammonium and acid carbonates of alkali metals give a precipitate of stannic acid insoluble in excess.

Antidotes.—In cases of poisoning by tin salts (dyer's tin liquor *e. g.*), solution of carbonate of ammonium should be given. White of egg is also said to form an insoluble precipitate with compounds of tin. Vomiting should be speedily induced, and the stomach pump quickly supplied.

GOLD.

Symbol Au. Atomic weight 196.7.

Source.—Gold occurs in the free state in nature, occasionally in nodules or *nuggets*, but commonly in a finer state of division termed *gold dust.*

Preparation.—Gold is separated from the sand, crushed quartz, or other earthy matter with which it may be associated, by agitation with water, when the gold, from its relatively greater specific gravity, falls to the bottom of the vessels first, the lighter mineral matter being allowed to run off with the water. From this rich sand the gold is dissolved out by mercury, the latter filtered, and the amalgam distilled, when the mercury volatilizes and gold remains. The amalgamation may be much facilitated by the use of a small proportion of sodium, as described under silver.

Pure gold is too soft for general use as a circulating medium. *Gold coin* is an alloy of copper and gold, that of Great Britain containing 1 of the former to 11 of the latter, or $8\frac{1}{3}$ per cent. of copper, that of France, Germany, and the United States about 10 per cent. *Jewellers' gold* varies in quality, every 24 parts containing 18, 15, 12, or 9 parts of gold, the alloys being technically termed 18, 15, 12, or 9 *carat fine.* Articles made of the better qualities are usually stamped by authority. Trinkets of inferior intrinsic worth are commonly thinly coated with pure gold by electro-deposition or otherwise. *Gold leaf* is nearly pure gold passed between rollers till it is about $\frac{1}{5000}$ of an inch in thickness and then hammered between sheets of animal membrane, termed gold-beater's skin and calf-skin vellum, till it is $\frac{1}{150000}$ or $\frac{1}{200000}$ of an inch in thickness. It may even be hammered till 280,000 leaves would be required to form a pile an inch thick.

Gold Coinage.—The weight of gold is expressed in Great Britain in ounces troy and decimal parts of an ounce, and the metal is always taken to be of standard fineness (11 gold and 1 alloy) unless otherwise described. The degree of fineness of gold, as ascertained by assay, is expressed decimally, fine pure gold ("gold free from metallic impurities," B. P.), being taken as unity, or 1.000. Thus gold of British standard is said to be 0.9166 fine, of French standard 0.900 fine. The legal weight of the sovereign is 0.2568 ounce of standard gold, or 123.274 grains. The weight came from one pound of standard gold (5760 grains) being coined into $44\frac{1}{2}$ guineas. Gold coins are legal tender to any amount, provided that the weight of each sovereign does not fall below 122.5 grains, or in the case of a half sovereign 61.125 grains; these are the "least current" weights of the coins.

Note.—In chemical analysis gold comes out among the sulphides of the metals precipitated by sulphuretted hydrogen; and of those sulphides, it, like the sulphides of tin, antimony, and arsenicum, is soluble in sulphydrate of ammonium.

Quantivalence.—Gold is trivalent (Au‴), but in some compounds univalent (Au′).

Reactions.

Synthetical Reaction.—Place a fragment of gold (*e. g.*, gold leaf) in ten or twenty drops of aqua regia (a mixture of one part of nitric and two or three of hydrochloric acid), and set the test-tube aside in a warm place; solution of perchloride of gold or auric chloride ($AuCl_3$) results.

When the metal is dissolved, evaporate nearly to dryness to remove most of the excess of fluid, dilute with water, and retain the solution for subsequent experiments. Sixty grains of gold treated thus, and the resulting chloride dissolved in five ounces of distilled water, constitutes "Solution of Chloride of Gold," B. P.

$$Au_2 + 2HNO_3 + 6HCl = 2AuCl_3 + 2NO + 4H_2O$$

This reaction has analytical interest also; for in examining a substance suspected to be or contain metallic gold, solution would have to be effected in the above way before reagents could be applied. Gold is insoluble in hydrochloric, nitric, and the weaker acids.

Analytical Reactions (*Tests*).

First Analytical Reaction.—Through a few drops of solution of an auric salt (the chloride, $AuCl_3$, is the only convenient one) pass sulphuretted hydrogen; brown auric sulphide (Au_2S_3) is precipitated. Filter, wash, and add sulphydrate of ammonium; the precipitate dissolves.

Second Analytical Reaction.—To solution of a salt of gold add ferrous chloride or sulphate, and set the tube aside; metallic gold is precipitated, a ferric salt remaining in solution.

This is a convenient way of preparing pure gold, or *fine gold* as it is termed, or of working up the gold residues of laboratory operations. The precipitate, after boiling with hydrochloric acid, washing, and drying, may be obtained in a button by mixing with an equal weight of borax or acid sulphate of potassium and fusing in a good furnace.

Third Analytical Reaction.—Add a few drops of dilute solutions of stannous and stannic chloride to a considerable quantity of distilled water; pour the liquid, a small quantity at a time, into a dilute solution of auric chloride ($AuCl_3$), well stirring; the mixture assumes a purple tint, and flocks of a precipitate, known as the *Purple of Cassius*, (from the name of the discoverer, M. Cassius), are produced.

The same compound is formed on immersing a piece of tin foil in solution of auric chloride; it is said to be a mixture of auric, aurous, stannic, and stannous oxides. It is the coloring agent in the finer varieties of ruby glass.

PLATINUM.

Symbol Pt. Atomic weight 198.

Source.—Platinum, like gold, usually occurs in nature in the free state, the chief sources of supply being Mexico, Brazil, and Siberia. It is separated from the alluvial soil by washing.

Uses.—The chief use of platinum is in the construction of foil, wire, crucibles, spatulas, capsules, evaporating-dishes, and stills, for the use of the chemical analyst or manufacturer. It is tolerably hard, fusible with very great difficulty, not dissolved by hydrochloric, nitric, or sulphuric acid, and only slightly affected by alkaline substances. It is attacked by aqua regia with production of perchloride of platinum or platinic chloride ($PtCl_4$). It forms fusible alloys with lead and other metals, and with phosphorus a phosphide, which easily melts. Neither of these substances, therefore, nor mixtures which may yield a metal, should be heated in platinum vessels.

The chemical position of platinum among the elements is close to that of gold. Its atom is quadrivalent in some compounds, in others apparently bivalent (Pt''). The higher salts are termed *platinic*, the lower *platinous*.

Reactions.

Perchloride of Platinum. Platinic Chloride.

Synthetical Reaction.—Place a fragment of platinum in a little aqua regia and set the vessel aside in a warm place, adding more acid from time to time if necessary; solution of perchloride of platinum ($PtCl_4$) results. Evaporate the solution to remove excess of acid, and complete the desiccation over a water-bath. Dissolve the residue in water and retain the solution for subsequent experiments, and as a reagent for the precipitation of salts of potassium and ammonium.

A quarter of an ounce of platinum treated in the above manner, and the resulting chloride dissolved in five ounces of water, constitutes "Solution of Perchloride of Platinum," B. P.

This reaction has analytical interest also; for in examining a substance suspected to be or to contain metallic platinum, solution would have to be thus effected before reagents could be applied.

Analytical Reactions (Tests).

First Analytical Reaction.—Through a few drops of a solution of a platinic salt ($PtCl_4$ is the only convenient one) to which an equal quantity of solution of chloride of sodium has been added, pass sulphuretted hydrogen; dark brown

platinic sulphide (PtS_2) is precipitated. Filter, wash, and add sulphydrate of ammonium; the precipitate dissolves.

If chloride of sodium be not present in the above reaction, the precipitated sulphide will contain platinous chloride, and detonate when heated.

Second Analytical Reaction.—Add excess of solution of carbonate of sodium and some sugar to solution of perchloride of platinum and boil; a precipitate of metallic platinum falls.

Platinum Black (B. P.) is the name of this precipitate. It possesses in a high degree a quality common to many substances, but largely possessed by platinum, namely, that of absorbing or occluding gases. In its ordinary state, after well washing and drying, it absorbs from the air and retains many times its bulk of oxygen. A drop of ether or alcohol placed on it is rapidly oxidized, the platinum becoming hot. This action may be prettily shown by pouring a few drops of ether into a beaker (one having portions of the top and sides broken off answers best), loosely covering the vessel with a card, and suspending within the beaker a platinum wire, one end being attached to the card by passing through its centre, the other terminating in a short coil or helix near the surface of the ether; on now warming the helix in a flame and then rapidly introducing it into the beaker, it will become red-hot and continue to glow so long as there is ether in the vessel. In this experiment real combustion goes on between the ether vapor and the concentrated oxygen of the air, the products of the oxidation revealing themselves by their odor.

Third Analytical Reaction.—To solution of perchloride of platinum add solution of chloride of ammonium; a yellow granular precipitate of double chloride of platinum and ammonium ($PtCl_4$, 2AmCl) falls. When slowly formed in dilute solutions, the precipitate is obtained in minute orange prisms.

Chloride of potassium (KCl) gives a similar precipitate ($PtCl_4$ 2KCl). Platinic chloride having been stated to be a test for potassium and ammonium salts, the reader is prepared to find that potassium and ammonium salts are tests for platinic salts. The double sodium compound ($PtCl_4 2NaCl$) is soluble in water.

Collect the precipitate, dry, and heat in a small crucible; it is decomposed, and metal, in the finely divided state of *spongy platinum*, remains.

$$3(PtCl_4 2NH_4Cl) = Pt_3 + 2NH_4Cl + 16HCl + 2N_2.$$

Heat decomposes the potassium salt into $Pt + 2KCl + Cl_4$, the chlorine escaping and the chloride of potassium remaining with the platinum.

In working up the platinum residues of laboratory operations, the mixture should be dried, burnt, boiled successively with hydrochloric acid, water, nitric acid, water, then dissolved in aqua regia, excess of acid removed by evaporation, chloride of ammonium added, the precipitate washed with water, dried, ignited, and the resulting spongy platinum retained or converted into perchloride for use as a reagent for alkali-metals. It is by this process that the native platinum is treated to free it from the rare metals palladium, rhodium, osmium, ruthenium, and iridium. The spongy platinum is converted into the massive condition by a refinement on the blacksmith's process of *welding* (German *wellen*, to join), or by fusing in a flame of pure oxygen and hydrogen gases—the oxyhydrogen blowpipe.

Occlusion by Spongy Platinum.—Spongy platinum has great power of occlusion. A small piece held in a jet of hydrogen causes ignition of the gas, owing to the close approximation of particles of oxygen (from the air) and hydrogen. Dobereiner's lamp is constructed on this principle—the apparatus being essentially a vessel in which hydrogen is generated by the action of diluted sulphuric acid on zinc, and a cage for holding the spongy platinum.

CADMIUM.

Symbol Cd. Atomic weight 112.

In most of its chemical relations cadmium (*Cadmium*, U. S. P.) resembles zinc. In nature it occurs chiefly as an occasional constituent of the ores of that metal. In distilling zinc containing cadmium, the latter, being the more volatile, passes over first. In analytical operations cadmium, unlike zinc, comes down among the metals precipitated by sulphuretted hydrogen; that is, its sulphide is insoluble in dilute hydrochloric acid, while sulphide of zinc is soluble. It is a white malleable metal nearly as volatile as mercury. Sp. gr. 8.7.

Beyond the occasional employment of the sulphide as a pigment (*jaune brillant*), and the iodide in photography and medicine, cadmium and its salts are but little used. The atom of cadmium is bivalent (Cd″).

Reactions.

Iodide of Cadmium.

First Synthetical Reaction.—Digest metallic cadmium in water in which a fragment of iodine is placed, until the color of the iodine disappears; solution of iodide of cadmium (*Cadmii Iodidum*, B. P.) (CdI_2) remains. Pearly micaceous crystals may be obtained on evaporating the solution.

This is the process alluded to in the British Pharmacopœia. The compound is used in medicine in the form of ointment, *Unguentum Cadmii Iodidi*, B. P. The salt is also employed, with other iodides,

in iodizing collodion for photographic purposes. It melts when heated, and is soluble in water or spirit, the solution reddening litmus paper.

Sulphate of Cadmium.

Second Synthetical Reaction.—Dissolve cadmium in nitric acid; pour the resulting solution of nitrate of cadmium ($Cd2NO_3$) into a solution of carbonate of sodium; dissolve the precipitate of carbonate of cadmium ($CdCO_3$) in dilute sulphuric acid, separate and crystallize. Sulphate of cadmium ($CdSO_4$) is a white crystalline salt soluble in water, (U. S. P.).

First Analytical Reaction.—Through solution of a cadmium salt (CdI_2 or $CdCl_2$) pass sulphuretted hydrogen; a yellow precipitate of sulphide of cadmium (CdS) falls, resembling in appearance arsenious, arsenic, and stannic sulphides. Add sulphydrate of ammonium; the precipitate, unlike the sulphides just mentioned, does not dissolve.

Sulphides of cadmium and copper may be separated by solution of cyanide of potassium, in which sulphide of copper is soluble and sulphide of cadmium insoluble.

Second Analytical Reaction.—To a cadmium solution add solution of potash; white hydrate of cadmium (Cd2HO) is precipitated, insoluble in excess of the potash.

Hydrate of zinc (Zn2HO), precipitated under similar circumstances, is soluble in solution of potash; the filtrate from the hydrate of cadmium may therefore be tested for any zinc occurring as an impurity by applying the appropriate reagent—sulphydrate of ammonium.

Before the blowpipe-flame, on charcoal, cadmium salts give a brown deposit of oxide of cadmium (CdO).

BISMUTH.

Symbol Bi. Atomic weight 208.

Source.—Bismuth occurs in the metallic state in nature. It is freed from adherent quartz, etc., by simply heating, when the metal melts, runs off, and is collected in appropriate vessels. It is also met with in combination with other elements. Bismuth is grayish-white, with a distinct pinkish tinge.

Uses.—Beyond the employment of some of its compounds in medicine, bismuth is but little used. Melted bismuth expands considerably on solidifying, and hence is valuable in taking sharp impressions of dies. It is a constituent of some kinds of type-metal and of pewter-solder.

The position of bismuth among the metals is close to that of arsenicum and antimony. Its atom is rarely quinquivalent (Bi^{v}); but in most compounds trivalent (Bi''').

Reactions having (*a*) Synthetical and (*b*) Analytical Interest.

(*a*) *Reactions having Synthetical Interest.*

Nitrate of Bismuth.

First Synthetical Reaction.—To a few drops of nitric acid and an equal quantity of water in a test-tube, add a little powdered bismuth, heating the mixture if necessary; nitric oxide (NO) escapes, and solution of *nitrate of bismuth* ($Bi3NO_3$) results.

$$\underset{\text{Bismuth.}}{Bi_2} + \underset{\text{Nitric acid.}}{8HNO_3} = \underset{\text{Nitrate of bismuth.}}{2(Bi3NO_3)} + \underset{\text{Nitric oxide.}}{2NO} + \underset{\text{Water.}}{4H_2O}$$

The solution evaporated gives crystals ($Bi3NO_3$, $5H_2O$), any arsenicum which the bismuth might contain remaining in the mother-liquor. Native bismuth (*Bismuthum*, B. P. and U. S. P.) commonly contains arsenicum, most of which is removed by roasting or by fusing two or three times with a tenth of its weight of nitre (*Bismuthum Purificatum*, B. P.), or, finally, by converting the metal into oxynitrate, as described in the next reaction, and reducing this with charcoal at a high temperature.

To make *nitrate* of bismuth and other salts on a larger scale, 2 ounces of the metal, in small fragments, are gradually added to a mixture of 4 fluidounces of nitric acid and 3 of water, and, when effervescence (due to escape of nitric oxide) has ceased, the mixture heated for ten minutes, poured off from any insoluble matter, evaporated to 2 fluidounces to remove excess of acid, and then either set aside for *crystals* to form, poured into half a gallon of water to form the *oxynitrate* of bismuth, or into a solution of 6 ounces of carbonate of ammonium in a quart of water to form the *oxycarbonate* as described in the following reactions. The precipitates should be washed with cold water and dried at a temperature not exceeding 150° F. Exposed in the moist state to 212° for any length of time, they undergo slight decomposition.

Subnitrate or Oxynitrate of Bismuth.

Second Synthetical Reaction.—Pour some of the above solution into a considerable quantity of water; decomposition occurs and oxynitrate of bismuth ($BiONO_3$) in a hydrous state ($BiONO_3$, H_2O) (*Bismuthi Subnitras*, B. P.) is precipitated:—

$$\underset{\text{Nitrate of bismuth.}}{Bi3NO_3} + \underset{\text{Water.}}{H_2O} = \underset{\text{Oxynitrate of bismuth.}}{BiONO_3} + \underset{\text{Nitric acid.}}{2HNO_3}$$

Filter, and test the filtrate for bismuth by adding excess of carbonate of sodium; a precipitate shows that some bismuth remains in solution. The following equation, therefore, probably more nearly represents the decomposition:—

$$\underset{\text{Nitrate of bismuth.}}{5(Bi3NO_3)} + \underset{\text{Water.}}{8H_2O} = \underset{\text{Oxynitrate of bismuth.}}{4(BiONO_3, H_2O)} + \underset{\text{Nitrate of bismuth in acid.}}{Bi3NO_3, 8HNO_3}$$

Decomposition of nitrate of bismuth by water is the process of the British Pharmacopœia for the preparation of oxynitrate or "subnitrate" of bismuth for use in medicine. For this purpose the original metal must contain no arsenicum. In manufacturing the compound, therefore, before pouring the solution of nitrate into water, the liquid should be tested for arsenicum by one of the hydrogen tests; if that element be present, the solution must be evaporated and only the deposited crystals be used in the preparation of the oxynitrate. For on pouring an arsenical solution of nitrate of bismuth into water, the arsenicum is not wholly removed in the supernatant liquid, unless the oxynitrate be redissolved and reprecipitated several times, according to the amount of arsenicum present.

In the United States Pharmacopœia the solution of nitrate (made from washed carbonate) is directed to be poured into dilute solution of ammonia. Such a product will probably contain more oxhydrate than oxynitrate.

Subnitrate of Bismuth is sometimes administered in the form of a lozenge (*Trochisci Bismuthi*, B. P.). It is used as a cosmetic under the name of *Pearl-white* (*Blanc de Perle*).

Oxysalts of Bismuth.—It will be noticed that the formula for subnitrate of bismuth ($BiNO_4$) does not accord with that of other nitrates, the characteristic elements of which are NO_3. Analogy would seem to indicate, however, that the fourth atom of oxygen has different functions to the three in the NO_3; for on pouring solution of chloride of bismuth ($BiCl_3$) into water, oxychloride is produced (BiOCl) (a white powder used as a cosmetic, also in enamels, and in some varieties of sealing-wax). The bromide ($BiBr_3$) and iodide (BiI_3) similarly yield oxybromide (BiOBr) and oxyiodide (BiOI). The subnitrate ($BiNO_4$) is, therefore, probably an analogous compound, an oxynitrate ($BiONO_3$). The sulphate ($Bi_2 3SO_4$) also decomposes when placed in water, giving what may be termed an oxysulphate ($Bi_2O_2SO_4$).

It is difficult to prove whether or not the water in the "subnitrate" or hydrous oxynitrate of bismuth ($BiONO_3, H_2O$) is an integral part of the salt. If it is, the compound is simply the hydratonitrate ($BiNO_3 2HO$) of bismuth.

Subcarbonate or Oxycarbonate of Bismuth.

Third Synthetical Reaction.—To solution of nitrate of bismuth add carbonate of ammonium; a white precipitate

of hydrous oxycarbonate ($2Bi_2O_2CO_3$, H_2O) (*Bismuthi Carbonas*, B. P.) falls.

$$\underset{\text{Nitrate of bismuth.}}{4(Bi3NO_3)} + \underset{\text{"Carbonate" of ammonium.}}{3N_4H_{16}C_3O_8} = \underset{\text{Nitrate of ammonium.}}{12NH_4NO_3} + \underset{\text{Oxycarbonate of bismuth.}}{2Bi_2O_2CO_3} + \underset{\text{Carbonic acid gas.}}{7CO_2}$$

According to the United States Pharmacopœia the oxycarbonate (*Bismuthi Subcarbonas*) is made by precipitating with carbonate of sodium a solution of the nitrate prepared from washed hydrate of bismuth.

This compound may be regarded as similar in constitution to the oxysalts just described. In Bi_2CO_5 one scarcely recognizes the characteristic elements of carbonates; but considering the preparation to be an oxycarbonate ($Bi_2O_2CO_3$) its relations to carbonates and oxides are evident. These subsalts may all be viewed as normal bismuth salts in which an atom of oxygen replaces an equivalent proportion of other acidulous atoms or radicals:—

Chloride	$Bi3Cl$	Oxychloride .	$BiOCl$
Bromide	$Bi3Br$	Oxybromide .	$BiOBr$
Iodide	$Bi3I$	Oxyiodide . .	$BiOI$
Nitrate	$Bi3NO_3$	Oxynitrate .	$BiONO_3$
Sulphate	Bi_23SO_4	Oxysulphate .	$Bi_2O_2SO_4$
Carbonate (unknown)	Bi_23CO_3	Oxycarbonate	$Bi_2O_2CO_3$

They may be viewed, in short, as salts in process of conversion to oxide; continue the substitution a little further, and each yields oxides of bismuth (Bi_2O_3). They have also been considered to be salts of a hypothetical univalent radical bismuthyl (BiO).

Citrate of Bismuth.

Fourth Synthetical Reaction.—To solution of nitrate of bismuth add citric acid and then solution of ammonia until the precipitate at first formed is redissolved, and the liquid after shaking has a slight ammoniacal odor. The product contains citrate of bismuth ($BiC_6H_5O_7$, H_2O?) dissolved in solution of citrate and nitrate of ammonium. Made with definite quantities of ingredients and an amount of bismuth salt equivalent to the three grains of oxide (Bi_2O_3) in a fluidrachm, the solution forms the *Liquor Bismuthi et Ammoniæ Citratis*, B. P.

(*b*) *Reactions having Analytical Interest* (*Tests*).

First Analytical Reaction.—Through solution of a bismuth salt (a slightly acid solution of nitrate, for example)

pass sulphuretted hydrogen; a black precipitate of sulphide of bismuth (Bi_2S_3) falls. Add ammonia (to neutralize acid) and then sulphydrate of ammonium; the precipitate, unlike As_2S_3 and Sb_2S_3, is insoluble.

Second Analytical Reaction.—Concentrate almost any acid solution of a bismuth salt and pour into water; a white salt is precipitated.

This reaction is characteristic of bismuth salts; it has already been amply explained. The precipitate is distinguished from one formed by antimony under similar circumstances, by being insoluble in solution of tartaric acid.

The reader is again advised to trace out the exact nature of each of the foregoing reactions, chiefly by aid of equations or diagrams.

QUESTIONS AND EXERCISES.

343. Enumerate the fifteen metals, salts of which are frequently employed in pharmacy.
344. Mention the eleven rarer metals.
345. Name the sources and official compounds of lithium.
346. Give an equation explanatory of the formation of Citrate of Lithium.
347. What is the strength of *Liquor Lithiæ Effervescens?*
348. On what chemical hypothesis are lithium compounds administered to gouty patients?
349. Describe the relation of lithium to other metals.
350. What is the chief test for lithium?
351. Write a paragraph on strontium, its natural compounds, chemical relations, technical applications, and tests.
352. What are the formulæ and properties of oxalate of cerium?
353. Name the commonest ore of manganese, and give an equation descriptive of its reaction with hydrochloric acid.
354. Explain the formation of permanganate of potassium, employing diagrams or equations.
355. In what manner do the manganates of potassium act as disinfectants?
356. What are the chief tests for manganese?
357. What are the chief uses of the compounds of cobalt?
358. How are salts of cobalt analytically distinguished from those of nickel?
359. Mention an application of nickel in the arts.
360. What is the general color of nickel salts?
361. State the method of preparation of red chromate of potassium.
362. Give the formulæ of red and yellow chromates of potassium.
363. How is red chromate of potassium obtained?

364. Describe the action of sulphuretted hydrogen on acidified solutions of chromates.

365. What is the formula of chrome alum?

366. Mention the chief tests for the chromic radical, and for chromium.

367. How would you detect iron, chromium, and aluminium in a solution?

368. Define the terms tinstone, stream-tin, block-tin, grain-tin, tinplate.

369. Describe the position occupied by tin in relation to other metals.

370. What is the difference between stannic acid and metastannic acid?

371. State the applications of tin in the arts.

372. Mention the chief tests for stannous and stannic salts.

373. Name the best antidote in cases of poisoning by tin solutions.

374. How is gold dust separated from the earthy matter with which it is naturally associated?

375. How much pure gold is contained in English coin, and in jewellers' gold?

376. State the average thickness of gold leaf.

377. What is the weight of a sovereign?

378. Explain the term "fineness" as applied to gold.

379. What effect is produced on gold by hydrochloric, nitric, and nitrohydrochloric acids respectively?

380. By what reagents is metallic gold precipitated from solutions of its salts?

381. How is Purple of Cassius prepared?

382. Whence is platinum obtained?

383. Why are platinum utensils peculiarly adapted for use in chemical laboratories?

384. How is perchloride of platinum prepared?

385. Name the chief tests for platinum.

386. What is "platinum black"?

387. Describe an experiment demonstrative of the large amount of attraction for gases possessed by metallic platinum.

388. How is "spongy platinum" produced?

389. By what process may the metal be recovered from platinum residues?

390. What is *occlusion* in chemistry?

391. In what condition does cadmium occur in nature?

392. By what process may Iodide of Cadmium be prepared? and in what form is it used in medicine?

393. Mention the chief test for cadmium.

394. Distinguish sulphide of cadmium from other sulphides of similar color.

395. How is cadmium separated from zinc?

396. How does bismuth occur in nature?

397. What is the quantivalence of bismuth?

398. Write down equations descriptive of the action of nitric acid on bismuth, and water on nitrate of bismuth.

399. How may pure salts be prepared from bismuth containing arsenicum?

400. Give a diagram of the process for the so-called Carbonate of Bismuth.

401. Write formulæ showing the accordance of the official Subnitrate and Carbonate with the other salts of Bismuth, and with ordinary Nitrates and Carbonates.

402. How is *Liquor Bismuthi et Ammoniæ Citratis* prepared?

403. What are the tests for Bismuth?

Practical Analysis.

Bismuth is the last of the metals whose synthetical or analytical relations are of general interest. The position of the rarer among the common metals, and the influence which either has on the other during the manipulations of analysis, will now be considered. These objects will be best accomplished, and a more intimate acquaintance with all the metals be obtained, by analyzing, or studying the methods of analyzing, solutions containing one or more metallic salts.

Of the following Tables, the first (1) includes directions for the analysis of an aqueous or only slightly acid solution containing but one salt of any of the metals hitherto considered. Here the color of the precipitate or precipitates afforded by a metal under given circumstances must be relied on to a considerable extent in attempting the detection of the various elements.

The second Table (2) is intended as a chart for the analysis of solutions containing salts of more than one of the common and rarer metals. It is simply a compilation from the foregoing reactions—an extension of the scheme for the analysis of salts of the ordinary metals. Hence it often may be altered or varied in arrangement to suit the requirements of the analyst.

The third (3) is a mere outline of the preceding Tables. It gives the position of the metals in relation to each other, and will much aid the memory in recollecting that relation.

[*To face page 229.*]

2) OF SHORT DIRECTIONS FOR APPLYING SOME OF THE FORIGOING ANALYTICAL REACTIONS TO THE ANALYSIS OF AN AQUEOUS OR ONLY SLIGHTLY ACID SOLUTION OF ORDINARY SALTS OF ANY OF THE COMMON OR RARER METALS.

ydrochloric acid.

Precipitate
Hg(ous) Pb Ag.
, boil with water, filter.

Filtrate
Cl Cu Hg(ic) Pb Bi As(ous)(ic) Sb Sn(ous)(ic) Zn Mn Co Ni Al Fe(ous)(ic) Cr Ba Ca Sr Mg L K Na Am.
Pass H_2S through the liquid, filter.

recipitate
Hg Ag.
, add AmHO.

Filtrate
Pb.
Add H_2SO_4.
White ppt.

Filtrate
Ag.
Add HNO_3.
White ppt.

See also p. 231.

Precipitate
Cd Cu Ag Pb Bi As Sb Sn.
Collect, wash, digest in AmHS, filter.

Filtrate
Zn Mn Co Ni Al Fe Cr Ba Ca Sr Mg L K Na Am.
Add AmCl, AmHO, and AmHS, warm gently and filter.

Precipitate
Cd Cu Hg Pb Bi.
Wash, boil in HNO_3, filter.

Filtrate
As Sb Sn.
Add dilute HCl, filter, drain well, add *strong* HCl, boil, dilute slightly, filter.

Precipitate
Zn Mn Co Ni Al Fe Cr.
Collect, wash, dissolve in HCl, with a few drops of HNO_3, boil, add AmHO, stir, filter.

Filtrate
Ba Ca Sr Mg L K Na Am.
Add Am_2CO_3, warm, filter.

Ppt.
Hg.
Black.
Confirm by Cu test in original solution.

Filtrate
Cd Cu Pb Bi.
Add AmHO, filter.

Insol.
As.
Yellow
Confirm by Fleitmann's test.

Filtrate
Sn Sb.
Pour into H-apparatus.

Precipitate*
Fe Al Cr.
Wash, dry, fuse on foil with Na_2CO_3 and KNO_3, boil in water and filter.

Filtrate
Zn Mn Co Ni
Acidify with $HC_2H_3O_2$, pass H_2S, filter.

Precipitate
Ba Sr Ca.
Collect, wash, dissolve in $HC_2H_3O_2$, add excess of K_2CrO_4, filter.

Filtrate
Mg L K Na Am.
Add Am_2HAsO_4, stir, filter.

Precipitate
Pb Bi.
Wash, add a few drops HNO_3, dilute, filter.

Filtrate
Cd Cu
Add KCy and H_2S.

Sn remains on Zn. Dissolve in HCl, and apply tests.

Sb escapes as SbH_3. Test as usual.

Residue Fe_2O_3, brown. Test original solution for ferrous or ferric state.

Filtrate
If yellow, Cr present. Divide in two parts.

Sol.
Mn.
Add AmHO and AmHS.
Pink, turning brown.

Ppt.
Ba,
yellow.

Filtrate
Sr Ca.
Add dilute H_2SO_4, let stand, filter.

Ppt.
Mg.

Filtrate
L K Na Am.
Evaporate to small bulk.
Add AmHO.

Ppt.
Bi.

Filt.
Pb.
Dilute, add H_2SO_4, set aside; white ppt.

Ppt.
Cd.
Yellow

Filt.
Cu
Acidify with $HC_2H_3O_2$
Brown ppt.

Sol.
Al.
Add AmCl, warm and filter,
white ppt.

Sol.
Cr.
Add $HC_2H_3O_2$ and excess of $AgNO_3$, red ppt.
Or boil with H_2SO_4 and spirit.
Green sol.

Filt.
Zn.
Add AmHS,
white ppt.

Precipitate
Co Ni.
Boil with HCl and a little HNO_3; add KHO, filter.

Precipitate
Co Ni.
Dissolve in HCl.
Add KCy in slight excess, boil in fume-closet with additional HCl till smell of HCy disappears; then add KHO.

Ppt.
Ni
green.

Sol.
Evap. to dryness, and test residue with borax bead.

Ppt.
Sr.

Filt.
Ca.
Add $Am_2C_2O_4$
white ppt.

Ppt.
L.

Filtrate
K Na Am.
Evaporate, ignite, dissolve. K by $PtCl_4$. Na by flame, Am in original solution.

See also p. 232.

See also p. 232.

Au and Pt are specially sought when necessary.

See also p. 233.

See also p. 233.

See also p. 233.

See p. 233.

* Test this also for Mn, by Crum's process, p. 207.

ydrochloric acid.

Precipitate
Hg(ous) Pb Ag.
, boil with water, filter.

Precipitate Hg Ag. , add AmHO.	Filtrate Pb. Add H_2SO_4. White ppt.
Filtrate Ag. Add HNO_3. White ppt.	

See also p. 231.

Precipitate
Cd Cu Ag Pb
Collect, wash, digest

Precipitate
Cd Cu Hg Pb Bi.
Wash, boil in HNO_3, filter.

Ppt.
Hg.
Black.
Confirm by Cu test in original solution.

Filtrate
Cd Cu Pb Bi.
Add AmHO, filter.

Precipitate Pb Bi. Wash, add a few drops HNO_3, dilute, filter.		Filtrate Cd Cu Add KCy and H_2S.	
Ppt. Bi.	Filt. Pb. Dilute, add H_2SO_4, set aside; white ppt.	Ppt. Cd. Yellow	Filt. Cu Acidify with $HC_2H_3O_2$ Brown ppt.

See also p. 232.

Add hydrochloric acid.

Precipitate Hg(ous) Pb Ag. Collect, wash, and add AmHO.
Hg ppt., blackened.
Pb ppt., still white.
Ag ppt., dissolved.
Sb and Bi may also be precipitated by HCl, but are dissolved on adding more HCl.

If HCl gave no precipitate the metal is still in the liquid; pass H_2S through the solution.

Precipitate Cd Cu Hg(ic) Pb Bi As Sb Sn Au Pt. Collect, wash, add AmHS.

Insoluble.		Soluble.	
Cd, yellow		As(ous & ic)	yellow.
Cu	black.	Sn(ic)	
Hg(ic)		Sb, orange	
Pb		Sn(ous)	black.
Bi		Au	
		Pt	

Apply special tests for each to the original solution. For these, see the previous pages.

If H_2S gave no precipitate add AmCl, AmHO, and AmHS.

Precipitate Zn Mn Co Ni Al Fe Cr.
Zn, Al } white.
Cr, green.
Mn, skin-tint.
Ni, Co, Fe } black.
Test specially for each in original solution. See previous pages.

If AmHS gave no precipitate add Am_2CO_3

Precipitate Ba Sr Ca. Collect, wash, dissolve in $HC_2H_3O_2$, add K_2CrO_4.

Ppt. Ba.	Sol. Sr Ca. Add dil. H_2SO_4.
	Ppt. Sol. Sr.—Ca.

If Am_2CO_3 gave no precipitate add Am_2HAsO_4.

Ppt. Mg.	If no precipitate, test original solution in flame on loop of Pt. wire. L, crimson. Na, yellow. K, violet. If neither, test orig. sol. for Am.

3. OUTLINE OF THE PRECEDING TABLES.

HCl	H_2S		AmHS		Am_2CO_3	Am_2HAsO_4	
Hg (as mercurous salt)	Cd	Insoluble in AmHS.	Zn	Hydrates soluble in AmHO.	Ba	Mg	K
	Cu		Mn		Sr		Na
Pb (some)	Hg (as mercuric salt)		Co		Ca		Am
Ag	Pb (a little)		Ni				
	Bi						
	As (as arsenious or arsenic salt)	Soluble in AmHS.	Al	Hydrates insol. in AmHO.			L
	Sb		Fe				
	Sn (as stannous or stannic salt)		Cr				
	Au						
	Pt						

The laboratory student should practise the examination of aqueous solutions of salts of the above metals until able to analyze with facility and accuracy.

Memoranda relating to the preceding Analytical Tables.

General Memoranda.

These charts are constructed for the analysis of salts more or less soluble in water.——The student has still to learn how substances insoluble in water are to be brought into a state of solution; but, once dissolved, their analysis is effected by the same scheme as that just given. The second Table may therefore be regarded as fairly representing the method by which metallic constituents of chemical substances are separated from each other and recognized.——The

methods of isolation of the complementary constituent of the salt (the reactions of non-metals and acidulous radicals) will form the next object of practical study.

The group-tests adopted in the Tables are, obviously, hydrochloric acid, sulphuretted hydrogen, sulphydrate of ammonium, carbonate of ammonium, and arseniate of ammonium. If a group-test produces no precipitate, it is self-evident that there can be no member of the group present. At first, therefore, add only a small quantity of a group-test, and if it produces no effect add no more; for it is not advisable to overload a solution with useless reagents; substances expected to come down as precipitates are not unfrequently held in the liquid by excess of acid, alkali, or strong aqueous solution of some group reagent, thoughtlessly added. Indeed, experienced manipulators not unfrequently make preliminary trials with group-reagents on a few drops only of the liquid under examination; if a precipitate is produced, it is added to the bulk of the original liquid and the addition of the group-reagent continued; if a precipitate is not produced, the few drops are thrown away and the unnecessary addition of a group-reagent thus avoided altogether, an advantage fully making up for the extra trouble of making a preliminary trial.—— While shunning excess, however, care must be taken to avoid deficiency; a substance only partially removed from solution through the addition of an insufficient amount of a reagent will appear where not expected, be consequently mistaken for something else, and cause much trouble; this will not occur if the appearance, odor, or reaction of the liquid on test-paper be duly observed. It is also a good plan, when a group-reagent has produced a precipitate and the latter has been filtered out, to add a little more of the reagent to the clear filtrate; if more precipitate is produced, an insufficient amount of the group-test was introduced in the first instance; but the error is corrected by simply refiltering; if no precipitate occurs, the mind is satisfied and the way cleared for further operations.

Group-precipitates, or any precipitates still requiring examination, should, as a rule, be well washed before further testing; this is to remove the aqueous solution of other substances adhering to the precipitate (the mother-liquor as it is termed), so that subsequent reactions may take place fairly between the reagent used and the precipitate only.——A precipitate is sometimes in so fine a state of division as to retard filtration by clogging the pores of the paper, or even to pass through the filter altogether; in these cases the mixture may be warmed or boiled, which usually causes aggregation of the particles of a precipitate, and hence facilitates the passage of liquids.

Division of Work.—It is immaterial whether a solution be first divided into group-precipitates or each precipitate be examined as soon as produced; if the former method be adopted, confusion will be avoided by labelling or marking the funnels or papers holding the precipitate "the HCl ppt.," "the H_2S ppt.," and so on.

The colors and general appearance of the various sulphides and hydrates precipitated should be borne in mind, as the absence of other bodies, as well as the presence of those thrown down, is often at once thus indicated. For example, if a precipitate by sulphydrate

of ammonium is white, neither cobalt, nickel, nor iron can be present, and only small quantities of manganese and chromium.

Applications of confirmatory tests must be frequent.

Results of analyses should be recorded neatly in a memorandum-book.

The various reactions which occur in an analysis have already come before the reader in going through the tests for the individual metals or in other analytical operations, it is unnecessary, therefore, again to draw out equations or diagrams. But the reactions should be thought over, and, if not perfectly clear to the mind, be written out again and again till thoroughly understood.

Special Memoranda.

The hydrochloric-acid precipitate may at first include some antimony and bismuth as oxychlorides, readily dissolved, however, by excess of acid.——If either of these elements be present the washings of the precipitate will probably be milky; in that case add a few drops of hydrochloric acid, which will clear the liquid and make way for the application of the test for lead.

The sulphuretted-hydrogen precipitate may be white, in which case it is nothing but sulphur; for, as already indicated, ferric salts are reduced to ferrous, and chromates to the lower salts of chromium by sulphuretted hydrogen, sulphur being deposited:—

$$2Fe_2Cl_6 + 2H_2S = 4FeCl_2 + 4HCl + S_2;$$
$$4H_2CrO_4 + 6H_2S + 12HCl = 2Cr_2Cl_6 + 16H_2O + 3S_2.$$

The proportion of the sulphuretted-hydrogen precipitate dissolved by sulphydrate of ammonium may include a trace of copper, sulphide of copper being not altogether insoluble in sulphydrate of ammonium.——On adding hydrochloric acid to the sulphydrate-of-ammonium solution, a white precipitate of sulphur only may be precipitated, the sulphydrate of ammonium nearly always containing free sulphur.——Carbonate of ammonium does not readily dissolve small quantities of sulphide of arsenicum out of much sulphide of antimony; and, on the other hand, carbonate of ammonium takes into solution a small quantity of sulphide of antimony if much sulphide of arsenicum is present. The precipitate or the original solution should therefore always be examined by the other tests for these elements if any doubt exists concerning the presence or absence of either. Tin remains in the hydrogen-bottle in the metallic state, deposited as a black powder on the zinc used in the experiment. The contents of the bottle are turned out into a dish, ebullition continued until evolution of hydrogen ceases, and the zinc is taken up by the excess of sulphuric acid employed; any tin is then filtered out, washed, dissolved in a few drops of hydrochloric acid, and the liquid tested for tin by the usual reagents.

The portion of the sulphuretted-hydrogen precipitate not dissolved by the sulphydrate of ammonium may leave a yellow semi-fused globule of sulphur on boiling with nitric acid. This globule may be black, not only from presence of mercuric sulphide, but also from inclosed particles of other sulphides protected by the sulphur

from the action of the acid. It may also contain sulphate of lead, produced by the action of nitric acid on sulphide of lead. In cases of doubt the mass must be removed from the liquid, boiled with nitric acid till dissolved, the solution evaporated to remove excess of acid, and the residue examined; but usually it may be disregarded. ——In testing for lead by sulphuric acid the liquid should be diluted and set aside for some time.

Mercury may also be isolated by digesting the sulphuretted-hydrogen precipitate in sulphydrate of sodium instead of sulphydrate of ammonium. The sulphides of arsenicum, antimony, tin, and mercury are thus dissolved out. The mixture is then filtered, excess of hydrochloric acid added to it, and the precipitated sulphides collected on a filter, washed, and digested in sulphydrate of ammonium; sulphide of mercury remains insoluble, while the sulphides of arsenicum, antimony, and tin are dissolved. By this method copper also appears in its right place only, sulphide of copper being quite insoluble in sulphydrate of sodium. The other metals are then separated in the usual way.

The sulphydrate-of-ammonium precipitate may, if the original solution was acid, contain Phosphates, Oxalates, Silicates, and Borates of Barium, Calcium, and Magnesium. These will subsequently come out with the iron, and, being white, give the iron precipitate a light-colored appearance; their examination must be conducted separately, by a method described subsequently in connection with the treatment of substances insoluble in water.——Precipitates containing aluminium, iron, and chromium often carry down some manganese, which afterwards comes out with the iron. This manganese may be detected by washing the ferric hydrate to remove all trace of chlorides, boiling with nitric acid, adding puce-colored oxide of lead, and setting the vessel aside; permanganic acid is formed, recognized in the clear liquid by its purple tint.——Sulphide of nickel is not easily removed by filtration (*vide* p. 209) until most of the excess of sulphydrate of ammonium has been dissipated by prolonged ebullition.

The *carbonate-of-ammonium precipitate* may not contain the whole of the barium, strontium, and calcium in the mixture, unless free ammonia be present; for the carbonates of those metals are soluble in water charged with carbonic acid. If, therefore, the liquid is not distinctly ammoniacal, solution of ammonia should be added. ——Neither carbonate nor hydrate of ammonium wholly precipitates magnesian salts; and as a partial precipitation is undesirable, a solvent, in the form of an alkaline salt (chloride of ammonium), if not already in the liquid, should be added.

Lithium.—The search for lithium may usually be omitted. Should a precipitate, supposed to be due to lithium, be obtained, it must be tested in a flame (= scarlet tint), as a little magnesium not unfrequently shows itself under similar circumstances.

Spectral Analysis.—If present only in minute proportions, the lithium may also remain with the alkalies; it can then only be detected by physical analysis (by a prism) of the light emitted from a tinged flame—by, in short, an instrument termed a spectroscope.

Such a method of examination is called spectral analysis, a subject of much interest and of no great difficulty, but scarcely within the range of Pharmaceutical Chemistry; it will be briefly described in connection with the methods of analyzing solid substances.

QUESTIONS AND EXERCISES.

404. Describe a general method of analysis by which the metal of a single salt in a solution could be quickly detected.

405. Give illustrations of black, white, light pink, yellow, and orange sulphides.

406. Mention the group-tests generally employed in analysis.

407. Under what circumstances may a hydrochloric precipitate contain antimony or bismuth?

408. If a sulphuretted-hydrogen precipitate is white, what substances are indicated?

409. Give processes for the qualitative analysis of liquids containing the following substances:—

a. Arsenicum and Cadmium.
b. Bismuth and Antimony.
c. Ferrous and Ferric salts.
d. Aluminium, Iron, and Chromium.
e. Arsenicum, Antimony, and Tin.
f. Lead and Strontium.
g. Iron and Phosphate of Calcium.
h. Mercury, Manganese, and Magnesium.
i. Zinc, Manganese, Nickel, and Cobalt.
j. Barium, Strontium, and Calcium.

THE ACIDULOUS RADICALS.

Introduction.—The twenty-six radicals which have up to this point mainly occupied attention are (admitting ammonium, NH_4) metals; and they have been almost exclusively studied not in the free state, but in the condition in which they exist in salts. Moreover these metals have been treated as if they formed the more important constituent, the stronger half, the foundation or base, of salts. Attention has been continuously directed to the metallic or *basylous* side of salts. There is, indeed, still one more basylous radical worthy of a passing notice, though it is usually supposed to play only a subordinate part in reactions—Hydrogen. Unlike the salts of most metals, those of hydrogen (the so-called acids) are never, in medicine or the arts generally, professedly used for the sake of their hydrogen, but always for the other half of the salt, the *acidulous* side. And it is not for their basylous radical that these hydrogen salts are now commended to notice,* but in order to study, under the most favorable circumstances, these acidulous groupings which have continually presented themselves in operations on salts, but which were for the time of secondary importance. They may now be treated as the primary object of attention; and there is no better way of doing so than in operating on their compounds with hydrogen, the relatively inferior medicinal importance of which element, as compared with potassium, iron, and other basylous radicals, will serve to give the desired prominence to the *acidulous radicals* in question.

Common Acids.—These salts of hydrogen are the ordinary, sharp, sour bodies termed *acids* (from the Latin root *acies*, an edge). The following Table includes the formulæ and usual names of the most important; others will be noticed subsequently. A few of those mentioned are unstable or somewhat rare; in such cases a common metallic salt containing the acidulous radical may be used for reactions.

* It must not be forgotten that the commonest salt of any radical whatsoever is a salt of hydrogen, the oxide of hydrogen (H_2O), or hydrate of hydrogen (HHO), *water*. In the reactions already performed, the value of this compound has been constantly recognized, both for its hydrogen and for its oxygen, but most of all as the vehicle or medium by which nearly all other atoms are enabled to come into that contact with each other without which their existence would be almost useless; for some atoms are like some animals, out of water they are as inactive as fishes. It is true that both fishes and salts have usually to be removed from water to be utilized by man; but before they can be assimilated, either as food or as medicine, they must again seek the agency of water—become dissolved.

HCl	hydrochloric acid.
HBr	hydrobromic acid.
HI	hydriodic acid.
HCN (HCy)	hydrocyanic acid.
HNO_3	nitric acid.
$HClO_3$	chloric acid.
$HC_2H_3O_2$	acetic acid.*
H_2S	hydrosulphuric acid.†
H_2SO_3	sulphurous acid.
H_2SO_4	sulphuric acid.
H_2CO_3 ?	carbonic acid.
$H_2C_2O_4$	oxalic acid.
$H_2C_4H_4O_6$	tartaric acid.
$H_3C_6H_5O_7$	citric acid.
H_3PO_4	phosphoric acid.
H_3BO_3	boracic acid.

The old names are here retained for these acids, but, in studying their chemistry and chemical relations to other salts, they are usefully spoken of by such more purely chemical names as (for hydrochloric acid) chloride of hydrogen, (for nitric acid) nitrate of hydrogen, and so on—sulphate of hydrogen, tartrate of hydrogen, phosphate of hydrogen.

A prominent point of difference will at once be noticed between the basylous radicals met with up to the present time and the acidulous groupings included in the above tabular list. The former are nearly all elements, ammonium only being a compound; the latter are mostly compounds, chlorine, bromine, iodine, and sulphur being the only elements. This difference will not, however, be so apparent when the chemistry of alcohols, ethers, and such bodies has been mastered, for they are all salts of *compound* basylous radicals.

Rarer Acids.—The above acids contain the only acidulous groupings that commonly present themselves in analysis, or in pharmaceutical operations. There are, however, several other acids (such as hypochlorous, nitrous, hypophosphorous, valerianic, benzoic, gallic, tannic, uric, hyposulphurous, hydroferrocyanic, hydroferridcyanic, and lactic) with which it is desirable to be more or less familiar; reactions concerning these will therefore be described. Arsenious, arsenic, stannic, manganic, and chromic acids have already been

* The hydrogen on the acidulous side must not be confounded with the basylous hydrogen in all these hydrogen salts or acids; the two perform entirely different functions. Hydrogen in the acidulous portion is like the hydrogen in the basylous radical ammonium, it has combined with other atoms, to form a group which plays more or less the part of an elementary radical, and to which a single symbol is not unfrequently applied (Am; Cy, $\overline{A}$, $\overline{O}$, $\overline{T}$, $\overline{C}$, etc.). Cobalt, chromium, iron, platinum, etc., resemble hydrogen in this respect in often uniting with other atoms to form definite acidulous radicals, in which the usual basylous character of the metals has for the time disappeared. In *hydrides* (p. 105) hydrogen itself is an acidulous radical.

† Synonyms: sulphydric acid and sulphuretted hydrogen.

treated of in connection with the metals they contain; in practical analysis they always become sufficiently altered to come out among the metals.

Quantivalence.—A glance at the foregoing Table is sufficient to show the quantivalence of the acidulous radicals. The first seven are clearly univalent; then follow six bivalent, leaving three trivalent.

These all combine with equivalent amounts of basylous radicals to form various salts; hence they may be termed monobasylous, dibasylous and tribasylous radicals. The acids themselves were formerly spoken of as monobasic, dibasic, and tribasic respectively, or monobasic and polybasic, in reference to the amount of *base* (hydrates or oxides) they could decompose; but the terms are no longer definite, and hence but little used in mineral chemistry.

Antidotes.—The antidotes in cases of poisoning by the strong acids will obviously be non-corrosive alkaline substances, as soap and water, magnesia, common washing "soda," or other carbonates. Vinegar, lemon-juice, and weak or non-corrosive acid, would be the appropriate antidotes to caustic alkalies.

Analysis.—The practical study of the acidulous side of salts will occupy far less time than the basylous. Salts will then be briefly examined as a whole.

One Word of Caution.—It is only for convenience in the division of chemistry for systematic study that salts may be considered to contain basylous and acidulous radicals, or separate sides, so to speak; for we possess no absolute knowledge of the internal arrangement of the atoms (admitting that there are such things) in the molecule of a salt. We only know that certain groups of atoms may be transferred from compound to compound in mass (that is, without apparent decomposition); hence the assumption that these groups are radicals. A salt is probably, however, a whole, having no such sides as those mentioned.

QUESTIONS AND EXERCISES.

410. Mention the basylous radical of acids.

411. Give illustrations of univalent, bivalent, and trivalent acidulous radicals, or monobasylous, dibasylous, and tribasylous radicals.

412. What is the difference between an elementary and a compound acidulous radical?

413. Name the grounds on which salts may be assumed to contain basylous and acidulous radicals.

HYDROCHLORIC ACID AND OTHER CHLORIDES.

Formula of hydrochloric acid HCl. Molecular weight* 36.5.

The acidulous radical of hydrochloric acid and of other chlorides is the element chlorine (Cl). It occurs in nature chiefly as chloride of sodium (NaCl), either solid, under the name of *rock-salt*, mines of which are not unfrequently met with, or in solution in the water of all seas. Common table-salt is more or less pure chloride of sodium in minute crystals. Chlorine, like hydrogen, is univalent (Cl′); its atomic weight is 35.5. Its molecule is symbolized thus, Cl_2, chloride of chlorine.

Reactions.

Hydrochloric Acid.

First Synthetical Reaction.—To a few fragments of chloride of sodium in a test-tube or small flask add about an equal weight of sulphuric acid; colorless and invisible gaseous hydrochloric acid is evolved, a sulphate of sodium remaining. Adapt to the mouth of the vessel, by a perforated cork, a piece of glass tubing bent to a right angle, heat the mixture, and convey the gas into a small bottle containing a little water; solution of hydrochloric acid results.

$$\underset{\text{Chloride of sodium.}}{NaCl} + \underset{\text{Sulphuric acid.}}{H_2SO_4} = \underset{\text{Hydrochloric acid.}}{HCl} + \underset{\text{Acid sulphate of sodium.}}{NaHSO_4}$$

Hydrochloric Acid.—The product of this operation is the nearly colorless and very sour liquor commonly termed hydrochloric acid. When of certain given strengths (estimated by volumetric analysis) it forms *Acidum Hydrochloricum*, B. P. and *Acidum Muriaticum*, U. S. P., and *Acidum Hydrochloricum Dilutum*, B. P. (and U. S. P., specific gr. 1.038). The former has a specific gravity of 1.16 (1.1578), and contains 31.8 per cent. of real acid, the latter specific gravity 1.052, with 10.58 per cent. of real acid, and is made by diluting 8 fluid parts of the strong acid with water until the mixture measures 26½ fluid parts. The above process is that of the Pharmacopœias—larger vessels being employed, and the gas being freed from any trace of sulphuric acid by washing. Other chlorides yield hydrochloric acid when heated with sulphuric acid; but chloride of sodium is always used because cheap and common.

Common yellow hydrochloric acid is a by-product in the manufacture of carbonate of sodium from common salt, a process in which the chloride of sodium is first converted into sulphate, hydrochloric acid being liberated. This impure acid is liable to contain iron, arsenic,

* The weight of a molecule is the sum of the weights of its atoms.

fixed salts, sulphuric acid, sulphurous acid, nitrous compounds, and chlorine.

The official (B. P.) *process* is as follows:—

"Take of chloride of sodium, dried, 48 ounces, sulphuric acid 44 fluidounces; water 36 fluidounces, distilled water 50 fluidounces; pour the sulphuric acid slowly into thirty-two ounces of the water, and, when the mixture has cooled, add it to the chloride of sodium previously introduced into a flask having the capacity of at least one gallon. Connect the flask by corks and a bent glass tube with a three-necked wash-bottle, furnished with a safety tube, and containing the remaining four ounces of the water; then, applying heat to the flask, conduct the disengaged gas through the wash-bottle into a second bottle containing the distilled water, by means of a bent tube dipping about half an inch below the surface, and let the process be continued until the product measures sixty-six ounces, or the liquid has acquired a specific gravity of 1.16. The bottle containing the distilled water must be kept cool during the whole operation."

Invisible gaseous hydrochloric acid forms visible grayish-white fumes on coming into contact with air. This is due to combination with the moisture of the air. The intense greediness of hydrochloric gas and water for each other is strikingly demonstrated on opening a test-tube full of the gas under water; the latter rushes into and instantly fills the tube. If the water is tinged with blue litmus, the acid character of the gas is prettily shown at the same time. The test-tube, which should be perfectly dry, may be filled from the delivery-tube direct; for the gas is somewhat heavier than, and therefore readily displaces, air. The mouth may be closed by the thumb of the operator.

Note.—The process, as described in the British Pharmacopœia, includes the use of as much sulphuric acid as is theoretically necessary for the production of acid sulphate of sodium ($NaHSO_4$) which remains in the generating vessel. A hot solution of this residue carefully neutralized by carbonate of sodium, filtered and set aside, yields normal sulphate (*Sodii Sulphas*, U. S. P.), in the form of transparent oblique efflorescent prisms ($Na_2SO_4, 10H_2O$).

$$\underset{\text{Acid sulphate of sodium.}}{2NaHSO_4} + \underset{\text{Carbonate of sodium.}}{Na_2CO_3} = \underset{\text{Sulphate of sodium.}}{2Na_2SO_4} + \underset{\text{Water.}}{H_2O} + \underset{\text{Carbonic acid gas.}}{CO_2}$$

Chlorine.

Second Synthetical Reaction.—To some drops of hydrochloric acid (that is, the common aqueous solution of the gas) add a few grains of black oxide of manganese, and warm the mixture; *chlorine*, the acidulous radical of all chlorides, is evolved, and may be recognized by its peculiar odor, or irritating effect on the nose and air-passages.

$$4HCl + MnO_2 = Cl_2 + 2H_2O + MnCl_2$$

Chlorine-water.—This is the process of the Pharmacopœias for the production of chlorine-water (*Liquor Chlori*, B. P., *Aqua Chlorinii*, U. S. P.), the gas being first washed and then passed into water. Six fluidounces of hydrochloric acid diluted with two ounces of water, and the gas passed through a wash-bottle containing about two ounces of water, yield enough chlorine to produce about a pint and a half of chlorine-water. On the small scale, less than half the acid is utilized through incomplete decomposition and incomplete absorption of the chlorine gas. Chlorine slowly decomposes water with production of hydrochloric acid and oxygen gas; it is best preserved in a green-glass well-stoppered bottle in a cool and dark place. At common temperatures (60° F.), if fresh and thoroughly saturated, chlorine-water contains more than twice (2.3) its bulk of chlorine, or less than 1 per cent. (about 0.75) by weight.

Note.—To obtain the chlorine from other chlorides, sulphuric acid, as well as black oxide of manganese, must be added. Hydrochloric acid is first formed. The action described in the above equation then goes on, except that half instead of the whole of the oxygen of the black oxide is available for the removal of the hydrogen from the chlorine of the hydrochloric acid, the other half being taken up by the hydrogen of the sulphuric acid. Thus, supposing common salt to be the chloride used, the following equations may represent the supposed steps of the process:—

$$\begin{aligned} 2NaCl + H_2SO_4 &= Na_2SO_4 + 2HCl, \\ MnO_2 + H_2SO_4 &= MnSO_4 + H_2O + O; \\ \text{then the } 2HCl + O &= H_2O + Cl_2 \end{aligned}$$

or the whole may be included in one equation:—

$$2NaCl + MnO_2 + 2H_2SO_4 = Na_2SO_4 + MnSO_4 + 2H_2O + Cl_2.$$

This reaction may have occasional analytical interest, a very small quantity of combined chlorine being recognized by its means. But the following test is nearly always applicable for the detection of this element, and leaves nothing to be desired in point of delicacy.

Analytical Reaction (*Test*).

To a drop of hydrochloric acid, or to a dilute solution of any other chloride, add solution of nitrate of silver; a white curdy precipitate falls. Pour off most of the supernatant liquid, add nitric acid and boil; the precipitate does not dissolve. Pour off the acid, and add ammonia; the precipitate quickly dissolves. Neutralize the solution by an acid, chloride of silver is once more precipitated.

The formation of this white precipitate, its appearance, insolubility in boiling nitric acid, solubility in ammonia, and reprecipitation by an acid, form abundant evidence of the presence of chlorine. Its occurrence as a chloride of a metal is determined by testing for the metal with the appropriate reagent; its occurrence as hydrochloric acid is considered to be indicated by the odor, if strong, and the sour

taste, if weak, of the liquid, and the action of the liquid on blue litmus paper, which, like other acids, it reddens. If hydrochloric acid be present in excessive quantity it will, in addition to the above reactions, give rise to strong effervescence on the addition of a carbonate, a chloride being formed. The chlorine in insoluble chlorides, such as calomel, "white precipitate," etc., may be detected by boiling with caustic potash, filtering, acidulating the filtrate by nitric acid, and then adding the nitrate of silver.

Antidotes.—In cases of poisoning by strong hydrochloric acid, solution of carbonate of sodium (common washing-soda) or a mixture of magnesia and water may be administered as an antidote.

QUESTIONS AND EXERCISES.

414. A specimen of official Hydrochloric Acid contains 31.8 per cent. by weight of gas, and its specific gravity is 1.16; work out a sum showing what volume of it will be required, theoretically, to mix with black oxide of manganese for the production of one gallon of chlorine-water, one fluidounce of which contains 2.66 grains of chlorine. Ans. $5\frac{1}{2}$ fluidounces, nearly.

415. Why does hydrochloric acid gas give visible fumes on coming into contact with air?

416. How much chloride of sodium will be required to furnish one pound of chlorine?

417. Give the analytical reactions of chlorides.

418. What antidotes may be administered in cases of poisoning by hydrochloric acid?

HYDROBROMIC ACID AND OTHER BROMIDES.

Formula of Hydrobromic Acid HBr. Molecular weight 81.

Bromine. Source, Preparation, and Properties.—The acidulous radical of hydrobromic acid and other bromides is the element bromine, Br (*Bromum*, B. P., *Brominium*, U. S. P.). It occurs in nature chiefly as bromide of magnesium ($MgBr_2$) in sea-water and certain saline springs. It may be liberated from its compounds by the process for chlorine from chlorides—that is, by heating with black oxide of manganese and sulphuric acid (see previous page). It is a dark-red volatile liquid, emitting an odor more irritating, if possible, than chlorine—of specific gravity 2.966, boiling-point 145.4°.

Quantivalence.—The atom of bromine, like that of chlorine, is univalent (Br′); its atomic weight is 80. Free bromine has the molecular formula Br_2, bromide of bromine.

Hydrobromic Acid.—The bromide of hydrogen, hydrobromic acid, is made by decomposing bromide of phosphorus by water—$PBr_5 + 4H_2O = 5HBr + H_3PO_4$.

Bromide of Potassium (KBr) is occasionally employed in phar-

macy, and is the salt, therefore, which may be used in studying the reactions of this acidulous radical. The official method of making the salt has been alluded to under the salts of potassium (page 63).

Other bromides are seldom used; they may be prepared in the same way as, and closely resemble, the corresponding chlorides or iodides.

Bromide of Ammonium (AmBr) (*Ammonii Bromidum*, B. P. and U. S. P.) is prepared by agitating iron wire with a solution of bromine until the odor of bromine can be no longer perceived, adding solution of ammonia, filtering and evaporating the filtrate to dryness. It forms a white, granular salt which becomes slightly yellow on exposure to air, is readily soluble in water, less so in spirit, and, when heated, sublimes.

Solution of Bromine, B. P., 10 minims in 5 ounces, is an aqueous solution, bromine being slightly soluble in water.

Hypobromites, *Bromates*, *Perbromates*, analogous to hypochlorites, chlorates, and perchlorates, are producible.

Analytical Reactions (*Tests*).

First Analytical Reaction.—To a few drops of solution of a bromide (KBr, or NH_4Br) add solution of nitrate of silver; a yellowish-white precipitate of bromide of silver (AgBr) falls. Treat the precipitate successively with nitric acid and ammonia, as described for the chloride of silver; it is only sparingly dissolved by the ammonia.

Second Analytical Reaction.—To solution of a bromide add a drop or two of chlorine-water, or a bubble or two of chlorine gas; then add a few drops of chloroform or ether, shake the mixture, and set the test-tube aside; the chlorine, from the greater strength of its affinities, liberates the bromine, which is dissolved by the chloroform or ether, the solution falling to the bottom of the tube in the case of the heavy chloroform, or rising to the top in the case of the light ether. Either solution has a distinct yellow, or reddish-yellow or red color, according to the amount of bromine present.

Notes.—This reaction serves for the isolation of bromine when mixed with many other substances. Excess of chlorine must be avoided, as colorless chloride of bromine is then formed. Iodides give a somewhat similar result; the absence of iodine must therefore be insured by a process given in the next section. The above solution in chloroform or ether may be removed from the tube by drawing up into a *pipette* (small pipe, a narrow glass tube, usually having a bulb or expanded portion in the centre) the bromide fixed by the addition of a drop of solution of potash or soda, the chloroform or ether evaporated off, and the residue tested as described in the next reaction.

The above operation is frequently employed for synthetical purposes.

Third Analytical Reaction.—Liberate bromine from a bromide by the cautious addition of chlorine or chlorine-water, then add a few drops of cold decoction of starch; a yellow combination of bromine and starch, commonly termed "bromide of starch," is formed.

Decoction of starch is made by rubbing down two or three grains of starch with some drops of cold water, then adding much more water and boiling the mixture.

The above reaction may be varied by liberating the bromine by a little black oxide of manganese and a drop of sulphuric acid, the upper part of the inside of the test-tube being smeared over with some thick decoction of starch or thin starch-paste.

HYDRIODIC ACID AND OTHER IODIDES.

Formula of Hydriodic Acid HI. Molecular weight 128.

Source.—The acidulous radical of hydriodic acid and other iodides is the element iodine (I). It occurs in nature chiefly as iodide of sodium and of magnesium in sea-water. Seaweeds, sponges, and other marine organisms, which derive much of their nourishment from sea-water, store up iodides in their tissues, and it is from the ashes of these that supplies of iodine (*Iodum*, B. P., *Iodinium*, U. S. P.) are obtained.

Process.—The seaweed ash or *kelp* is treated with water, insoluble matter thrown away, and the decanted liquid evaporated and set aside to allow of the deposition of most of the sulphates, carbonates, and chlorides of sodium and potassium. The residual liquor is treated with excess of sulphuric acid, which causes evolution of carbonic and sulphurous or sulphuretted gases, deposition of sulphur and more sulphate of sodium, and formation of hydriodic acid. To the decanted liquid is added black oxide of manganese, and the mixture is then slowly distilled; the iodine sublimes, and is afterwards purified by re-sublimation.

$$2HI + MnO_2 + H_2SO_4 = MnSO_4 + 2H_2O + I_2.$$

The analogy of chlorine, bromine, and iodine is well indicated by the fact that each is obtained from its compounds by the same reaction. Iodine is liberated from any iodide as bromine from bromides, or chlorine from chlorides—namely, by the action of black oxide of manganese and sulphuric acid.

Properties.—Iodine is a crystalline purplish-black substance; its vapor, readily seen on heating a fragment in a test-tube, is dark violet. Its vapors are irritating to the lungs; but a trace may be inhaled with safety (*Vapor Iodi*, B. P.). It melts at 239°, boils at about 392°, and is entirely volatilized, the first portions containing

any cyanide of iodine that may be present. The latter body occurs in slender colorless prisms, emitting a pungent odor.

Quantivalence.—The atom of iodine, like those of bromine and chlorine is univalent* (I′); its atomic weight is 127, its molecular formula I_2.

The Iodide of Hydrogen, or Hydriodic Acid, is a heavy, colorless gas. Its solution in water is made by passing sulphuretted hydrogen through water in which iodine is suspended.

$$2H_2S + 2I_2 = S_2 + 4HI.$$

Iodide of potassium (KI) is largely used in medicine, and hence is the most convenient iodide on which to experiment in studying the reactions of this acidulous radical. Solid iodine itself might be taken for the purpose; but its use and action in that state have already been alluded to in describing the iodides of potossium, cadmium, and mercury; its analytical reactions in the combined condition are those which may now occupy attention.

Solution of Iodine.—Iodine is slightly soluble in water (iodine-water), and readily soluble in an aqueous solution of iodide of potassium. Twenty grains of iodine and 30 of iodide of potassium, dissolved in 1 ounce of distilled water, form *Liquor Iodi*, B. P.; *Liquor Iodinii Compositus*, U. S. P., is of the same character and about the same strength; 32 grains of iodine and 32 of iodide of potassium, rubbed with 1 fluidrachm of proof spirit, and 2 ounces of lard gradually mixed in, form *Unguentum Iodi*, B. P. *Unguentum Iodinii Compositum*, U. S. P., and *Unguentum Iodinii*, U. S. P., are similar preparations. It is more soluble in spirit (*Tinctura Iodinii*, U. S. P.), or in a spirituous solution of iodide of potassium (*Tinctura Iodi*, B. P., *Tinctura Iodinii Composita*, U. S. P.). It combines with sulphur, forming an unstable grayish-black solid iodide (S_2I_2), having a radiated crystalline structure (*Sulphuris Iodidum*, B. P. and U. S. P., and *Unguentum Sulphuris Iodidi*). If 100 grains be thoroughly boiled with water the iodine will pass off in vapor, and about 20 grains of sulphur remain.—*B. P.* and *U. S. P.*

Analytical Reactions (*Tests*).

First Analytical Reaction.—To a few drops of an aqueous solution of an iodide (*e. g.* KI) add solution of nitrate of silver; a yellowish-white precipitate of iodide of silver (AgI) falls. Pour away the supernatant liquid and treat the precipitate with nitric acid, it is not dissolved; pour away the acid and then add ammonia, it is only sparingly dissolved.

* There is a compound of iodine having the formula ICl_3. Iodine would therefore seem to be a trivalent element (I‴); and bromine and fluorine, from their close chemical analogy with iodine, would necessarily be regarded as trivalent also. From this aspect the position of chlorine would be anomalous.

This reaction is useful in separating iodine from most other acidulous radicals, but does not distinguish iodine from bromine.

Ammonia, it will be remembered, dissolves chloride of silver readily; hence the presence of chloride of potassium in bromide or iodide may be detected by dissolving in water, adding excess of nitrate of silver, collecting the precipitate, washing, digesting in ammonia, filtering and adding excess of nitric acid to the filtrate; a white curdy precipitate indicates a chloride (of potassium).

Second Analytical Reaction.—Liberate iodine from an iodide by the cautious addition of chlorine, then add cold decoction of starch; a deep-blue combination of iodine and starch, commonly termed "iodide of starch," is formed.

Starch is highly sensitive to the action of iodine; this reaction is consequently very delicate and characteristic. Excess of chlorine must be avoided, or colorless chloride of iodine will be produced. Nitrous acid, or a nitrite acidulated with sulphuric acid, may be used instead of chlorine. The reaction is not observed in hot liquids.

In testing bromine for iodine the bromine must be nearly all removed by solution of sulphurous acid before the decoction of starch is added.

Ozone (O_3).—Papers soaked in mucilage of starch containing iodide of potassium, form a test for free chlorine and nitrous acid, and are also employed by meteorologists to detect an allotropic and energetic form of oxygen termed by Schönbein *ozone* (from ὀζω, *ozō*, to smell). This substance liberates iodine from iodide of potassium (with formation of iodide of starch), and is supposed to occur normally in the atmosphere, the salubrity or insalubrity of which is said to be dependent to some extent on the presence or absence of ozone. The possible occurrence of nitrous or chlorinoid gases in the air, however, renders the test untrustworthy. Houzeau proposes to test for ozone by exposing litmus paper of a neutral tint soaked in a dilute solution of iodide of potassium; the potash set free by action of the ozone turns the paper blue. The same paper without iodide would indicate the extent to which the effect might be due to ammonia vapor. Ozone, or rather ozonized air, is produced artificially in large quantities on passing air through a box (Beane's Ozone-generator) highly charged with electricity. Small quantities may be obtained by exposing in a loosely closed bottle a stick of phosphorus partially covered by water. It is a powerful bleaching, disinfecting, and general oxidizing agent; insoluble in water, soluble in oils of turpentine, cinnamon, and some other liquids. From experiments that have been made by Soret on the specific gravity of ozone, its molecular formula would seem to be O_3, that of ordinary oxygen being O_2. Its smell is peculiar. (See p. 211, also "Blood.")

Third Analytical Reaction.—To a neutral aqueous solution of an iodide add a solution containing one part of sulphate of copper to two parts of green sulphate of iron; a dirty-white precipitate of cuprous iodide (Cu_2I_2) falls.

$$2KI + 2CuSO_4 + 2FeSO_4 = Cu_2I_2 + K_2SO_4 + F_23SO_4$$

Separation of Chlorides, Bromides, and Iodides.—Chlorides and bromides are not affected in this way; the reaction is useful, therefore, in removing iodine from a solution in which chlorides and bromides have to be sought. The total removal of iodine by this process is insured by supplementing the addition of the cupric and ferrous sulphate by a few drops of ammonia, any acid which might be keeping cuprous iodide in solution being thereby neutralized, ferric or ferrous hydrate, precipitated at the same time, not affecting the reaction. Chloride of the rare metal palladium performs a similar useful office in removing iodine, but not bromine or chlorine, from solutions. Chlorides may be separated from bromides by taking advantage of the ready solubility of chloride of silver, and almost complete insolubility of bromide of silver in ammonia.

Fourth Analytical Reaction.—Iodides have been shown to be useful in testing for mercuric salts (see the Mercury reactions, p. 172); a mercuric salt (corrosive sublimate, for example) may therefore be used in testing for iodides, a scarlet precipitate of mercuric iodide (HgI_2) being produced.

This reaction may be employed where large quantities of an iodide are present; but its usefulness in analysis is much impaired by the fact that the precipitate is soluble in excess of the dissolved iodide, or in excess of the mercuric reagent. Its color and insolubility in water distinguish it from mercuric chloride, bromide, and cyanide, which are white soluble salts.

Fifth Analytical Reaction.—Iodides have also (see the Lead reactions, p. 190) been shown to be useful in testing for lead salts; similarly a lead salt (acetate, for example) may be used in testing for iodides, a yellow precipitate of iodide of lead (PbI_2) soluble in hot water and crystallizing in yellow scales on cooling, being produced.

Chloride, bromide, and cyanide of lead are white; hence the above reaction may occasionally be useful in distinguishing iodine from the allied radicals. But iodide of lead is slightly soluble in cold water; hence small quantities of iodide cannot be detected by this reaction. (For *Iodates* see p. 263.)

Analogies between Chlorine, Bromine, Iodine, and their Compounds.—These elements form a natural group or family, each distinct from the other yet closely related. Moreover their dissimilarities are so curiously gradational as to irresistibly suggest the idea that some day we may find the differences between these bodies to be in degree rather than in kind. Thus chlorine is a gas and iodine a solid, while bromine occupies the intermediate condition. The atomic weight of bromine is nearly midway between those of chlorine and iodine. The same may be said of the weight of equal volumes

of each in the gaseous state. The specific gravity of fluid chlorine is 1.33, of iodine 4.95, while bromine is nearly 3. Liquid chlorine is transparent, iodine opaque, bromine intermediate. The crystalline forms of the chloride, bromide, and iodide of a metal are commonly identical. One volume of either element in the gaseous state combines with an equal volume of hydrogen (at the same temperature) to form two volumes of a gaseous acid, very soluble in water (hydrochloric acid, hydrobromic acid, hydriodic acid). Many other analogies are traceable.

QUESTIONS AND EXERCISES.

419. State the method by which Bromine is obtained from its natural compounds.
420. Mention the properties of bromine.
421. How may the Bromides of Potassium and Ammonium be made?
422. By what reagents may bromides be distinguished from chlorides?
423. Whence is iodine obtained?
424. By what process is iodine isolated?
425. State the properties of iodine.
426. What is the nature of Iodide of Sulphur?
427. Give the analytical reactions of iodides.
428. Which three substances may be detected by a mixture of iodide of potassium and mucilage of starch?
429. Describe a method by which iodides may be removed from a solution containing chlorides and bromides.

HYDROCYANIC ACID AND OTHER CYANIDES.

Formula of Hydrocyanic Acid HNC or HCy.

Molecular weight 27.

History of Cyanogen.—The acidulous radical of hydrocyanic acid and other cyanides is a compound body, cyanogen (Cy). It is so named from κύανος *kuanos*, blue, and γεννάω, *gennaō*, I generate, in allusion to its prominent chemical character of forming, with iron, the different varieties of Prussian blue. It was from Prussian blue that Scheele, in 1782, first obtained what we now, from our knowledge of its composition, term hydrocyanic acid, but which he called Prussic acid. Cyanogen was isolated by Gay-Lussac in 1814, and was the first compound radical distinctly proved to exist.

Sources.—Cyanogen does not occur in nature, and is only formed from its elements under certain circumstances. It is found in small quantities among the gases of iron-furnaces, and is produced to a slight extent in distilling coals for gas. In the form of ferrocyanide of potassium it is obtained abundantly by heating animal refuse

containing nitrogen, such as the scrapings of horns, hoofs, and hides (5 parts) with carbonate of potassium (2 parts) and waste iron (filings, etc.) in a covered iron pot. The residual mass is boiled with water, the mixture filtered, and the filtrate evaporated and set aside for crystals to form. The cyanogen, produced from the carbon and nitrogen of the animal matter, unites with the potassium and afterwards, on boiling with water, with iron to form what is known as the yellow prussiate of potash (*Potassæ Prussias Flava*, B. P.), or ferrocyanide of potassium ($K'_4Fe''Cy'_6$, (*Potassii Ferrocyanidum*, U. S. P.), a compound occurring in four-sided tabular yellow crystals. It contains the elements of cyanogen, yet it is not a cyanide, for it is not poisonous, and is otherwise different from cyanides; it will be further noticed subsequently. From this salt all cyanides are directly or indirectly prepared.

Cyanide of potassium (KCy) (*Potassii Cyanidum*, U. S. P.), which is the most common, is procured by fusing ferrocyanide of potassium in a crucible; carbonic acid gas (CO_2) is evolved, iron (Fe) is set free, and cyanate of potassium (KCyO), a body that will be subsequently noticed, is formed at the same time:—

$$2K_4FeCy_6 + 2K_2CO_3 = 10KCy + 2KCyO + Fe_2 + 2CO_2.$$

Double cyanides exist, such as the cyanide of sodium and silver (NaCy,AgCy), formed in the process (subsequently described), of quantitatively determining the amount of hydrocyanic acid in a liquid by a standard solution of nitrate of silver: these compounds have, more or less, the properties of their constituents. But other cyanogen compounds, not double cyanides, occur in which the cyanogen is so intimately united with a metal as to form a distinct radical: such are ferrocyanides and ferridcyanides—salts which will be noticed in due course.

Cyanogen, like chlorine, bromine, and iodine, is univalent (Cy'). It may be isolated by simply heating mercuric cyanide ($HgCy_2$) or cyanide of silver (AgCy). It is a colorless gas, burning, when ignited, with a beautiful peach-blossom-colored flame.

Mercuric cyanide is produced in crystals on dissolving 1 part of ferrocyanide of potassium in 15 parts of boiling water, adding 2 parts of mercuric sulphate, keeping the whole hot for ten or fifteen minutes, and then filtering and setting aside to cool. In addition to mercuric cyanide ($HgCy_2$), mercury (Hg), ferric sulphate (Fe_23SO_4) and sulphate of potassium (K_2SO_4), are formed. Any excess of ferrocyanide also gives Prussian blue by reaction with ferric sulphate. It (*Hydrargyri Cyanidum*, U. S. P.) may also be made by dissolving red oxide of mercury in diluted hydrocyanic acid. A small flame of cyanogen may be obtained on heating a few crystals of mercuric cyanide in a short piece of glass tubing closed at one end, and applying a light to the other end as soon as evolution of gas commences.

Reactions.

Diluted Hydrocyanic Acid.

Synthetical Reaction.—Dissolve 2 or 3 grains of ferrocyanide of potassium in 5 or 6 times its weight of water in a test-tube, add a few drops of sulphuric acid and boil the mixture, conveying the evolved gas by a bent glass tube (adapted to the test-tube by a cork) into another test-tube containing a little water; the product is a dilute solution of hydrocyanic acid. Made by this process in large quantities of a certain definite strength (2 per cent.), this solution is the *Acidum Hydrocyanicum Dilutum*, B. P. and U. S. P. "A colorless liquid of a peculiar odor. Specific gravity 0.997."

$$2K_4FeCy_6 + 6H_2SO_4 = FeK_2Fe''Cy_6 + 6KHSO_4 + 6HCy.$$

The details of the official process are as follows: Dissolve $2\frac{1}{4}$ ounces of ferrocyanide of potassium in 10 ounces of water, add 1 fluidounce of sulphuric acid previously diluted with four ounces of water and cooled. Put the solution into a flask or other suitable apparatus of glass or earthenware, to which are attached a condenser and a receiver arranged for distillation; and having put 8 ounces of distilled water into the receiver, and provided efficient means for keeping the condenser and receiver cold, apply heat to the flask, until, by slow distillation, the liquid in the receiver is increased to 17 fluidounces. Add to this 3 ounces of distilled water, or as much as may be sufficient to bring the acid to the required strength, so that 100 grains (or 110 minims) of it, precipitated with a solution of nitrate of silver (*vide* paragraphs on quantitative analysis) shall yield 10 grains of dry cyanide of silver.

The residue of this reaction is acid sulphate of potassium ($KHSO_4$), which remains in solution, and ferrocyanide of potassium and iron ($Fe''K_2FeCy_6$), an insoluble powder sometimes termed Everitt's yellow salt, from the name of the chemist who first made out the nature of the reaction. The latter compound becomes bluish-green during the reaction, owing to absorption of oxygen. *Diluted hydrocyanic acid* may also be prepared by reaction of cyanide of silver and diluted hydrochloric acid.

Pure anhydrous hydrocyanic acid is a colorless, highly volatile, intensely poisonous liquid, solidifying when cooled to a low temperature. It may be made by passing sulphuretted hydrogen over mercuric cyanide. The official solution of the acid is fairly stable, but is said to be rendered more so by the presence of a minute trace of sulphuric or hydrochloric acid.

Note.—A few drops of diluted hydrocyanic acid so placed that its vapor may be inhaled, forms the *Vapor Acidi Hydrocyanici*, B. P., or Inhalation of Hydrocyanic Acid.

Hydrocyanic acid also occurs in cherry-laurel water and bitter-almond water (*vide* Index).

The methods of determining the strength of solutions of hydrocyanic acid will be described in connection with volumetric and gravimetric quantitative analysis. They are based on the formation of cyanide of silver and its solubility in solution of cyanide of potassium, as described in the next reaction.

The hydrocyanic acid used in pharmacy is extremely liable to variation in strength. It should frequently be tested volumetrically.

Analytical Reactions (*Tests*).

First Analytical Reaction.—To a few drops of the hydrocyanic acid solution produced in the above reaction, or to any solution of a cyanide, add excess of solution of nitrate of silver; a white precipitate of cyanide of silver (AgCy) falls. When the precipitate has subsided, pour away the supernatant liquid, and place half of the residue in another test-tube: to one portion add nitric acid, and notice that the precipitate does not dissolve; to the other add ammonia, and observe that the precipitate is insoluble or only sparingly soluble. (Chloride of silver, which is also white, is readily soluble in ammonia.) Cyanide of silver dissolves in solutions of cyanides of alkali-metals, soluble double cyanides being formed (*e. g.*, KCy, AgCy).

Solubility of precipitates in strong solutions of salts.—Cyanide of silver and many other precipitates insoluble in acids (similar remarks apply to precipitates insoluble in alkalies) are often soluble in the strong saline liquids formed by the addition of acids and alkalies to one another. Hence the precaution of adding the latter reagents to separate portions of a precipitate, or of not adding the one until the other has been poured away.

Cyanogen in an insoluble cyanide, such as cyanide of silver itself, is readily recognized on heating the substance in a short piece of glass tubing closed at one end like a test-tube and drawn out at the other end, so as to have but a small opening; on applying a flame, the escaping cyanogen ignites and burns with a characteristic peach-blossom tint.

Antidote.

Second Analytical Reaction.—To a dilute solution of hydrocyanic acid, or a soluble cyanide, add a few drops of solution of a ferrous salt and a drop or two of solution of a ferric salt (ferrous sulphate and ferric chloride are usually at hand); to the mixture add potash or soda (magnesia or carbonate of sodium), and then hydrochloric acid; a precipitate of Prussian blue remains. The decompositions may be traced in the following equations:—

$$HCy + KHO = KCy + H_2O$$
$$2KCy + FeSO_4 = FeCy_2 + K_2SO_4$$
$$4KCy + FeCy_2 = K_4FeCy_6 \text{ or } K_4Fcy$$
$$3K_4Fcy + 2Fe_2Cl_6 = 12KCl + Fe_4Fcy_3.$$

The test depends on the conversion of the cyanogen into ferrocyanogen by the iron of a ferrous salt, and the combination of the ferrocyanogen, so produced, with the iron of a ferric salt.

Hence a mixture of green sulphate of iron, solution of perchloride of iron, and either magnesia or carbonate of sodium, is the recognized *antidote* in cases of poisoning by hydrocyanic acid or cyanide of potassium.

In such an alkaline mixture the poisonous cyanide, by reaction with ferrous hydrate, is at once converted into innocuous ferrocyanide of potassium or sodium; should the mixture become acid, the ferric salt present reacts with the soluble ferrocyanide forming insoluble Prussian blue, which is also inert. From the rapidity of the action of these poisons, however, there is seldom time to prepare an antidote. Emetics, the stomach-pump, the application of a stream of cold water to the spine, and the above antidote form the usual treatment.

Third Analytical Reaction.—To solution of hydrocyanic acid add ammonia, and common yellow sulphydrate of ammonium, and evaporate the liquid nearly or quite to dryness in a small dish, occasionally adding ammonia till the excess of sulphydrate of ammonium is decomposed; acidify the liquid with hydrochloric acid, and then add a drop of solution of a ferric salt; a blood-red solution of sulphocyanide of iron will be formed.

This is a very delicate reaction. Some free sulphur in the yellow sulphydrate of ammonium unites with the alkaline cyanide and forms sulphocyanate ($2AmCy + S_2 = 2AmCyS$); the ammonia combines with excess of free sulphur and forms, among other salts, sulphydrate of ammonium, the whole of which is removed by the ebullition. If the liquid has not been evaporated far enough, sulphydrate of ammonium may still be present, and give black sulphide of iron on the addition of the ferric salt.

Hydrocyanic acid in the blood.—According to Buchner the blood of animals poisoned by hydrocyanic acid, instead of coagulating as usual, remains liquid and of a clear cherry-red color for several days. In one case he obtained the reactions of the acid on diluting and distilling the blood fifteen days after death, and applying the usual reagents to the distillate. Aqueous solution of peroxide of hydrogen (p. 88) changes such blood to a deep brown color.

Schönbein's test for hydrocyanic acid is said to be extremely delicate. Filtering paper is soaked in a solution of 3 parts of guaiacum resin in 100 of alcohol. A strip of this paper is dipped in a solution of 1 part of sulphate of copper in 50 of water; a little of the suspected

solution is placed on this paper and exposed to the air, when it immediately turns blue. Or the paper may be placed over the neck of an open bottle of medicine supposed to contain hydrocyanic acid, or otherwise exposed to the vapor of the acid.

QUESTIONS AND EXERCISES.

430. Write a paragraph on the history of cyanogen.
431. Mention the source of the cyanogen of all cyanides.
432. How is Ferrocyanide of Potassium prepared?
433. What is the formula of ferrocyanide of potassium?
434. Is ferrocyanide of potassium poisonous?
435. Write an equation expressive of the reaction which ensues when ferrocyanide and carbonate of potassium are brought together at a high temperature.
436. What are the properties of cyanogen? How may it be obtained in a pure condition?
437. How is mercuric cyanide prepared?
438. How much real hydrocyanic acid is contained in the official liquid?
439. Give details of the preparation of hydrocyanic acid, and an equation of the reaction.
440. State the proportion of water that must be added to an aqueous solution containing 15 per cent. of hydrocyanic acid to reduce the strength to 2 per cent.—*Ans.* 6½ to 1.
441. What are the characters of pure hydrocyanic acid? How may it be obtained?
442. Enumerate the tests for cyanogen, giving equations.
443. Explain the action of the best antidote in cases of poisoning by hydrocyanic acid or cyanide of potassium.

NITRIC ACID AND OTHER NITRATES.

Formula of Nitric Acid HNO_3. Molecular weight 63.

Introduction.—The group of elements represented by the formula NO_3 is that characteristic of nitric acid and all other nitrates; hence it is expedient to regard these elements as forming an acidulous radical, which may be termed *the nitric radical.* Like the hypothetical basylous radical ammonium (NH_4), this supposed acidulous radical (NO_3) has not been isolated. Possibly it is liberated when chlorine is brought into contact with nitrate of silver; but if so, its decomposition into white crystalline nitric anhydride (N_2O_5) and oxygen (O) is too rapid to admit of its identification.

Sources.—The nitrogen and oxygen of the air combine and ultimately form nitric acid whenever a current of electricity (as in the occurrence of lightning) passes. Nitrates are commonly met with in waters, soils, and the juices of plants. In the concentrated plant juices termed medicinal "Extracts," small prismatic crystals of ni-

trate of potassium may occasionally be observed. (The cubical crystals often met with on extracts are chloride of potassium.) Nitric acid and other nitrates are obtained from nitrates of potassium and sodium, and these from the surface soil of tropical countries. *Nitrate of potassium* or *prismatic nitre* (from the form of its crystals) is chiefly produced in and about the villages of India. The natives simply scrape the surface of waste grounds, mud heaps, banks, and other spots where a slight incrustation indicates the presence of appreciable quantities of nitre, mix the scrapings with wood-ashes (carbonate of potassium, to decompose the nitrate of calcium always present), digest the mixture in water, and evaporate the liquor. The impure product is purified by careful recrystallizations, and is sent into commerce in the form of white crystalline masses or fragments of striated six-sided prisms. Besides its use in medicine (*Potassii Nitras*, U. S. P.), it is employed in very large quantities in the manufacture of gunpowder. *Nitrate of Sodium* (*Sodii Nitras*, U. S. P.) occurs in more distinct incrustations on the surface of the ground in Peru, Bolivia, and Chili, more especially in the district of Atacama; it is distinguished as Chili saltpetre or (from the form of its crystals—obtuse rhomboids) cubic nitre, and is chiefly used as a manure and as a source of nitric acid, its tendency to absorb moisture unfitting it for use in gunpowder. In many parts of Europe nitrate of potassium is made artificially by exposing heaps of animal manure, refuse, ashes, and soil to the action of the air and the heat of the sun: in the course of a year or two the nitrogen of the animal matter becomes oxidized to nitrates, and the latter are removed by washing.

Note.—The word *nitric* is from *nitre*, the English equivalent of the Greek νίτρον (nitron), a name applied to certain natural deposits of *natron* (carbonate of sodium), for which nitrate of potassium seems at first to have been mistaken. *Saltpetre* is simply *sal petræ*, salt of the rock, in allusion to the natural origin of nitrate of potassium. *Sal prunella* (from *sal*, a salt, and *pruna*, a live coal) is nitrate of potassium melted over a fire and cast into cakes or bullets.

The nitric radical is univalent (NO_3').

Constitution of Salts.

It is here necessary again to caution the reader against regarding salts as invariably possessing a known constitution, or supposing that they always possess two or more sides, or contain definite radicals. The erroneous conception which, of all others, is most likely to be imperceptibly formed is that of considering salts binary bodies. For, first the names of salts are necessarily binary. A student hears the names "sulphate of iron," "sulphate of copper," and simultaneously receives the impression that each salt has two sides, copper or iron occupying one and something indicated by the words "sulphate of" the other. Such words "vitriol," green or blue, or "nitre," would perhaps implant unitary ideas in the mind; but it is simply impossible to give such names to all salts as will convey the impression that each salt is a whole, and therefore unitary. The name "sulphate of potash" produces binary impressions; and the less incorrect name,

"sulphate of potassium," is in this respect no better. Secondly, it is impracticable to study salts as a whole. Teachers are unanimous in the opinion that students should first master the reactions characteristic of the metals in salts, and then the residues which, with those metals, make up the salts, or *vice versâ*. It is not only impracticable, but impossible, to study salts as a whole; binary ideas concerning them are therefore almost inevitably imbibed. We come to regard a salt as a body which splits up in one direction only, look upon nitre, for instance, and all other nitrates, as containing NO_3 and a metal, K; whereas KNO_3 may be split up into KNO_2 and O; or into K_2O, N_2, and O_5; or may contain K_2O and N_2O_5. These are the chief disadvantages attending the employment of the binary hypothesis in studying chemical compounds: if they be borne in mind, the hypothesis may be freely used without much danger of permanent mental bias. Thus in nitre let the group of elements (NO_3) which, with potassium, makes up the whole salt be called the nitric radical, the name of the latter being directly derived from its hydrogen salt. Similarly allow the acidulous residues of other salts of metals to be termed respectively the chloric, acetic, sulphurous, sulphuric, carbonic, oxalic, tartaric, phosphoric, citric, boracic radicals. In short, these compound radicals should be regarded as groupings common to many salts, and which may usually be transferred without any apparent breaking or splitting; at the same time we must be prepared to find that occasionally a salt divides in other directions. In this way perhaps erroneous impressions will gain least hold on the mind, and a way be left open for the easy entrance of new truths, should the real constitution of salts be discovered.

Formerly salts (such as sulphate of magnesium) were regarded as containing (*a*) an oxide of a metal (MgO) and an anhydride (SO_3), the latter being incorrectly called an acid (sulphuric acid), or (*b*) as containing two simple radicals (*e. g.* KI, NaCl, KCy, HgS)—the former being called *oxyacid salts*, or *oxysalts*, and the latter *haloid salts* (from ἁλς, *als*, seasalt, and εἶδος, *eidos*, likeness). Such distinction is no longer maintained, the two classes being merged. This is an important educational gain on the side of simplicity; for, whereas under the old system much time was necessarily expended before salts of a metal and salts of the oxide of that metal could be distinguished (*e. g.* KI and MgO,SO_3), now, all salts being regarded as salts of the metals themselves (*e. g.* KI and $MgSO_4$), no such distinction is necessary.

Reactions.

Nitric Acid.

Synthetical Reaction.—To a fragment of nitrate of potassium or nitrate of sodium in a test-tube add a drop or two of sulphuric acid, and warm; nitric acid (HNO_3) is evolved in vapor. The fumes may be condensed by a bent tube fitted to the test-tube, not by a cork as for hydrochloric acid, because the nitric vapors would strongly act on it,

but by plaster of Paris, a paste of which sets hard on being set aside for a short time, and is unaffected by the acid.

On a somewhat larger scale nitric acid may be prepared by heating, in a stoppered or plain retort, a mixture of equal weights of nitrate of potassium and sulphuric acid; the acid distils over, and acid sulphate of potassium remains behind:—

$$\underset{\text{Nitrate of potassium.}}{KNO_3} + \underset{\text{Sulphuric acid.}}{H_2SO_4} = \underset{\text{Nitric acid.}}{HNO_3} + \underset{\text{Acid sulphate of potassium.}}{KHSO_4}$$

Half the quantity of sulphuric acid may be taken; but in that case neutral sulphate of potassium (K_2SO_4) is produced, which, from its hard, slightly soluble character, is removed with difficulty from the retort. On the manufacturing scale the less proportion is used; but instead of retorts iron cylinders are employed, from which the residual salt is removed by chisels. Moreover the cheaper sodium salt is the nitrate, from which manufacturers usually prepare nitric acid, seven parts of nitrate of sodium and four of sulphuric being employed.

Note.—The acid sulphate of potassium is readily converted into neutral sulphate (*Potassii Sulphas*, U. S. P.) by dissolving in water, adding carbonate of potassium until effervescence ceases to occur, filtering, and setting aside to crystallize.

Pure nitric acid (HNO_3) is a colorless liquid, somewhat difficult of preparation; its specific gravity is 1.52. The strongest acid met with in commerce has a sp. gr. of 1.5, and contains 93 per cent. of real nitric acid (HNO_3); it fumes disagreeably, is unstable, and, except as an escharotic, is seldom used. The British and United States Pharmacopœias contain two acids: *Acidum Nitricum*, prepared as above, of sp. gr. 1.42 (also in U. S. P.), and containing 70 per cent. of real acid (HNO_3); and another, *Acidum Nitricum Dilutum*, sp. gr. 1.101 (U. S. P. 1.068), containing nearly 17½ (17.44) per cent. Either of the stronger liquids, although containing water, is usually simply termed "nitric acid." The official nitric acid, of sp. gr. 1.42, is a definite hydrous acid ($2HNO_3, 3H_2O$); it distils at 250° F. without change. If a weaker acid be heated it loses water, if a stronger acid be heated it loses nitric acid, until the density of 1.42 is reached. *Aqua fortis* is an old name for nitric acid (*Aqua fortis simplex*, sp. gr. 1.22 to 1.25; *Aqua fortis duplex*, 1.36). The strength of a specimen of nitric acid is determined by volumetric analysis. *Nitric anhydride* (N_2O_5), sometimes but erroneously called *anhydrous nitric acid*, is a solid crystalline substance formed on passing dry chlorine over dry nitrate of silver.

Aqua Regia.—Three fluidounces of nitric acid (B. P.), four of hydrochloric acid (B. P.), (3 to 5 by weight forms the *Acidum Nitromuriaticum*, U. S. P.), and twenty-five of water, give the *Acidum Nitrohydrochloricum Dilutum* of the British Pharmacopœia. The acids are ordered to be mixed twenty-four hours before dilution to insure mutual decomposition and full development of the chief active product, chlorine:—

$$\underset{\text{Nitric acid.}}{2HNO_3} + \underset{\text{Hydrochloric acid.}}{6HCl} = \underset{\text{Chloronitric gas.}}{N_2O_2Cl_4} + \underset{\text{Water.}}{4H_2O} + \underset{\text{Chlorine.}}{Cl_2}$$

In the later stages of the reaction, the decomposition expressed in the following equation also probably occurs :—

$$\underset{\text{Nitric acid.}}{HNO_3} + \underset{\text{Hydrochloric acid.}}{3HCl} = \underset{\text{Chloronitrous gas.}}{NOCl} + \underset{\text{Water.}}{2H_2O} + \underset{\text{Chlorine.}}{Cl_2}$$

The same reaction occurs if the acids are mixed after dilution, but is not complete for a week or a fortnight (Tilden). The undiluted mixture of acids is known as *aqua regia*, so called from its property of dissolving gold, "the king" of metals.

Analytical Reactions (Tests).

First Analytical Reaction.—To a solution of any nitrate (*e. g.* KNO_3) add sulphuric acid, and then copper turnings, and warm; colorless nitric oxide gas (NO) is evolved, which at once unites with the oxygen in the tube, giving *red fumes* of nitric peroxide or peroxide of nitrogen (NO_2).

$$2KNO_3 + 5H_2SO_4 + Cu_3 = 2NO + 3CuSO_4 + 4H_2O + 2KHSO_4;$$
$$2NO + O_2 = 2NO_2.$$

Performed on a larger scale, in a vessel to which a delivery-tube is attached, this reaction becomes of synthetical interest, being the process for the preparation of nitric oxide gas for the purposes of chemical experiment.

Small amounts of a nitrate may be overlooked by this test, the color of the red fumes not being very intense.

Undiluted nitric acid poured on to copper turnings gives dense red vapors of *nitrous acid* (HNO_2), *nitrous anhydride* (N_2O_3), and *nitric peroxide* (NO_2).

Second Analytical Reaction.—To a cold solution of the nitrate, even if very dilute, add three or four crystals of sulphate of iron, shake gently for a minute in order that some of the sulphate may become dissolved, and then pour eight or ten drops of strong sulphuric acid down the side of the test-tube, so that it may form a layer at the bottom of the vessel; a reddish-purple or black coloration will appear between the acid and the supernatant liquid.

This is a very delicate test for the presence of nitrates. The black color is due to a solution or, perhaps, combination of nitric oxide with a portion of the ferrous salt. The nitric oxide is liberated from the nitrate by the reducing action of the hydrogen of the sulphuric acid, the sulphuric radical of which is absorbed by the ferrous sulphate, the latter salt becoming ferric sulphate.

$$2HNO_3 + 3H_2SO_4 + 6FeSO_4 = 4H_2O + 3(Fe_23SO_4) + 2NO.$$

The process of oxidation is one frequently employed in experimental chemistry; and nitrates, from their richness in oxygen, but more especially because always at hand, are the oxidizers usually selected for the purpose. In the operation they generally split up in one way, namely, into oxide of their basylous radical, nitric oxide gas, and available oxygen. Thus hydrogen nitrate (nitric acid) yields oxide of hydrogen (water) and the other bodies mentioned, as shown in the following equation:—

$$4NHO_3 = 2H_2O + 4NO + 3O_2.$$

When nitrates, other than nitric acid, are used for the purpose of oxidation, a stronger acid, generally sulphuric, is commonly added in order that nitric acid may be formed; the hydrogen nitrate splitting up more readily than other nitrates.

Nitrate of ammonium (*Ammonii Nitras*, U. S. P.) is readily formed on neutralizing nitric acid with carbonate of ammonium. It occurs in long prismatic crystals or in fused masses, soluble in about half its weight of water at 70° and in twice its weight of alcohol, and when heated, yields *nitrous oxide*, or laughing-gas (N_2O).

$$NH_4NO_3 = N_2O + 2H_2O.$$

Nitrous oxide is thus prepared for use as an anæsthetic. When required for inhalation, it should be washed from any possible trace of acid or nitric oxide, by being passed through solution of potash, and through solution of ferrous sulphate.

Nitrous oxide is slightly soluble in warm water, more so in cold. By pressure it may be liquefied to a colorless fluid, and by simultaneous cooling solidified. It supports combustion almost as well as oxygen.

The five oxides of nitrogen have now been mentioned, namely—

Nitrous oxide	N_2O		N_2O
Nitric oxide*	NO		N_2O_2
Nitrous anhydride . .	N_2O_3	or	N_2O_3
Nitric peroxide* . . .	NO_2		N_2O_4
Nitric anhydride . . .	N_2O_5		N_2O_5

Nitrous oxide is a colorless gas not altered by exposure to air; nitric oxide is also colorless, but gives red fumes in the air; nitrous anhydride is a red vapor condensible to a blue liquid; nitric peroxide is a red vapor condensible to an orange liquid; nitric anhydride is a colorless crystalline solid. The two anhydrides by absorbing water yield respectively nitrous acid (HNO_2) and nitric acid (HNO_3). This series of compounds forms a good illustration of the doctrine of multiple proportions (p. 42).

Third Analytical Reaction.—Direct the blowpipe-flame on to charcoal until a spot is red-hot; now place on the spot a fragment of nitrate; deflagration ensues.

* The specific gravities of these gases indicate that NO and NO_2 are the correct formulæ, and not N_2O_2 and N_2O_4.

This reaction does not distinguish nitrates from chlorates. It is insufficient for the recognition of very small quantities of either class of salts, especially when they are mixed with other substances.

Gunpowder is an intimate mechanical mixture of 75 parts of nitre, 15 to 12½ parts of charcoal, and 10 to 12½ parts of sulphur. In burning it may be said to give sulphide of potassium (the white smoke, K_2S), nitrogen (N), carbonic oxide (CO), and carbonic acid (CO_2) gases, though the decomposition is seldom complete. The sudden production of a large quantity of heated gas from a small quantity of a cold solid is sufficient to account for all the effects of gunpowder.

Fourth Analytical Reaction.—To nitric acid or other nitrate add solution of "sulphate of indigo;" the color is discharged.

"*Solution of Sulphate of Indigo,*" B. P. (Sulphindylic or Sulphindigotic acid), is made by digesting 5 grains of dry finely powdered indigo in a small quantity of strong sulphuric acid in a test-tube for an hour, the mixture being kept hot by a water-bath; the blue liquid is then poured into 10 ounces of sulphuric acid, the whole well shaken, set aside, and the clear liquid decanted. Free chlorine also destroys the color of this reagent.

Indigo B. P. (C_8H_5NO) is a blue coloring-matter deposited when infusion of various species of *Indigofera* is exposed to air and slight warmth. Under these circumstances, *indican*, a yellow transparent amorphous substance, soluble in water, breaks up into indigo, which is insoluble and falls as a sediment, and a sort of sugar termed *indiglucin*. The indigo is collected, drained, pressed, and dried. By action of deoxidizing agents indigo is converted into soluble colorless *indigogen, reduced indigo,* or *white indigo;* 1 part of powdered indigo, 2 of green sulphate of iron, 3 of slaked lime, and 200 of water, shaken together and set aside in a well-closed bottle, gives this colorless indigo. A piece of yarn, calico, or similar fabric, dipped into such a solution, and exposed to air, becomes dyed blue, deposition of insoluble indigo-blue occurring within the cells and vessels of the fibre. This operation is readily performed on the small scale, and forms a good illustration of the characteristic feature of the art of dyeing, namely, the introduction of soluble coloring-matter into a fabric by permeation of the walls of its cellular and vascular tissue, and the imprisonment of that coloring-matter by conversion into a solid and insoluble form (*vide* also p. 117).

Pure indigo, or *indigotin*, may be obtained in beautiful needles by spreading a paste of indigo and plaster of paris on a tin plate, and when dry placing a lamp underneath, moving the latter from place to place as the indigo sublimes and condenses on the surface of the plaster. It may also be obtained in crystals by gently boiling finely powdered indigo with aniline, filtering while hot, and setting aside; these crystals may be washed with alcohol. Hot paraffin may be employed instead of aniline. It is possible to obtain indigotin artificially.

Distinction between nitric acid and other nitrates.—Presence of the nitric radical in a solution having been proved by the above reac-

tions, its occurrence as the nitrate of a metal is demonstrated by the neutral, or nearly neutral, deportment of the liquid with test-paper and the detection of the metal—its occurrence as nitric acid by the sourness of the liquid to the taste and the effervescence produced on the addition of a carbonate.

Antidote.—In cases of poisoning by strong nitric acid, solution of carbonate of sodium (common washing-soda) or a mixture of magnesia and water may be administered as antidotes.

QUESTIONS AND EXERCISES.

444. Trace the origin of nitrates.

445. In what does cubic nitre differ, chemically, from prismatic nitre?

446. Describe a process by which nitrate of potassium may be obtained artificially.

447. State the difference between nitrate of potassium, nitre, saltpetre, and sal prunella.

448. What group of elements is characteristic of all nitrates? and what claim has this group to the title of radical?

449. Mention the usual theory regarding the manner in which atoms are arranged in reference to each other in such salts as nitrate of potassium.

450. How is Nitric Acid prepared?

451. Give the properties of nitric acid.

452. What reactions occur when strong nitric and hydrochloric acids are mixed?

453. How is nitric oxide prepared?

454. Enumerate and explain the tests for nitrates.

455. Into what substances does nitric acid usually split when employed as an oxidizing agent?

456. How is nitrous oxide prepared?

457. Enumerate the five oxides of nitrogen.

458. What is the nature of gunpowder?

459. Write a few sentences on the chemistry of indigo, one of the tests for nitric acid.

460. How is nitric acid distinguished from other nitrates?

461. What quantity of cubic nitre will be required to produce ten carboys of official nitric acid, each containing 114 pounds?—*Ans.* $1076\frac{2}{3}$ pounds.

CHLORIC ACID AND OTHER CHLORATES.

Formula of Chloric Acid $HClO_3$. Molecular weight 84.5.

Hypochlorous Acid (HClO), and other Hypochlorites.

Place a few grains of red oxide of mercury in a test-tube, half-fill the tube with chlorine-water and well shake the mix-

ture; the resulting liquid is a solution of hypochlorous acid, mercuric oxychloride remaining undissolved:—

$$2HgO + 2Cl_2 + H_2O = 2HClO + Hg_2OCl_2.$$

By the double decomposition of hypochlorous acid and oxides or hydrates, other pure hydrochlorites are formed:—

$$HClO + NaHO = NaClO + H_2O.$$

The direct action of chlorine on metallic hydrates is supposed to give a mixture of chloride and hypochlorite, as described in connection with the synthetical reactions of Sodium (p. 72, *Liquor Sodæ Chloratæ*, B. P.) and Calcium (p. 96, *Calx chlorata*, B. P.).

$$Cl_2 + 2NaHO = NaCl,NaClO + H_2O;$$
$$2Cl_2 + 2CaH_2O_2 = CaCl_2,Ca2ClO + 2H_2O.$$

But the presence of chlorides cannot be directly demonstrated in these bodies; so that their constitution is not definitely determined. The action of acids on them results in the evolution of chlorine; hence the great value of the calcium compound (chlorinated lime, or chloride of lime) in bleaching operations:—

$$CaCl_2, Ca2ClO + 2H_2SO_4 = 2Cl_2 + 2CaSO_4 + 2H_2O.$$

The solubility of hypochlorites in water, their peculiar odor, greatly intensified on the addition of acid, and their bleaching-powers (see the above calcium reaction) are the characters on which to rely in searching for hypochlorites.

Chlorates.

The group of elementary atoms represented by the formula ClO_3 is that characteristic of chloric acid and all other chlorates; hence it is expedient to regard it as being an acidulous radical, which may be termed the chloric radical. Like the nitric radical, it has not been isolated. Chloric anhydride also (Cl_2O_5) unlike nitric anhydride, has not yet been obtained in the free condition.

Chlorates are artificial salts. They are formed by simply boiling aqueous solutions of the common bleaching salts (chlorinated lime, chlorinated soda, chlorinated potash). Heat thus converts

3(NaCl, NaClO) Chlorinated Soda.	into	$NaClO_3$ Chlorate of sodium.	and	5 NaCl Chloride of sodium.
3(KCl, KClO) Chlorinated potash.	into	$KClO_3$ Chlorate of potassium.	and	5KCl Chloride of potassium.
3($CaCl_2$, Ca2ClO) Chlorinated lime.	into	$Ca2ClO_3$ Chlorate of calcium.	and	5CaCl Chloride of calcium.

One chlorate may also be made from another by double decomposition. In making chlorates economically the chlorinated salt is specially prepared for, and in the same vessel as, the chlorate.

Chlorate of Potassium.

Thus Chlorate of Potassium (*Potassii Chloras*, U. S. P.) is commercially made by saturating with chlorine gas a moistened mixture of three parts of chloride of potassium and ten of slaked lime, and well boiling the product. Chlorinated lime is first formed; this, on boiling with water, splits up into chloride of calcium and chlorate of calcium, and the latter reacting on the chloride of potassium yields chloride of calcium and chlorate of potassium.

$$6(Ca2HO) + 6Cl_2 = 3(CaCl_2,Ca2ClO) + 6H_2O;$$
$$3(CaCl_2,Ca2ClO) = Ca2ClO_3 + 5CaCl_2;$$
$$Ca2ClO_3 + 2KCl = CaCl_2 + 2KClO_3.$$

The operation may be conducted on a small scale by rubbing together in a mortar the above proportions of ingredients in ounces or half-ounces, adding enough water to make the whole assume the character of damp lumps, placing the porous mass in a funnel (loosely plugged with stones or pieces of glass) and passing chlorine gas (p. 24) up through the neck of the funnel. When the whole mass has become of a slight pink tint (due to a trace of permanganate) it should be turned into a dish, well boiled with water, filtered, the filtrate evaporated if necessary, and set aside; the chlorate of potassium crystallizes out in colorless rhomboidal plates, chloride of calcium remaining in the mother-liquor.

In the official process, carbonate of potassium instead of chloride is used; but otherwise it is similar to the method just described. Chlorinated potash and chlorinated lime are first formed—

$$K_2CO_3 + Ca2HO + Cl_2 = KCl, KClO + CaCO_3 + H_2O,$$
$$6(Ca2HO) + 6Cl_2 = 3(CaCl_2,Ca2ClO) + 6H_2O;$$

these, on boiling with water, split up into chlorates and chlorides—

$$3(KCl, KClO) = KClO_3 + 5KCl$$
$$3(CaCl_2, Ca2ClO) = Ca2ClO_3 + 5CaCl_2,$$

the whole of the chloride of potassium and chlorate of calcium finally yielding chlorate of potassium and chloride of calcium,

$$2KCl + Ca2ClO_3 = CaCl_2 + 2KClO_3.$$

Neglecting intermediate decomposition, the reactions may be represented by the following equation:—

$$\underset{\text{Chlorine.}}{6Cl_2} + \underset{\text{Carbonate of potassium.}}{K_2CO_3} + \underset{\text{Hydrate of calcium.}}{6CaH_2O_2} = \underset{\text{Chlorate of potassium.}}{2KClO_3} + \underset{\text{Carbonate of calcium.}}{CaCO_3} + \underset{\text{Chloride of calcium.}}{5CaCl_2} + \underset{\text{Water.}}{6H_2O}.$$

Chlorate of potassium is soluble in water to the extent of 6 or 7 parts in 100 at common temperatures. It is usually administered medicinally in aqueous solution, sometimes also in lozenges (*Trochisci Potassii Chloratis*, U. S. P.). Chlorate of potassium must on no account be rubbed with sulphur in a mortar or otherwise, friction of such a mixture resulting in violent explosion.

Chlorate of potassium, when heated, yields chloride of potassium and oxygen, and is the salt commonly employed in the preparation of the gas for experimental purposes. But if the action be arrested when one-third of the oxygen has escaped, the residual salt is found to contain perchlorate of potassium ($KClO_4$):—

$$2KClO_3 = KClO_4 + KCl + O_2.$$

Chloric acid ($HClO_3$) may be isolated, but is unstable, quickly decomposing into chlorine, oxygen, and perchloric acid; some other chlorate (*e. g.* $KClO_3$) must therefore be used in studying the reactions of the chloric radical. *Perchloric acid* ($HClO_4$) may be obtained by distilling perchlorate of potassium with sulphuric acid; it is quite stable, and is occasionally administered in medicine.

Table of the Chlorine Acids.

Hydrochloric acid	HCl.
Hypochlorous acid	HClO.
Chlorous acid	$HClO_2$.
Chloric acid	$HClO_3$
Perchloric acid	$HClO_4$.

The chloric radical is univalent (ClO_3). The acidulous radicals of the other chlorine acids are also univalent.

Analytical Reactions (*Tests*).

First Analytical Reaction.—To solution of a chlorate (*e. g.* chlorate of potassium) add solution of nitrate of silver; no precipitate falls, showing that the chlorine must be performing different functions to those it possesses in chlorides. Evaporate the solution to dryness, and place the residue in a small dry test-tube, or at once drop a fragment of a chlorate into a test-tube, and heat strongly; oxygen is evolved, and may be recognized by its power of reinflaming an incandescent match inserted in the tube. Boil the residue with water, and again add solution of nitrate of silver; a white precipitate falls, having all the

characters of chloride of silver, as described under hydrochloric acid.

This is a trustworthy test, and, omitting the recognition of the oxygen, may be applied in the detection of small quantities of chlorates.

Second Analytical Reaction.—To a fragment of a chlorate add two or three drops of strong sulphuric acid; an explosive gas (Cl_2O_4) is evolved, having a peculiar odor, somewhat like chlorine, but deeper in color than that element.

$$3KClO_3 + H_2SO_4 = Cl_2O_4 + KClO_4 + K_2SO_4 + H_2O.$$

Warm the upper part of the test-tube to 150° or 200° F., or introduce a hot wire; a sharp explosion ensues, due to decomposition of the gas, peroxide of chlorine, into its elements.

Third Analytical Reaction.—Heat a small fragment of a chlorate with hydrochloric acid; a yellowish-green explosive gas termed *euchlorine*, is evolved. Its color is deeper than that of chlorine, hence the name (from εὖ, *eu*, well, and χλωρός, *chlōros*, green). In odor it resembles chlorine, and is probably a mixture of that element with one of the oxides of chlorine.

Fourth Analytical Reaction.—Direct the blowpipe-flame on to charcoal until a spot is red-hot, and then place on the spot a fragment of a chlorate; deflagration ensues as with nitrates.

Bromates.

Bromates are salts closely resembling chlorates and iodates. The formula of Bromic acid is $HBrO_3$.

Iodates.

Iodic Acid (HIO_3).—Iodine is boiled in a flask with five times its weight of the strongest nitric acid (sp. gr. 1.5), in a fume-cupboard, until all action ceases. On cooling, iodic acid separates in small pyramidal crystals. These are removed, the residual liquid evaporated to dryness to remove excess of nitric acid, the residue and the first crop dissolved in a small quantity of boiling water, and the solution set aside to crystallize.

Iodate of Potassium (KIO_3).—Powder together equal weights of iodine and chlorate of potassium; to the mixture add twice its weight of water and about one-eighth of its weight of nitric acid; warm the whole until iodine disappears, and evaporate quite to dryness over a water-bath. The residue dissolved in water forms "Solution of Iodate of Potash," B. P.

In this reaction the small quantity of nitric acid furnishes corresponding amounts of nitrate of potassium and chloric acid. The chloric acid with iodine gives iodic acid and chlorine, thus:—

$$2HClO_3 + I_2 = 2HIO_3 + Cl_2.$$

The iodic acid and some chlorate of potassium then yield chloric acid and iodate of potassium,

$$HIO_3 + KClO_3 = HClO_3 + KIO_3;$$

and the two reactions alternate until the whole of the iodine has displaced the whole of the chlorine.

Iodate of potassium and sulphurous acid decompose each other with elimination of iodine (or with formation of a blue color, if starch be present). Sulphurous acid occurring as an impurity in acetic and other acids may thus be detected.

$$2KIO_3 + 5H_2SO_3 = I_2 + 3H_2SO_4 + 2KHSO_4 + H_2O.$$

Ferric Iodate, or rather *Oxyiodate* ($Fe_2O4IO_3, 8H_2O$), is precipitated on adding solution of ferric chloride to solution of iodate of potassium.

QUESTIONS AND EXERCISES.

462. How may hypochlorous acids be formed?

463. What are the relations of hypochlorous acid to common bleaching powder?

464. By what reaction is chlorine eliminated from hypochlorites?

465. State the general reaction by which chlorates are formed.

466. Give details of the preparation of chlorate of potassium.

467. Mention the properties of chlorate of potassium.

468. What decompositions occur when chlorate of potassium is heated?

469. Find the molecular weight of chlorate of potassium.

470. What weight of oxygen is yielded when 1 oz. of chlorate of potassium is completely decomposed, and how much chloride of potassium remains?

471. One hundred cubic inches of oxygen, at 60° F. and barometer at 30 inches, weighing 34.203 grains, and 1 gallon containing $277\frac{1}{4}$ cubic inches, what weight of chlorate of potassium will be required to yield 10 gallons of the gas?—*Ans.* $5\frac{1}{2}$ ounces.

472. How many cubic inches of oxygen are producible from 1 oz. of chlorate of potassium?

473. Calculate the weight of chlorate of potassium theoretically obtainable from 100 parts of chloride.

474. How is perchloric acid prepared?

475. Enumerate the chlorine acids.

476. How may the presence of chlorides in chlorates be demonstrated?

477. Mention the tests for chlorates.

478. Give the formula of peroxide of chlorine.
479. What is euchlorine?
480. How may iodic acid be made?
481. Describe the preparation of iodate of potassium.

ACETIC ACID AND OTHER ACETATES.

Formula of Acetic Acid $HC_2H_3O_2$, or $H\overline{A}$. Molecular weight 60.

Source.—Acetic acid is said to occur naturally in certain plant juices and animal fluids in minute proportions, but otherwise is an artificial product. Much is furnished by the destructive distillation of wood, hence the term *pyroligneous acid* for the crude product, a hybrid word from πῦρ, *pūr*, fire, and *lignum* wood. This impure product, neutralized by carbonate of sodium, the whole evaporated and the residue gently heated to drive off the volatile tarry matters, gives acetate of sodium, which after recrystallization furnishes by distillation with oil of vitriol and water acetic acid in a fair state of purity. In Germany and France large quantities of acetic acid are made by the spontaneous oxidation of the alcohol in inferior wines, hence the *white-* and *red-wine vinegar* (*vinegar*, from the French *vin*, wine, and *aigre*, sour). In England also the domestic form of acetic acid (brown vinegar) has a similar origin: infusion of malt and unmalted grain is fermented; and the resulting oxidation of its sugar, instead of being arrested when the product is an alcoholic liquid, a sort of beer, is allowed to go on to the next stage, acetic acid; it usually contains from 3 to 6 per cent of real acetic acid ($HC_2H_3O_2$).

Vinegars.—The official vinegar (*Acetum*, U. S. P.) contains nearly $5\frac{1}{2}$ (5.4) per cent. The so-called Vinegar of Cantharides (*Acetum Cantharidis*, B. P.) is a solution of the active principle of cantharides in very strong acetic acid, not in vinegar. The Vinegar of Squill (*Acetum Scillæ*, B. P. and U. S. P.) is also a solution of the active principle of squill in dilute acetic acid, not in true vinegar. The same may be said of *Acetum Lobeliæ*, U. S. P., *Acetum Opii*, U. S. P., and *Acetum Sanguinariæ*, U. S. P. (Vinegar of Bloodroot). Distilled vinegar (*Acetum Destillatum*, U. S. P.) is a form of Dilute Acetic Acid not now official in Great Britain. The *Acetum Opii* or *Black Drop* of America is made from nutmeg, saffron, and sugar, as well as Opium and Diluted Acetic Acid. In the British Pharmacopœia, vinegar, except its use for its own sake, is only employed in the preparation of *Emplastrum Cerati Saponis*.

The Acetic Radical.—The group of elements represented by the formula $C_2H_3O_2$ is that characteristic of acetic acid and other acetates, and may, for convenience of study, be assumed to be an acidulous univalent radical. It has not been isolated, unless indeed a compound of similar composition, resulting from the action of peroxide of barium on acetic anhydride, is the radical in question.

Acetyl.—The characteristic grouping in acetates, $C_2H_3O_2$, is frequently considered to contain, rather than to be, a radical—C_2H_3O, termed *acetyl*. Acetates may be made to yield a body having the

composition C_2H_3OCl, which is regarded as chloride of acetyl; from this may be obtained acetic anhydride ($C_4H_6O_3$), which by absorbing water becomes acetic acid.



The relation of acetic acid to alcohol will be evident from the following equation representing empirically the formation of the acid :—

$$\underset{\text{Alcohol.}}{C_2H_6O} + O_2 = \underset{\text{Acetic acid.}}{C_2H_4O_2} + H_2O$$

Acetates in aqueous solution are liable to decomposition. In solution of acetate of morphia a myceloid growth occasionally forms, acetic acid disappears, and morphia is deposited. Solution of acetate of ammonium is liable to a similar change, gradually becoming alkaline.

Synthetical Reaction.

Acetic Acid.

Synthetical Reaction.—To a few grains of acetate of sodium in a test-tube add a little water and some sulphuric acid, and heat the mixture; acetic acid is evolved, and may be condensed by a bent tube adapted to the test-tube by a cork in the usual way.

Acetic Acid.—This is the process by which acetate of sodium or calcium (the neutralized products of the distillation of wood) is made to yield acetic acid on the large scale. As with nitric and hydrochloric acids, the loose term "acetic acid" is that usually applied to aqueous solutions of acetic acid. The *Acidum Aceticum*, B. P., contains nearly 33 per cent. of real acid—that is, of $HC_2H_3O_2$; for it contains only 28 per cent. of acetic anhydride ($C_4H_6O_3$). Its specific gravity is 1.044, the specific gravity of *Acidum Aceticum*, U. S. P., being 1.047. *Acidum Aceticum Dilutum*, B. P. and U. S. P., contains $4\frac{1}{2}$ per cent. of $HC_2H_3O_2$. Glacial acetic acid ($HC_2H_3O_2$) contains no water. It solidifies to a crystalline mass at temperatures below 63° F., hence the appellation *glacial* (from *glacies*, ice). Good commercial glacial acetic acid (*Acidum Aceticum Glaciale*, B. P.) does not contain more than 1 per cent. of water, corresponding to 84.15 per cent. of acetic anhydride; it solidifies at 34°, and again liquefies at 48°: its specific gravity is 1.065. Although water is lighter than this acetic acid, yet the addition of water at first renders the acid heavier; evidently therefore condensation, or contraction in bulk, occurs on mixing the liquids: after 10 per cent. has been added, the addition of more water produces the usual effect of dilution of a heavy liquid by a lighter, namely, reduction of relative weight. This matter will be better understood after the subject of specific gravity has been studied.

The following equation is expressive of the above reaction:—

$$\underset{\text{Acetate of sodium.}}{NaC_2H_3O_2} + \underset{\text{Sulphuric acid.}}{H_2SO_4} = \underset{\text{Acetic acid.}}{HC_2H_3O_2} + \underset{\text{Acid sulphate of sodium.}}{NaHSO_4}$$

or, assuming the existence of acetyl (C_2H_3O) in acetic acid, and a corresponding radical sulphuryl (SO_2) in sulphuric acid,

$$\left.\begin{matrix}C_2H_3O\\Na\end{matrix}\right\}O + \left.\begin{matrix}SO_2\\H_2\end{matrix}\right\}O_2 = \left.\begin{matrix}C_2H_3O\\H\end{matrix}\right\}O + \left.\begin{matrix}SO_2\\NaH\end{matrix}\right\}O_2;$$

or, thirdly, on the assumption that salts contain the oxide of a basylous radical united with the anhydride of an acid (the old view under which such names as acetate of soda were formed),

$$Na_2O,C_4H_6O_3 + 2H_2O,SO_3 = Na_2O,H_2O,2SO_3 + H_2O,C_4H_6O_3.$$

Note on the Constitution of Salts.

Which of these three equations, or, more broadly, which of the three views of the constitution of salts illustrated by the equations, is correct, it is impossible to say. Whether it is $C_2H_3O_2$, C_2H_3O, or $C_4H_6O_3$, which migrates from one acetic compound to another, whether it is SO_4, SO_2, or SO_3, which migrates from one sulphuric compound to another, and so on with other acidulous groupings, cannot at present be determined. There are strong objections to each view; and possibly neither is right. Either the given radicals cannot be isolated, or application of the forces of heat, light, and electricity do not confirm views arrived at by the results of operations with the chemical force; or a salt comes to be regarded as having so large a number of constituent parts that the view, however true, breaks down in practice from the sheer inability of the mind to grasp the complicated analogies involved. Yet for the purposes of description, study, and conversation some system must be adopted. Let the first, then, be generally taken, over-reliance on it being checked by the use of general instead of special names for the hypothetical radicals, and other systems be employed in certain cases. (See also p. 253.)

Impurity.—Acetic acid often contains sulphurous acid. The methods by which this impurity is detected are described on pages 264 and 274.

Analytical Reactions (Tests).

First Analytical Reaction.—To an acetate add sulphuric acid and heat the mixture; acetic acid, recognized by its odor, is evolved.

Note 1.—Iodine, sulphurous acid, and other substances of powerful odor mask that of acetic acid; they must be removed, therefore, usually by precipitation or oxidation, before applying this test.

Note 2.—It will be noticed that this reaction is identical with the previous one; it has synthetical or analytical interest, according to the object and method of its performance.

Second Analytical Reaction.—Repeat the above action, a few drops of spirit of wine being first added to the acetate; acetic ether (acetate of ethyl, $C_2H_5C_2H_3O_2$), also of characteristic odor, is evolved.

The basylous radical ethyl (C_2H_5) will be referred to subsequently.

Third Analytical Reaction.—Heat a fragment of a dry acetate in a test-tube, and again notice the odor of the gaseous products of the decomposition, among them is *acetone* (C_3H_6O), the smell of which is characteristic. Carbonate of the metal remains in the test-tube.

Fourth Analytical Reaction.—To a solution of an acetate, made neutral by the addition of acid or alkali, as the case may be, add a few drops of neutral solution of perchloride of iron; a deep-red liquid results, owing to the formation of ferric acetate ($Fe_26C_2H_3O_2$).

Note.—It will be noticed that the formation of characteristic precipitates, the usual method of removing radicals from solution for recognition, is not carried out in the qualitative analysis of acetates. This is because all acetates are soluble. Acetate of silver ($AgC_2H_3O_2$) and mercurous acetate ($HgC_2H_3O_2$) are only sparingly soluble in cold water, but the fact can seldom be utilized in analysis. Hence peculiarities of color and odor, the next best characters on which to rely, are adopted as means by which acetates may be detected. Acetates, like other organic compounds, char when heated to a high temperature.

QUESTIONS AND EXERCISES.

482. What is the formula of acetic acid?
483. State the relation of acetic acid to other acetates.
484. What is the molecular weight of acetic acid?
485. Name the sources of acetic acid.
486. What is pyroligneous acid?
487. From what compound is the acetic acid of foreign and English vinegar immediately derived?
488. How much real acid is contained in official vinegar?
489. What is the nature of the "Vinegars" of Pharmacy?
490. How may acetic acid be obtained from acetate of sodium?
491. How much real acid is contained in the official acetic acid?
492. Mention the strength of commercial glacial acetic acid.
493. Give three or more views of the constitution of acetates, illustrating each by formulæ.
494. Enumerate the tests for acetates.

HYDROSULPHURIC ACID AND OTHER SULPHIDES.

Formula of Hydrosulphuric Acid H_2S. Molecular weight 34.

Source and Varieties of Sulphur.—The acidulous radical of *hydrosulphuric acid*, *sulphydric acid*, or *sulphuretted hydrogen*, and other sulphides, is the element sulphur (S). It occurs in nature in combination with metals, as already stated in describing the ores of some of the metals, and also in the free state. Most of the sulphur used in medicine is imported from Sicily, where it occurs chiefly associated with blue clay. It is purified by fusion, sublimation, or distillation. Melted and poured into moulds, it constitutes a crystalline mass termed *roll sulphur*. If distilled and the vapor carried into large chambers, so that it may be rapidly condensed, the crystals are so minute as to give the sulphur a pulverulent character; this is *sublimed sulphur* (*Sulphur Sublimatum*, B. P. and U. S. P.) or *flowers of sulphur:* the same washed constitutes *Sulphur Lotum*, U. S. P. The third common form, *milk of sulphur*, will be noticed subsequently. Sulphur also occurs in nature in combination as a constituent of animal and vegetable tissues, as sulphurous acid gas (SO_2) in volcanic vapors, and as sulphuretted hydrogen in some waters, as those of Harrogate.

Plastic sulphur is one of the allotropic varieties of the element, obtained on heating sulphur considerably beyond its melting-point and pouring into cold water.

Quantivalence.—Sulphur is sexivalent, as seen in sulphuric anhydride (SO_3), a substance which will be noticed under sulphuric acid. It also occasionally exhibits quadrivalent (SO_2) and still oftener bivalent affinities (H_2S).

Molecular weight.—At very high temperatures sulphur follows the rule that, under similar circumstances of heat and pressure, atomic weights (in grammes, grains, etc.) of elements occupy equal volumes of vapor; its formula therefore is S_2, and molecular weight 64. At lower temperatures the volume weighs three times as much as it should do if following usual laws, and then the molecule would appear to contain six atoms (S_6).

Acid Salts.—Sulphur (S″) being the first acidulous radical of bivalent activity met with in these sections on acids, it is desirable here to draw attention to a new class of salts to which such a radical will generally give rise. These are acid salts, which are intermediate between normal salts and acids. Univalent radicals with an atom of hydrogen give an acid, and with an atom of other basylous radicals an ordinary or normal salt. But bivalent radicals, from the fact that they give with two atoms of hydrogen an acid, and with two atoms of univalent metals a normal salt, may obviously give intermediate bodies containing one atom of hydrogen and one atom of metal; these are appropriately termed acid salts: they are neither normal acids nor normal salts, but *acid salts.* (Examples:—$KHCO_3$, $NaHSO_4$, $KHC_4H_4O_6$, Na_2HPO_4, $CuHAsO_3$, CaH_42PO_4.) Whether or not these salts give an acid reaction with blue litmus paper depends on the strength of the respective radicals. Usually

they do redden the test-paper, but sometimes not; thus the acid sulphide or sulphydrate of potassium (KHS), of sodium (NaHS), or ammonium (AmHS) has alkaline properties.*

Synthetical Reactions.

Sulphuretted Hydrogen.

First Synthetical Reaction.—The preparation of sulphuretted hydrogen.—This operation was described on page 81, and probably has already been studied by the reader.

Precipitated Sulphur.

Second Synthetical Reaction.—Prepare the variety of the radical of sulphides known as *Precipitated Sulphur* (*Sulphur Præcipitatum*, B. P. and U. S. P.) or *milk* of sulphur by boiling a few grains of flowers of sulphur (5 parts) with slaked lime (3 parts) (10 parts U. S. P.) and some water (20 parts) in a test-tube (larger quantities in an evaporating-basin), filtering, and (reserving a small portion of the filtrate) adding dilute hydrochloric acid until the well-stirred liquid has a faint acid reaction on test-paper; sulphur is precipitated, and may be collected on a filter, washed, and dried (at about 120°). Excess of acid must be avoided, or hydrosulphyl, the liquid persulphide of hydrogen (H_2S_2) will be formed, causing the particles of sulphur to aggregate to a gummy mass.

This is the process of the Pharmacopœias. Polysulphide of calcium and hyposulphite of calcium are formed:—

$$\underset{\text{Hydrate of calcium.}}{3CaH_2O_2} + \underset{\text{Sulphur.}}{6S_2} = \underset{\text{Polysulphide of calcium.}}{2CaS_5} + \underset{\text{Hyposulphite of calcium.}}{CaS_2O_3} + \underset{\text{Water.}}{3H_2O}$$

On adding the acid, both salts are decomposed and sulphur separates:—

$$\underset{\text{Polysulphide of calcium.}}{2CaS_5} + \underset{\text{Hyposulphite of calcium.}}{CaS_2O_3} + \underset{\text{Hydrochloric acid.}}{6HCl} = \underset{\text{Chloride of calcium.}}{3CaCl_2} + \underset{\text{Water.}}{3H_2O} + \underset{\text{Sulphur.}}{6S_2}$$

Polysulphide of calcium alone would yield sulphuretted hydrogen as well as sulphur on the addition of acid. Hyposulphite of calcium alone would yield sulphurous acid gas as well as sulphur. If these

* Some chemists regard these sulphydrates as compounds of basylous radicals with HS, a univalent grouping termed hydrosulphyl (persulphide of hydrogen, H_2S_2), just as hydrates are similarly viewed as compounds of the univalent radical hydroxyl (HO) (peroxide of hydrogen, H_2O_2)—H_2S becoming HHS or HHs (hydrosulphylide of hydrogen), and H_2O becoming HHO or HHo (hydroxylide of hydrogen).

gases are formed in the above operation, they at once react and give sulphur and water, very little, if any, sulphuretted hydrogen escaping.

$$4H_2S + 2SO_2 = 3S_2 + 4H_2O.$$

Impure Precipitated Sulphur.—To a sulphur solution prepared as before (or to the reserved portion) add sulphuric acid; the precipitate is in this case largely mixed with sulphate of calcium:—

$$\underset{\text{Polysulphide of calcium.}}{2CaS_5} + \underset{\text{Hyposulphite of calcium.}}{CaS_2O_3} + \underset{\text{Sulphuric acid.}}{3H_2SO_4} = \underset{\text{Sulphate of calcium.}}{3CaSO_4} + \underset{\text{Water.}}{3H_2O} + \underset{\text{Sulphur.}}{6S_2}$$

Place a little of each of these specimens of precipitated sulphur with a drop of the supernatant liquid on a strip of glass, cover each spot with a piece of thin glass, and examine the precipitates under a microscope; the pure sulphur will be found to consist of minute grains or globules, the impure to contain comparatively large crystals (sulphate of calcium).

Note.—By far the larger proportion of precipitated sulphur met with in trade still (1873) contains, to the knowledge of the Author, sulphate of calcium, most specimens affording two-thirds of their weight of that substance. Moreover, this adulteration has been so persistently practised that many persons have become sufficiently accustomed to the satiny appearance of the impure article to regard the pure article with suspicion, sometimes refusing to purchase it.

To ascertain the amount of sulphate of calcium in an impure specimen of precipitated sulphur, place a weighed quantity in a tared crucible and heat till no more vapors are evolved. The weight of the residual anhydrous sulphate of calcium ($CaSO_4$=136), with one-fourth thereof added, is the amount of crystalline sulphate of calcium ($CaSO_4$, $2H_2O$=172) present in the original quantity of impure sulphur.

Pharmacists should refuse all parcels of sulphur which yield a white ash when a little is burnt off on the end of a table-knife or spatula. (No more damage is done to the steel than a rub on a knife-board will remove.)

Analytical Reactions (Tests).

To a sulphide add a few drops of hydrochloric acid; sulphuretted hydrogen will probably be evolved, well known by its smell. If the sulphide is not acted upon by the acid, or if free sulphur be under examination, mix a minute portion with a fragment of solid caustic potash or soda, and fuse on a silver coin or spoon. When cold, place a drop of dilute hydrochloric acid on the spot, sulphuretted hydrogen is evolved, and a black stain, due to sulphide of silver (Ag_2S), left on the coin.

Other sulphur reactions may be adopted as tests, but the above are sufficient for all ordinary purposes. The most convenient reagent for detecting sulphur in solution of ammonia is ammonio-sulphate of copper, which gives a black precipitate of sulphide of copper if sulphur be present.

The *Iodide of Sulphur* (S_2I_2) has been mentioned under "Iodine." A chloride (S_2Cl_2) and bromide (S_2Br_2) may also be formed from their elements. A mixture of sulphur and chloride of sulphur is sometimes met with under the name of *hypochloride of sulphur.*

QUESTIONS AND EXERCISES.

495. In what form does sulphur occur in nature?

496. State the modes of preparation of the three chief commercial varieties of sulphur.

497. To what extent does the atom of sulphur vary in quantivalence?

498. State the relations of acid salts to acids and to normal salts.

499. Define sulphides and sulphydrates.

500. Describe the preparation of sulphuretted hydrogen.

501. What are the characters of pure precipitated sulphur?

502. Give equations explanatory of the reactions which occur in precipitating sulphur according to the official process.

503. Describe the microscopic test for impure precipitated sulphur.

504. Mention a ready physical method of detecting the adulteration of precipitated sulphur by sulphate of calcium.

505. Mention the tests for sulphides, and the character by which sulphurretted hydrogen is distinguished from other sulphides.

506. How are sulphides insoluble in acids tested for sulphur?

507. Give a method for the detection of a trace of sulphur in solution of ammonia.

SULPHUROUS ACID AND OTHER SULPHITES.

Formula of sulphurous acid H_2SO_3. Formula of sulphurous acid gas or sulphurous anhydride, commonly termed sulphurous acid, SO_2. Molecular weight of sulphurous acid 82; of the gas 64.

When sulphur is burned in the air it combines with oxygen and forms sulphurous acid gas (SO_2), more correctly termed sulphurous anhydride, or commonly, but erroneously, sulphurous acid. It is a pungent, colorless gas, readily liquefied on being passed through a tube externally cooled by a *freezing-mixture* composed of two parts of well-powdered ice (or, better, snow) with one part of common salt. If sulphurous acid gas becomes moist or is passed into water, heat is evolved and true sulphurous acid (H_2SO_3) formed. The latter body may be obtained in crystals; but it is very unstable, and hence the properties of the sulphurous radical must be studied under the form

of some other sulphite; sulphite of calcium ($CaSO_3$), or sulphite of sodium (Na_2SO_3), may be used for the purpose.

Quantivalence.—The radical of the sulphites is bivalent (SO_3''), and hence forms acid sulphites, such as acid sulphite of potassium ($KHSO_3$) and normal sulphites, such as sulphite of sodium (Na_2SO_3).

Note on Nomenclature.—The sulphites are so named from the usual rule, that salts corresponding with acids whose names end in *ous* have a name ending in *ite*. They are generally made by passing sulphurous acid gas over moist oxides or carbonates—in the latter case carbonic acid gas escaping.

Synthetical Reaction.—To a few drops of sulphuric acid in a test-tube add a piece of charcoal and apply heat; sulphurous acid gas is evolved, and may be conveyed by a bent tube into a small quantity of cold water in another test-tube. Larger quantities may be made in a Florence flask. The product is the *Acidum Sulphurosum*, B. P. and U. S. P. It is said to contain, if saturated, nearly 12 (11.79) per cent. of sulphurous acid (H_2SO_3) or about 9 (9.2) per cent. of the gas (SO_2). The process is also that described in the Pharmacopœia, except that the gas is purified by passing through a small wash-bottle before final collection. Specific gravity 1.04 (1.035, U. S. P.).

Sulphurous acid may also be made by boiling copper, mercury, or iron with sulphuric acid, sulphates of the metals being formed. Also by boiling sulphur with sulphuric acid.

If in this process the water were replaced by solutions of or solid metallic oxides or carbonates, sulphites of the various metals would be formed. The formula of sulphite of potassium (*Potassii Sulphis*, U. S. P.) is $K_2SO_3,2H_2O$; of sulphite of sodium (*Sodii Sulphis*, U. S. P.) $Na_2SO_3,7H_2O$; of the bisulphite or acid sulphite $NaHSO_3$. Under the name of *antichlor* the former is used for removing traces of chlorine from paper pulp. Sulphite of magnesium crystallized from a strong solution of sulphurous acid in water has the formula $MgSO_3,6H_2O$.

$$\underset{\text{Sulphuric acid.}}{4H_2SO_4} + \underset{\text{Carbon (charcoal).}}{C_2} = \underset{\text{Carbonic acid gas.}}{2CO_2} + \underset{\text{Water.}}{4H_2O} + \underset{\text{Sulphurous acid gas.}}{4SO_2}$$

$$\underset{\text{Sulphurous acid gas.}}{SO_2} + \underset{\text{Water.}}{H_2O} = \underset{\text{Sulphurous acid.}}{H_2SO_3}$$

Analytical Reactions (Tests).

First Analytical Reaction.—To a sulphite (of sodium, for instance—made by passing sulphurous acid into solution of carbonate of sodium) add a drop or two of dilute hydro-

chloric acid; sulphurous acid gas escapes, known by its peculiar pungent smell.

This smell is the same as that evolved on burning lucifer matches that have been tipped with sulphur. It is due, probably, not to the gas (SO_2), but to sulphurous acid (H_2SO_3) formed by the union of sulphurous acid gas with either the moisture of the air or that on the surface of the mucous membrane of the nose. It is highly suffocating.

Second Analytical Reaction.—To a sulphite add a little water, a fragment or two of zinc, and then hydrochloric acid; sulphuretted hydrogen will be evolved, known by its putrid odor and action on a piece of paper placed like a cap on the mouth of the test-tube, and moistened with a drop of solution of acetate of lead, black sulphide of lead being formed. Sulphurous acid may be detected in acetic acid, or in hydrochloric acid, by this test.

$$H_2SO_3 + H_6 = H_2S + 3H_2O.$$

Other Analytical Reactions.

To solutions of neutral sulphites add nitrate or chloride of barium, chloride of calcium, or nitrate of silver; in each case white sulphites of the various metals are precipitated. The barium sulphite is soluble in weak hydrochloric acid; but if a drop or two of chlorine-water is first added, barium sulphate is formed, which is insoluble in acids. The other precipitates are also soluble in acids. The silver sulphite is decomposed on boiling, sulphuric acid being formed, and metallic silver set free.

To recognize the three radicals in an aqueous solution of sulphides, sulphites, and sulphates, add chloride of barium, filter, and wash the precipitate. In the filtrate sulphides are detected by the sulphuretted hydrogen involved on adding an acid. In the precipitate sulphites are detected by the odor of sulphurous acid produced on adding hydrochloric acid, and sulphates by their insolubility in the acid.

QUESTIONS AND EXERCISES.

508. What are the differences between sulphurous acid and sulphurous acid gas, sulphites and acid sulphites?

509. State the characters of sulphurous acid gas.

510. How is the official Sulphurous Acid prepared?

511. By what test may sulphurous acid be recognized in acetic acid?

512. Give a method by which sulphites may be detected in presence of sulphides and sulphates.

SULPHURIC ACID AND OTHER SULPHATES.

Formula of Sulphuric Acid H_2SO_4. Molecular Weight 98.

Sulphates occur in nature; but the common and highly important hydrogen sulphate, sulphuric acid, is made artificially.

Preparation of Sulphuric Acid. General Nature of the Process.—Sulphur itself, or sometimes the sulphur in iron pyrites, is first converted into sulphurous acid gas by burning in air, and this gas, by moisture and oxygen, into sulphuric acid ($SO_2+H_2O+O=H_2SO_4$).

Details of the process.—The oxygen necessary to oxidize the sulphurous acid gas cannot directly be obtained from air, but indirectly, the agency of nitric oxide (NO) being employed—this gas becoming nitric peroxide (NO_2) by action of the air, and the nitric peroxide again becoming nitric oxide by the action of the sulphurous acid gas, and so on. A small quantity of nitric oxide gas will in this way act as carrier of oxygen from the air to very large quantities of sulphurous acid.

The following equations represent the successive steps:—

$$\underset{\text{Sulphur.}}{S_2} + \underset{\text{Oxygen (of the air).}}{2O_2} = \underset{\text{Sulphurous acid gas.}}{2SO_2}$$

$$\underset{\text{Sulphurous acid gas.}}{SO_2} + \underset{\text{Water.}}{H_2O} = \underset{\text{Sulphurous acid.}}{H_2SO_3}$$

$$\underset{\text{Nitric oxide.}}{2NO} + \underset{\text{Oxygen (of the air).}}{O_2} = \underset{\text{Nitric peroxide.}}{2NO_2}$$

$$\underset{\text{Sulphurous acid.}}{H_2SO_3} + \underset{\text{Nitric peroxide.}}{NO_2} = \underset{\text{Sulphuric acid.}}{H_2SO_4} + \underset{\text{Nitric oxide.}}{NO}$$

On the large scale the sulphurous acid gas is produced by burning sulphur in furnaces; it is carried, together with the nitric vapors, by flues into leaden chambers, where jets of steam supply the necessary moisture; the steam also, condensing, prevents other reactions. The resulting dilute sulphuric acid is concentrated by evaporation in leaden vessels.

The nitric peroxide is in the first instance obtained from nitric acid, and this from nitrate of potassium or sodium by the action of a small quantity of the sulphuric acid of a previous operation.

$$\underset{\text{Nitrate of sodium.}}{2NaNO_3} + \underset{\text{Sulphuric acid.}}{H_2SO_4} = \underset{\text{Sulphate of sodium.}}{Na_2SO_4} + \underset{\text{Nitric acid.}}{2HNO_5}$$

$$\underset{\text{Sulphurous acid.}}{3H_2SO_3} + \underset{\text{Nitric acid.}}{2HNO_3} = \underset{\text{Sulphuric acid.}}{3H_2SO_4} + \underset{\text{Water.}}{H_2O} + \underset{\text{Nitric oxide.}}{2NO}$$

Other processes.—Sulphuric acid may be obtained by other processes, as by distilling the sulphate of iron resulting from the natural oxidation of iron pyrites by air; but it is seldom so made at the present day. The sulphate of iron was formerly called *green vitriol*, and the distilled product *oil of vitriol*, in allusion to its consistence and origin.

Experiment.—For purposes of practical study, a small quantity may be made by passing, *a*, sulphurous acid gas (p. 272), *b*, nitric oxide (p. 257), *c*, air (forced through by aid of bellows or a gas-holder), and, occasionally, *d*, steam (generated in a Florence flask) through glass tubes, nearly to the bottom of a two- or three-quart flask.

$$SO_2 + H_2O = H_2SO_3; \quad | \quad 2NO + O_2 = 2NO_2;$$
$$H_2SO_3 + NO_2 = H_2SO_4 + NO.$$

A slow current of sulphurous acid gas, air, and steam, and a small quantity of nitric oxide, will furnish, in the course of a few minutes, enough sulphuric acid for recognition by the first of the following analytical reactions.

Purification.—Sulphuric acid may contain arsenic, nitrous compounds, and salts. Arsenic may be detected by the hydrogen-test (p. 149), nitrous compounds by powdered sulphate of iron (which acquires a violet tint if they are present), and salts by the residue left on boiling a little to dryness in a crucible in a fume-chamber. If only nitrous compounds are present, the acid may be purified by heating with about half per cent. of sulphate of ammonium—water and nitrogen being produced (Pelouze). If arsenic occurs, boil with a small quantity of hydrochloric acid, which converts the arsenic into chloride of arsenicum; or heat with a little nitric acid, which converts arsenious (As_2O_3) into arsenic anhydride (As_2O_5), then add sulphate of ammonium, and distil in a retort containing pieces of quartz and heat by an annular-shaped burner (to prevent "bumping"). The arsenic anhydride remains in the retort. (Arsenious anhydride would be carried over with the sulphuric-acid vapors.) By distillation the acid is also purified from salts (such as $NaHSO_4$) which are not volatile.

Quantivalence.—The sulphuric radical being bivalent (SO_4''), acid as well as normal sulphates may exist. Acid sulphate of potassium ($KHSO_4$) is an illustration of the former, sulphate of sodium (Na_2SO_4) of the latter; *double sulphates* may also occur, such as that of potassium and magnesium ($K_2SO_4, MgSO_4, 6H_2O$). Sulphates generally contain water of crystallization.

Pure sulphuric acid (H_2SO_4) is of specific gravity 1.848. The best "oil of vitriol" of commerce, a colorless liquid of oily consistence, is of specific gravity 1.843, and contains 96.8 per cent. of real acid (H_2SO_4). This is the *Acidum Sulphuricum*, B. P. and U. S. P. The *Acidum Sulphuricum Dilutum*, B. P., sp. gr. 1.094 (U. S. P. 1.082) contains about 13½ (13.64) per cent. of acid (H_2SO_4); and the *Acidum Sulphuricum Aromaticum*, B. P. and U. S. P., a dilute acid in which are dissolved the soluble aromatic parts of cinnamon and ginger, also contains nearly 13½ (13.36) per cent. of acid (H_2SO_4). There are some definite compounds of sulphuric acid with water; the first (H_2SO_4, H_2O) may be obtained in crystals.

Sulphuric anhydride (SO_2) is a white silky crystalline solid, having no acid properties. It is made by distilling sulphuric acid with phosphoric anhydride ($3H_2SO_4 + P_2O_5 = 2H_3PO_4 + 3SO_3$). It appears to unite with sulphuric acid and some other normal sulphates to form compounds (R'_2SO_4, SO_3) resembling in constitution

red chromate of potassium or borax. The fuming sulphuric acid (H_2SO_4, SO_3), made at Nordhausen in Saxony, seems to be such a body.

Note.—Sulphuric acid is a most valuable compound to all chemists and manufacturers of chemical substances. It is the key by which hundreds of chemical salts are unlocked, and their contents utilized. To describe its uses would be to write a work on chemistry.

Analytical Reactions (*Tests*).

First Analytical Reaction.—To solution of a sulphate add solution of a barium salt; a white precipitate of sulphate of barium ($BaSO_4$) falls. Add nitric acid and boil the mixture, the precipitate does not dissolve.

This reaction is as highly characteristic of sulphates as it has been stated to be of barium salts (*vide* page 88). The only error likely to be made in its application is that of overlooking the fact that nitrate and chloride of barium are less soluble in strong acid than in water. On adding the barium salt to the acid liquid, therefore, a white precipitate may be obtained, which is simply the nitrate or chloride of barium. The appearance of such a precipitate differs considerably from that of the barium sulphate; hence a careful operator will not be misled. Should any doubt remain, water should be added, which will dissolve the nitrate or chloride, but not affect the sulphate.

Second Analytical Reaction.—Mix a fragment of an insoluble sulphate ($BaSO_4$ *e. g.*) with carbonate of potassium or of sodium; or, better, with both carbonates, and fuse the mixture in a small crucible. Digest the residue when cold, in water, and filter; the filtrate may be tested for the sulphuric radical.

This is a convenient method of qualitatively analyzing insoluble sulphates, such as those of barium and lead.

Third Analytical Reaction.—Mix a fragment of an insoluble sulphate with a little alkaline carbonate on a piece of charcoal, taking care that some of the charcoal-dust is included in the mixture. Heat the little heap in the blow-pipe-flame until it fuses, and, when cold, add a drop of acid; sulphuretted hydrogen is evolved, recognized by its odor.

This is another process for the recognition of insoluble sulphates. Other preparations of sulphur, and sulphur itself, give a similar result. It is therefore rather a test for sulphur and its compounds than sulphates only; but the absence of other salts can generally, if necessary, be previously determined.

Note.—The presence of the sulphuric radical in a solution having been proved by the above reactions, its occurrence as the normal sulphate of a metal is demonstrated by the neutral, or nearly neutral, deportment of the liquid with test-paper, and the detection of the metal—its occurrence as sulphuric acid or an acid sulphate by the sourness of the liquid to the taste, and the effervescence produced on the addition of a carbonate.

Antidote.—In cases of poisoning by strong sulphuric acid, solution of carbonate of sodium (common washing-soda), magnesia and water, etc., may be administered as antidotes.

QUESTIONS AND EXERCISES.

513. What is the formula of sulphuric acid, and what its molecular weight?

514. How is it related to other sulphates?

515. Write a short article on the manufacture of sulphuric acid, giving diagrams.

516. How may nitrous compounds be detected in, and eliminated from, sulphuric acid?

517. State the method by which the presence of arsenic is detected in sulphuric acid, and explain the process by which it may be removed.

518. Define sulphates, acid sulphates, and double sulphates.

519. What percentage of real acid is contained in commercial oil of vitriol?

520. State the strength of the official "diluted" and "aromatic" sulphuric acid.

521. By what process is sulphuric anhydride obtained from Nordhausen sulphuric acid?

522. Explain the reactions which occur in testing for sulphates.

523. Ascertain by calculation the weight of oil of vitriol (of 96.8 per cent.) necessary for the production of one ton of dry sulphate of ammonium.—*Ans.* 1718 pounds.

524. Name the antidotes in cases of poisoning by strong sulphuric acid.

CARBONIC ACID AND OTHER CARBONATES.

Formula of carbonic acid H_2CO_3. Molecular weight 62. Formula of carbonic acid gas, or carbonic anhydride, commonly termed carbonic acid, CO_2.

Sources.—Carbonates (compounds containing the grouping CO_3) are very common in nature, the calcium carbonate ($CaCO_3$) being widely distributed as chalk, limestone, or marble. The hydrogen carbonate, true carbonic acid, is not known, unless, indeed, carbonic acid gas assumes that condition on dissolving in water (*Aqua Acidi Carbonici*, U. S. P.). Such a solution (see page 71) changes the

color of blue litmus-paper. and the gas does not; this may be because only the true acid (H_2CO_3) affects the litmus, or because the gas (CO_2) cannot come into real contact with the litmus without a medium. From the commonest natural carbonate, carbonate of calcium, are derived the carbonic constituents of the one most frequently used in medicine, carbonate of sodium.

Carbonate of sodium is prepared from the chief natural salt, the chloride. After the chloride has been converted into sulphate (salt-cake) by sulphuric acid,

$$2NaCl + H_2SO_4 = Na_2SO_4 + 2HCl,$$

the sulphate is roasted with limestone and small coal, by which carbonate of sodium and sulphide of calcium are formed:—

$$Na_2SO_4 + C_4 + CaCO_3 = CaS + Na_2CO_3 + 4CO.$$

Carbonic oxide gas and a little carbonic acid gas from the excess of chalk escape; the residual mass (black ash) is digested in water, in which the carbonate of sodium dissolves, the sulphide of calcium with a little oxide remaining insoluble. The solution is evaporated to dryness, and yields crude carbonate of sodium. This is roasted with a small quantity of sawdust, to convert any caustic soda resulting from the action of the lime on the carbonate, into normal carbonate. The product is *soda-ash*. Dissolved in water and crystallized, it constitutes the ordinary "soda" used for washing purposes: recrystallized and sometimes ground, it forms the official carbonate of sodium (*Sodii Carbonas*, U. S. P.) ($Na_2CO_3, 10H_2O$). The reaction is rendered more intelligible by regarding it as occurring in two stages: 1st, the reduction of the sulphate of sodium to sulphide by the carbon of the coal,

$$Na_2SO_4 + C_4 = Na_2S + 4CO;$$

2d, the reaction of the sulphide of sodium and carbonate of calcium, giving soluble carbonate of sodium, thus—

$$Na_2S + CaCO_3 = Na_2CO_3 + CaS.$$

The sulphur in the residual sulphide of calcium may be recovered by exposure to air, and the subsequent action of hydrochloric acid. Some hyposulphite of calcium (CaS_2O_3) is first formed and the action of the acid on this and undecomposed sulphide gives chloride of calcium, water, and sulphur.

Carbonic acid gas (CO_2) is a product of the combustion of all carbonaceous matters. It is constantly exhaled by animals and inhaled by plants, its intermediate storehouse being the atmosphere, throughout which it is equally distributed by *diffusion* (*vide* p. 22) to the extent of about 4 parts in 10,000. A larger proportion than that just mentioned gives to confined air depressing effects, 4 or 5 per cent. rendering the atmosphere poisonous when taken into the blood from the lungs. Carbonic acid, however, may be taken into the stomach with beneficial sedative effects; hence, probably, much of the value of such effervescing liquids as soda-water, lemonade, and solutions of the various granulated preparations and effervescing

powders (*vide* p. 73). The gas liquefies on being compressed, and the liquid solidifies on being cooled. Carbonic acid gas is twenty-two times as heavy as hydrogen, and about half as heavy again as air.

Reactions.

Synthetical and Analytical Reactions.—1. To a fragment of marble in a test-tube add water and then hydrochloric acid; carbonic acid gas (CO_2) is evolved, and may be conveyed into water or solutions of salts by the usual delivery-tube.

This is the process of the British Pharmacopœia, and the one usually adopted for experimental purposes. Passed into carbonate of sodium, the gas gives *Sodii Bicarbonas* (p. 69), and into carbonate of potassium, *Potassii Bicarbonas* (p. 58). On the large scale the gas is prepared from chalk or marble and sulphuric acid, frequent stirring promoting its escape.

2. Pass the gas into lime-water; a white precipitate of carbonate of calcium ($CaCO_3$) falls. Solution of subacetate of lead may be used instead of, and is perhaps even a more delicate test than, lime-water.

The evolution of a gas on adding an acid to a salt, warming the mixture if necessary, the gas being inodorous and giving a white precipitate with lime-water, is sufficient evidence of the presence of a carbonate. Carbonates in solution of ammonia, potash, or soda, may be detected by the direct addition of solution of lime.

3. Blow air from the lungs through a glass tube into lime-water; the presence of carbonic acid gas is at once indicated.

The passage of a considerable quantity of normal air through lime-water produces a similar effect. A bottle containing lime-water soon becomes coated with carbonate of calcium from absorption of carbonic acid gas.

4. Fill a dry test-tube with the gas, by passing the delivery-tube of the above apparatus to the bottom of the test-tube. Being rather more than once and a half as heavy as the air (1.529), it will displace the latter. Prove the presence of the gas by pouring it slowly, as if a visible liquid, into another test-tube containing lime-water; the characteristic cloudiness and precipitate are obtained on gently shaking the lime-water.

In testing for carbonates by bringing evolved gas into contact with lime-water, the preparation and adaptation of a delivery-tube may often be avoided by pouring the gas from the generating-tube into that containing the lime-water in the manner just indicated.

5. Pass carbonic acid gas through lime-water until the precipitate at first formed is dissolved. The resulting liquid is a solution of carbonate of calcium in carbonic acid water. Boil the solution; carbonic acid gas escapes, and the carbonate is again precipitated.

This experiment will serve to show how chalk is kept in solution in ordinary well-waters, giving the property of "hardness," and how the *fur* or stone-like deposit in tea-kettles and boilers is formed. It should be here stated that sulphate of calcium produces similar hardness, and that these, with small quantities of the sulphate and carbonate of magnesium, constitute the hardening constituents of well-waters, a curd (oleate of calcium or magnesium) being formed whenever soap is used with such waters. An enormous amount of soap is wasted through the employment of hard water for washing-purposes. The hardness produced by the earthy carbonates is termed "temporary hardness," because removable by ebullition; that by the earthy sulphates "permanent hardness" because unaffected by ebullition. The addition of lime-water or a mixture of lime and water removes temporary hardness (reac. 2, page 280), and carbonate of sodium, "washing soda," both temporary and permanent hardness, in the latter case sulphate of sodium remaining in solution. Carbonate of barium (ground witherite) also decomposes sulphates of calcium and magnesium, sulphate of barium being precipitated and carbonates of calcium or magnesium formed; the latter and the carbonates originally in the water may then be precipitated by ebullition or by the action of lime-water. But the injurious effects of barium salts on man and the lower animals prevents the carbonate being used for purifying water for drinking purposes, as by accident or an unforeseen reaction a portion might become dissolved.

QUESTIONS AND EXERCISES.

525. Name the chief natural carbonates.

526. What are the formulæ of carbonic acid and carbonic acid gas?

527. Adduce evidence of the existence of true carbonic acid.

528. Trace the steps by which the carbonic constituents of chalk are transferred to sodium by the process usually adopted in alkali-works—the manufacture of "soda."

529. Carbonic acid gas is constantly exhaled from the lungs of animals; why does it not accumulate in the atmosphere?

530. What is the effect of pressure on carbonic acid gas?

531. State the specific gravity of carbonic acid gas.

532. By what processes may carbonic acid gas be obtained for experimental and manufacturing-purposes?

533. Describe the action of carbonic acid gas on the carbonates of potassium or sodium.

534. How may carbonic acid be detected in expired air?

535. To what extent is carbonic acid gas heavier than air?

536. What quantity of chalk (90 per cent. pure) will be required to furnish the carbonic acid necessary to convert one ton of carbonate of potassium (containing 83 per cent. of K_2CO_3) into acid carbonate, supposing no gas to be wasted?—*Ans.* 1500 lbs.

537. Define "hardness" in water.

538. How may the presence of carbonates be demonstrated?

OXALIC ACID AND OTHER OXALATES.

Formula of Oxalic Acid $H_2C_2O_4, 2H_2O$. Molecular weight 126.

Sources.—Oxalates occur in nature in the juices of some plants, as wood-sorrel, rhubard, the common dock, and certain lichens; but the hydrogen oxalate (oxalic acid) and other oxalates are all made artificially. Many organic substances yield oxalic acid when boiled with nitric acid, and an alkaline oxalate when roasted with a mixture of the hydrates of potassium and sodium.

Experimental Process.—On the small scale, a mixture of nitric acid and loaf sugar yields the acid in the purest form, the two being boiled together for some time.

Manufacturing Process.—On the large scale, sawdust is roasted with alkalies, resulting oxalate of sodium decomposed by lime with formation of oxalate of calcium, the latter digested with sulphuric acid, and the liberated oxalic acid (Oxalic Acid of Commerce, B. P.) purified by recrystallization (Oxalic Acid, Purified, B. P., *Acidum Oxalicum*, U. S. P.).

Quantivalence.—The elements represented by the formula C_2O_4 are those characteristic of oxalates. They form a bivalent grouping; hence normal oxalates ($R'_2C_2O_4$), and acid oxalates ($R'HC_2O_4$) exist.

Salt of sorrel is a crystalline compound of oxalic acid with acid potassium oxalate, the crystals containing two molecules of water of crystallization ($KHC_2O_4, H_2C_2O_4, 2H_2O$).

Oxalate of iron (*Ferri Oxalas*, U. S. P.) is a crystalline powder made by precipitating a solution of sulphate of iron with oxalic acid. When heated in contact with air it decomposes with a faint combustion, and leaves a residue of not less than forty-eight per cent. of red oxide of iron.

Analytical Reactions (*Tests*).

First Analytical Reaction.—To solution of an oxalate (oxalate of ammonium *e. g.*) add solution of chloride of calcium; a white precipitate falls. Add to the precipitate excess of acetic acid; it is insoluble. Add hydrochloric acid; the precipitate is dissolved.

The formation of a white precipitate on adding a calcium or barium salt, insoluble in acetic but soluble in hydrochloric or nitric acid, is

usually sufficient proof of the presence of an oxalate. The action of the liquid on litmus paper, effervescence with carbonate of sodium, and absence of metals, would indicate that the oxalate is that of hydrogen, oxalic acid.

Antidote.—In cases of poisoning by oxalic acid or salt of sorrel, chalk and water may be administered as a chemical antidote (with the view of producing the insoluble oxalate of calcium), emetics and the stomach-pump being used as soon as possible.

Second Analytical Reaction.—Heat a fragment of a fixed metallic oxalate (an oxalate of potassium for example) in a test-tube; decomposition occurs, carbonic oxide (CO) (a gas that will be noticed subsequently) is liberated, and a carbonate of the metal remains. Add water and then an acid to the residue; effervescence occurs.

This is a ready test for insoluble oxalates, and is trustworthy if, on heating the substance, no charring occurs. Organic salts of metals decompose when heated, and leave a residue of carbonate, but except in the case of oxalate, the residue is always accompanied by much charcoal.

Other Analytical Reactions.—Nitrate of silver gives, with oxalates, white oxalate of silver ($Ag_2C_2O_4$).——Dry oxalates are decomposed when heated with strong sulphuric acid, carbonic oxide and carbonic acid gases escaping. If much of the substance be operated on, the gas may be washed with an alkali, the carbonic acid be thus removed, and the carbonic oxide be ignited; it will be found to burn with a characteristic bluish flame.——Oxalates, when mixed with water, black oxide of manganese (free from carbonates), and sulphuric acid, yield carbonic acid gas, which may be tested by lime-water in the usual manner.——Insoluble oxalates, such as those of calcium and magnesium, may be decomposed by ebullition with solution of carbonate of sodium; after filtration the oxalic radical will be found in the clear liquid as soluble oxalate of sodium.

Test of Purity.—"Purified oxalic acid . . . . is entirely dissipated by a heat below 350° F." (B. P.)

QUESTIONS AND EXERCISES.

539. Explain the constitution of oxalates.
540. State how oxalates are obtained.
541. What is the quantivalence of the oxalic radical?
542. Give the formula of "salt of sorrel."

543. Mention the chief test for oxalic acid and other soluble oxalates.

544. Name the antidote for oxalic acid, and describe its action.

545. By what reactions are insoluble oxalates recognized?

TARTARIC ACID AND OTHER TARTRATES.

Formula of Tartaric Acid $H_2C_4H_4O_6$, or $H_2\overline{T}$.

Molecular weight 150.

Sources.—Tartrates exist in the juice of many fruits; but it is from that of the grape that our supplies are usually obtained. Grape-juice contains much acid tartrate of potassium, which is gradually deposited when the juice is fermented, as in making wine; for acid tartrate of potassium, not very soluble in aqueous liquids, is still less so in spirituous, and hence crystallizes out as the sugar of the grape-juice is gradually converted into alcohol. It is found with tartrate of calcium lining the vessels in which wine is kept; and it is from this crude tartar* (argal or argol), as well as from what tartar may be remaining in the marc left after the juice has been pressed from the grapes, that tartaric acid and other tartrates are prepared.

Cream of Tartar, purified by crystallization (*Potassæ Tartras Acida*, B. P., *Potassii Bitartras*, U. S. P.), occurs as a "gritty white powder, or fragments of cakes crystallized on one surface;" of a pleasant acid taste, soluble in 180 parts of cold and 6 of boiling water, insoluble in spirit.

Quantivalence.—The elements represented by the formula $C_4H_4O_6$ are those characteristic of tartrates. They form a bivalent grouping; hence normal tartrates ($R'_2\overline{T}$) and acid tartrates ($R'H\overline{T}$) exist. Tartrate of potassium, the *Potassii Tartras* of the U. S. Pharmacopœia ($K_2C_4H_4O_6$) and Rochelle Salt, or tartrate of potassium and sodium ($KNaC_4H_4O_6$, $4H_2O$); the official *Potassii et Sodii Tartras* (*Soda Tartarata*, B. P.), are illustrations of normal tartrates, while Cream of Tartar is an example of acid tartrates. The only official tartrate not apparently included in these general formulæ is tartar-emetic (*Antimonium Tartaratum*, B. P., *Antimonii et Potassii Tartras*, U. S. P.), which is sometimes regarded as the double tartrate of potassium and a hypothetical radical, antimonyl (SbO), thus, $KSbOC_4H_4O_6$. Possibly, however, it is but an oxytartrate of antimony ($Sb_2O_2\overline{T}$) with normal tartrate of potassium ($K_2\overline{T}$); for there are several oxycompounds of antimony analogous to the oxycompounds

* "It is called *tartar*," says Paracelsus, "because it produces oil, water, tincture, and salt, which burn the patient as tartarus does." *Tartarus* is Latin (Τάρταρος Tartaros, Greek) for *hell*. The products of its destructive distillation are certainly somewhat irritating in taste and smell; and the "salt" (carbonate of potassium) that is left is diuretic, and, in larger quantities, powerfully corrosive.

A boiling solution of tartar yields a floating crust of minute crystals on cooling, hence the term *cream* of tartar.

of bismuth that have been described (p. 225), normal salts partially decomposed by water into oxides, and many of these oxycompounds readily unite with normal salts of other basylous radicals. Tartar emetic would thus be oxytartrate of antimony with tartrate of potassium ($Sb_2O_2\overline{T}$, $K_2\overline{T}$, or $Sb_2O_2C_4H_4O_6$, $K_2C_4H_4O_6$).

Tartaric Acid.

Tartaric Acid (*Acidum Tartaricum*, B. P. and U. S. P.) is obtained, according to the British Pharmacopœia, by boiling cream of tartar (*Potassæ Tartras Acida*, B. P., *Potassii Bitartras*, U. S. P.) with water, adding chalk till effervescence ceases, and then chloride of calcium so long as a precipitate falls; the two portions of tartrate of calcium thus consecutively formed are thoroughly washed, treated with sulphuric acid, the mixture boiled for a short time, resulting sulphate of calcium mostly separated by filtration, the filtrate concentrated by evaporation, any sulphate of calcium that may have deposited removed as before, and concentration continued until the solution is strong enough to crystallize. Tartrate of calcium from 9 ounces of cream of tartar requires 5 ounces by weight of sulphuric acid for complete decomposition.

$$\underset{\text{Acid tartrate of potassium.}}{2KH\overline{T}} + \underset{\text{Carbonate of calcium.}}{CaCO_3} = \underset{\text{Tartrate of calcium.}}{Ca\overline{T}} + \underset{\text{Tartrate of potassium.}}{K_2\overline{T}} + \underset{\text{Water.}}{H_2O} + \underset{\text{Carbonic acid gas.}}{CO_2}$$

$$\underset{\text{Tartrate of potassium.}}{K_2\overline{T}} + \underset{\text{Chloride of calcium.}}{CaCl_2} = \underset{\text{Tartrate of calcium.}}{Ca\overline{T}} + \underset{\text{Chloride of potassium.}}{2KCl}$$

$$\underset{\text{Tartrate of calcium.}}{2Ca\overline{T}} + \underset{\text{Sulphuric acid.}}{2H_2SO_4} = \underset{\text{Sulphate of calcium.}}{2CaSO_4} + \underset{\text{Tartaric acid.}}{2H_2\overline{T}}$$

Tartaric acid occurs in colorless crystals, or the same powdered. It is strongly acid and readily soluble in water or spirit. One part in 8 of water and 2 of spirit of wine forms "Solution of Tartaric Acid," B. P. Its aqueous solution is not stable.

Parcels of tartaric acid often contain crystals of an allotropic or physically isomeric modification (*vide* "Allotropy" and "Isomerism" in Index). It is termed *Paratartaric acid* (*παρά*, *para*, beside) or *Racemic acid* (*racemus*, a bunch of grapes), and is a combination of ordinary tartaric acid, whose solution twists a ray of polarized light to the right hand (dextrotartaric or dextroracemic acid) and of lævotartaric or lævoracemic acid, whose solution twists a polarized ray to the left. Racemic acid is inactive in this respect, the opposite properties of its constituents neutralizing each other. Racemic acid is less soluble in alcohol than tartaric acid.

Reactions.

Tartrate of Potassium.

Synthetical Reactions.—To a small quantity of a strong solution of carbonate of potassium add acid tartrate of potassium so long as effervescence occurs; the resulting

liquid is solution of normal tartrate of potassium (*Potassii Tartras*, U. S. P.) ($K_2\overline{T}$), crystals of which may be obtained on evaporation.

Note.—This is a common method of converting an acid salt of a bivalent acidulous radical into a normal salt. The carbonate added need not be a carbonate of the same, but may be of a different metal; compounds like Rochelle salt ($KNa\overline{T}$) are then obtained. Thus:—

Tartrate of Potassium and Sodium.

To a strong hot solution of carbonate of sodium add acid tartrate of potassium until effervescence ceases; the resulting liquid is solution of tartrate of potassium and sodium; on cooling, it yields crystals. This is the official process (*Soda Tartarata*, B. P., *Potassii et Sodii Tartras*, U. S. P.) ($KNaC_4H_4O_6,4H_2O$).

$$\underset{\text{Carbonate of sodium.}}{Na_2CO_3} + \underset{\text{Acid tartrate of potassium.}}{2KHC_4H_4O_6} = \underset{\text{Tartrate of potassium and sodium.}}{2KNaC_4H_4O_6} + \underset{\text{Water.}}{H_2O} + \underset{\text{Carbonic acid gas.}}{CO_2}$$

Crystals of Rochelle salt are usually halves of colorless, transparent, right rhombic prisms, slightly efflorescent in dry air, soluble in five parts of boiling water. Tartrate of potassium is slightly deliquescent, soluble in about four parts of boiling water.

Equivalent Weights *of Tartaric Acid, Carbonate of Potassium, Bicarbonate of Potassium, Carbonate of Sodium, Bicarbonate of Sodium, and Carbonates of Ammonium and Magnesium; repeated for* 20 *parts of each* (and, incidentally, for other proportions.)

Tart. Acid.....	$H_2C_4H_4O_6$..... = 150	20	18¼	15	10½	17¾	25½	31½
Carb. Potas.....	K_2CO_3 (of 84 per cent.)... = 164	22	20	16½	11½	19½	28	34½
Bicarb. Pot.....	$2(KHCO_3)$..... = 200	26¾	24½	20	14	23¾	34	42
Carb Soda (cryst.)	$Na_2CO_3,10H_2O$..... = 286	38	34¾	28½	20	34	48½	60
Bicarb. Sod.....	$2(NaHCO_3)$..... = 168	22½	20¼	16¾	11¾	20	28½	35¼
Carb. Ammon....	$(N_4H_{16}C_3O_3)\div 2$..... = 118	15¾	14½	11¾	8¼	14	20	24¾
Carb. Magnes.....	$(MgCO_3)_3Mg2HO,4H_2O$.... = 95.5	12¾	11½	9¾	6¾	11¼	16	20

Thus 20 parts (grains or other weights) of tartaric acid neutralize 22 of carbonate of potassium, 26¾ of bicarbonate of potassium, 38 of carbonate of sodium, 22½ of bicarbonate of sodium, 15¾ of carbonate of ammonium, or 12¾ of carbonate of magnesium. Other quantities of tartaric acid (18¼, 15, 10½, 17¾, 25½, 31½) saturate the amounts of salts mentioned in the other columns and *vice versâ*. A similar Table for Citric Acid will be found at page 290, and for both acids in the Appendix. These Tables afford good illustrations

of the laws of chemical combination (page 40). The reader should verify a few of the numbers by calculation from the atomic weights of the elements concerned in the reactions, remembering that the salts formed are considered to be neutral in constitution. In medical practice effervescing saline draughts are often designedly prescribed to contain an amount of acid or alkali considerably in excess of the proportions required for perfect neutrality.

A common form of *Seidlitz Powder* consists of 3 parts of Rochelle salt (120 grains) with 1 (40 grains) of acid carbonate of sodium (the mixture usually wrapped in blue paper), and 1 (40 grains) of tartaric acid (wrapped in white paper). When administered, the latter is dissolved in a tumbler rather more than half full of water, the former added, and the mixture drunk during effervescence. It will be seen that the salts swallowed are tartrate of potassium and sodium ($KNa\overline{T},4H_2O$), tartrate of sodium ($Na_2\overline{T},2H_2O$), and acid tartrate of sodium or potassium. The last-mentioned salt results because $11\frac{1}{4}$ per cent. ($4\frac{1}{2}$ grains) of the tartaric acid is in excess of the quantity necessary for the formation of neutral tartrate of sodium. This amount of acid salt gives agreeable acidity to the draught. The United States formula (*Pulveres Effervescentes Aperientes*, U. S. P.) includes rather less tartaric acid, so that only neutral salts are formed.

Analytical Reactions (*Tests*).

First Analytical Reaction.—To solution of any normal tartrate, or tartaric acid made neutral by solution of soda, add solution of chloride of calcium; a white precipitate, tartrate of calcium, falls. Collect the precipitate on a filter, wash, place a small quantity in a test-tube, and add solution of potash; on stirring the mixture the precipitate dissolves. Heat the solution; the tartrate of calcium is again precipitated.

The solubility of tartrate of calcium in cold potash solution enables the analyst to distinguish between tartrates and citrates, otherwise a difficult matter. Citrate of calcium is not soluble in the alkali. The absence of much ammonical salt must be insured in both cases, the precipitates being soluble in such liquids.

Second Analytical Reaction.—Acidulate a solution of a tartrate with acetic acid, add acetate of potassium, and well stir the mixture; a crystalline precipitate of acid tartrate of potassium slowly separates. The precipitate being insoluble in alcohol, the addition of a little spirit of wine renders the test more delicate.

This reaction is not applicable in testing for very small quantities of tartrates, the acid tartrate of potassium being not altogether insoluble.

Third Analytical Reaction.—To a neutral solution of a tartrate add solution of nitrate of silver; a white precipitate of tartrate of silver, $Ag_2C_4H_4O_6$, falls. Boil the mixture; it blackens, owing to the reduction of the salt to metallic silver.

Other Reactions.—Tartrates heated with strong sulphuric acid char immediately.——Tartaric acid and the soluble tartrates prevent the precipitation of ferric and other hydrates by alkalies, soluble double tartrates being formed (which on evaporation yield liquids that do not crystallize, but, spread on sheets of glass, dry up to thin transparent plates or scales). The ferri et potassii tartras, U. S. P. (*Ferrum Tartaratum*, B. P.), is a preparation of this kind. ——Tartrates decompose when heated, carbonates being formed and carbon set free, the gaseous products having a peculiar, more or less characteristic smell, resembling that of burnt sugar.

QUESTIONS AND EXERCISES.

546. State the origin of tartaric acid and other tartrates, and explain the deposition of argol, crude acid tartrate of potassium, during the manufacture of wine.

547. What are the chemical formula and characters of "cream of tartar?"

548. Mention the formula and quantivalence of the tartaric radical.

549. Write formulæ of normal, acid, and double tartrates, tartar-emetic being treated as an oxytartrate of antimony with tartrate of potassium.

550. Give equations or diagrams illustrative of the production of tartaric acid from cream of tartar.

551. By what general process may normal or double tartrates be obtained from acid tartrate of potassium?

552. Work out sums proving the correctness of some of the figures given on p. 286 as showing the saturating power of tartaric acid for various quantities of different carbonates, and give diagrams or equations of the reactions.

553. State the names and quantities of the salts resulting from the admixture of 120 grains of tartrate of potassium and sodium, 40 grains of acid carbonate of sodium, and 40 grains of tartaric acid (Seidlitz powder).

554. Enumerate the tests for tartrates, and explain the effects of heat on tartrates of the metals.

CITRIC ACID AND OTHER CITRATES.

Formula of Citric Acid $H_3C_6H_5O_7$, H_2O or $H_3\overline{Ci}Aq$.
Molecular weight 210.

Source.—Citric acid (*Acidum Citricum*, B. P. and U. S. P.) exists in the juice of many of our common garden fruits; thus the pulp of the fruit of *Tamarindus indica* (*Tamarindus*, B. P. and U. S. P.) contains nearly 10 per cent. (in addition to 1.5 of tartaric acid, .5 of malic acid, and 3 per cent. of acid tartrate of potassium). But it is from the lemon or lime that the acid of commerce is usually obtained.

Process.—The British Pharmacopœia directs that the hot lemon-juice (4 pints) be saturated by powdered chalk (4½ ounces), the resulting citrate of calcium collected on a filter, washed with hot water till the liquor passes from it colorless (by which not only the coloring matter but the mucilage, sugar, and other constituents of the juice are got rid of), then mixed with cold water (1 pint), decomposed by sulphuric acid (2½ fluidounces in 1½ pint of water), the mixture boiled for half an hour, filtered, the solution evaporated to a density of 1.21, set aside for 24 hours, then poured off from any deposit of crystalline sulphate of calcium, further concentrated, and set aside to crystallize.

$$\underset{\text{Citric acid (impure).}}{2H_3C_6H_5O_7} + \underset{\text{Carbonate of calcium.}}{3CaCO_3} = \underset{\text{Citrate of calcium.}}{Ca_3 2C_6H_5O_7} + \underset{\text{Water.}}{3H_2O} + \underset{\text{Carbonic acid gas.}}{3CO_2}$$

$$\underset{\text{Citrate of calcium.}}{Ca_3 2C_6H_5O_7} + \underset{\text{Sulphuric acid.}}{3H_2SO_4} = \underset{\text{Citric acid (pure).}}{2H_3C_6H_5O_7} + \underset{\text{Sulphate of calcium.}}{3CaSO_4}$$

Quantivalence.—The elements represented by the formula $C_6H_5O_7$ are those characteristic of citrates. They form a trivalent grouping; hence three classes of salts may exist—one, two, or three atoms of the basylous hydrogen in the acid, $H_3C_6H_5O_7$, being displaced by equivalent proportions of other basylous radicals.

Citric acid itself is the only citric compound of much direct importance to the pharmacist. It usually occurs in colorless crystals soluble in half their weight of boiling and three-fourths of cold water, less soluble in spirit, and insoluble in ether. A solution of about 34 grains in 1 ounce of water forms a sort of artificial lemon-juice. Citrates heated with strong sulphuric acid to about 212° F. evolve carbonic oxide gas, and at higher temperatures acetone and carbonic acid gas.

Action of heat on citric acid.—Citric acid slowly heated first loses its water of crystallization; afterwards (347° F.) the elements of another molecule of water are evolved and a residue obtained from which ether extracts *aconitic acid* ($H_3C_6H_3O_6$), identical with the aconitic acid (and the acid first termed *equisetic*) in various species of *Aconitum* and *Equisetum*.

"*Effervescing Citrate of Magnesia*," so-called, is generally a mixture of bicarbonate of sodium, citric acid, tartaric acid, sugar, either carbonate or sulphate of magnesium (sometimes neither) and

occasionally essence of lemon. True citrate of magnesium is easily made by heating together calcined magnesia and citric acid; it is frequently prescribed in France in doses of two ounces. *Liquor Magnesii Citratis*, U. S. P., is a bottled mixture of magnesia, citric acid, and syrup, with bicarbonate of potassium, and sufficient water to nearly fill the bottle, which is closed by a cork secured with twine.

The official Lemon Juice (*Succus Limonum*, B. P., *Limonis Succus*, U. S. P.) is to be freshly expressed from the ripe fruit, and contain an average of 32.5 grains of citric acid in 1 fluidounce. The acidity may be ascertained by adding solution of potash or soda (the strength of which has been previously determined with pure crystals of citric acid) till red litmus paper is fairly turned blue. Before applying this test to commercial specimens, the absence of notable quantities of sulphuric, hydrochloric, acetic, tartaric, or other acid must be insured by application of appropriate reagents.

Mistura Potassii Citratis, U. S. P., is lemon juice completely neutralized by bicarbonate of potassium. It is a slightly impure but flavored solution of citrate of potassium.

Equivalent Weights *of Citric Acid, Carbonate of Potassium, Bicarbonate of Potassium, Carbonate of Sodium, Bicarbonate of Sodium, and Carbonates of Ammonium, and Magnesium; repeated for* 20 *parts of each* (and, incidentally, for other proportions).

Citric Acid.....	$H_3C_6H_5O_7,H_2O$..... = 210	20	17	14	9¾	16⅔	23¾	29½
Carb. Potas.....	(K_2CO_3; of 84 p.ct.)÷2×3 = 246½	23½	20	16½	11½	19¾	28	34½
Bicarb Pot.....	$3(KHCO_3)$..... = 300	28½	24½	20	14	24	34	41¾
Carb. Sod.(cryst.)	($Na_2CO_3,10H_2O$)÷2×3.... = 429	40	34¾	28½	20	34½	48½	60
Bicarb. Sod.....	$3(NaHCO_3)$..... = 252	24	20¾	16¾	11¾	20	28½	35
Carb. Ammon....	($N_4H_{16}C_6O_8$)÷4×3..... = 177	16¾	14¼	11¾	8¼	14	20	24¾
Carb. Magnes....	$(MgCO_3)_3Mg2HO,4H_2O$ ÷S×3 = 143¼	13½	11¾	9½	6⅝	11½	16¼	20

Thus 20 parts (grains, or other weights) of citric acid neutralize 23½ of carbonate of potassium. 28½ of bicarbonate of potassium, 40 of carbonate of sodium, 24 of bicarbonate of sodium, 16¾ of carbonate of ammonium, or 13½ of carb. of magnesium. Other quantities of acid (17, 14, 9¾, 16⅔, 23¾, 29¼) saturate the amounts of salts mentioned in the other columns, and *vice versâ*.

This Table, the similar one for tartaric acid (p. 286), and that for both acids (*vide* Appendix) afford good illustrations of some of the laws of chemical combination (p. 40). The reader should verify a few of the numbers by calculation from the atomic weights of the elements concerned in the reactions, remembering that the salts formed are considered to be neutral in constitution. In medical practice, effervescing saline draughts are often designedly prescribed to contain an amount of acid or alkali considerably in excess of the proportions required for perfect neutrality.

Analytical Reactions (Tests).

First Analytical Reaction.—To a dilute solution of any neutral citrate, or citric acid carefully neutralized by alkali, add solution of chloride of calcium and boil; a white precipitate, citrate of calcium ($Ca_3\overline{Ci}_2$), falls. Treat the precipitate as for tartrate of calcium (p. 287); it is *not* dissolved by the potash.

A mixture of citrates and tartrates can be separated by this reaction. They are precipitated as calcium salts, and the washed precipitate mixed with solution of potash, diluted, and filtered; the filtrate contains the tartrate, which is shown to be present by reprecipitation on boiling. The precipitate still on the filter is washed, dissolved in solution of chloride of ammonium, and the solution boiled; the citrate of calcium is reprecipitated. The presence of much sugar interferes with this reaction. A dilute solution of a citrate is not precipitated by chloride of calcium until the liquid is heated: precipitation from a strong solution, also, is not thoroughly complete without ebullition of the mixture.

Second Analytical Reaction.—To a neutral solution of a citrate add solution of nitrate of silver; a white precipitate of citrate of silver ($Ag_3\overline{Ci}$) falls. Boil the mixture; the precipitate does not turn black as a tartrate of silver does.

Other Analytical Reactions.—Citric acid forms no precipitate corresponding with the acid tartrate of potassium. ——Lime-water, in excess, gives no precipitate with citric acid or citrates, unless the solution is boiled, citrate of calcium being slightly soluble in cold but not in hot water; it usually precipitates tartrates in the cold.——Citrates, when heated with strong sulphuric acid, do not char immediately.——Citric acid and citrates prevent the precipitation of oxide of iron by alkalies, soluble double compounds being formed. The *Ferri et Ammonii Citras*, U. S. P., is a preparation of this kind.——Metallic citrates decompose when heated, carbonates being formed and carbon set free: the odor of the gaseous products is not so characteristic as that of tartrates.

QUESTIONS AND EXERCISES.

555. What is the source of citric acid?

556. Describe the method by which citric acid is prepared, giving diagrams.

557. Illustrate by formulæ the various classes of tartrates and citrates.

558. State the average proportion of citric acid in lemon-juice.

559. Work out the sums proving the correctness of some of the figures given on page 290 as showing the saturating-power of citric acid for various carbonates.

560. What are the tests for citrates?

561. How are the tartrates separated from citrates?

PHOSPHORIC ACID AND OTHER PHOSPHATES.

Formula of Phosphoric Acid H_3PO_4. Molecular weight 98.

Source.—The source of the ordinary normal phosphates and of phosphorus itself (*Phosphorus*, B. P. and U. S. P.) is the normal phosphate of calcium (Ca_32PO_4). It is the chief constituent of the bones of animals, being derived from the plants on which they feed, plants again obtaining it from the soil. Compounds of phosphorus are also met with in the brain, nerves, muscles, blood, saliva, and, according to Kirkes, even in tissues so simple that one must assume them to be necessary constituents of the substance of the primary cell. They escape from the system both in the urine and fæces.

Process.—Phosphorus (P = 31) is obtained from bones by the following processes: The bones are burnt to remove all traces of animal matter. The resulting *bone-earth* is treated with sulphuric acid and water, by which an acid phosphate (CaH_42PO_4), often called *superphosphate of lime*, is produced:—

$$Ca_32PO_4 + 2H_2SO_4 = CaH_42PO_4 + 2CaSO_4.$$

The acid phosphate (strained from the sulphate) is mixed with charcoal and sand, and heated to dull redness in an iron pot. At this stage water escapes and metaphosphate of calcium (Ca_2PO_3, see Index) remains:—

$$CaH_42PO_4 = Ca2PO_3 + 2H_2O.$$

The mixture is then transferred to a retort and distilled at a strong red heat; silicate of calcium ($CaSiO_3$) is formed and remains in the retort, phosphorus vapor is evolved and condensed under water, and carbonic oxide gas escapes:—

$$2(Ca2PO_3) + 2SiO_2 + C_{10} = 2CaSiO_3 + 10CO + P_4.$$

It is purified by melting under water containing sulphuric acid and red chromate of potassium.

Properties.—Phosphorus is "a semitransparent, colorless, wax-like solid (in sticks or cakes), which emits white vapors when exposed to the air. Specific gravity 1.77. It is soft and flexible at common temperatures, melts at 110°, ignites in the air at a temperature a little above its melting-point, burning with a luminous flame and producing dense white fumes. Insoluble in water, but soluble in ether and in boiling oil of turpentine," also in bisulphide of carbon. It is very poisonous.

Granulated or pulverulent phosphorus is obtained by placing under equal parts of spirit and water in a bottle, standing the bottle in warm water till the phosphorus melts, then inserting the stopper (glass, not cork) and shaking the whole till cold.

Red or Amorphous Phosphorus.—Ordinary phosphorus kept at a temperature of about 450° Fahr., in an atmosphere from which air is excluded, becomes red, opaque, insoluble in liquids in which ordinary phosphorus is soluble, oxidizes extremely slowly, and only ignites when heated to near 500° Fahr. It is used in the manufacture of several varieties of lucifer-matches, not emitting the poisonous jaw-destroying fumes given by ordinary phosphorus.

Quantivalence.—The atom of phosphorus is quinquivalent, as seen in the pentachloride (PCl_5) and oxychloride (PCl_3O); but it often exhibits trivalent activity, as seen in the trichloride (PCl_3) and trihydride (PH_3).

Molecular Weight.—Phosphorus is an exception to the rule that the atomic weights (in grains, grammes, etc.) of elements occupy similar volumes of vapor at similar temperatures, the equivalent weight of phosphorus (31) only giving half such a volume. Hence while the molecular weights, that is, double the atomic weights, of oxygen ($O_2 = 32$), hydrogen ($H_2 = 2$), nitrogen ($N_2 = 28$), etc. give a similar bulk of vapor at any given temperature; the double atomic weight of phosphorus ($P_2 = 62$) only gives half this bulk; that is, four times the atomic weight of phosphorus must be taken to obtain the whole bulk. It would appear therefore that the molecule of phosphorus contains four atoms ($P_4 = 124$). As with sulphur, however, phosphorus in the state ordinarily known to us may be abnormal, and a variety yet be found in which the molecular weight is double the atomic weight.

Phosphoric Acid.

The chief use of phosphorus in pharmacy is in the formation of Diluted Phosphoric Acid. Phosphorus is boiled with nitric acid and water until dissolved. The solution, evaporated to a low bulk to remove nitrous compounds, and rediluted so as to contain nearly 14 (13.8) per cent. of acid (H_3PO_4), equivalent to 10 per cent. of phosphoric anhydride (P_2O_5), constitutes the *Acidum Phosphoricum Dilutum*, B. P. and U. S. P., a colorless sour liquid of specific gravity 1.08 (1.056 U. S. P.). If the necessary appliances are at hand, four or five ounces of this acid may be prepared as follows: A quarter of a pint is made by boiling together, in a retort attached to a Liebig's condenser, 103 grains of phosphorus, $1\frac{1}{2}$ fluidounce of the official nitric acid, and 2 ounces of water. When about 1 oz. of water has distilled over, it should be returned to the retort, and the operation repeated until the phosphorus has disappeared.

$$\underset{\text{Phosphorus.}}{3P_4} + \underset{\text{Nitric acid.}}{20HNO_3} + \underset{\text{Water.}}{8H_2O} = \underset{\text{Phosphoric acid.}}{12H_3PO_4} + \underset{\text{Nitric oxide.}}{20NO}$$

The liquid remaining in the retort is then transferred to a dish (preferably of platinum), evaporated down to about half an ounce, and, lastly, diluted with distilled water to 5 fluidounces.

The use of the water in this process is to moderate the reaction. Strong hot nitric acid oxidizes phosphorus with almost explosive rapidity, hence must not only be diluted in the first instance, but be rediluted, from time to time, to prevent its becoming too strong by loss of water. Deficiency of nitric acid must also be avoided, or some phosphorous acid (H_2PHO_3) will be formed. A flask, in the neck of which a funnel is inserted, and a second funnel inverted, so that its mouth rests within the mouth of the first, is an efficient and convenient arrangement of apparatus for this process, especially if the operation be conducted slowly.

Solution of phosphoric acid evaporated leaves a residue which melts at a low red heat, yielding *pyrophosphoric acid*, and, finally, *metaphosphoric acid* (*Glacial Phosphoric Acid*).

Quantivalence.—The elements represented by the formula PO_4 are those characteristic of phosphates. The grouping is trivalent; hence there may exist trimetallic or normal phosphate (M'_3PO_4), dimetallic acid phosphates (M'_2HPO_4), monometallic acid phosphates ($M'H_2PO_4$), and, lastly, trihydric phosphate (H_3PO_4), or common phosphoric acid. These are the ordinary phosphates met with in nature or used in pharmacy; the rarer pyrophosphates, metaphosphates, phosphites, and hypophosphites will be mentioned subsequently.

Analytical Reactions (*Tests*).

First Analytical Reaction.—To an aqueous solution of a phosphate (*e. g.* Na_2HPO_4) add solution of sulphate of magnesium with which chloride of ammonium and ammonia have been mixed; a white crystalline precipitate of ammonio-magnesium phosphate falls ($MgAmPO_4$).

Chloride of ammonium is added to prevent the precipitation of hydrate of magnesium. Arseniates, from their close analogy to phosphates, give a similar precipitate with the magnesium reagent.

Second Analytical Reaction.—To a neutral aqueous solution of a phosphate add solution of nitrate of silver; light-yellow phosphate of silver (Ag_3PO_4) is precipitated. To a portion of the precipitate add ammonia; it dissolves. To another portion add nitric acid; it dissolves.

By this reaction phosphates may be distinguished from their close allies the arseniates, arseniate of silver being of a chocolate color.

Third Analytical Reaction.—To a solution (in a few drops of acid) of a phosphate insoluble in water (*e. g.* $Ca_3 2PO_4$) add an alkaline acetate (that is, a mixture of soda or ammonia with excess of acetic acid), and then a drop or two of solution of perchloride of iron; yellowish-white ferric phosphate (Fe_2PO_4) is precipitated.

Too much of the ferric chloride must not be added, or ferric acetate will be produced, in which ferric phosphate is to some extent soluble.

To remove the whole of the phosphoric radical from the solution, add ferric chloride so long as a precipitate is produced, and then boil the mixture; ferric phosphate and ferric oxyacetate are precipitated.

To obtain confirmatory evidence of the presence of phosphate in this precipitate, and to separate the phosphoric radical as a pure unmixed phosphate, collect the precipitate on a filter, wash, drop some solution of ammonia on it, then sulphydrate of ammonium, and finally wash with water; black ferrous sulphide remains on the filter, while phosphate of ammonium occurs in the filtrate. To the filtrate add a mixture of solutions of sulphate of magnesium and chloride of ammonium, and well stir; ammonio-magnesian phosphate is precipitated.

The above reaction is useful in the analysis of bone-earth, other earthy phosphates, phosphate of iron, and all phosphates insoluble in water. Only arseniates give similar appearance; but the acid solution of these may be decomposed by sulphuretted hydrogen (H_2S), especially after agitation with sulphurous acid and subsequent ebullition.

Other Analytical Reactions.—Solutions of barium and calcium salts give, with aqueous solutions of phosphates, white precipitates of the respective phosphates $BaHPO_4$, or $Ba_3 2PO_4$, and $CaHPO_4$, or $Ca_3 2PO_4$, all of which are soluble in acetic and the stronger acids.

QUESTIONS AND EXERCISES.

562. State the source of phosphorus.

563. Give equations or diagrams explanatory of the isolation of phosphorus from its natural compounds.

564. What is the composition of farmers' "superphosphate," and how prepared?

565. Enumerate the properties of phosphorus.

566. Mention some solvents of phosphorus.
567. How is the official Diluted Phosphoric Acid made?
568. Describe the precautions necessary to be observed in making this acid.
569. What is the strength of the official acid?
570. Write formulæ illustrative of all classes of orthophosphates.
571. Mention the chief tests for soluble and insoluble phosphates.
572. By what reactions may phosphates be distinguished from arseniates?

Vanadium, V. 51.3, is a very rare element, and is here mentioned only because of its exceedingly interesting relationship to nitrogen, phosphorus, and arsenicum. Discovered but not isolated by Sefstrom, and its compounds investigated by Berzelius, it has only recently been obtained in the free state and fully studied by Roscoe.

Oxides of Nitrogen.		Oxides of Vanadium	
$N_2O_5, N_2O_4, N_2O_3, N_2O_2, N_2O.$		$V_2O_5, V_2O_4, V_2O_3, V_2O_2, V_2O$	
Orthophosphates	$R_3'PO_4$	Orthovanadates	$R_3'VO_4$
Pyrophosphates	$R_4'P_2O_7$	Pyrovanadates	$R_4'V_2O_7$
Metaphosphates	$R'PO_3$	Metavanadates	$R'VO_3$

Isomorphous Minerals.

Apatite	$3(Ca_32PO_4),CaFl_2$
Pyromorphite	$3(Pb_32PO_4),PbCl_2$
Mimetesite	$3(Pb_32AsO_4),PbCl_2$
Vanadinite	$3(Pb_32VO_4),PbCl_2$

BORACIC ACID AND OTHER BORATES.

Formula of Boracic Acid H_3BO_3. Molecular weight 62.

The composition of artificial boracic acid is expressed by the formula H_3BO_3; but at a temperature of 212° F. this body loses the elements of water and yields metaboracic acid, HBO_2. The latter acid exists in the jets of steam (*fumerolles* or *suffioni*) that issue from the earth in some districts of Tuscany, and collects in the water of the *lagoni* (lagoons or little lakes) formed at the orifice of the steam-channel. This acid liquid evaporated by aid of the waste natural steam and neutralized by carbonate of sodium gives common borax ($2NaBO_2$, $2HBO_2$,$9H_2O$), possibly an acid metaborate of sodium, with water of crystallization. It occurs "in transparent colorless crystals, sometimes slightly effloresced, with a weak alkaline reaction; insoluble in rectified spirit, soluble in water." Borax is also found native, particularly in Thibet. Fused borax readily dissolves metallic oxides, as will have been already noticed in testing for cobalt and

manganese. Hence, besides its use in medicine (*Sodii Boras*, U. S. P.; *Borax; Mel Boracis*, B. P., or *Mel Sodii Boratis*, U. S. P., and *Glycerinum Boracis*, B. P.), it is employed as a flux in refining and other metallurgic and ceramic operations.

Quantivalence.—The boracic radical is trivalent (BO_3'''), the metaboracic, univalent (BO_2'); they have not been isolated. The element boron, like carbon, occurs in the amorphous, graphitoidal, and crystalline conditions. It is a trivalent element (B'''), yielding definite salts, such as the chloride (BCl_3) and fluoride (BF_3). Its atomic weight is 11.

Reactions.

First Synthetical Reaction.—To a hot solution of a crystal of borax add a few drops of sulphuric acid and set aside; on cooling, crystalline scales of boracic acid (H_3BO_3) are deposited. They may be purified by collecting on a filter, slightly washing, drying, digesting in hot alcohol, filtering, and setting aside; pure boracic acid (B. P.) is deposited. The acid may also be recrystallized from water. Fifty grains dissolved in one ounce of rectified spirit constitutes "Solution of Boracic Acid," B. P.

When heated, these crystals lose water and yield, first, metaboracic acid (HBO_2), and, subsequently, when fused, boracic anhydride (B_2O_3).

Boracic acid is very weak. It only slowly decomposes carbonates, and resembles alkaline compounds in coloring turmeric brown. Indeed the alkalinity of borax is as great as if it contained no acidulous radical whatever.

Second Synthetical Reaction.—Mix together 1 part of boracic acid, 4 of acid tartrate of potassium, and 10 or 20 of water; evaporate to a syrupy consistence, spread on plates, and set aside for dry scales to form. The resulting substance is, in water, far more readily soluble than either of its constituents, and is known as *boro-tartrate of potassium*, *soluble tartar*, or *soluble cream of tartar*. The Prussian *tartarus boraxatis* differs from the foregoing French variety in containing 1 part of *borax* to 3 of acid tartrate of potassium.

Analytical Reactions (Tests).

First Analytical Reaction.—Dip a piece of turmeric paper (paper soaked in tincture of turmeric tubers and dried) into a solution of boracic acid; it is colored brown-red, as by alkalies.

The usual way of applying this test is as follows: Add to any borate a few drops of hydrochloric acid, immerse half of a slip of

turmeric paper in the liquid, then remove the hydrochloric acid by drying the paper over a flame. Concentrated hydrochloric acid and ferric chloride produce a somewhat similar effect.

Second Analytical Reaction.—To a fragment of a borate or metaborate (borax, for example) in a small dish or watch-glass add a drop of sulphuric acid and then a little alcohol, warm the mixture and set light to the spirit; the resulting flame will be tinged of a greenish color at its edges by the volatilized boracic acid or boracic anhydride.

The liquid should be well stirred while burning. Salts of copper and some metallic chlorides produce a somewhat similar color.

Other Analytical Reactions. — In solutions of borax, barium salts give a white precipitate of barium metaborate ($Ba2BO_2$) soluble in acids and alkaline salts. Nitrate of silver gives metaborate of silver ($AgBO_2$) soluble in nitric acid and in ammonia. Chloride of calcium, if the solution is not too dilute, gives white borate of calcium.

QUESTIONS AND EXERCISES.

573. Illustrate the relation of vanadium to nitrogen by formulæ of compounds of each element.

574. Describe the preparation of borax.

575. Give the formulæ of boracic acid, metaboracic acid, and borax.

576. Mention the tests for borates or metaborates.

The foregoing acids and other salts contain the only acidulous radicals that are commonly met with in analysis or in ordinary pharmaceutical operations. There are, however, many others which occasionally present themselves. The chief of these will now be shortly noticed; they are arranged in alphabetical order to facilitate reference.

SALTS OF RARER ACIDULOUS RADICALS.

Benzoic Acid ($HC_7H_5O_2$) and other Benzoates.—Slowly heat a fragment of benzoin (*Benzoinum*, B. P. and U. S. P.) in a test-tube; benzoic acid (*Acidum Benzoicum*, B. P. and U. S. P.) rises in vapor and condenses in small, white, feathery plates and needles, on the cool sides of the tube. If the benzoin is first mixed with twice its weight of sand or roughly powdered pumice-stone, and the heat very

cautiously applied, the product will be less likely to be burnt, and a larger quantity be obtained.

A more economical process is to boil the benzoin with one-fourth its weight of lime, filter, concentrate, decompose the solution of benzoate of calcium by hydrochloric acid, collect the precipitated benzoic acid, press between paper, dry, and sublime in a tube or other vessel.

$$\underset{\text{Benzoic acid (impure).}}{2HC_7H_5O_2} + \underset{\text{Hydrate of calcium.}}{Ca2HO} = \underset{\text{Benzoate of calcium.}}{Ca2C_7H_5O_2} + \underset{\text{Water.}}{2H_2O}$$

$$\underset{\text{Benzoate of calcium.}}{Ca2C_7H_5O_2} + \underset{\text{Hydrochloric acid.}}{2HCl} = \underset{\text{Chloride of calcium.}}{CaCl_2} + \underset{\text{Benzoic acid (pure).}}{2HC_7H_5O_2}$$

Benzoic acid is also prepared on a large scale artificially from naphthalin, one of the crystalline by-products in the distillation of coal for gas. The naphthalin is oxidized by nitric acid to naphthalic or phthalic acid:—

$$\underset{\text{Naphthalin.}}{C_{10}H_{18}} + \underset{\text{Oxygen.}}{4O_2} = \underset{\text{Phthalic acid.}}{H_2C_8H_4O_4} + \underset{\text{Oxalic acid.}}{H_2C_2O_4}$$

The phthalic acid is neutralized by lime and the phthalate of calcium heated with hydrate of calcium in a covered vessel at a temperature of about 640° for several hours. Benzoate and carbonate of calcium are formed, and from the powder benzoic acid set free by action of hydrochloric acid.

$$\underset{\text{Phthalate of calcium.}}{2CaC_8H_4O_4} + \underset{\text{Hydrate of calcium.}}{Ca2HO} = \underset{\text{Benzoate of calcium.}}{Ca2C_7H_5O_2} + \underset{\text{Carbonate of calcium.}}{2CaCO_3}$$

The crystalline deposit formed when essential oil of almonds (hydride of benzoyl or benzoic aldehyd) is exposed to the air is benzoic acid.

$$\underset{\text{Hydride of benzoyl.}}{2C_7H_5OH} + \underset{\text{Oxygen.}}{O_2} = \underset{\text{Hydrate of benzoyl.}}{2C_7H_5OHO} \text{ or } \underset{\text{Benzoic acid.}}{2HC_7H_5O_2}$$

There is always associated with the product a minute quantity of a volatile oil of agreeable odor, suggesting that of hay.

Benzoate of Ammonium.—To a little benzoic acid add a few drops of solution of ammonia; it readily dissolves, forming benzoate of ammonium (*Ammonii Benzoas*, U. S. P.) ($NH_4C_7H_5O_2$).

$$\underset{\text{Benzoic acid.}}{HC_7H_5O_2} + \underset{\text{Ammonia.}}{NH_4HO} = \underset{\text{Benzoate of ammonium.}}{NH_4C_7H_5O_2} + \underset{\text{Water.}}{H_2O}$$

On evaporation, acid crystals or, ammonia being added, neutral crystals of benzoate of ammonium are deposited.

Properties.—Benzoic acid is also soluble in other alkaline liquids, forming benzoates. It is slightly soluble in cold

water, more so in hot, and readily soluble in rectified spirit. It melts at 248° F., and boils at 462°, evaporating with only a slight residue.

Tests.—The following are the *tests* for benzoic acid: To a portion of the above solution of benzoate of ammonium add a drop or two of sulphuric or hydrochloric acid; a white crystalline precipitate of benzoic acid separates. To another portion, carefully made neutral, add a drop or two of neutral solution of perchloride of iron; reddish ferric benzoate is precipitated. Benzoic acid is distinguished from an allied body, cinnamic acid (occurring in Balsams of Peru, Tolu, and Storax), by not yielding hydride of benzoyl (C_7H_5OH) (oil of bitter almonds) when distilled with chromic acid—that is, with a mixture of red chromate of potassium and sulphuric acid.

Carminic Acid ($C_{14}H_{14}O_8$).—This is the coloring principle of cochineal (*Coccus*, B. P. and U. S. P.). The *carmine* of trade, when unadulterated (*vide* Pharmaceutical Journal, 1859–60, p. 546), is carminic acid united with about five per cent. of alumina, or occasionally, of oxide of tin or albumen. It should be wholly soluble in solution of ammonia. Carmine, with French chalk, or starch, constitutes *face-rouge* or *animal rouge*.

Merrick tests the relative value of several samples of cochineal or carmine by observing how much solution of permanganate of potassium is required to change the color of a decoction to faint pink.

Cetraric Acid ($H_2C_{34}H_{30}C_{16}$) is the bitter principle of Iceland moss (*Cetraria*, B. P. and U. S. P.). In the lichen it is associated with much starch.

Chrysophanic Acid ($C_{10}H_8O_3$?).—This acid is the chief coloring-matter of various species of rhubarb root (*Rhei Radix*, B. P., *Rheum*, U. S. P.) and parmelia. It may be obtained in crystals of a golden-yellow color, hence the name (from χρυσὸς, *chrusos*, gold, and φαίνω, *phainō*, I shine). Its synonyms are *Rhaponticin*, *Rheic acid*, *Rhein*, *Rheumin*, *Rheubarbaric acid*, *Rheubarbarin*, *Rumicin*. Chrysophanic acid, black, red-brown, and red resins (*Aporetine*, *Phœoretine*, and *Erythroretine*), a bitter principle, and tannic acid are considered to be the conjoint source of the therapeutic properties of rhubarb.

Cyanic Acid (HCyO) and other Cyanates.—The valuable reducing-power of cyanide of potassium (KCy) (or ferrocyanide, K_4Fcy) on metallic compounds is due to the avidity with which cyanate (KCyO) is formed.

Process.—Fuse a few grains of cyanide of potassium in a small porcelain crucible, and add powdered oxide of lead; a globule of metallic lead is at once set free, excess of the oxide converting the whole of the cyanide of potassium into cyanate of potassium.

Urea.—Cyanate of potassium (KCNO), or, better, cyanate of lead (Pb2CNO), treated with sulphate of ammonium, yields cyanate of ammonium (NH_4CNO); and solution of cyanate of ammonium, when simply heated, changes to artificial *urea* (CH_4N_2O), the most important constituent of urine, and the chief form in which the nitrogen of food is eliminated from the animal system. The process will be more fully described subsequently in connection with urea.

Formic Acid ($HCHO_2$).—The red ant (*Formica rufa*) and several other insects, when irritated, eject a strongly acid, acrid liquid, having a composition expressed by the above formula, and which has appropriately received the name of formic acid; it is also contained in the leaves of the stinging-nettle.

Process.—It may be artificially prepared by heating equal weights of oxalic acid and glycerine to a temperature of from 212° to 220° for fifteen hours. The glycerine has, apparently, no chemical action, but, for some unknown reason, induces decomposition of the oxalic acid at a lower temperature than would otherwise be necessary; at a higher temperature the formic acid itself is decomposed. On distilling the mixture with water, the formic acid slowly passes over. The dilute acid may be concentrated by neutralizing with carbonate of lead, filtering, evaporating to a small bulk, collecting the deposited crystalline formate of lead, drying, decomposing in a current of sulphuretted hydrogen, and separating the resulting syrupy acid, or distilling the formate of lead with strong sulphuric acid.

$$\underset{\text{Oxalic acid.}}{H_2C_2O_4} = \underset{\text{Formic acid.}}{HCHO_2} + \underset{\text{Carbonic acid gas.}}{CO_2}$$

Formic acid may be instructively though not economically prepared by the oxidation of methylic alcohol (wood-spirit), just as acetic acid and valerianic acid are obtained from ethylic alcohol and amylic alcohol respectively.

$$\underset{\text{Wood spirit.}}{CH_3HO} + \underset{\text{Oxygen.}}{O_2} = \underset{\text{Formic acid.}}{HCHO_2} + \underset{\text{Water.}}{H_2O}$$

Tests.—Formic acid does not char when heated alone or with sulphuric acid, but splits up into carbonic oxide gas and water. It is recognized by this property and by its reducing-action on salts of gold, platinum, mercury, and silver. It is solid below 32°.

Gallic Acid.—See *Tannic Acid.*

Hemidesmic Acid.—The supposed active principle of hemidesmus root (*Hemidesmi Radix*, B. P.).

Hippuric Acid ($HC_9H_8NO_3$) is a constituent of human urine (much increased on taking benzoic acid), but is best prepared from the urine of the horse (hence the name, from ἵππος, *hippos*, a horse), or, better, from that of the cow. To such urine add a little milk of

lime, boil for a few minutes, remove precipitated phosphates by filtration, drop in hydrochloric acid until the liquid, after well stirring, is exactly neutral to test-paper, concentrate to about one-eighth the original bulk, and add excess of strong hydrochloric acid; impure hippuric acid is deposited. From a solution of the impure acid in hot water chlorine gas removes the color, and the liquid deposits crystals of pure hippuric acid on cooling. Its constitution is that of *benzoic glycocine*, $C_2H_2(C_7H_5O)(NH_2)O_2$.

Tests.—To a solution of hippurate add neutral solution of ferric chloride; a brown precipitate (ferric hippurate) results. Salts of silver and mercury give white precipitates. Heat hippuric acid in a test-tube; it chars, benzoic acid sublimes, and vapors of characteristic odor are evolved; they contain, amongst other bodies, hydrocyanic acid and a substance smelling somewhat like Tonka bean.——The crystalline form of hippuric acid is characteristic; it will be described in connection with the subject of urine.

QUESTIONS AND EXERCISES.

577. Give the preparation, composition, properties, and tests of benzoic acid, employing equations or diagrams.

578. What is the nature of carmine?

579. Name the bitter principle of Iceland moss.

580. Mention the coloring principle of rhubarb.

581. To what is rhubarb considered to owe its medicinal activity?

582. How is cyanate of potassium prepared, how converted into an ammonium salt, and what the relations of the latter to urea?

583. Give the formulæ of cyanic acid, cyanate of ammonium, and urea.

584. What is the chemical formula of formic acid?

585. Describe the artificial production of formic acid.

586. Describe the relation of formic acid to wood-spirit.

587. State the sources, characters, and tests of hippuric acid.

HYDROFERROCYANIC ACID ($H_4Fe''Cy_6$, or H_4Fcy'''') AND OTHER FERROCYANIDES.—The ferrocyanide of most interest is that of potassium (*Potassii Ferrocyanidum*, U. S. P.), the yellow prussiate of potash (*Potassæ Prussias Flava*, B. P.) ($K_4FeC_6N_6, 3H_2O$), the formation of which was alluded to in connection with hydrocyanic acid (see page 248). It cannot be regarded as simply a double salt of cyanide of potassium with cyanide of iron ($FeCy_2, 4KCy$), its chemical properties being entirely different from either of those substances; moreover, unlike cyanide of potassium, it is not poisonous. Most of its reactions point to the conclusion that its iron and cyanogen are intimately united to form a definite quadrivalent radical appropriately termed *ferrocyanogen* ($FeCy_6$, or Fcy). One part of ferrocyanide of potassium in 20 of water forms the official "Solution of Yellow Prussiate of Potash," B. P.

Tests.—Many of the ferrocyanides are insoluble, and are therefore precipitated when solution of ferrocyanide of potassium is added to the various salts. Those of iron and copper, being of characteristic color, are adopted as tests of the presence of the metals or of the ferrocyanogen, as the case may be.

$$3K_4Fcy + 2(Fe_2 3SO_4) = Fe_4Fcy_3 + 6K_2SO_4.$$

To solution of ferrocyanide of potassium add a ferric salt; ferrocyanide of iron (Fe_4Fcy_3) (Prussian Blue) (*Ferri ferrocyanidum*, U. S. P.) is precipitated.

To another portion add solution of a copper salt; reddish-brown ferrocyanide of copper (Cu_2Fcy) is precipitated.

Note.—The ferrocyanogen in ferrocyanide of potassium is broken up when the salt is heated with sulphuric acid, *carbonic oxide* being evolved if the acid is strong, and *hydrocyanic acid* if weak:—

$$K_4FeC_6N_6 + 6H_2O + 6H_2SO_4 = 2K_2SO_4 + FeSO_4 + 3(NH_4)_2SO_4 + 6CO.$$

$$2K_4FeCy_6 + 6H_2SO_4 + xH_2O = FeK_2FeCy_6 + 6KHSO_4 + 6HCy \times xH_2O.$$

Hydrocyanic Acid has already been described. (*Vide* p. 249.)

Carbonic oxide (CO).—Heat two or three fragments of ferrocyanide of potassium with eight or ten times their weight of sulphuric acid, and, as soon as the gas begins to be evolved, remove the test-tube from the flame; for the action, when once set up, proceeds somewhat tumultuously. Ignite the carbonic oxide at the mouth of the tube; it burns with a pale blue flame, the product of combustion being carbonic acid gas (CO_2).

Carbonic oxide is a direct poison. It is generated whenever coke, charcoal, or coal burns with an insufficient supply of air. Hence the danger of open fires in the more or less closed apartments of ordinary dwellings.

Carbonic oxide may also be obtained from oxalic acid. (*Vide* p. 283.)

Hydroferridcyanic Acid ($H_6Fe'''_2Cy_{12}$, or $H^I_6Fdcy^{VI}$) and other Ferridcyanides.—Pass chlorine gas slowly through solution of ferrocyanide of potassium until the liquid, after frequent shaking, ceases to give a blue precipitate, when a minute portion is taken out on the end of a glass rod and brought into contact with a drop of a dilute solution of a ferric salt; it now contains ferridcyanide of potassium ($K_6Fe'''_2Cy_{12}$, or $K^I_6Fdcy^{VI}$), *red prussiate of potash* (B. P.), as it is termed from the color of its crystals. Excess of chlorine must be carefully avoided, as chloride of cyanogen and other compounds are then formed.

$$2K'_4Fe''Cy'_6 + Cl'_2 = 2K'Cl' + K'_6Fe'''_2Cy'_{12}.$$

Note.—The removal of two atoms of potassium from the ferrocyanide is the only change of composition that occurs; but the ferrocyanogen is altered in quality, its iron passing from the ferrous to the ferric condition, from bivalent to trivalent activity, a condition in which it no longer precipitates ferric salts, but, on the other hand, gives a dark-blue precipitate with ferrous salts. The radical is distinguished as ferridcyanogen.

Ferridcyanide of potassium may also be prepared by a modification of the foregoing method in which nascent instead of free chlorine is employed (Wenzell). Take of Bichromate of Potash 1 part, Ferrocyanide of Potassium Cryst. 5.72 parts, Hydrochloric Acid, of spec. grav. 1.16, 3 parts, by weight, Water 60 parts. Dissolve the two salts in hot water, add the acid, heat to boiling, continuing the ebullition, replacing the water evaporated during the process until a portion of the filtered liquid is not precipitated on the addition of sesquichloride of iron. When reaction is completed, filter the liquid, and wash the hydrate of chromium, unite the liquids, and concentrate to crystallization. If the evaporated liquid possess an acid reaction, the addition of caustic potash, in sufficient quantity to cause a weak alkaline reaction, will greatly facilitate the subsequent crystallization.

$$6(K_4FeCy_6) + K_2Cr_2O_7 + 8HCl = 3(K_6Fe_2Cy_{12}) + 8KCl + H_2O + Cr_2HO.$$

Test.—To a portion of the solution add solution of ferrous sulphate; a precipitate falls. This precipitate is ferridcyanide of iron (Turnbull's blue), $Fe''_3Fe'''_2Cy'_{12}$, or $Fe^{II}_3Fdcy^{VI}$.

$$K_6Fdcy + 3FeSO_4 = Fe_3Fdcy + 3K_2SO_4.$$

It will be noticed that the change in the condition of the iron keeps up the balance of the atomic values of the various parts of the radicals or of the salts; the quantivalential equilibrium is maintained.

A solution of 1 of ferridcyanide of potassium in 20 of water constitutes the "Solution of Red Prussiate of Potash," B. P.

Hydrofluoric Acid (HF) and Other Fluorides.—Molecular weight of HF, 20. The chief use of hydrofluoric acid is in the etching on glass. The operation, performed on the small scale, also constitutes the best test for fluorine, the elementary radical of all fluorides.

Process and Test.—Warm any odd piece of window-glass, having an inch or two of surface, until a piece of beeswax rubbed on one side yields a thin oily film. When cool make a cross, letter, or other mark on the glass by pressing a pointed piece of wood, a penknife, or file, through the wax. Place a few grains of powdered fluor spar, the commonest natural fluoride, in a porcelain crucible (or a lead cup), add a drop or two of sulphuric acid, cover

the crucible with the prepared glass, waxed side downwards, and gently warm the bottom of the crucible in a fume-chamber or in the open air, in such a way as not to melt the wax. After a few minutes remove the glass, wash the waxed side by pouring water over it, scrape off most of the wax, then warm the glass, and wipe off the remainder; the marks made through the wax will be found to be permanently etched on the glass; the acid has eaten into or *etched* (from the German *ätzen*, to corrode) the glass.

In the above operation the fluoride of calcium and sulphuric acid yield hydrofluoric acid, thus:—

$$CaF_2 + H_2SO_4 = CaSO_4 + 2HF.$$

The hydrofluoric acid gas and the silica of the glass then yield gaseous fluoride of silicon (SiF_4), which escapes, and water, thus:—

$$4HF + SiO_2 = 2H_2O + SiF_4.$$

The silica being removed from the glass, leaves furrows or etched portions.

Note.—In the experiment just described, the liberated hydrofluoric acid also attacks the siliceous glazing of the porcelain crucible; so that in important cases, where search is made for very small quantities of fluorine, vessels of platinum or lead must be employed.

Uses.—The aqueous solution of hydrofluoric acid used by etchers, and commonly termed simply hydrofluoric acid, or fluoric acid, is prepared in leaden stills and receivers, and kept in leaden or gutta-percha bottles. Except these materials, as well as platinum and fluor spar, hydrofluoric acid rapidly attacks any substance of which bottles and basins are usually made. It quickly cauterizes the skin, producing a painful slow-healing sore.

Quantivalence.—The atom of fluorine, like that of chlorine, bromine, or iodine, is univalent (F′). The great analogy existing between these radicals extends to their compounds.

Fluorine is said to be a colorless gas; but, from the avidity with which it combines with all elements (except oxygen), it is so difficult of isolation as hitherto to preclude satisfactory study of its physical properties.

HYPOPHOSPHOROUS ACID (H_3PO_2, or HPH_2O_2) AND OTHER HYPOPHOSPHITES.—Boil together, in a fume-chamber, a grain or two of phosphorus, a few grains of slaked lime, and about a quarter of an ounce of water until phosphoretted hydrogen, a spontaneously inflammable, badly smelling gas, ceases to be evolved. The mixture, filtered, yields solution of hypophosphite of calcium ($Ca2PH_2O_2$).

$$P_8 + 6H_2O + 3CaH_2O_2 = 3(Ca2PH_2O_2) + 2PH_3.$$

The solution, when concentrated by evaporation, has been known to explode, probably from formation of phosphoretted hydrogen.

This may be prevented, it is said, by evaporating at a low temperature, especially towards the close of the operation ; or by adding alcohol, which decomposes any traces of liquid phosphoretted hydrogen (PH_2) or solid phosphoretted hydrogen (P_2H) which possibly may be present, and to which it is conceivable explosion may be due.

Phosphoretted hydrogen (PH_3).—The above reaction is also that by which phosphoretted hydrogen, the third hydride of phosphorus, may be prepared. If the gas is to be collected, the phosphorus and water may first be boiled in a flask until spontaneously a jet of phosphorus vapor escapes, with steam, from the end of the attached delivery-tube. Strong solution of caustic potash or soda is next very gradually poured into the flask through a funnel tube previously fitted into the cork, the liquid being kept boiling. Phosphoretted hydrogen is then evolved, and if the delivery-tube dip under water may be collected, or allowed to slowly pass up through the water bubble by bubble so as to form the peculiar rings of smoke (phosphoric anhydride) characteristic of the experiment.

Hypophosphite of calcium may be obtained in crystals (*Calcii Hypophosphis*, U. S. P.); but the solution is usually at once evaporated to dryness, a white pulverulent salt being obtained. The hypophosphites of Potassium and Sodium (*Potassii Hypophosphis*, U. S. P., and *Sodii Hypophosphis*, U. S. P.) may be obtained in the same way from their hydrates, and many other hypophosphites similarly from other hydrates, or by double decomposition of the calcium salt and carbonates. Hypophosphorous acid, the hydrogen hypophosphite, may be prepared by decomposing the barium salt with sulphuric acid or the calcium salt by oxalic acid; hypophosphite of quinine by dissolving the alkaloid in hypophosphorous acid, or by decomposing sulphate of quinine by hypophosphite of barium. Hypophosphite of Iron (*Ferri Hypophosphis*, U. S. P.) may be obtained by dissolving ferric hydrate in cold aqueous hypophosphorous acid and evaporating the solution. The hypophosphites are often used in medicine in the form of syrups. The term hypophosphite is in allusion to the smaller amount (ὑπὸ, *hupo*, under or deficiency) of oxygen in these compounds (R'_3PO_2) than in the phosphites (R_3PO_3), a class of salts having again less oxygen in their molecules than exists in those of the phosphates (R_3PO_4). The prefix *hypo* has similar significance in such words as hyposulphite and hypochlorite.

Tests.—To a portion of the above solution of hypophosphite of calcium add solution of chloride of barium, chloride of calcium, or acetate of lead; in neither case is a precipitate obtained, whereas soluble phosphates and phosphites yield white precipitates of phosphate or phosphite of barium, calcium, or lead. To other portions add solutions of nitrate of silver and mercuric chloride; the respective metals are precipitated as by phosphites. To another small portion add zinc and dilute sulphuric acid; hydrogen and phosphoretted hydrogen are evolved as from phosphites. To another portion add sufficient oxalic acid to remove the calcium; filter; to the solution of hypophosphorous acid

add solution of sulphate of copper and slowly warm the mixture; solid brown hydrate of copper is precipitated: increase the heat to the boiling-point; hydrogen is evolved and metallic copper set free. Heat a small quantity of a solid hypophosphite on the end of a spatula in a flame; it splits up into pyrophosphate, phosphoretted hydrogen, and water, burning with a phosphorescent light.

$$2(Ca2PH_2O_2) = Ca_2P_2O_7 + 2PH_3 + H_2O.$$

HYPOSULPHUROUS ACID ($H_2S_2O_3$) AND OTHER HYPOSULPHITES.—The only hyposulphite of much interest in pharmacy is the sodium salt (Hyposulphite of Soda, B. P., *Sodii Hyposulphis*, U. S. P.) ($Na_2S_2O_3, 5H_2O$).

Process.—Heat together gently, or set aside in a warm place, a mixture of solution of sulphite of sodium (Na_2SO_3), and a little powdered sulphur; combination slowly takes place, and hyposulphite of sodium is formed. The solution, filtered from excess of sulphur, readily yields crystals. [The solution of sulphite of sodium may be made by saturating a solution of soda with sulphurous acid gas.]

Use of hyposulphite of sodium in quantitative analysis.—In the British Pharmacopœia hyposulphite of sodium is given as a reagent for the quantitative estimation of free iodine in volumetric analysis. To a few drops of iodine-water add cold mucilage of starch; a deep-blue color (starch iodide) is produced. To the product add solution of hyposulphite of sodium until the blue color just disappears. This absorption of iodine is sufficiently definite and delicate to admit of application for quantitative purposes. It depends on the combination of the iodine with half of the sodium in two molecules of the hyposulphite, the hyposulphurous radicals of the two molecules apparently coalescing to form a new radical, the tetrathionic (from τέτρας, *tetras*, four, and θειον, *theion*, sulphur), tetrathionate ($Na_2S_4O_6$) and iodide of sodium being formed.

Sulphur Oxyacids.—It will be as well here to give the formulæ of other oxyacids of sulphur, forming with the four already mentioned a series that is as useful as the series of compounds of nitrogen and oxygen in illustrating the soundness of Dalton's atomic theory (p. 43).

Hydrosulphurous Acid	H_2SO_2
Sulphurous Acid	H_2SO_3
Sulphuric Acid	H_2SO_4
Hyposulphurous Acid	$H_2S_2O_3$
Dithionic Acid	$H_2S_2O_6$
Trithionic Acid	$H_2S_3O_6$
Tetrathionic Acid	$H_2S_4O_6$
Pentathionic Acid	$H_2S_5O_6$

Use of "Hypo" in Photography.—The sodium hyposulphite is largely used in photography to dissolve chloride, bromide, or iodide of silver off plates which have been exposed in the camera. Prepare a little chloride of silver by adding a chloride (chloride of sodium) to a few drops of solution of nitrate of silver. Collect the precipitated chloride on a filter, wash, and add a few drops of solution of hyposulphite of sodium; the silver salt is dissolved, solution of double hyposulphite of sodium and silver being formed. The solution of this double hyposulphite has a remarkably sweet taste, sweeter than syrup. The double hyposulphite of sodium and gold is employed for giving a pleasant tint to photographic prints.

Test.—To solution of a hyposulphite add a few drops of dilute sulphuric or other acid; hyposulphurous acid is set free, but at once begins to decompose into sulphurous acid, recognized by its odor, and free sulphur ($2H_2S_2O_3 = 2H_2SO_3 + S_2$). This reaction constitutes the best test for hyposulphites. Another good test of a soluble simple hyposulphite is its power of dissolving chloride of silver with production of a sweet solution.

QUESTIONS AND EXERCISES.

588. Give the formula of ferrocyanide of potassium.

589. What is the supposed constitution of ferrocyanide of potassium?

590. Enumerate the tests for ferrocyanogen.

591. What are the respective reactions of ferrocyanide of potassium with strong and weak sulphuric acid?

592. Mention and explain a common source of carbonic oxide in households?

593. Write equations or diagrams illustrative of the changes effected on ferrocyanide of potassium during its conversion into ferridcyanide.

594. By what reactions may the presence of a ferridcyanide in a solution be demonstrated?

595. State the difference between Prussian blue and Turnbull's blue.

596. Describe the source, mode of preparation, chief use of, and test for hydrofluoric acid.

597. Illustrate by a diagram the preparation and composition of hyposulphite of sodium.

598. Mention the uses and characteristic reactions of hyposulphite of sodium.

599. Give the names and formulæ of eight acids, each containing hydrogen, sulphur, and oxygen.

Lactic Acid ($H_2C_3H_4O_3$) and other Lactates.—When milk turns sour its sugar has become converted into an acid appropriately termed lactic (*lac, lactis*). Other saccharine and amylaceous substances also by fermentation yield lactic acid. Neither the hydrogen lactate (lactic acid) nor other lactates are much used in England, but the former is official in America (*Acidum Lacticum*, U. S. P.).

Process.—Lactate of calcium and lactic acid may be prepared as follows: Mix together eight parts of sugar, one of common cheese, three of chalk, and fifty of water, and set aside in a warm place (about 80° F.) for two or three weeks; a mass of small crystals of lactate of calcium results. Remove these, recrystallize from hot water, decompose by sulphuric acid, avoiding excess, digest in alcohol, filter off the sulphate of calcium, evaporate the clear solution to a syrup; this residue is lactic acid; sp. gr. 1.212.

Lactate of Iron (*Ferri Lactas*, U. S. P.) is made by digesting iron filings in warm diluted lactic acid (1 acid to 16 water) till effervescence of hydrogen ceases, filtering and setting aside to cool and crystallize. The crystals are collected, washed with alcohol, and dried. This ferrous lactate occurs in greenish-white crystalline crusts or grains, of a mild, sweetish, ferruginous taste, soluble in forty-eight parts of cold, and twelve of boiling water, but insoluble in alcohol. Exposed to heat it froths up, gives out thick, white, acid fumes, and becomes black; sesquioxide of iron being left. If it be boiled for fifteen minutes with nitric acid of the specific gravity 1.20, a white, granular deposit of mucic acid will occur on the cooling of the liquid.

Test.—No single reaction of lactic acid is sufficiently distinctive to form a test. The crystalline form of the lactate of calcium, as seen by the microscope, is characteristic. The production of this salt, and the isolation of the syrupy acid itself, are the only means, short of quantitative analysis, on which reliance can be placed.

A variety of lactic acid has been obtained from the juice of fish; it is termed *sarcolactic* acid (from σάρξ, gen. σαρκός, flesh).

Malic Acid ($H_2C_4H_3O_5$) and other Malates (from *malum*, an apple).—The juice of unripe apples, gooseberries, currants, rhubarb stalks, etc., contains malic acid and malate of potassium. When isolated it occurs in deliquescent prismatic crystals.

Tests.—Malate of calcium ($CaHC_4H_3O_5$) is soluble in water; hence the aqueous solution of malic acid or other malate is not precipitated by lime-water or chloride of cal-

cium; but on adding spirit of wine a white precipitate falls, owing to the insolubility of the calcium malate in alcohol. Malates are precipitated by lead-salts; on warming the malate of lead with acetic acid it dissolves, separating out in acicular crystals on cooling. If the mixture be heated without acid the malate of lead agglutinates and fuses.

Hot strong sulphuric acid chars malic acid far less readily than it does nearly all other organic acids.

Malic acid is one of the chief products of the action of nitrous acid on asparagin ($C_4H_8N_2O_3,H_2O$), a crystalline body extracted from asparagus and marshmallow (*Althea*, U. S. P.).

Meconic Acid ($H_3C_7HO_7$). Opium contains meconic acid (from μήκων, *mēkōn*, a poppy) partially combined with morphia. To concentrated infusion of opium, nearly neutralized by ammonia, add solution of chloride of calcium, meconate of calcium is precipitated. Wash the precipitate, place it in a small quantity of hot water, and add a little hydrochloric acid; the clear liquid (filtered, if necessary) deposits scales of meconic acid on cooling.

Test.—To solution of meconic acid or other meconate, or to infusion of opium, add a *neutral* solution of ferric chloride; a red solution of meconate of iron is produced. To a portion of the mixture add solution of corrosive sublimate; the color is not destroyed; to another portion add hydrochloric acid; the color is discharged. (These reagents act on sulphocyanate of iron, which is of similar tint, in exactly the opposite manner.)

The normal meconates of potassium, sodium, and ammonium are soluble in water, the acid meconates very slightly soluble, the meconates of barium, calcium, lead, copper, and silver insoluble in water but soluble in acetic acid.

Metaphosphoric Acid (HPO_3) and other Metaphosphates.—Prepare phosphoric anhydride (P_2O_5) by burning a small piece of phosphorus in a porcelain crucible placed on a plate and covered by an inverted test-glass, tumbler, half-pint measure-glass, or some such vessel. After waiting a few minutes for the phosphoric anhydride to fall, pour a little water on the plate and filter the liquid; the product is solution of metaphosphoric acid (from μετά, *meta*, a preposition denoting change).

$$P_2O_5 + H_2O = 2HPO_3.$$

Tests.—To solution of metaphosphoric acid add ammonio-nitrate of silver, or to a neutral metaphosphate add

solution of nitrate of silver; a white precipitate ($AgPO_3$) is obtained. This reaction sufficiently distinguishes metaphosphates from the ordinary phosphates or orthophosphates (from ὀρθὸς *orthos*, straight), as the common phosphates may, for distinction, be termed (which give, it will be remembered, a *yellow* precipitate with nitrate of silver). Another variety of phosphates shortly to be considered, the pyrophosphates, also give a white precipitate with nitrate of silver. To the solution of metaphosphoric acid obtained as above or by the action of acetic acid on a metaphosphate, add an aqueous solution of white of egg; coagulation of the albumen ensues. Neither orthophosphoric nor pyrophosphoric acid coagulates albumen. Boil the aqueous solution of metaphosphoric acid for some time; on testing the solution the acid will be found to have been converted into orthophosphoric acid:

$$HPO_3 + H_2O = H_3PO_4.$$

The ordinary medicinal phosphoric acid is made from phosphorus and nitric acid, the liquid being evaporated to a syrupy consistence to remove the last traces of nitric acid. It may contain pyrophosphoric and metaphosphoric acids, if the heat employed be high enough to remove the elements of water:—

$$H_3PO_4 - H_2O = HPO_3.$$

On redilution the metaphosphoric acid only slowly reabsorbs water. If, therefore, on testing, metaphosphoric be found to be present, the solution should be boiled until conversion to orthophosphoric acid has occurred.

Nitrous Acid (HNO_2) and other Nitrites.—Strongly heat a fragment of nitrate of potassium or of sodium on a piece of platinum foil; oxygen is evolved and nitrite of potassium remains.

Test.—Dissolve the residue in water, add a few drops of dilute sulphuric acid, then a little weak solution of iodide of potassium, and, lastly, some mucilage of starch; the deep-blue compound of iodine and starch is at once produced. Repeat this experiment, using nitrate of potassium instead of nitrite; no blue color is produced.

$$2HI + 2HNO_2 = 2H_2O + 2NO + I_2.$$

Test for Nitrites in Water.—This liberation of iodine by nitrites and not by nitrates is a reaction of considerable value in searching for nitrites in ordinary drinking-waters, the occurrence of such salts

being held to indicate the presence of nitrogenous organic matter in a state of oxidation or decay. The sulphuric acid used in the operation must be pure, and the iodide of potassium free from iodate.

Commercial Nitrous Acid.—The liquid commonly termed in pharmacy nitrous acid is simply nitric acid impure from the presence of nitrous acid.

The only nitrite used in medicine is a nitrite of an organic basylous radical, ethyl; nitrite of ethyl ($C_2H_5NO_2$), or nitrous ether, is the chief constituent of "*sweet spirit of nitre*" (*Spiritus Ætheris Nitrosi*, B. P. and U. S. P.: *vide* Index).

Phosphorous Acid (H_3PO_3, or H_2PHO_3).—It is necessary to notice this compound in order that the reader may have brought before him the three acids of phosphorus, namely, phosphoric acid (H_3PO_4), phosphorous acid (H_2PHO_3), and hypophosphorous acid (HPH_2O_2): it will be noticed that in composition they differ from each other simply in the proportion of oxygen, the molecules containing four, three, and two atoms respectively. In constitution they differ by the hypothetical phosphoric radical or grouping being trivalent, the phosphorous bivalent, and the hypophosphorous univalent. These three acids and corresponding salts must not be confounded with pyrophosphoric and metaphosphoric acids and salts; the former are acids of phosphorus; the latter, varieties of phosphoric acid: the former, in composition, differ from each other in the proportion of oxygen they contain; the latter, by the elements of water:—

Acids of Phosphorus.	*Varieties of Phosphoric Acid.*
H_3PO_4 phosphoric acid.	H_3PO_4 (ortho)phosphoric acid.
H_3PHO_3 phosphorous acid.	$H_4P_2O_7$ pyrophosphoric acid.
HPH_2O_2 hypophosphorous acid.	HPO_3 metaphosphoric acid.

When hypophosphorous acid is exposed to the air, oxygen is absorbed and phosphorous acid results; by prolonged exposure more oxygen is absorbed and phosphoric acid is obtained. When phosphoric acid, or rather, for distinction, orthophosphoric acid is heated, every two molecules yield the elements of a molecule of water, and pyrophosphoric acid results; by prolonged exposure to heat more water is evolved, and metaphosphoric acid is obtained. These differences will be further evident if the formulæ be written empirically, nearly all being doubled, thus:—

$H_6P_2O_4$ hypophosphorous acid.
$H_6P_2O_6$ phosphorous acid.
$H_6P_2O_8$ { phosphoric acid, or orthophosphoric acid.
$H_4P_2O_7$ pyrophosphoric acid.
$H_2P_2O_6$ metaphosphoric acid.

Or thus:—

phosphoric acid
$H_6P_2O_8$.

phosphorous acid
$H_6P_2O_6$.

pyrophosphoric acid
$H_4P_2O_7$.

hypophosphorous acid
$H_6P_2O_4$.

metaphosphoric acid
$H_2P_2O_6$.

From the central compound, phosphoric acid, the acids of phosphorus differ by regularly diminishing proportions of the element oxygen (see previous page), the varieties of phosphoric acid by regularly diminishing proportions of the elements of water.

Prepare phosphorous acid by exposing a moist stick of phosphorus to the air; a thin stream of heavy white vapor falls, which is the acid in question. The best method of collection is to place the stick in an old test-tube having a hole in the bottom, to support this tube by a funnel or otherwise, the neck of the funnel being supported in a bottle, test-glass, or tube, at the bottom of which is a little water. Having collected some phosphorous acid in this way, apply the various tests already alluded to under *Hypophosphorous Acid*, first carefully neutralizing the phosphorous acid by an alkali. The means by which the varieties of phosphoric acid are distinguished have been given under *Metaphosphoric Acid.*

Other soluble phosphites are prepared by neutralizing phosphorous acid with alkalies, and the insoluble phosphites by double decomposition.

PYROGALLIC ACID.—See *Tannic Acid.*

PYROPHOSPHORIC ACID ($H_4P_2O_7$) AND OTHER PYROPHOSPHATES.—Heat ordinary phosphate of sodium (Na_2HPO_4, $12H_2O$) in a crucible; water of crystallization is first evolved, and dry phosphate (Na_2HPO_4) remains. Continue the heat to redness; two molecules of the salt yield one molecule of water, and a salt having new properties is obtained:—

$$2Na_2HPO_4 - H_2O = Na_4P_2O_7.$$

It is termed pyrophosphate of sodium, in allusion to its origin (πῦρ, *pūr*, fire). Other pyrophosphates are produced in a similar way, or by double decomposition and precipitation, or by neutralizing pyrophosphoric acid by an oxide, hydrate, or carbonate. Possibly the pyrophosphates are only compounds or orthophosphates with metaphosphates:—

$$Na_4P_2O_7 = Na_3PO_4, NaPO_3.$$

Tests.—To solution of a pyrophosphate add solution of nitrate of silver; white pyrophosphate of silver ($Ag_4P_2O_7$) falls as a dense white powder, differing much in appearance from the white gelatinous metaphosphate of silver or the yellow orthophosphate. To pyrophosphoric acid, or to a pyrophosphate mixed with acetic acid, add an aqueous solution of albumen (white of egg); no precipitate occurs. Metaphosphoric acid, it will be remembered, gives a white precipitate with albumen.

QUESTIONS AND EXERCISES.

600. What are the sources of lactic acid?
601. How is lactic acid usually prepared?
602. Name some of the plants in which malic acid is found.
603. Whence is meconic acid derived?
604. By what process may meconic acid be isolated?
605. Which is the best test for the meconic radical?
606. Distinguish meconates from sulphocyanates.
607. Give the mode of manufacture of hypophosphites.
608. How is phosphoretted hydrogen prepared?
609. By what ready method may metaphosphoric acid be obtained for experimental purposes?
610. Name the tests for metaphosphates.
611. How may meta- or pyro-phosphoric acid be converted into orthophosphoric acid?
612. Describe the preparation of phosphorous acid.
613. State the relations which the acids of phosphorus bear to each other.
614. How are pyrophosphates prepared?
615. Offer two views of the constitution of pyrophosphates.
616. Define, by formulæ, metaphosphates, pyrophosphates, orthophosphates, phosphites, and hypophosphites.
617. Mention the tests by which meta-, pyro-, and orthophosphates are analytically distinguished.
618. Name the reactions by which hyposulphites and phosphites are detected.

Silicic Acid (H_4SiO_4) and other Silicates.—Silicates of various kinds are among the commonest of minerals. The various *clays* are aluminium silicates; *meerschaum* is an acid silicate of magnesium; the ordinary *sandstones* are chiefly silica; *sand*, *flint*, *quartz*, *agate*, *chalcedony*, and *opal* are silicic anhydride or *silica* (SiO_2). *Asbestos* or *amianth* is a fibrous silicate of calcium and magnesium. Artificial silicates are familiar under the forms of *glass* and *earthenware*. Common English window-glass is usually silicate of calcium, sodium, and aluminium; French glass, silicate of calcium and sodium; Bohemian, chiefly silicate of potassium and calcium; English flint- or crystal-glass for ornamental, table, and optical purposes, is mainly silicate of potassium and lead. Earthenware is mostly silicate of aluminium, (clay), with more or less of silicate of calcium, sodium, and potassium, and, in the commoner forms, iron. The various kinds of *porcelain* (China, Sèvres, Meissen, Berlin, English), *Wedgwood-ware*, and *stoneware* are varieties of earthenware. *Crucibles*, *bricks*, and *tiles* are clay-silicates. *Mortar* is essentially silicate of calcium. *Portland*, *Roman*, and other hydraulic *cements* are silicates of calcium with more or less silicate of aluminium.

Mix together a few grains of powdered flint or sand with about five or six times its weight of carbonate of sodium

and an equal quantity of carbonate of potassium, and fuse a little of the mixture on platinum-foil in the blowpipe-flame; the product is a kind of *soluble glass*. Boil the foil in water for a few minutes, filter; to a portion add excess of hydrochloric acid, evaporate the solution to dryness, and again boil the residue in water and acid; oxide of silicon, or *silica*, (SiO_2) remains as a light, flaky, insoluble powder.

The *soluble glass* or *glass liquor* of trade commonly contains 10 or 12 per cent. of soda (NaHO) to 20 or 25 per cent. of silica (SiO_2).

The foregoing operation constitutes the *test* for silicates. By fusion with alkali the silicate is decomposed, and a soluble alkaline silicate formed. On addition of acid, silicic acid (H_4SiO_4) is set free, but remains in solution if sufficient water is present. The heat subsequently applied eliminates water and reduces the silicic acid to silica (SiO_2), which is insoluble in water or acid. By the addition of hydrochloric acid to soluble glass, and removal of the resulting alkaline chloride and excess of hydrochloric acid by dialysis (a process to be subsequently described), a pure aqueous solution of silicic acid may be obtained; it readily changes into a gelatinous mass of silicic acid. Possibly some of the natural crystallized varieties of silica may have been obtained from the silica contained in such an aqueous solution, nearly all waters yielding a small quantity of silica when treated as above described.

A variety of silicic acid (H_2SiO_3) sometimes termed *dibasic*, to distinguish it from the normal or *tetrabasic* acid (H_4SiO_4), results when the aqueous solution of the latter is evaporated in *vacuo*.

Siliciuretted hydrogen, or hydride of silicon (SiH_4), is a spontaneously inflammable gas formed on treating silicide of magnesium with hydrochloric acid. It is the analogue of light carburetted hydrogen (CH_4). A liquid chloride of silicon ($SiCl_4$) and a gaseous fluoride (SiF_4) also exist.

Succinic Acid ($H_2C_4H_4O_4$).—Amber (*Succinum*) is a peculiar resin usually occurring in association with coal and lignite. From the fact that fragments of coniferous fruit are frequently found in amber, and impressions of bark on its surface, it is considered to have been an exudation from a species of Pinus now probably extinct. Heated in a retort, amber yields, first, a sour aqueous liquid containing acetic acid and another characteristic body appropriately termed *succinic acid;* second, a volatile liquid known as *oil of amber* (*Oleum Succini Rectificatum*, U. S. P.) resembling the oil yielded by most resinous substances under similar circumstances; and, third, a pitchy residue allied to asphalt. The succinic acid is a normal constituent of the amber, the acetic acid is produced during distillation. Succinic acid has also been found in wormwood, in several pine-resins, and in certain animal fluids, such as those of hydatid cysts and hydrocele. It may be obtained artificially from butyric, stearic, or margaric acid by oxidation. Tartaric, malic, and succinic acids are also convertible the one into the other.

The *succinates* are normal ($R'_2C_4H_4O_4$) and acid ($R'HC_4H_4O_4$); a double succinate of potassium and hydrogen ($KHC_4H_4O_4,H_2C_4H_4O_4,H_2O$), analogous to the superacid oxalate, salt of sorrel, also exists.

Soluble succinates give a bulky brown precipitate with neutral ferric chloride, only less voluminous than ferric benzoate; a white precipitate with acetate of lead, soluble in excess of either reagent; with nitrate of silver a white precipitate after a time; with chloride of barium no precipitate at first, but a white one of succinate of barium on the addition of ammonia and alcohol. Succinates are distinguished from benzoates by the last-named reaction, and by not yielding a precipitate on the addition of acids (*vide* p. 300).

SULPHOCYANIC ACID (HCyS) AND OTHER SULPHOCYANATES.—Boil together sulphur and solution of *pure* cyanide of potassium; solution of sulphocyanate of potassium (KCyS) is formed.

Tests.—Filter, and to a small portion of the solution add a ferric salt (Fe_2Cl_6); a deep-blood-red solution of ferric sulphocyanate is formed. To a portion of the red liquid add hydrochloric acid; the color is not discharged (meconate of iron, a salt of similar tint, is decomposed by hydrochloric acid). In the acid liquid place a fragment or two of zinc, sulphuretted hydrogen is evolved, and the red color disappears. To another portion of the ferric sulphocyanate add solution of corrosive sublimate; the color is at once discharged. (Ferric meconate is unaffected by corrosive sublimate.) The ferric is the best test of the presence of a sulphocyanate; indirectly, it is a good test of the presence of hydrocyanic acid or cyanogen.

To solution of a sulphocyanate add solution of mercuric nitrate; mercuric sulphocyanate is precipitated as a white powder.

Pharaoh's Serpents.—Mercuric sulphocyanate, thoroughly washed and made up into little cones, forms the toy called Pharaoh's serpent. It readily burns when ignited, the chief product being a light solid matter (mellon, C_9N_{13}, and the melam, $C_3H_6N_6$), which issues from the cone in a snake-like coil of extraordinary length. The other products are mercuric sulphide (of which part remains in the snake and part is volatilized), nitrogen, sulphurous, and carbonic acid gases, and vapor of metallic mercury. (For details concerning the economical manufacture of sulphocyanates see *Pharmaceutical Journal*, second series, vol. vii. p. 581, and p. 152.)

The sulphocyanic radical (CyS) is often termed sulphocyanogen (Scy), and its compounds regarded as *sulphocyanides.*

TANNIC ACID OR TANNIN ($C_{27}H_{22}O_{17}$).—This is a common astrin-

gent constituent of plants, but is contained in largest quantity in galls (excrescences on the oak formed by the puncture and deposited ova of an insect). English galls contain from 14 to 28 per cent. of tannic acid; Aleppo galls (*Galla*, B. P. and U. S. P.) from 25 to 65 per cent. (*Acidum Tannicum*, B. P. and U. S. P.)

Process.—"Expose powdered galls (about an ounce is sufficient for the purpose of study) to a damp atmosphere for two or three days, and afterwards add sufficient ether to form a soft paste. Let this stand in a well-closed vessel for twenty-four hours, then, having quickly enveloped it in a linen cloth, submit it to strong pressure so as to separate the liquid portion, which contains the bulk of the tannin in solution. Reduce the pressed cake to powder, mix it with sufficient ether, to which one-sixteenth of its bulk of water has been added, to form again a soft paste, and press this as before. Mix the expressed liquids, and expose the mixture to spontaneous evaporation until, by the aid subsequently of a little heat, it has acquired the consistence of a soft extract; then place it on earthen plates or dishes, and dry it in a hot-air chamber at a temperature not exceeding 212°."

The resulting tannic acid occurs in "pale yellow vesicular masses or thin glistening scales, with a strongly astringent taste, and an acid reaction, readily soluble in water and rectified spirit, very sparingly soluble in pure ether, though soluble in common ether (which contains alcohol) when the ether is saturated with water.

Medicinal Uses.—Tannic acid is very soluble in water, and in this form is usually administered in medicine. Its official preparations are *Glyceritum Acidi Tannici*, *Suppositoria Acidi Tannici*, and *Trochisci Acidi Tannici*.

Tests.—To an aqueous solution of tannic acid add aqueous solution of gelatine, a yellowish-white flocculent compound of the two substances is precipitated. This is a good test of the presence of tannic acid.

Tanning.—The above reaction also serves to explain the chemical principle involved in *tanning*—the operation of converting skin into leather. In that process the skin is soaked in infusion of oak-bark (*Quercus Cortex*), the tannic acid of which uniting with the gelatinous tissues of the skin yields a compound very well represented by the above precipitate. The outer bark of the oak contains little or no tannic acid, and is commonly shaved off from the pieces of bark which are large enough to handle; useless coloring matter is thus also rejected. Other infusions and extracts besides that of oak-bark (chiefly catechu, sumach, and valonia) are largely used by tanners;

if used alone these act too quickly, and give a harsh, hard, less durable leather. The tannic acid of these preparations is probably slightly different from that of oak-bark.

To an aqueous solution of tannic acid add a neutral solution of a ferric salt; dark bluish-black tannate of iron is slowly precipitated. This is an excellent test for the presence of tannic acid in vegetable infusions. The precipitate is the basis of nearly all black writing-ink. Ferrous salts give at first only a slight reaction with tannic acid; but the liquid gradually darkens. Characters written with this liquid become quite black in a few hours, and are very permanent.

To an aqueous solution of tannic acid add solution of tartar-emetic; tannate of antimony is precipitated. This reaction and that with gelatine are useful in the quantitative estimation of the amount of tannic acid in various substances.

Tannic acid is a glucoside; that is, like several other substances, it yields glucose (grape-sugar) when boiled with dilute sulphuric or hydrochloric acid, the other product being gallic acid:—

$$C_{27}H_{22}O_{17} + 4H_2O = C_6H_{12}O_6 + 3H_3C_7H_3O_5.$$

Catechu (*Catechu*, U. S. P., *Catechu pallidum*, B. P.), *Gambir*, or *Terra Japonica*, *Kino* (*Kino*, B. P. and U. S. P.), *Elm Bark* (*Ulmi Cortex*, B. P.), and Slippery Elm Bark (*Ulmus fulva*, U. S. P.), and some other vegetable products contain a variety of tannic acid (*mimo-tannic acid*), which gives a greenish precipitate with neutral solutions of ferric salts.

Bael fruit (*Belœ fructus*, B. P.), from the *Ægle Marmelos*, is said to owe its astringency to a variety of tannic acid. In India a jelly and preserve have long been made from the Marmelos—whence the word *marmalade* for similar preserves. The astringency of Pomegranate-root Bark (*Granati Radicis Cortex*, B. P. and U. S. P.) and *Fruit* (*Granati Fructus Cortex*, U. S. P.) is due to tannic acid (its anthelmintic properties probably to a resinoid matter); and the same may be said of logwood (*Hœmatoxyli Lignum*, B. P. and U. S. P., the *color* of which is due to oxidized *hœmatoxylin*). *Rhatany*-root (*Krameriœ Radix*, B. P. and U. S. P.) contains about 40 per cent. of tannic acid, its active astringent principle; rhubarb-root about 9 per cent. *Bearberry*-leaves (*Uvœ Ursi Folia*, B. P. and U. S. P.) owe most of their therapeutic power to about 35 per cent. of tannic acid. (The cause of their influence on the kidneys is not yet traced.) They also contain *arbutin*, a crystalline glucoside.

Gallic Acid ($H_3C_7H_3O_5,H_2O$) (*Acidum Gallicum*, B. P. and U. S. P.) occurs in small quantity in oak-galls and other vegetable substances, but is always prepared from tannic acid. Powdered galls are moistened with water and set

aside in a warm place for five or six weeks, occasionally being remoistened; fermentation occurs, and impure gallic acid is formed. The product is treated with about three times its weight of water, boiled to dissolve the gallic acid, filtered, the solution set aside to cool, deposited gallic acid collected, drained, pressed between folds of paper to remove all mother-liquor, and, if necessary, purified by recrystallization from water, or by solution in hot water with animal charcoal, which absorbs coloring matter. On filtering and cooling, most of the acid separates in the form of fawn-colored slender acicular crystals. Gallic acid is soluble in about 100 times its weight of cold or 3 of boiling water, freely in spirit, sparingly in ether, also in glycerine (*Glyceritum Acidi Gallici*, U. S. P.).

The nature of the action by which gallic acid is thus produced is probably similar to that of the action of dilute acids on tannic acid. During the process oxygen is absorbed and carbonic acid gas evolved, the sugar being thus broken up or perhaps prevented from being formed.

Test.—To an aqueous solution of gallic acid add a neutral solution of ferric salt; a bluish-black precipitate of gallate of iron falls, similar in appearance to tannate of iron. Ferrous salts are also blackened by gallic acid. To more of the solution add an aqueous solution of gelatine; no precipitate occurs. By the latter test gallic is distinguished from tannic acid.

Pyrogallic Acid ($C_6H_6O_3$).—This substance sublimes in light feathery crystals when gallic acid is heated. To an aqueous solution add a neutral solution of a ferric salt, a red color is produced. To another portion add a ferrous salt; a deep-blue color results.

Test for the three acids.—To three separate small quantities of milk of lime in test-tubes add, respectively, tannic, gallic, and pyrogallic acids; the first slowly turns brown, the second more rapidly, while the pyrogallic mixture at once assumes a beautiful purplish-red color changing to brown. These reactions are highly characteristic. They are accompanied by absorption of oxygen from the air.

Use of Pyrogallic Acid in Gas-analysis.—A mixture of pyrogallic acid and solution of potash absorbs oxygen with such rapidity and completeness that a strong solution of each, passed up successively by a pipette into a graduated tube containing air or other gas, forms an excellent means of estimating free oxygen. The value of this method may be roughly proved by pouring a small quantity of each solution into a phial, immediately and firmly closing its mouth with a cork, thoroughly shaking the mixture and then removing the cork under water; the water rushes in and occupies about one-fifth of the previous volume of air, indicating that the atmosphere contains one-fifth of its bulk of oxygen. The small amount of carbonic

acid gas present in the air is also absorbed by the alkaline liquid; in delicate experiments this thould be removed by the alkali before the addition of pyrogallic acid.

URIC ACID ($H_2C_5H_2N_4O_3$) AND OTHER URATES.—Acidulate a few ounces of human urine with hydrochloric acid, and set aside for twenty-four hours; a few minute crystals of uric acid will be found adhering to the sides and bottom of the vessel and floating on the surface of the liquid.

Microscopical Test.—Remove some of the floating particles by a slip of glass, and examine by a powerful lens or microscope; the chief portion will be found to be in yellowish semitransparent crystals, more or less square, two of the sides of which are even, and two very jagged; but other forms are common (*vide* Frontispiece).

Chemical Test.—Collect more of the deposit, place in a watch-glass or small white evaporating-dish, remove adherent moisture by a piece of blotting or filter-paper, add a drop or two of strong nitric acid, and evaporate to dryness; the residue will be red. When the dish is cold, add a drop of solution of ammonia; a purplish-crimson color results. The color is deepened on the addition of a drop of solution of potash.

Notes.—Uric acid (or lithic acid) and urates (or lithates) of sodium, potassium, calcium, and ammonium are common constituents of animal excretions. Human urine contains about one part of urate (usually urate of sodium) in 1000. When more than this is present the urate is often deposited as a sediment in the excreted urine, either at once, or after standing a short time. Uric acid or other urate is also occasionally deposited before leaving the bladder, and, slowly accumulating there, forms a common variety of urinary calculus.——Some urates are not definitely crystalline; but, when treated with dilute nitric acid or a drop of solution of potash and then a drop or two of acetic acid, jagged microscopic crystals of uric acid are usually formed.—All urates yield the crimson color when treated as above described.—This color is due to a definite substance, *murexid* ($C_8H_8N_6O_6$) (from the *murex*, a shell-fish of similar tint); and the test is known as *the murexid test.* The formation of murexid is due to the action of ammonia on *alloxan* ($C_4H_2N_2O_4,4H_2O$) and other white crystalline products of the oxidation of uric acid by nitric acid. Murexid is a good dye; it may be prepared from *guano* (the excrement of sea-fowl), which contains a large quantity of urate of ammonium. The excrement of the serpent is almost pure ammonium urate.

Uric acid and the urates will be again alluded to in connection with the subject of morbid urine.

VALERIANIC ACID OR VALERIC ACID ($HC_5H_9O_2$) AND OTHER VALERIANATES.—In a test-tube place a few drops of

amylic alcohol (fousel oil) with a little dilute sulphuric acid and a grain or two of red chromate of potassium, cork the tube, set aside for a few hours, and then heat the mixture; valerianic acid, of characteristic valerian-like odor, is evolved.

Valerianic acid occurs naturally in valerian-root in association with the essential oil from which it is derived (*vide* Index), but is usually prepared artificially, by the foregoing process, from amylic alcohol, to which it bears the same relation as acetic acid does to common alcohol:—

$$C_2H_5HO + O_2 = HC_2H_3O_2 + H_2O$$
$$C_5H_{11}HO + O_2 = HC_5H_9O_2 + H_2O.$$

Valerianate of Sodium ($NaC_5H_9O_2$) (*Sodæ Valerianas*, B. P.) is prepared from the valerianic acid and valerianate of amyl obtained on distilling the mixture of amylic alcohol (4 fl. ozs.), sulphuric acid ($6\frac{1}{2}$ fl. ozs. with 10 of water), and red chromate of potassium (9 ozs. in 70 of water). The mixture should stand for several hours before heat is applied.

$$\underset{\text{Red chromate of potassium.}}{2(K_2CrO_4,CrO_3)} + \underset{\text{Sulphuric acid.}}{8H_2SO_4} = \underset{\text{Sulphate of potassium and chromium. (Chrome alum.)}}{2(K_2SO_4,Cr_23SO_4)} + \underset{\text{Water.}}{8H_2O} + \underset{\text{Oxygen.}}{3O_2}$$

$$\underset{\text{Amylic alcohol.}}{C_5H_{11}HO} + \underset{\text{Oxygen.}}{O_2} = \underset{\text{Valerianic acid.}}{HC_5H_9O_2} + \underset{\text{Water.}}{H_2O}$$

$$\underset{\text{Amylic alcohol.}}{2C_5H_{11}HO} + \underset{\text{Oxygen.}}{O_2} = \underset{\text{Valerianate of amyl.}}{C_5H_{11}C_5H_9O_2} + \underset{\text{Water.}}{2H_2O}$$

The distillate (70 or 80 ozs.) is saturated with soda, which not only yields valerianate of sodium with the free valerianic acid, but decomposes the valerianate of amyl produced at the same time, more valerianate of sodium being formed and some amylic alcohol set free, according to the following equations:—

$$\underset{\text{Valerianic acid.}}{HC_5H_9O_2} + \underset{\text{Soda.}}{NaHO} = \underset{\text{Valerianate of sodium.}}{NaC_5H_9O_2} + \underset{\text{Water.}}{H_2O}$$

$$\underset{\text{Valerianate of amyl.}}{C_5H_{11}C_5H_9O_2} + \underset{\text{Soda.}}{NaHO} = \underset{\text{Valerianate of sodium.}}{NaC_5H_9O_2} + \underset{\text{Amylic alcohol.}}{C_5H_{11}HO}$$

From the solution of valerianate of sodium (which should be made neutral to test-paper by careful addition of soda solution) the solid white salt is obtained by evaporation to dryness and cautious fusion of the residue. The mass obtained on cooling should be broken up and kept in a well-closed bottle. It is entirely soluble in spirit.

Other Valerianates, as valerianate of zinc (*Zinci Valerianus*, B. P. and U. S. P.), and ferric valerianate, may be made by double decomposition of valerianate of sodium

with the sulphate or other salt of the metal the valerianate of which is desired, the new valerianate precipitating or crystallizing out. A hot solution of sulphate of zinc ($5\frac{3}{4}$ parts) and valerianate of sodium (5 parts) in water (40 parts) gives a crop of crystals of valerianate of zinc on cooling.

Tests.—Heated with diluted sulphuric acid, valerianates of the metals give valerianic acid, which has a highly characteristic smell. Valerianate of sodium thus treated, and the resulting oily acid liquid purified by agitation with sulphuric acid and distillation, furnishes the *Acidum Valerianicum* of the United States Pharmacopœia. Sp. gr. 933. Dry ammonia gas passed into valerianic acid gives white lamellar crystals of valerianate of ammonium (*Ammonii Valerianas*, U. S. P.).

The amylic alcohol ($C_5H_{11}HO$) from which valerianates are prepared may contain the next lower homologue, *butylic alcohol* (C_4H_9HO). This, during oxidation, will be converted into *butyric acid* ($HC_4H_7O_2$), the next lower homologue of valerianic acid ($HC_5H_9O_2$), and hence the various valerianates be contaminated by some *butyrates*. These are detected by distillation with diluted sulphuric acid and addition of solution of acetate of copper to the distillate, which at once becomes turbid if butyric acid be present. In this reaction valerianic and butyric acids are produced by double decomposition of the valerianate and butyrate by the sulphuric acid, and distil over on the application of heat. On the addition of acetate of copper ($Cu2C_2H_3O_2$) butyrate of copper ($Cu2C_4H_7O_2,H_2O$) is formed, and, being almost insoluble in water, is at once precipitated, or remains suspended, giving a bluish-white opalescent liquid. Valerianate of copper ($Cu2C_5H_9O_2$) is also formed after some time, but is far more soluble than the butyrate, and only slowly collects in the form of greenish oily drops, which gradually pass into greenish-blue hydrous crystalline valerianate of copper (Larocque and Huralt).

QUESTIONS AND EXERCISES.

619. What is the constitution of nitrites?
620. Mention a test for nitrites in potable waters.
621. Which nitrite is official?
622. Give the names of some natural and artificial silicates.
623. What is "soluble glass?"
624. Distinguish between silica and silicic acid.
625. How are silicates detected?
626. What is the quantivalence of silicon?
627. Mention the sources, formulæ, and analytical reactions of succinates.
628. State the mode of manufacture and tests of sulphocyanates.
629. What proportion of tannic acid is contained in galls?

630. Describe the official process for the preparation of Tannic Acid.
631. Explain the chemistry of "tanning."
632. Enumerate the tests for tannic acid?
633. What is the assumed constitution of tannic acid?
634. Mention other official substances whose astringency is due to tannic acid.
635. How is gallic acid prepared?
636. By what reaction is gallic distinguished from tannic acid?
637. Mention the characteristic properties of pyrogallic acid.
638. Explain the murexid test for uric acid.
639. Describe the artificial preparation of valerianic acid and other valerianates, giving diagrams or equations.
640. What is the formula of valerianic acid?
641. How are butyrates detected in presence of valerianates?

DETECTION OF THE ACIDULOUS RADICALS OF SALTS SOLUBLE IN WATER.

Analytical operations may now be resumed, the detection of acidulous radicals being practised for two or three days, and then full analyses made, both for basylous and acidulous radicals. To this end a few compounds of stated metals (potassium, sodium, or ammonium) should be placed in the hands of the practical student for examination according to the following paragraphs and Tables. Mixtures in which both basylous and acidulous radicals may be sought should then be analyzed.

In examining salts soluble in water, and concerning which no general information is obtainable, search must first be made for any basylous radicals by the appropriate methods (*vide* pages 196 or 229). Certain metals having been thus detected, a little reflection on the character of their salts will at once indicate what acidulous radicals may be, and what cannot be, present. Thus, for instance, if the substance under examination is freely soluble in water, and lead is found, only the nitric and acetic radicals need be sought, none other of the lead salts than nitrate or acetate being freely soluble in water. Moreover, the salt is more likely to be acetate than nitrate of lead, for two reasons: the former is more soluble than the latter, and is by far the commoner salt of the two. Medical and pharmaceutical students have probably, in dispensing, already learned much concerning the solubility of salts, and whether a salt is rarely employed or in common use. And although but little dependence can be placed on the chances of a salt being present or absent according to its rarity, still the point may have its proper weight. If, in a mixture of salts, ammonium, potassium, and magnesium have been found associated with the sulphuric, nitric, and hydrochloric radicals, and we are asked how we suppose these bodies may exist in the mixture, it is far more in accordance with common sense to suggest that sal-ammoniac, nitre, and Epsom salt were originally mixed together than to suppose any other possible combination. Such appeals to experience regarding the solubility or rarity of salts cannot be made by

any one not previously acquainted, or insufficiently acquainted, with the characters of salts; in such cases the relation of a salt to water and acids can be ascertained by referring to the following Table (p. 325) of the solubility or insolubility of about five hundred of the common or rarer salts met with in chemical operations.

The opposite course to the above (namely, to acertain what acidulous radicals are present in a mixture, and then to appeal to experience to tell what basylous radicals may be and what cannot be present) is impracticable; for acidulous radicals cannot be separated out, one after the other, from one and the same quantity of substance by a similar treatment to that already given for basylous radicals. Indeed such a sifting of acidulous radicals could scarcely be accomplished at all, or only by a vast deal of labor. The basylous radicals must, therefore, be first detected.

Even when the basylous radicals have been found, the acidulous radicals which may be present must be sought for singly, the only additional aid which can be brought in being the action of sulphuric acid, a barium salt, a calcium salt, nitrate of silver, and ferric chloride on *separate* small portions of the solution under examination, as detailed in the second of the following Tables.

Commence the analysis of an aqueous solution of a salt or salts, the basylous radicals in which are known, by writing out a list of the acidulous radicals which may be, or, if more convenient, of those which cannot be present. To this end consult the following Table (p. 325) of the solubility of salts in water. Look for the name of the metal of the salt in the vertical column; the letters S and I indicate which salts are soluble and which insoluble in water, an asterisk attached to the S meaning that the salt is slightly soluble. The acidulous part of the name is given in the top line of the Table. All the names are in alphabetical order, for facility of reference.

Some of the salts marked as insoluble in water are soluble in aqueous solutions of soluble salts, a few forming soluble double salts. To characterize salts as soluble, slightly soluble, or insoluble, only roughly indicates their relation to water: on the one hand, very few salts are absolutely insoluble in water; on the other, there is a limit to the solubility of every salt.

If only one, two, or perhaps three given acidulous radicals can be in the liquid, test directly for it or them according to the reactions given in the previous pages. If several may be present, pour small portions of the solutions, rendered neutral if necessary by ammonia, into five test-tubes, and add respectively sulphuric acid, nitrate or chloride of barium, chloride of calcium, nitrate of silver, and ferric chloride; then consult the Table on page 326, *in order to correctly interpret the effects these reagents may have produced.*

	Acetate.	Arsenate.	Arsenite.	Carbonate.	Chloride.	Citrate.	Chromate.	Cyanide.	Hydrate.	Iodide.	Nitrate.	Oxalate.	Oxide.	Phosphate.	Sulphate.	Sulphide.	Sulphite.	Tartrate.
Aluminium	S	I	I	I	S	S*	I	?	I	?	S	I	I	I	S	I	I	S
Ammonium	S	S	S	S	S	S	S	?	S	S	S	S	?	S	S	S	S	S
Antimony	S	I	?	S	S	?	S	?	S	I	?	S*	I	S	S	S	S	I
Barium	S	I	I	I	S	S*	I	S	I	S	S	I	I	I	I	I	I	I
Bismuth	S	I	?	I	S	S*	I	?	I	S	S	I	I	I	I	S	I	I
Cadmium	S	?	?	I	S	S*	?	?	I*	S	S	I	I	I	S*	S	S	S*
Calcium	S	I	I	I	S	S*	S	I	S*	S	S	I	I*	I	S*	S	S*	S*
Chromium	S	I	?	I	S	S	I	I	I	S	S	S	I	I	S	S	S*	S
Cobalt	S	I	I	I	S	S	?	I	I	S	S	I	I	I	I	I	S*	S
Copper	S	I	I	I	S	S	S	I	I	I	S	I	I	I	S	I	I	S*
Ferric	S	I	?	I	S	S	S	?	I	S	S	S*	I	I	S	I	?	S
Ferrous	S	I	I	?	S	S	?	I	I	S	S	S*	I	I	S	I	?	S*
Gold	?	I	?	?	S	?	?	I	I	I	?	?	I	I	?	I	?	?
Lead	S	I	I	I	S*	S*	I	I	S*	I	S	I	I	I	I	I	S	I
Magnesium	S	I	I	I	S	S	S	?	I	S	S	I	I	I	S	?	S	S*
Manganese	S	I	?	I	S	I	S	?	I	S	S	I	I	I	S	I	S	I
Mercuric	S	I	I	I	S	?	S*	S	I	I	S	I	I	I	S*	I	?	I
Mercurous	S*	I	I	I	I	I	I	?	?	S	S	I	I	I	S*	I	?	I*
Nickel	S	I	I	I	S	S	I	I	I	S	S	I	I	I	S	I	S*	S*
Platinum	?	I	?	I	S	?	?	?	I	S*	S	I	I	?	S	I	S	?
Potassium	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S
Silver	S*	I	I	I	I	I	I	?	I	S	S	I	I	I	S*	I	I	I
Sodium	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S	S
Stannic	S	S	I	?	S	?	?	?	I	S	S	S	I	I	S	S	?	?
Stannous	S	I	I	?	S	?	I	?	I	S	S	I	I	I	S	I	I	S
Strontium	S	I	I	I	S	I	I	S	S	S	S	I	S	I	S	S	I	S*
Zinc	S	I	?	I	S	S*	S	I	?	S	S	I	I	I	S	I	S*	S*

TABLE TO AID IN THE DETECTION OF CHLORIDES, BROMIDES, IODIDES, CYANIDES, NITRATES, CHLORATES, BORATES, ACETATES, SULPHIDES, SULPHITES, SULPHATES, CARBONATES, OXALATES, TARTRATES, PHOSPHATES, AND CITRATES, IN A NEUTRAL AQUEOUS SOLUTION.

(For remarks concerning this Table see next page.)

Sulphuric acid decomposes	Chloride of Barium precipitates	Chloride of Calcium precipitates	Nitrate of Silver precipitates	Ferric Chloride precipitates	Not precipitated
Sulphides. Sulphites. Carbonates, with effervescence—hydrosulphuric, sulphurous, and carbonic acid gases, known by smell, being evolved. Cyanides, with production of the odor of hydrocyanic acid. Acetates, with production of the odor of acetic acid when the solution is warmed.	Borates. Sulphites. Sulphates. Carbonates. Oxalates. Tartrates. Phosphates. Citrates. Of these white barium precipitates the sulphate is the only one insoluble in hydrochloric acid; the tartrate and citrate char when heated on platinum foil; the sulphite and carbonate are decomposed with effervescence by acids.	Borates. Oxalates. Sulphites. Tartrates. Sulphates. Phosphates. Carbonates. Citrates. Of these white calcium precipitates, the sulphate only is soluble in much water; the borate, tartrate, and citrate are soluble in solution of chloride of ammonium; all are soluble in acetic acid except oxalate and some sulphate; all are soluble in hydrochloric acid, much sulphate excepted; the dry tartrate and citrate char when heated; the sulphite and carbonate effervesce with acids.	Chlorides, white. Bromides, white. Iodides, yellow. Cyanides, white. Borates, white. Sulphides, black. Sulphites, white. Carbonates, white. Oxalates, white. Tartrates, white. Phosphates, yellow. Citrates, white. Of these silver precipitates, the chloride, bromide, iodide, cyanide, and sulphide are insoluble in dilute nitric acid; the rest soluble.	Borates, yellowish. Sulphides, black Carbonates, reddish. Oxalates, yellow. Phosphates, yel.-white. Gives red color with acetates, if neutral.	Nitrates. Chlorates. Apply special tests.

Note.—The student should practise the examination of aqueous solutions of salts until able to detect acidulous radicals with facility and precision. For this purpose he may finish the analyses of salts or solutions already examined for common and rarer metals, or have aqueous solutions of salts, or the salts themselves, specially prepared for present use, the metals of the salts being stated. He will then be in a position to effectively study the analysis of salts which may or may not be soluble in water, examining them for both basylous and acidulous radicals.

REMARKS ON THE PRECEDING TABLE.

The first point of value to be noticed in connection with this Table is one of a negative character; namely, if either of the reagents gives no reaction it is self-evident that the salts which it decomposes with production of a precipitate must be absent. Then, again, if the action of one of the reagents indicates the absence of certain acidulous radicals, those radicals cannot be precipitated by the other reagents; thus, if the action of sulphuric acid points to the absence of sulphides, sulphites, carbonates, cyanides, and acetates, these salts may be struck out of the other lists, and the examination of subsequent precipitates be so far simplified. Or, if the barium precipitate is soluble in hydrochloric acid and the calcium precipitate in acetic acid, neither sulphates nor oxalates can be present. Observing these and other points of difference, which will be seen on careful and thoughtful reflection, and remembering the facts suggested by a knowledge of what basylous radicals are present, one acidulous radical after the other may be struck off as absent or present, leaving only one or two as the objects of special experiment. Among the chief difficulties to be encountered will be the separation from each other of chlorides, bromides, iodides, and cyanides, or of tartrates from citrates, and confirmatory tests of the presence of certain compounds. These may all be surmounted on referring back to the reactions of the various radicals, as described under their hydrogen salts, the acids.

The rarer acidulous radicals will very seldom be met with. *Benzoates*, *hippurates* (which give benzoic acid), *hypochlorites*, *hyposulphites*, *nitrites*, and *valerianates* show themselves under the sulphuric treatment. *Ferrocyanides*, *ferridcyanides*, *meconates*, *succinates*, *sulphocyanates*, *tannates*, and *gallates* appear among the salts whose presence is indicated by ferric chloride; *formiates*, *hypophosphites*, *malates*, and others by nitrate of silver. *Urates* char when heated, giving an odor resembling that of burnt feathers.

In actual practice the analyst nearly always has some clue to the nature of rarer substances placed in his hands.

If chromium and arsenicum have been detected among the basylous radicals, those elements may be present in the form of *chromates*, *arseniates*, and *arsenites*, yielding with chloride of barium yellow chromate of barium and white arseniate and arsenite of barium, and with nitrate of silver red chromate, brown arseniate, and yellow arsenite of silver.

QUESTIONS AND EXERCISES.

642. In analyzing an aqueous solution of salts, for which radicals would you first search, the basylous or the acidulous? and why?

643. In an aqueous solution there have been found magnesium (Mg) and potassium (K), with the sulphuric radical (SO_4), and iodine (I); state the nature of the salts which were originally dis-

solved in the water, and mention the principles which guide you in the conclusions.

644. Give a sketch of the method by which to analyze a neutral or only faintly acid aqueous liquid for the acidulous radical of salts. In what stage of the process would the following salts be detected?

a. Carbonates and Sulphates.
b. Oxalates.
c. Tartrates and Nitrates.
d. Acetates and Sulphites.
e. Bromides and Cyanides.
f. Borates.
g. Iodides and Phosphates.
h. Chlorates, Oxalates, and Acetates.
i. Chlorides and Iodides.
j. Sulphites.
k. Sulphides, Carbonates, and Nitrates.
l. Citrates and Sulphates.

645. Nitrate of silver gives no precipitate in an aqueous solution; what salts may be present?

646. Chloride of barium gives no precipitates in a neutral solution, but nitrate of silver a white; what acidulous radicals are indicated?

647. Ferric chloride produces a deep red color in a solution, chloride of calcium yielding no precipitate; what salts may be present, and how might they be distinguished from each other?

648. Ferric chloride gives a black precipitate in a solution in which sulphuric acid develops no odor; to what is the effect due?

ANALYSIS OF SALTS,

SINGLE OR MIXED, SOLUBLE OR INSOLUBLE.

Thus far all material substances, especially those of pharmaceutical interest, have been regarded as being definite compounds, and as having certain well-defined parts, termed, for convenience, basylous and acidulous respectively: moreover attention has been designedly restricted to those definite compounds which are soluble in water. But there are many substances having no definite or known composition; and of those having definite composition there are many having no definite or ascertained parts. Again, of those having definite composition, and whose constitution admits of the entertainment of theory, there are many insoluble in water.

Chemical substances of whose composition or constitution little or nothing is at present known, are chiefly of animal and vegetable origin, and figure in tables of analysis under the convenient collective title of "extractive matter;" they are not of immediate importance, and may be omitted.

Of substances which are definite in composition, but whose parts or radicals, if they have any, are unknown or imperfectly known, there are only a few (such as the alkaloids, amylaceous and saccharine matters, the glucosides, alcoholic bodies, albuminoid, fatty, resinoid, and colorific substances) which have any considerable amount of pharmaceutical interest; these will be noticed subsequently.

Definite compounds most frequently present themselves; and of these by far the larger proportion (namely, the salts soluble in water) have already been fully studied. There remain, however, many salts which are insoluble in water, but which must be brought into a state of solution before they can be effectively studied from an analytical, pharmaceutical, or a physiological point of view. The next subject of laboratory work is therefore the analysis of substances which may or may not be soluble in water. This will involve no other analytical schemes than those which have been given, will in only one or two cases increase the difficulty of the analysis of the precipitate produced by a group-reagent, but will give roundness, completeness, and a practical bearing to the reader's analytical knowledge. Such a procedure will at the same time bring into notice the methods by which substances insoluble in water are manipulated for pharmaceutical purposes, or made available for use as food by plants, or as food and medicine by man and animals generally.

Preliminary Examination of Solid (chiefly mineral) Salts.

Before attempting to dissolve a salt for analysis, its appearance and other physical properties should be noted, and the influence of heat and strong sulphuric acid be ascertained. If the operator knows how to interpret what is thus observed, and to what extent to place confidence in the observations, he may more certainly obtain a high degree of precision in analysis, and will always gain some valuable negative information. But if he has only slight experience of the appearance and general properties of bodies, or has the habit of turning what should be inferences from tentative processes into foregone conclusions, he should omit the preliminary examination altogether, or only follow it out under the guidance of a judicious tutor; for it is impracticable here to do more than hint at the results which may be obtained by such an examination, or to so adapt description as to prevent a student from allowing unnecessary weight to preconceived ideas.

Whatever be the course pursued, short memoranda describing results should invariably be entered in the note book.

1. Examine the physical characters of the salt in various ways, but never, or only rarely, by the palate, on account of the danger to be apprehended.

If the salt is white, colored substances cannot be present; if colored, the tint may indicate the nature of the substance or of one of its constituents, supposing that the learner is already acquainted with the colors of salts. Closer observation, aided perhaps by a lens, may reveal the occurrence, in a pulverulent mixture, of small

crystals or pieces of a single substance; these should be picked out by a needle and examined separately. In a powder or roughly divided mixture of substances, the process of sifting (through such sieves as muslin of different degrees of fineness) often mechanically separates substances, and thus greatly facilitates analysis. The body may present an undoubted metallic appearance, in which case only the metals existing under ordinary atmospheric conditions need be sought. Peculiarity in smell reveals the presence of ammonia, hydrocyanic acid, hydrosulphuric acid, etc. Between the fingers a substance is, perhaps, hard, soft, or gritty; consequent inferences follow. Or the matter may be heavy, like the salts of barium or lead; or light, like the carbonates and hydrates of magnesium.

2. Place a grain or two of the salt in a small dry test-tube or in a piece of ordinary tubing, closed at one end, and heat it, at first gently, then more strongly, and finally, if necessary, by the blowpipe.

Gases or vapors of characteristic appearance or odor may be evolved; such as iodine, nitrous fumes, sulphurous, hydrocyanic, or ammoniacal gases. Much steam given by a dry substance indicates either hydrates or salts containing water of crystallization. (A small quantity of interstitial moisture often causes heated crystalline substance to *decrepitate*—from *decrepo*, to crackle—that is, break up with slight explosive violence, owing to the expansive force of the steam suddenly generated.) A sublimate may be obtained, due to salts of mercury or arsenicum, to oxalic or benzoic acid, or to sulphur free or as a sulphide—a salt wholly volatile containing such substances only. The compound may blacken, pointing to the presence of organic matter—which, in common definite salts, will probably be in the form of acetates, tartrates, and citrates, or as common salts of the alkaloids morphia, quinia, strychnia, or as starch, sugar, salicin, or in other definite or indefinite forms common in pharmacy and for which tests will be given in subsequent pages. If no charring occurs, the important fact that no organic matter is present is established. The residue may change color from presence or development of oxide of zinc, oxide of iron, etc., or melt from the presence of a fusible salt and absence of any large proportion of infusible salt, or be unaltered, showing the absence of any large amount of such substances.

3. Place a grain or two of the salt in a test-tube, add a drop or two of strong sulphuric acid, cautiously smelling any gas that may be evolved; afterward slowly heat the mixture, noticing the effect, and stopping the experiment when any sulphuric fumes begin to escape.

Iodine, bromine, and nitrous or chlorinoid fumes will reveal themselves by their color, indicating the presence of iodides, bromides, iodates, bromates, nitrates, and chlorates. The evolution of a colorless gas fuming on coming into contact with air, and having an irritating odor, points to chlorides, fluorides, or nitrates. Gaseous

products having a greenish color and odor of chlorine indicate chlorates, hypochlorites, or chlorides mixed with other substances. Slight sharp explosions betoken chlorates. Evolution of colorless gas may proceed from cyanides, acetates, sulphides, sulphites, carbonates, or oxalates. Charring will be due to citrates, tartrates, or other organic matter. If none of these effects are produced, most of the bodies are absent or only present in minute quantity. The substances apparently unaffected by the treatment are metallic oxides, borates, sulphates, and phosphates.

4. Exposure of the substance to the blowpipe-flame, on platinum wire with or without a bead of borax or of microcosmic salt (phosphate of sodium, ammonium, and hydrogen, $NaAmHPO_4$)—on platinum foil, in a porcelain crucible, or on a crucible lid with or without carbonate of sodium—on charcoal, alone or in conjunction with carbonate of sodium, cyanide of potassium, or nitrate of cobalt, will sometimes yield important information, especially to one who has devoted much attention to reactions producible by the blowpipe-flame. The interior portions of the flame consist of hydrocarbon gases heated to a temperature at which they combine with oxygen with great avidity, abstracting that element from metallic oxides or other oxidized substance which may be brought within their influence; the exterior portions, on the other hand, contain excess of heated oxygen; the former is the *reducing*, the latter the *oxidizing* part of the flame. The medical or pharmaceutical student, however, will seldom have time to work out this subject to an extent sufficient to make it a trustworthy guide in analysis. (See Plattner and Muspratt "On the Use of the Blowpipe," and a chapter in Galloway's "Manual of Qualitative Analysis.")

Methods of dissolving and analyzing single or mixed solid substances.

Having submitted the substance to preliminary examination, proceed to dissolve and analyze by the following methods. These operations consist in treating a substance well powdered, consecutively with cold or hot water, hydrochloric acid, nitric acid, nitrohydrochloric acid, or fusion with alkaline carbonates and solution of the product in water and acid. Resulting liquids are analyzed in the manner already described, or by slightly modified processes as detailed in the following paragraphs.

Solution in Water.—Boil about a grain of the salt presented for analysis in about a third of a test-tubeful of water. If it dissolves prepare a solution of about 20 or 30

grains in half an ounce or more of water, and *proceed with the analysis in the usual way*, testing first for the basylous radical or radicals by the proper group reagents (HCl, H_2S, AmHS, Am_2CO_3, Am_2HPO_4), pp. 199 or 230, and then for the acidulous radical or radicals, directly or by aid of the prescribed reagents (H_2SO_4, $BaCl_2$, $CaCl_2$, $AgNO_3$, Fe_2Cl_6), p. 326.

If the salt is not *wholly* dissolved by the water, ascertain whether or not any has entered into solution, by filtering, if necessary, and evaporating a drop or two of the clear liquid to dryness on platinum foil; the presence or absence of a residue gives the information sought. If anything is dissolved, prepare a sufficient quantity of solution for analysis and proceed as usual, reserving the insoluble portion of the mixture, after thoroughly exhausting with water for subsequent treatment by acids.

Solution in Hydrochloric Acid.—If the salt is insoluble in water, digest about a grain of it (or of the insoluble portion of a mixed salt) in a few drops of hydrochloric acid, adding water, and boiling if necessary. If the salt wholly dissolves, prepare a sufficient quantity of the liquid, noticing whether or not any effervescence (due to the presence of sulphides, sulphites, carbonates, or cyanides) occurs, and proceed with the analysis as before, except that the first step, the addition of hydrochloric acid, may be omitted.

The analysis of this solution will in most repects be simpler than that of an aqueous solution, inasmuch as the majority of salts (all those soluble in water) will be absent. This acid solution will, in short, only contain: chlorides produced by the action of the hydrochloric acid on sulphides, sulphites, carbonates, cyanides, oxides, and hydrates; and certain borates, oxalates, phosphates, tartrates, and citrates (possibly silicates and fluorides) which are insoluble in water but soluble in acids without apparent decomposition. The first four—sulphides, sulphites, carbonates, and cyanides—will have revealed themselves by the occurrence of effervescence during solution; and the presence of oxides and hydrates may often be inferred by the absence of compatible acidulous radicals. The borates, oxalates, phosphates, tartrates, and citrates alluded to will be reprecipitated in the general analysis as soon as the acid of the solution is neutralized; that is, will come down in their original state when ammonia and sulphydrate of ammonium are added in the usual course. Of these precipitates, only the oxalate of calcium and the phosphates of calcium and magnesium need occupy attention now; for oxalate and phosphate of barium seldom or never occur, and the borates, tartrates, and citrates met with in medicine or in general analysis are all soluble in water. These phosphates and oxalates,

then, will be precipitated in the course of analysis along with iron, their presence not interfering with the detection of any other metal. If, from the unusual light color of the ferric precipitate, phosphates and oxalates are suspected, the precipitate is treated according to the following Table (reference to which should be inserted in the Table for metals, under Fe, pp. 199 and 230).

PRECIPITATE OF PHOSPHATES, OXALATES, AND FERRIC HYDRATE.

Dissolve in HCl, add citric acid, then NH_4HO, and filter.

<table>
<tr><td rowspan="3">Filtrate
Fe
Add HCl and
K_4Fcy
Blue ppt.</td><td colspan="3">Precipitate.
$Ca_3 2PO_4$, CaC_2O_4, $Mg_3 2PO_4$.
Boil in acetic acid and filter.</td></tr>
<tr><td>Insoluble
CaC_2O_4.
White.</td><td colspan="2">Filtrate
$Ca_3 2PO_4$, $Mg_3 2PO_4$.
Add $Am_2C_2O_4$, stir, filter.</td></tr>
<tr><td>Precipitate
white, indicating
$Ca_3 2PO_4$.</td><td>Filtrate,
Add AmHO.
White ppt.
$MgNH_4PO_4$.</td></tr>
</table>

In analyzing phosphates and oxalates advantage is also frequently taken of the facts that the phosphoric radical is wholly removed from solution of phosphates in acid by the addition of an alkaline acetate, ferric chloride, and subsequent ebullition, as described under "Phosphoric Acid" (p. 293), and that dry oxalates are converted into carbonates by heat, as mentioned under "Oxalic Acid" (p. 282).

Certain arseniates and arsenites, insoluble in water but soluble in hydrochloric acid, may accompany the above phosphates and oxalates if from any cause hydrosulphuric acid gas has not been previously passed through the solution, or passed for an insufficient length of time.

If the substance insoluble in water does not *wholly* dissolve in hydrochloric acid, ascertain if any has entered into solution, by filtering, if necessary, and evaporating a drop of the clear liquid to dryness on platinum foil; the presence or absence of a residue gives the information sought. If anything is dissolved, prepare a sufficient quantity of solution for analysis, and proceed as usual, reserving the insoluble portion of the mixture, after thoroughly exhausting with hydrochloric acid and well washing with water, for the following treatment by nitric acid.

Solution in Nitric Acid.—If the salt is insoluble in water and hydrochloric acid, boil it (or that part of it which is insoluble in those menstrua) in a few drops of nitric acid. If it wholly dissolves, remove excess of acid by evaporation, dilute with water, and proceed with the analysis.

This nitric solution can contain only very few substances; for nearly all salts soluble in nitric acid are also soluble in hydrochloric acid, and therefore will have been previously removed. Some of the metals, however (Ag, Cu, Hg, Pb, Bi), as well as amalgams and alloys, unaffected or scarcely affected by hydrochloric acid, are readily attacked and dissolved by nitric acid. Many of the sulphides, also insoluble in hydrochloric acid, are dissolved by nitric acid, usually with separation of sulphur. Calomel is converted, by long boiling with nitric acid, into mercuric chloride and nitrate. The nitrates here produced are soluble in water.

This nitric solution, as well as the hydrochloric and aqueous solutions, should be examined separately. Apparently time would be saved by mixing the three solutions together and making one analysis. But the object of the analyst is to separate every radical from every other; and when this has been partially accomplished by solvents, it would be unwise to again mix and separate a second time. Moreover, solvents often do what the chemical reagents cannot—namely, separate *salts* from each other. This is important, inasmuch as the end to be obtained in analysis is not only an enumeration of the radicals present, but a statement of the actual condition in which they are present; the analyst must, if possible, state of what salts a given mixture was originally formed—how the basylous and acidulous radicals were originally distributed. In attempting this, much must be left to theoretical considerations; but a process by which the salts themselves are separated is of trustworthy practical assistance; hence the chief advantage of analyzing separately the solutions resulting from the action of water and acids on a solid substance.

Solution in Nitro-Hydrochloric Acid.—If the salt or any part of a mixture of salts is insoluble in water, hydrochloric acid, and nitric acid, digest it in nitro-hydrochloric acid, boiling, if necessary; evaporate to remove excess of acid, dilute, and proceed as before.

Sulphide of mercury and substances only slowly attacked by hydrochloric or nitric acid, as, for example, calomel and ignited ferric oxide, are sufficiently altered by the free chlorine of aqua regia to become soluble.

If the substance is insoluble in water and acids, it is one or more of the following substances: Sand and certain silicates, such as pipeclay and other clays; fluor spar; cryolite ($3NaF,AlF_3$); sulphates of barium, strontium, and possibly calcium; tinstone; glass; felspar (double silicate

of aluminium and other metals); chloride of silver; sulphate of lead. It may also be or contain carbon or carbonaceous matter, in which case it is black and combustible, burning entirely or partially away when heated in the air—or be or contain sulphur, in which case sulphurous gas is evolved, detected by its odor, when the substance is exposed to heat. For the other substances proceed according to the following (Bloxam's) method:—

Four or five grains of the substance are intimately mixed with twice the quantity of dried carbonate of sodium, and this mixture well rubbed in a mortar with five times its weight of *deflagrating flux* (1 of finely powdered charcoal to 6 of nitre). The resulting powder is placed in a thin porcelain dish, or crucible, or clean iron tray, and a lighted match applied to the centre of the heap. Deflagration ensues, and decomposition of the various substances occurs, the acidulous radicals going to the alkali-metals to form salts soluble in water, the basylous radicals being simultaneously converted into carbonates or oxides. The mass is boiled in water for a few minutes, the mixture filtered, and the residue well washed. The filtrate may then be examined for acidulous radicals and aluminium, and the residue dissolved in dilute hydrochloric acid and analyzed by the ordinary method.

The only substance which resists this treatment is chrome-iron-ore.

To detect alkali in felspar, glass, or cryolite, Bloxam recommends deflagration of the powdered mineral with one part of sulphur and six of nitrate of barium. The mass is boiled in water, the mixture filtered, hydrate and carbonate of ammonium added to remove barium, the mixture again filtered, and the filtrate evaporated and examined for alkalies by the usual process.

QUALITATIVE ANALYSIS OF SUBSTANCES HAVING UNKNOWN PROPERTIES.

Substances are presented to the analyst in one of the three forms in which all matter exists—namely, solid, liquid, or gaseous.

The method of analysis in the case of solid bodies has just been described (pp. 329–35).

In the case of liquids, the solvents as well as the dissolved matters claim attention. A few drops are evaporated to dryness on platinum foil to ascertain if solid mat-

ter of any kind is present; the liquid is tested by red and blue litmus paper to ascertain if free alkalies, free acids, or neither are present; a few drops are heated in a test-tube and the odor of any vapor noticed, a piece of glass tubing bent to a right angle being, if necessary, adapted to the test-tube by a cork, and some of the distilled liquid collected and examined; finally, the usual group-reagents for the several basylous and acidulous radicals are consecutively applied.

Proceeding in this way, the student, who has already had some experience in pharmacy, will not be likely to overlook such solvents as water, acids, alcohol, ether, fixed oils, and essential oils, or to miss the substances which these menstrua may hold in solution. He must not, however, suppose that he will always be able to qualitatively analyze, say, a bottle of medicine; for the various infusions, decoctions, tinctures, wines, syrups, liniments, confections, extracts, pill-masses, and powders contain vegetable matters, most of which at present are quite beyond the reach of the analyst. Neither the highest skill in analysis nor the largest amount of experience concerning the odor, appearance, taste, and uses of drugs is sufficient for the detection of all these vegetable matters. Skill and experience combined, however, will do much, and in most cases even so difficult a task as the one just mentioned be accomplished with reasonable success. Qualitative analysis alone will not enable the experimenter to produce a mixture of substances similar to that analyzed; to this end recourse must be had to quantitative analysis, a subject reserved for subsequent consideration.

Gas-analysis, or *Eudiometry* (from εὐδία, *eudia*, calm air, and μέτρον, *metron*, a measure, in allusion to the *eudiometer*, an instrument used in measuring the proportion and, as the early chemists thought, the salubrity of the gases of the air), is a branch of experimental investigation, chiefly of a quantitative character, concerning which information must be sought in other treatises. The analysis of atmospheric air from various localities, coal-gas, and gases obtained in chemical researches, involves operations which are scarcely within the sphere of Chemistry applied to Medicine. Beyond the recognition, therefore, of oxygen, hydrogen, nitrogen, carbonic, sulphurous, and hydrosulphuric acid gases, the experimental consideration of the chemistry of gaseous bodies may be omitted. Their study, however, should not be neglected, as existing conceptions of the constitution of chemical substances are largely dependent on the observed relations of the volumes of gaseous compounds to their elements. The best work on this subject is a small book by Hofmann, 'Introduction to Modern Chemistry.'

Spectral Analysis.—It may be as well to state here that the preliminary and final examinations of minute quantities of solid matter may, in certain cases, profitably include their exposure to a temperature at which they emit light, the flame being physically analyzed by a spectroscope. A spectroscope consists essentially of a prism to decompose a ray of light into its constituent colors, with tubes and

lenses to collect and transmit the ray or rays to the eye of an observer. The material to be examined is placed on the end of a platinum wire, which is then brought within the edge of a spirit-lamp or other smokeless flame; volatilization, attended usually in the case of a compound by decomposition, at once occurs, and the whole flame is tinged with a characteristic hue. A flat ribbon of rays is next cut off by bringing near to the flame a brass tube, the cap of which is pierced by a narrow slit. At the other end of the tube, at focal distance for parallel rays, is a lens, through which the ribbon of light passes to a prism; the prism decomposes the ribbon, spreading out its constituent colors like a partially opened fan, and the colored beam or *spectrum* thus produced is then examined by help of a telescope attached by a movable joint to the stand which carries the prism and object-tube. Sodium compounds, under these circumstances, give yellow light only, indicated by a double band of light in a position corresponding to the yellow part of an ordinary solar spectrum. The potassium spectrum is mainly composed of a red and violet band; lithium a crimson, and at very high temperatures a blue band. Most of the other elements give equally characteristic spectra.

QUESTIONS AND EXERCISES.

649. Describe the preliminary treatment to which a salt may be subjected prior to systematic analysis.

650. Mention substances which might be recognized by smell.

651. Which classes of salts are heavy, and which light?

652. Name some bodies detectable by their color.

653. What inference may be drawn from the appearance of steam when dry substances are heated?

654. Why do certain crystals decrepitate?

655. If a powder sublimes on being heated, to what classes of compounds may it belong?

656. When heat causes charring, what conclusion is drawn?

657. No change occurring by heat, which substances cannot be present?

658. Give examples of salts which are identified by their reaction with strong sulphuric acid; by their comportment in the blowpipe-flame, with or without borax or microcosmic salt.

659. What are the solvents usually employed in endeavoring to obtain a substance in a state of solution, and what is the order of their application?

660. Name a few salts which may be present in an aqueous solution.

661. Mention some common compounds insoluble in water, but soluble in hydrochloric acid.

662. What substances are attacked only by nitric acid or nitro-hydrochloric acid?

663. Sketch out a method for the complete analysis of a liquid suspected to be an aqueous solution of neutral salts.

664. How can earthy phosphates and oxalates with ferric oxide be separated from each other?

665. By what process may substances insoluble in water or acids be analyzed?

666. How are different solvents recognized?

667. By what methods would you attempt the analysis of a bottle of medicine?

668. Give a short sketch of spectral analysis.

CHEMISTRY OF CERTAIN SUBSTANCES OF VEGETABLE AND ANIMAL ORIGIN.

Except alcohol and a few acids, the compounds which have hitherto engaged notice have been of mineral origin. But the two other kingdoms of nature, the animal and vegetable, furnish a large number of medicinal substances. These, indeed, when discovered, were producible only by highly organized living structures, and were hence termed *organic* compounds.*

A few of these compounds, of common occurrence in pharmacy and possessing prominent characteristics, may now occupy attention; reactions of the alkaloids and some other principles may be performed, and the methods of examining morbid urine be experimentally studied. There will then remain to be studied certain galenical, as distinguished from chemical, substances, solid and liquid, which can only be fairly regarded from a pharmacist's point of view, and a still larger number, doubtless, not yet brought within the grasp of the chemist, and of which, therefore, we must at present be content to remain in ignorance. An opportunity, however, will be afforded of noticing the effect of a mixture of definite and indefinite organic matter, such as a vomit or the contents of a stomach, in masking or preventing the reaction by which mineral and vegetable poisons are detected.

ALKALOIDS.

Constitution of Alkaloids or Organic Bases.

The alkaloids, or alkali-like (εἶδος, *eidos*, likeness) bodies have many analogies with ammonia. Their constitution is not yet known;

* *Organic*, from ὄργανον, *organon*, an organ. A large number of organic compounds can now be obtained artificially—without the aid of a living organism: hence the distinction formerly drawn between organic and inorganic compounds, organic and inorganic chemistry, is fast breaking down.

but they are probably derivative of a single molecule of ammonia (NH_3), or of double, triple, or quadruple molecules (N_2H_6, N_3H_9, N_4H_{12}). A large number of artificial alkaloids or organic bases having such a constitution have already been formed. Those are termed *amines*, and are primary, secondary, and tertiary according as one, two, or three atoms of hydrogen in ammonia (the tri-hydrogen amine) have been displaced by radicals; as seen in the following general formulæ (R = any univalent radical. *Vide* Index, "Alcohol radicals")—

$$\left.\begin{matrix} R \\ H \\ H \end{matrix}\right\} N \qquad \left.\begin{matrix} R \\ R \\ H \end{matrix}\right\} N \qquad \left.\begin{matrix} R \\ R \\ R \end{matrix}\right\} N;$$

or the following examples—

$$\left.\begin{matrix} C_2H_5 \\ H \\ H \end{matrix}\right\} N \qquad \left.\begin{matrix} C_2H_5 \\ C_2H_5 \\ H \end{matrix}\right\} N \qquad \left.\begin{matrix} C_2H_5 \\ C_2H_5 \\ C_2H_5 \end{matrix}\right\} N$$

Ethylamine or ethylia. Diethylamine or diethylia. Triethylamine or tryethylia.

The three classes have also been termed amidogen-, imidogen-, and nitrile-bases. *Propylamine* or *trytylia* (C_3H_7HHN) is a volatile oil, one of the products resulting from the destructive distillation of bones and other animal matters.

The displacing radicals may be similar or different; and, while the radical displacing one atom of hydrogen is keeping its place, any of the many known radicals may occupy the position of one or both of the other atoms of hydrogen. Thus, for example, we have methyl-ethyl-amyl-amine ($CH_3C_2H_5C_5H_{11}N$, or MeEtAyN), a colorless, oily body, of agreeable aromatic odor.

The organic bases derived from one molecule of ammonia are termed monamines; from two molecules, diamines; from three, triamines; and from four, tetramines :—

$$\left.\begin{matrix} R \\ R \\ R \end{matrix}\right\} N \qquad \left.\begin{matrix} R_2 \\ R_2 \\ R_2 \end{matrix}\right\} N_2 \qquad \left.\begin{matrix} R_3 \\ R_3 \\ R_3 \end{matrix}\right\} N_3 \qquad \left.\begin{matrix} R_4 \\ R_4 \\ R_4 \end{matrix}\right\} N_4$$

In these amines any bivalent, trivalent, or quadrivalent radical may occupy the place of two, three, or four univalent radicals.

Attempts to form artificially the natural organic bases have hitherto failed; but the primary, secondary, or tertiary character of some of them has been indicated by the introduction or elimination of methyl, ethyl, and other radicals for hydrogen.

Note on Nomenclature.—The first syllables of the names of the natural alkaloids recall the name of the plant whence they were obtained, or some characteristic property. It is to be regretted that the last syllable is not either *ine* or *ia*, instead of sometimes one and sometimes the other: general usage seems to be in favor of the latter, a plan that distinguishes the alkaloids from some other substances the names of which end in *ine*, as chlorine, bromine, iodine, fluorine, glycerine, gelatine, etc. The names of the salts of the alkaloids are given on the assumption that the acid unites with the alka-

loid without decomposition. Thus hydrochlorate of morphia is regarded as morphia with hydrochloric acid just as we might assume sal-ammoniac to be ammonia (NH_3) with hydrochloric acid (HCl), and name it hydrochlorate of ammonia (NH_3HCl) instead of chloride of ammonium (NH_4Cl).

Antidotes.—In cases of poisoning by alkaloids, emetics and the stomach-pump must be relied on rather than chemical agents. Astringent liquids may be administered, as tannic acid precipitates many of the alkaloids from their aqueous solution, absorption of the poison being thus possibly retarded.

MORPHIA, OR MORPHINE.

Formula $C_{17}H_{19}NO_3$, H_2O. Molecular weight 303.

Occurrence.—Morphia occurs in opium (the inspissated juice of the fruit, *Papaveris capsulæ*, of the White Poppy, *Papaver somniferum*) as meconate of morphia.

Morphia, U. S. P., is made by adding to infusion of opium an equal bulk of alcohol, then slight excess of ammonia, and setting aside for crystalline morphia to separate. It is purified by recrystallization.

Process for Hydrochlorate.—The hydrochlorate $C_{17}H_{19}NO_3,HCl, 3H_2O$ (*Morphiæ Hydrochloras*, B. P.), occurs in slender white acicular crystals; it is prepared by simply decomposing an aqueous infusion of opium with chloride of calcium, meconate of calcium and hydrochlorate of morphia being produced. (If the infusion, which is always acid, be first nearly neutralized by the cautious addition of small quantities of very dilute solution of ammonia, the chloride of calcium then at once causes a precipitate of meconate of calcium, which can be filtered off, leaving a colored solution of hydrochlorate of morphia. On the large scale—*vide* B. P.—the details are somewhat different.) The salt is partially purified by crystallization from the evaporated liquid, then by treatment of the solution of the impure hydrochlorate by animal charcoal, and lastly by precipitation of the morphia from the still colored liquid by ammonia and resolution of the morphia in hot dilute hydrochloric acid; hydrochlorate of morphia separates out on cooling. The process of U. S. P. consists in neutralizing morphia by hydrochloric acid. (*Morphiæ Murias*, U. S. P.)

Morphiæ Sulphas, U. S. P., by neutralizing morphia with sulphuric acid.

Process for Acetate.—Acetate of morphia ($C_{17}H_{19}NO_3C_2H_4O_2$) (*Morphiæ Acetas*, B. P. and U. S. P.) is a white pulverulent salt prepared by dissolving pure morphia in acetic acid, the morphia being prepared (B. P.) from a solution of the hydrochlorate by precipitation with ammonia. Eight parts of hydrochlorate yield about seven of acetate.

Both the hydrochlorate and acetate of morphia are soluble in water, but the solution is not stable unless acidulated and containing alcohol; hence the official solutions, 4 grains in one ounce—1 in 110

(*Liquor Morphiæ Hydrochloratis*, B. P., and *Liquor Morphiæ Acetatis*, B. P.), consist of three parts water and 1 part rectified spirit, a few minims per ounce of hydrochloric or acetic acid being added. *Liquor Morphiæ Sulphatis*, U. S. P., is a solution in water. 1 in 456. The other official preparations are *Suppositoria Morphiæ*, *Trochisci Morphiæ*, and *Trochisci Morphiæ et Ipecacuanhæ*.

When a simple but strong solution of acetate of morphia in water is required (for hypodermic injection) one part of the salt, if recently made, may be dissolved in six parts of water. If the acetate of morphia is old, it either will not dissolve, or, if dissolved by aid of warmth and a little acetic acid, will soon be re-deposited. The aqueous solution, however well made, cannot be kept in its normal condition for any great length of time.

Other alkaloids exist in opium. In the above process a considerable quantity of *narcotine* ($C_{22}H_{23}NO_7$) remains in the exhausted opium, and may be extracted by digesting in acetic acid, filtering, precipitating by ammonia, and crystallizing from alcohol. *Codeia* ($C_{18}H_{21}NO_3,H_2O$) is soluble in the slight excess of ammonia employed in precipitating the morphia. From the mother-liquors there have also been obtained *thebaia* ($C_{19}H_{21}NO_3$), *papaverine* ($C_{20}H_{21}NO_4$), *opianine* ($C_{21}H_{21}NO_7$?), *narceia* ($C_{23}H_{29}NO_9$), *cryptopia* ($C_{21}H_{23}NO_5$), *meconine* ($C_{10}H_{10}O_4$), *laudanine* ($C_{20}H_{25}NO_4$), *codamine* ($C_{20}H_{23}NO_4$), *pseudomorphia* (?), *protopine* ($C_{20}H_{19}NO_5$), *laudanosine* ($C_{21}H_{27}NO_4$), *hydrocotarnine* ($C_{12}H_{15}NO_3$).

Analytical Reactions.

First Analytical Reaction.—To a minute fragment of a salt of morphia add one drop of water, and warm the mixture until the salt dissolves, then stir the liquid with a glass rod moistened by a strong *neutral* solution of perchloride of iron; a dirty blue color is produced. This effect is not observed in dilute solutions.

Second Analytical Reaction.—To a drop or two of a strong solution of a morphia salt in a test-tube add a minute fragment of iodic acid (HIO_3, page 263); iodine is set free. Into the upper part of the tube insert a glass rod covered with mucilage of starch, and warm the solution; dark-blue starch iodide is produced. If the mixture of morphia and iodic acid be shaken up with chloroform or bisulphide of carbon, a violet solution is obtained.

This reaction is only confirmatory of others, as albuminous matters also reduce iodic acid.

Third Analytical Reaction.—To a few drops of an aqueous infusion of opium add a drop of *neutral* solution of perchloride of iron; a red solution of meconate of iron is produced. Add solution of corrosive sublimate; the color

is not destroyed (as it is in the case of sulphocyanide of iron, a salt of similar tint).

In cases of poisoning by a preparation of opium, this test is almost as conclusive as a direct reaction of morphia (the poison itself), meconic acid being obtainable from opium only.

Other Reactions.—Add carbonate of sodium to a solution of a salt of morphia; a white precipitate of morphia falls, slowly and of a crystalline character if the solution is dilute. Collect this precipitate and moisten it with neutral solution of perchloride of iron; the bluish tint above referred to is produced.——Add an alkali to a solution of hydrochlorate or acetate of the alkaloid; morphia is precipitated, soluble in excess of the fixed alkali, far less readily so in ammonia.——Moisten a particle of a morphia salt with nitric acid; an orange-red coloration is produced.——Heat morphia on platinum foil; it burns entirely away.

Apomorphia ($C_{17}H_{17}NO_2$).

Apomorphia (ἀπὸ, *apo*, from, and *morphia*) is an alkaloid recently obtained from morphia by Matthiessen and Wright. It possesses remarkable physiological effects; $\frac{1}{10}$ of a grain (in aqueous solution) injected under the skin, or $\frac{1}{4}$ of a grain taken into the stomach, is said to produce vomiting in from four to ten minutes.

Process.—Hydrochlorate of morphia is hermetically sealed in a thick tube with considerable excess of hydrochloric acid, and heated to nearly 300° F. for two or three hours. The product is purified by diluting the contents of the tube with water, precipitating with bicarbonate of sodium, and treating the precipitate with ether or chloroform.——On shaking up the ethereal or chloroform solution with a very small quantity of strong hydrochloric acid, the sides of the vessel become covered with crystals of the hydrochlorate of the new base. These may be drained from the mother-liquor, washed with a little cold water, in which the salt is sparingly soluble, recrystallized from hot water, and dried on bibulous paper or over sulphuric acid. The formula ($C_{17}H_{17}NO_2$,HCl) indicates that the new alkaloid is derived from morphia by abstraction of the elements of water.

Codeia, also, according to the same chemists, yields apomorphia by similar treatment, a reaction that would seem to indicate that codeia is methyl-morphia:—

$$\underset{\text{Codeia.}}{C_{17}H_{17}CH_3HNO_3} + HCl = \underset{\text{Chl. of methyl.}}{CH_3Cl} + H_2O + \underset{\text{Apomorphia.}}{C_{17}H_{17}NO_2}$$

Dr. C. R. A. Wright has recently obtained several new derivatives of codeia.

QUESTIONS AND EXERCISES.

669. Write some general formulæ of artificial alkaloids.

670. Name the substances represented by the following formulæ:—

$$\left.\begin{matrix}C_3H_7\\H\\H\end{matrix}\right\}N, \qquad \left.\begin{matrix}C_3H_7\\C_3H_7\\H\end{matrix}\right\}N, \qquad \left.\begin{matrix}C\ H_3\\C_2H_5\\C_5H_{11}\end{matrix}\right\}N.$$

$$\left.\begin{matrix}CH_3\\H\\H\end{matrix}\right\}N, \qquad \left.\begin{matrix}CH_3\\CH_3\\H\end{matrix}\right\}N, \qquad \left.\begin{matrix}CH_3\\CH_3\\CH_3\end{matrix}\right\}N.$$

671. What is the assumed constitution of the salts of the alkaloids?

672. Describe the treatment in cases of poisoning by alkaloids.

673. Give the process for the preparation of Hydrochlorate of Morphia. In what form does morphia occur in opium?

674. How is Acetate of Morphia prepared?

675. What plan is adopted for preventing the decomposition of the official solutions of morphia?

676. Mention the analytical reactions of morphia.

677. In addition to the reaction of morphia, what test may be employed in searching for opium in a liquid or semifluid material?

678. How is apomorphia prepared, and what are its properties?

679. Describe the relation of morphia to codeia.

QUINIA, OR QUININE.

Formula $C_{20}H_{24}N_2O_2,3H_2O$. Molecular weight 378.

Source.—Quinia and other similar alkaloids exist in cinchona-bark as kinates. In the yellow bark (*Cinchonæ Flavæ Cortex*, B. P. and U. S. P.) quinia is almost exclusively present; in the pale bark (*Cinchonæ Pallidæ Cortex*, B. P. and U. S. P.) cinchonia is equally characteristic; while in the red bark (*Cinchonæ Rubræ Cortex*, B. P. and U. S. P.) these alkaloids occur in more nearly equal proportions.

Process for Sulphate.—Sulphate of quinia (*Quiniæ Sulphas*, B. P.) is prepared according to the British Pharmacopœia by treating the yellow bark with dilute hydrochloric acid, precipitating the resulting solution of hydrochlorate of quinia by soda, and redissolving the precipitated quinia in the proper proportion of hot dilute sulphuric acid. The sulphate crystallizes out on cooling in silky acicular crystals containing two atoms of quinia ($2C_{20}H_{24}N_2O_2$), one of sulphuric acid (H_2SO_4), and seven of water of crystallization ($7H_2O$).

In the process of the United States Pharmacopœia lime is used instead of soda and the precipitated quinia is dissolved in boiling alcohol, the latter recovered by distillation, the residual quinia neutralized by diluted sulphuric acid, the solution treated with animal charcoal, filtered

while hot, set aside to crystallize, and recrystallized if necessary.

Sulphate of quinia, or, more correctly, disulphate, is only slightly soluble in water; on the addition of dilute sulphuric acid a neutral sulphate is formed which is freely soluble. The latter salt may be obtained in large rectangular prisms, having a composition expressed by the formula $C_{20}H_{24}N_2O_2,H_2SO_4,7H_2O$. The ordinary disulphate of quinia is more soluble in alcohol or alcoholic liquids than in water; hence the *Tinctura Quiniæ*, B. P., which is a solution (saturated at 55° or 60° F.) of the salt in tincture of orange-peel (eight grains in the ounce). Quinia wine (*Vinum Quiniæ*, B. P.) is a solution of neutral sulphate and citrate of quinia in orange-wine, made by dissolving the disulphate (one grain in the ounce) in orange-wine by the help of citric acid. The only official preparation of the pure disulphate is *Pilula Quiniæ*, containing three parts salt to one of confection of hips (gum arabic and honey, U. S. P.). The remaining Pharmacopœial preparation of quinia is the mixed citrates of iron, ammonium, and quinia (*Ferri et Quiniæ Citras*, B. P. and U. S. P.), the well-known scale compound. It is made by dissolving ferric hydrate, prepared from ferric sulphate, and quinia, prepared from the sulphate, in solution of citric acid, ammonia also being added: the liquid, evaporated to a syrupy consistence and dried in thin layers on glass plates, yields the usual greenish-yellow scales (*vide* p. 130).

Quiniæ Valerianas, U. S. P., is made by dissolving precipitated quinia in warm aqueous solution of valerianic acid and setting aside to crystallize.

Citrate of Quinia has the formula $(C_{20}H_{24}N_2O_2)_2,H_3C_6H_5O_7,5H_2O$.

Reactions.

First Analytical Reaction.—To a solution of quinia or its salts in faintly acid water add fresh chlorine-water and then solution of ammonia; a green coloration (thalleiochin) is produced. According to Flückiger, in very dilute solutions of quinine bromine-vapor is more useful than chlorine for this reaction.

Second Analytical Reaction.—Repeat the foregoing reaction, but precede the addition of ammonia by solution of ferrocyanide of potassium; an evanescent red coloration is produced (Livonius and Vogel).

Third Analytical Reaction.—Quinia may be impure from the presence of the other alkaloids (chiefly quinidia, cinchonia) of cinchona-bark; the following tests will determine the point. The first is Stoddart's modification of Liebig's process.

Into a glass tube or bottle put ten grains of the suspected salt, dissolve in 10 minims of dilute sulphuric acid and 60

minims of distilled water; to this add 150 minims of *pure* ether, 3 minims of spirits of wine, and 40 minims of a solution of soda (1 part of solid hydrate to 12 of water). Agitate well and set aside for twelve hours, when, if the slightest trace of quinidia and cinchonia be present, they will be seen at the line of separation between the ether and solution of sulphate of sodium.

If only a small percentage of quinidia be present, it will appear as an oily substratum, appearing under a lens as dust, from the minuteness of its particles. Cinchonia will appear more decidedly crystalline. With a little practice the eye will easily distinguish which of the alkaloids is deposited.

Fourth Analytical Reaction.—This is Stoddart's chemico-microscopic test. Into an ounce of distilled water drop 10 drops of dilute sulphuric acid (British Pharmacopœia strength). To this add 14 grains (or as much as will saturate the acid) of the suspected salt. Filter through paper, and to a little of the filtered solution add a few drops of solution of sulphocyanide of potassium (180 grains in $1\frac{1}{2}$ ounce of water). An immediate precipitate of the several alkaloids takes place, each of which is distinct and characteristic. If quinia, quinidia, and cinchonia be present, they will all be seen on the slide, becoming more and more distinct during the first hour. A good plan is to place on a glass slip a drop of the solution to be tested, and to put another of the sulphocyanide by its side—the drops not being larger than good-sized pin-heads. Over both place a piece of thin glass, which will cause the drops to touch. Examine the line of junction under a half-inch object-glass, when the crystals are readily seen and recognized. By this method $\frac{1}{10000}$ of a grain of quinidia or cinchonia may be easily detected. The particles arrange themselves into the respective groups—the long slender needles of the quinia salt, the round crystalline masses of the quinidia, and the large well-formed prisms of the cinchonia salts. This reaction is sufficiently constant to enable an observer who has accustomed himself to the microscopic appearance of the three pure sulphocyanides to at once distinguish the respective salts from each other.

The sulphocyanide-of-potassium solution should be of the strength indicated. If not at hand it may quickly be made, sufficiently pure for this reaction, by the following process: Cyanide of potassium (fused), sublimed sulphur, of each 120 grains; distilled water an ounce and a half. Boil in a

glass flask for fifteen minutes, filter, and make up the quantity to $1\frac{1}{2}$ ounce with sufficient distilled water.

A small quantity of quinia in much cinchonia or quinidia cannot be recognized by the above reaction. Therefore, before concluding that no quinia is present in a specimen of those alkaloids, the sample should be treated with ether, filtered, the solution evaporated to dryness, and the residue, if any, examined for quinia.

Other Characters. — Concentrated sulphuric acid dissolves quinia with production of only a faint yellow color; salicin, with which quinia may possibly be adulterated, slowly gives, under the same circumstances, a deep red.

Concentrated nitric acid dissolves quinia, yielding a colorless solution; on heating, the solution becomes yellowish.

Quinia and its salts, heated on platinum foil, burn entirely away.

Salicin in quinia may be detected by several other tests (*vide* "Salicine" in Index).

Cinchonia or Cinchonine ($C_{20}H_{24}N_2O$) and quinia are distinguished from morphia by non-solubility of the alkaloid precipitated by a fixed alkali in excess of the alkaline solution. They are distinguished from each other by the solubility of the precipitated quinia and insolubility of cinchonia when ether is added to the alkaline mixture. Cinchonia, moreover, does not give the green coloration with chlorine-water and ammonia. Strychnia is also precipitated by fixed alkalies and insoluble in excess, but this alkaloid has such strongly marked reaction of its own as to preclude confusion.

Sulphate of Cinchonia (*Cinchoniæ Sulphas*, U. S. P.) occurs in the mother-liquors of sulphate of quinia, and is directly prepared from several kinds of bark. It forms white, shining crystals, having the form of short, oblique prisms, with dihedral summits. Like sulphate of quinia, when heated, it fuses to a resinoid mass of a rich red color. It dissolves in fifty-four parts of cold water, in much less boiling water, in seven parts of alcohol, and very sparingly in ether. Its aqueous solution gives with terchloride of gold a yellow precipitate, and with chloride of calcium a white one. Ammonia, added to its solution in chlorine water, causes a white precipitate. If the salt be rubbed with water of ammonia, and then treated with ether, the cinchonia, separated by the former, will not be dissolved by the latter.

Quinidia or *Quinidine* is an isomer of quinia, and *Cinchonidia* or *Cinchonidine* an isomer of cinchonia. *Cinchovatia* or *Cinchovatine* occurs in a particular variety of cinchona-bark. *Quinicia* or *Quinicine* and *Cinchonicia* or *Cinchonicine* are the products of the action of heat on quinia and cinchonia.

STRYCHNIA, OR STRYCHNINE.

Formula $C_{21}H_{22}N_2O_2$. Molecular weight 334.

Source.—This alkaloid exists in Nux Vomica (*Strychnos Nux Vomica*, B. P. and U. S. P.) and in St. Ignatius's bean (*Strychnos Ignatia*) (*Ignatia*, U. S. P.) chiefly in combination with lactic acid.

Process.—According to the British official process for its preparation (*Strychnia*, B. P.) the nuts, disintegrated by subjection to steam and, after drying, grinding in a coffee-mill, are exhausted with spirit, the latter removed by distillation, the extract dissolved in water, coloring and acid matters precipitated by acetate of lead, the filtered liquid evaporated to a small bulk, the strychnia precipitated by ammonia, the precipitate washed, dried, and exhausted with spirit, the spirit recovered by distillation, and the residual liquid set aside to crystallize. Crystals of strychnia having formed, the mother-liquor (which contains the brucia of the seeds) is poured away, and the crystals of strychnia washed with spirit (to remove any brucia) and recrystallized.

In the U. S. P. process the rasped Nux Vomica is exhausted by very dilute hydrochloric acid, milk of lime added to the evaporated decoction to decompose the hydrochlorate of strychnia, the precipitated and dried mixture of strychnia and lime treated with diluted alcohol to remove brucia, and then with strong hot alcohol to dissolve out strychnia: the alcohol having been recovered by distillation, the residual impure strychnia is dissolved in very dilute sulphuric acid, the solution decolorized by animal charcoal, evaporated, and set aside to crystallize, the crystals of sulphate of strychnia (*Strychniæ Sulphas*, U. S. P.) redissolved in water, ammonia added to precipitate pure strychnia, and the latter dried.

Properties.—Strychnia occurs "in right square octahedrons or prisms, colorless and inodorous; sparingly soluble in water, but communicating to it its intensely bitter taste; soluble in boiling rectified spirit and in chloroform, but not in absolute alcohol or in ether."

Reactions.

First Analytical Reaction.—Place a minute particle of strychnia on a white plate, and near to it a small fragment of red chromate of potassium; to each add one drop of concentrated sulphuric acid: after waiting a minute or so for the chromate to fairly tinge the acid, draw the latter, by a glass rod, over the strychnia spot; a beautiful purple color is produced, quickly fading into a yellowish-red. The following oxidizing agents may be used in the place of the chromate: puce-colored oxide of lead, fragments of black oxide of manganese, ferridcyanide of potassium, or permanganate of potassium.

This reaction is highly characteristic; a minute fragment dissolved in much dilute alcohol, or, better, chloroform, and one drop of the liquid evaporated to dryness on a porcelain crucible-lid or other white surface, yields a residue which immediately gives the purple color on being oxidized in the manner directed.

Other Reactions.—Strong sulphuric acid does not act on strychnia, even at the temperature of boiling water, a fact of which advantage is taken in separating strychnia from other organic matter for purposes of toxicological analysis.——Sulphocyanide of potassium produces, even in dilute solutions of strychnia, a white precipitate, which, under the microscope, is seen to consist of tufts of acicular crystals.——Strong nitric acid does not color strychnia in the cold, and on heating only turns it yellow.

The Physiological Test.—A small frog placed in an ounce of water to which $\frac{1}{10}$ of a grain of a salt (acetate) of strychnia is added, is, in two or three hours, seized with tetanic spasms on the slightest touch, and dies shortly afterwards.

Strychnia has an intensely bitter taste. Cold water dissolves only $\frac{1}{2500}$ part; yet this solution, even when largely diluted, is distinctly bitter. Alcohol is a somewhat better solvent. The salts of the alkaloid are more soluble. The official solution (*Liquor Strychniæ*, B. P.) contains four grains of strychnia to the ounce, the solvent being three parts water, one part spirit, and a few minims (6 per ounce) of hydrochloric acid (rather more than sufficient to form hydrochlorate of strychnia).

Brucia, or Brucine ($C_{23}H_{26}N_2O_4,4H_2O$), is an alkaloid accompanying strychnia in Nux Vomica. It is readily distinguished by the intense red color produced when nitric acid is added to it. *Igasuria* is another alkaloid of Nux Vomica. This alkaloid is said to occur in no less than nine varieties, each slightly differing from the other in chemical composition. They resemble strychnia in physical properties.

Distinction of Brucia from Morphia.—The red coloration produced by the action of nitric acid on brucia is distinguished from that yielded by morphia by the action of reducing agents (such as stannous chloride, hyposulphite of sodium, sulphydrate of sodium), which decolorize the morphia-red, but change that of the brucia to violet and green (Cotton).

Distinction of Free Alkaloids or their Salts from each Other.—This is accomplished by remembering the appearance and other physical characters of the substances as met with in pharmacy, the effect of heat, the action of such solvents as water, alcohol, and ether, the influence of strong and diluted acids, strong and weak alkalies, oxidizing agents, chlorine-water and ammonia, and other reagents.

QUESTIONS AND EXERCISES.

680. What alkaloids are more or less characteristic of the different varieties of cinchona-bark? In what form do they occur?

681. By what method is Disulphate of Quinia obtained?

682. Give the characters of disulphate of quinia.
683. Describe the tests for quinia.
684. How is the adulteration of disulphate of quinia by salicin detected?
685. Show how the sulphates of quinidia or cinchonia may be proved to be present in commercial quinia.
686. How are cinchonia and quinia distinguished from morphia?
687. Whence is strychnia obtained?
688. Describe the official process for the isolation of strychnia.
689. Give the characters of strychnia.
690. Enumerate the tests for strychnia, and describe their mode of application.
691. By what reagent is brucia distinguished from strychnia?
692. Distinguish between brucia and morphia.
693. By what general methods would you distinguish common alkaloids from each other?

ALKALOIDS OF LESS FREQUENT OCCURRENCE.

ACONITIA, ACONITINA, or ACONITINE ($C_{30}H_{47}NO_7$) is an alkaloid obtained from aconite (*Aconitum Napellus*) leaves (*Aconiti Folia*, B. P. and U. S. P.) and root (*Aconiti Radix*, B. P. and U. S. P.). The alkaloid itself is only slightly soluble in water; it occurs in the plant in combination with a vegetable acid, forming a soluble salt.

Process.—The official process for its preparation (*Aconitia*, B. P. and U. S. P.) consists in dissolving out the natural salt of the alkaloid from the root by rectified spirit, recovering the latter by distillation, mixing the residue with water, filtering, precipitating the aconitia by ammonia, drying the precipitate and digesting it in ether (in which some of the accompanying impurities are insoluble), recovering the ether by distillation, dissolving the dry residue in the retort in water acidulated by sulphuric acid, again precipitating the alkaloid by ammonia, and finally washing and drying.

Properties.—Aconitia usually occurs as a white powder, but has been obtained and studied in the crystalline state by Groves and by Duquesnel. It is soluble in 150 parts of cold water, 50 of hot, and much more soluble in alcohol and in ether. It is one of the most violent poisons known. "When rubbed on the skin it causes a tingling sensation, followed by prolonged numbness."

The thousandth part of a grain on the tip of the tongue produces, after a minute or so, a characteristic tingling sensation and numbness: larger quantities rubbed into the skin cause numbness and loss of feeling. To a strong solution of phosphoric acid (the ordinary acid concentrated over a water-bath to a syrupy consistence) a mere trace imparts a lasting violet tint (Flückiger). Oil of vitriol turns it of a yellowish, and afterwards, dirty violet color.

Several alkaloids have been obtained from different species and varieties of aconite. They are under research by chemists.

Unguentum Aconitiæ, B. P., contains eight grains of the alkaloid to one ounce of prepared lard.

Atropia, or Atropine ($C_{17}H_{23}NO_3$), exists in the Belladonna, or Deadly Nightshade (*Atropa Belladonna: Belladonnæ Folia et Radix*, B. P. and U. S. P.), as soluble acid malate of atropia.

Process.—It is obtained in the pure state by exhausting the root with spirit, precipitating the acid and some coloring-matter by lime, filtering, adding sulphuric acid to form sulphate of atropia (which is somewhat less liable to decomposition during subsequent operations than the alkaloid itself), recovering most of the spirit by distillation, adding water to the residue, and evaporating till the remaining spirit is removed; solution of carbonate of potassium is then poured in till the liquid is nearly but not quite neutral, by which resinous matter is precipitated; the latter is filtered away, excess of carbonate of potassium then added, and the liberated atropia dissolved out by shaking the liquid with chloroform. The latter solution, having subsided, is removed, the chloroform recovered by distillation, the residual atropia dissolved in warm spirit, coloring matter separated by digesting the liquid with animal charcoal, the solution filtered, evaporated, and set aside to deposit crystals.

Solubility.—Atropia is sparingly soluble in water, the liquid giving an alkaline reaction—more soluble in alcohol and ether.

Tests.—Atropia-solutions give with perchloride of gold a yellow precipitate. One drop of a dilute aqueous solution (two grains to the ounce) powerfully dilates the pupil of the eye. It is applied on a piece of thin tissue paper or small disk placed between the eyelid and the eye.

Preparations.—The alkaloid itself (*Atropia*), its sulphate (*Atropiæ Sulphas*, a colorless powder soluble in water, made by neutralizing atropia with sulphuric acid), their solutions (*Liquor Atropiæ*, four grains per ounce, and *Liquor Atropiæ Sulphatis*, four grains per ounce), and an ointment (*Unguentum Atropiæ*, eight grains per ounce) are the preparations official in the British Pharmacopœia. The alkaloid and its sulphate are official in the United States Pharmacopœia.

Daturia or *Daturine*, an alkaloid in *Datura Stramonium* or Thorn-apple (*Stramonii Folia et Semina*, B. P. and U. S. P.), appears to be identical with atropia.

Beberia, or Beberine ($C_{19}H_{21}NO_3$), is an alkaloid existing in the bark of Bebeeru (*Nectandra Rodiæi*).

Process.—According to the British Pharmacopœia, it, or rather its sulphate, $C_{38}H_{42}N_2O_6$, H_2SO_4 (*Beberiæ Sulphas*, B. P.), may be prepared by exhausting the bark (*Nectandræ Cortex*, B. P. and U. S. P.) with water acidulated by sulphuric acid, concentrating, removing most of the acid by lime, filtering, precipitating the alkaloid by ammonia, filtering, drying, dissolving in spirit (in which some accompanying matters are insoluble), recovering most of the spirit by distillation, neutralizing by dilute sulphuric acid, evaporating to dryness, dissolving the residual sulphate in water, evaporating to the consistence of a syrup, and spreading on glass plates, drying the product at 140°. Thus obtained, it occurs in thin dark-brown translucent scales, yellow when powdered, strongly bitter, soluble in water and in alcohol.

Tests.—Alkalies give a pale yellow precipitate of beberia when added to an aqueous solution of a salt of the alkaloid; the precipitate is soluble in ether. With red chromate of potassium and sulphuric acid beberia gives a black resin, and with nitric acid a yellow resin.

Nectandria ($C_{20}H_{23}NO_4$).—Drs. Maclagan and Gamgee have recently discovered this second alkaloid in Bebeeru bark. It differs from beberia in fusing when placed in boiling water, in being much less soluble in ether, in giving with strong sulphuric acid and black oxide of manganese a beautiful green and then violet coloration, and in having a distinct molecular weight. They are of opinion that two other alkaloids exist in Bebeeru bark.

Berberia, or Berberine ($C_{20}H_{17}NO_4$), is an alkaloid existing in several plants of the natural order *Berberideæ*, in Calumba-root (*Calumbæ Radix*, B. P. and U. S. P.), *Goldthread* (*Coptis trifolia*, U. S. P.) according to Mayer, and in many yellow woods. The color of the tissues of these vegetables is apparently due to berberia; for the alkaloid itself is remarkable for its beautiful yellow color.

Tests.—When a dilute solution of iodine in iodide of potassium is added to solution of any salt of berberia in hot spirit, excess of iodine being carefully avoided, brilliant green spangles are deposited. The reaction is sufficiently delicate to form, according to Perrins, an excellent test of the presence of berberia. This iodo-compound polarizes light, and has other analogies with a similar quinine-salt termed herapathite.

Berberia is not an official alkaloid; but the plants in which it occurs are used as medicinal agents in all parts of the world.

Process.—Berberia is readily extracted by boiling the raw material with water, evaporating the strained liquid to a soft extract, digesting the residue in alcohol, recovering the alcohol by distillation, boiling the residue with diluted sulphuric acid, filtering and setting aside; the sulphate of berberia separates out, and may be purified by recrystallization from hot water. The alkaloid itself is obtained by shaking hydrate of lead with a hot aqueous solution of the sulphate of berberia (Procter).

Podophyllum-root (*Podophylli Radix*, B. P., *Podophyllum*, U. S. P.), contains berberia. In preparing the resin of podophyllum or May-apple (*Podophylli Resina*, B. P. and U. S. P.) an alcoholic extract of the root is poured into water acidulated by hydrochloric acid, whereby the whole of the hydrochlorate of berberia, which is almost insoluble in dilute mineral acids, is precipitated with the resin (Maisch). No acid is ordered in U. S. P.

Capsicia, or Capsicine, is an alkaloid occurring in Cayenne pepper or Capsicum-fruit (*Capsici Fructus*, B. P. and U. S. P.), associated with resin and volatile oil. It is crystalline, and forms crystallizable salts with acids.

Cissampelia, Cissampeline, Pelosia, or Pelosine ($C_{18}H_{21}NO_3$), is an alkaloid occurring in the root (*Pareiræ Radix*, B. P. and U. S. P.) of *Cissampelos Pareira*. It is the tonic and diuretic principle of the drug.

Conia, Conylia, Conine, Conicine, or Cicutine.—Formula

$C_8H_{15}N$, or $(C_8H_{14})''HN$. This alkaloid is a volatile liquid, occurring in hemlock (*Conium maculatum*). It is not official.

Process.—It may be obtained by distilling hemlock-fruit (*Conii Fructus*, B. P.) with water rendered slightly alkaline by caustic soda or potash, or by similarly treating the fresh juice of the leaves. The alkaloid is a yellow oily liquid, floating on the water that distils over; by redistillation it is obtained colorless and transparent.

The salts of conia have no odor, but when moistened with solution of an alkali yield the alkaloid, the strong smell of which, at once recalling hemlock, is characteristic. Extract of hemlock leaves (*Conii Folia*, B. P. and U. S. P.), to which solution of potash and boiling water have been added, forms the official Inhalation of Conia (*Vapor Coniæ*, B. P.).

Tests.—Sulphuric acid turns conia purplish-red, changing to olive-green, nitric acid a blood-red; perchloride of gold produces a yellowish-white precipitate, perchloride of platinum no precipitate, in aqueous solutions.

Hemlock also contains *methyl-conia* $(C_8H_{14})''CH_3N$ (Kekulé and Van Planta).

According to Schiff, conia, isomeric, at least, with the natural alkaloid, may be produced artificially by action of ammonia on butyric aldehyd and destructive distillation of the resulting compound.

Daturia, or Daturine, *vide* Atropia.

Emetia, or Emetine ($C_{30}H_{44}N_2O_8$).—This alkaloid is the active emetic principle of *Cephælis ipecacuanha* (*Ipecacuanha*, B. P. and U. S. P.). It occurs in combination with ipecacuanhic acid. The nitrate is peculiarly slightly soluble in water (Lefort). In the *Pulvis Ipecacuanhæ*, B. P. and U. S. P., or "Dover's Powder" (Powdered Ipecacuanha, 1 part: Powdered Opium, 1 part; and Sulphate of Potassium, 8 parts), minute division of the active ingredients is promoted by prolonged trituration with sulphate of potassium, which is a very hard salt.

Hyosciamia, or Hyosyamine ($C_{18}H_{28},N_2O_3$; other authors, $C_{15}H_{23}NO_3$), a volatile alkaloid, is said to occur in the leaves (*Hyoscyami Folia*, B. P. and U. S. P., *Hyoscyami Semen*, U. S. P.), and other parts of Henbane. Its effect on the eye is similar to that of atropia.

Lobelia, or Lobeline.—A volatile alkaloid first isolated from the dried flowering herb *Lobelia inflata* (*Lobelia*, B. P. and U. S. P.) by Bastick. In the pure state it smells slightly of the plant, but mixed with ammonia it emits a strong and characteristic smell of the herb.

Nectandria, *vide* Beberia.

Nicotia, Nicotina, Nicotylia, or Nicotine.—Formula $C_{10}H_{14}N_2$, or $(C_5H_7)'''_2N_2$. This is also a volatile liquid alkaloid, forming the active principle of tobacco (*Nicotiana tabacum*), malate and citrate of nicotina being the forms in which it occurs in the leaf (*Tabaci Folia*, B. P. and U. S. P.). Its odor is characteristic; like conia, it yields a precipitate with perchloride of gold; but, unlike that alkaloid, its aqueous solutions are precipitated yellowish-white by perchloride of platinum. It is not official.

Physostigmia, or Physostigmine.—An alkaloid contained in the Calabar Bean (*Physostigmatis Faba*), the seed of *Physostigma venenosum* (Jobst and Hesse). A trace of it powerfully contracts the pupil of the eye; a small quantity is highly poisonous. Fraser also isolated this principle, and termed it *Eserin*, from Eserĕ, the name of this ordeal-poison at Calabar.

Piperia, or Piperine ($C_{17}H_{19}NO_3$), is a feeble alkaloid occurring in *white*, *black* (*Piper Nigrum*, B. P. and U. S. P.), *long*, and *cubeb pepper* (*Cubeba*, B. P. and U. S. P.), associated with volatile oil and resin; to these three substances the odor, flavor, and acridity belong. Piperia is obtained on boiling white pepper with alcohol, and evaporating the liquid with solution of potash, which retains resin. Recrystallized from alcohol, piperia forms colorless prisms fusible at 212°. With acids it forms salts, and distilled with strong alkali yields *piperidia* or *piperidine*, an alkaloid of strong chemical properties.

Sanguinarina, or *Sanguinarine* ($C_{37}H_{64}N_4O_8$), is a colorless alkaloid obtained from the rhizome of *Sanguinaria Canadensis* (U. S. P.) or Blood-root. Its salts have a red, crimson, or scarlet color.

Solania, or Solanine ($C_{43}H_{70}NO_{16}$).—An alkaloid said to exist in the Woody Nightshade or Bitter-sweet (*Solanum dulcamara*). The dried young branches of the plant are official (*Dulcamara*, B. P. and U. S. P.). The alkaloid is only slightly soluble in water, alcohol, or ether; nitric acid colors it yellow; sulphuric acid produces at first a yellow, then a violet, and finally a brown coloration.

Sparteia, or Sparteine ($C_{15}H_{26}N$), is a poisonous volatile alkaloid occurring in Broom-tops (*Scoparii Cacumina*, B. P. and U. S. P.). Its discoverer, Stenhouse, considers that the diuretic principle of broom is *Scoparin*, a non-poisonous body.

Theia, Theine, or Caffeine ($C_8H_{10}N_4O_2+H_2O$).—This alkaloid occurs in tea, coffee (*Caffea*, U. S. P.), Paraguay tea, guarana, and the kola-nut. Infusions and preparations of these vegetable products are used chiefly as beverages by three-fourths of the human race. It is remarkable that the instinct of man, even in his savage state, should have led him to select, as the bases of common beverages, just the four or five plants which out of many thousands are the only ones, so far as we know, containing theia. Theia is volatile. Large quantities may be collected by condensing the vapors evolved during the roasting of coffee on the large scale. The infusion of tea, from which astringent and coloring-matters have been precipitated by solution of subacetate of lead, and which has been evaporated to a small bulk, yields a precipitate of theia on the addition of a strong solution of carbonate of potassium. It may be crystallized from alcohol or by sublimation.

Test.—Concentrated nitric acid, or a mixture of chlorate of potassium and hydrochloric acid, rapidly oxidizes theia, forming compounds which with ammonia yield a beautiful purple-red color, resembling the murexid obtained under similar circumstances from uric acid; the oxidation must not be carried too far. Theine boiled with caustic potash yields methylamine (CH_3HHN), the vapor of which has a peculiar, characteristic odor.

The chemical action of theia on the system is not yet made out. Liebig thinks it may aid in the production of a substance a normal amount of which is so necessary, an abnormal so unpleasant—namely, bile. Most chemists agree that it arrests the rapid consumption of tissue and consequent feeling of fatigue which is especially experienced after hard work with mind or body.

VERATRIA, or VERATRINE ($C_{32}H_{52}N_2O_8$).—This alkaloid, as gallate of veratria, is stated to occur in various species of *Veratrum* (Hellebore) (as *Veratri Viridis Radix*, B. P.), in *Cevadilla* (*Sabadilla*, B. P.), and in *Colchicum autumnale* (*Colchici Cormus; Colchici Semina*, B. P.); but, according to C. Bullock, *Veratrum viride* contains an alkaloid soluble in ether and one insoluble in that menstruum, neither answering in chemical reactions to veratria. White Hellebore is also said to contain three other alkaloids, *sabadillia* or *sabadilline*, *colchicia* or *colchicine*, and *jervia* or *jervine*. A mere trace of veratria brought into contact with the mucous membrane of the nose causes violent fits of sneezing. Fuming sulphuric acid colors it yellow, red, and violet in succession. Colchicia is colored of a brownish-yellow by sulphuric acid, and of a reddish-blue turning to greenish-yellow by nitric acid.

The official process for the preparation of the alkaloid (*Veratria*, B. P.) consists in exhausting the disintegrated cevadilla seeds by alcohol, recovering most of the spirit by distillation, pouring the residue into water, by which much resin is precipitated, filtering, and precipitating the veratria from the aqueous solution by ammonia. It is purified by washing with water, solution in dilute hydrochloric acid, decolorization of the liquid by animal charcoal, reprecipitation by ammonia, washing, and drying. The U. S. P. process is similar, but includes treatment of the first crude veratria by diluted sulphuric acid and precipitation of alkaloid by magnesia.

Unguentum Veratriæ, B. P., contains eight grains of the slightly impure alkaloid obtained as just described, rubbed down with half a drachm of olive oil and diffused through one ounce of prepared lard.

QUESTIONS AND EXERCISES.

694. How is Aconitia prepared?

695. Give the strengths of the official preparations of Atropia.

696. Describe the properties of atropia.

697. What is the active principle of stramonium?

698. Mention pharmacopœial substances containing beberia and berberia respectively.

699. Give the characters of beberia.

700. In what does nectandria differ from beberia?

701. Mention the characteristics of conia.

702. What is the active principle of Ipecacuanha?

703. Name the alkaloid of Tobacco.

704. Give the name and properties of the active principle of Calabar Bean.

705. What are the sources of piperia ?
706. Whence is theia obtained ?
707. Describe the preparations of Veratria.
708. State the properties of veratria.

BITTER (TONIC) SUBSTANCES.

The following official articles, commonly employed medicinally in such forms as Decoction, Extract, Infusion, Tincture, contain active principles which have not yet been thoroughly examined. Some of these principles have been isolated, and a few have been obtained in the crystalline condition ; but their constitution has not been sufficiently well made out to admit of the classification of the bodies either among alkaloids, glucosides, acids, or other well-marked principles.

Absinthium (Absinthin).
Anthemidis flores.
Aurantii cortex.
Buchu folia.
Canellæ albæ cortex.
Cascarillæ cortex.
Chirata.
Chimaphila (Arbutin).
Cusparice cortex, or *Angustura*, U. S. P., contains Cusparin or Angusturin.
Gentianæ radix.
Lactuca (Lactucin).
Lupulus.
Maticæ folia.
Marrubium.
Quassiæ lignum (Quassin, $C_{10}H_{12}O_2$).
Serpentariæ radix.
Spigelia marilandica.
Taraxaci radix (Taraxacin).

AMYLACEOUS AND SACCHARINE SUBSTANCES.

STARCH.

Formula $C_6H_{10}O_5$.

Processes.—Rasp or grate, or, with a knife, scrape a portion of a clean raw potato, letting the pulp fall on to a piece of muslin placed over a small dish or test-glass, and then pour a slow stream of water over the pulp; minute particles or *granules* of starch pass through the muslin and sink to the bottom of the vessel, fibrous matter remaining on the seive. This is potato-starch. Even diseased potatoes furnish good starch by this method. Wheat-starch (*Amylum*, B. P. and U. S. P.) may be obtained by tying up some flour in a piece of calico and kneading the bag in a slow stream of water flowing from a tap, the washings running into a deep vessel, at the bottom of which the white starch collects: the sticky matter remaining in the bag is

gluten. The *blue starch* of the shops is artificially colored with smalt or indigo, to neutralize the yellow tint of recently washed linen; it should not be used for medicinal purposes. Starch dried in mass splits up into curious columnar masses, resembling the basaltic pillars of Fingal's Cave in Staffa, or those of the Giant's Causeway in the North of Ireland. The cause of the phenomenon, which may also be seen in grain-tin, is not conclusively known.

Gluten is the body which gives tenacity to dough and bread. It seems to be a mixture of vegetable fibrin, vegetable casein, and an albuminous matter termed glutin. These substances and gluten itself are closely allied; each contains about 16 per cent. of nitrogen. *Wheaten Flour* (*Farina Tritici*, B. P.) contains about 72 per cent. of starch and 11 of gluten, as well as sugar, gum, fine bran, water, and ash. The compactness of barley, well seen in Husked or Pearl Barley (*Hordeum Decorticatum*, B. P. and U. S. P.), is said to be due to the large amount of vegetable fibrin present. During germination the fibrin is destroyed, hence, probably, the cretaceous character of malt. *Oatmeal* (*Avenæ Farina*, U. S. P.) is very rich in albuminoid or flesh-forming constituents, containing nearly 16 per cent. *Sago*, U. S. P., is granulated starch from the Sago Palm. *Tapioca*, U. S. P., is granulated starch from the Bitter Cassava.

Mucilage of Starch.—Mix two or three grains of starch with first a little and then more water, and heat to the boiling-point; mucilage of starch (*Mucilago Amyli*, B. P.) results.

This mucilage or paste is not a true solution; by long boiling, however, a portion of the starch becomes dissolved. In the latter case the starch probably becomes somewhat altered.

Chemical Test.—To some of the mucilage add a little free iodine; a deep-blue color is produced.

This reaction is a very delicate test of the presence of either iodine or starch. The starch must be in the state of mucilage; hence in testing for starch the substance supposed to contain it must be first boiled in water. The solutions used in the reactions should also be cold, or nearly so, as the blue color disappears on heating, though it is partially restored on cooling. The iodine reagent may be iodine-water or tincture of iodine. In testing for iodine its occurrence in the free state must be insured by the addition of a drop, or even less, of chlorine-water. Excess of chlorine must be avoided, or chloride of iodine will be formed, which does not color starch.

The so-called *iodide of starch* scarcely merits the name of a chemical compound, the state of union of its constituents being feeble. Substances that attack free iodine remove that element from iodide of starch. The alkalies, hydrosulphuric acid, sulphurous acid, and other reducing agents destroy the blue color.

Microscopical Test.—All kinds of starch yield the blue color

with iodine, showing their chemical similarity. But physically the granules of starch from different sources differ much in size and appearance when examined by the microscope with or without the aid of polarized light. The granules of potato-starch are large, of rice-starch very small, arrowroot (*Maranta*, U. S. P.), and wheat-starch being intermediate. By polarized light the granules of potato-starch appear as if traversed by a black cross, the wheat-starch granules, as seen in common flour, similarly influence polarized light, but oat-starch yields no such effect. (See the frontispiece plates of the original edition of Pereira's "Materia Medica.") The granules of *Tous les Mois* (*Canna*, U. S. P.) are very large.

DEXTRIN.—Mix a grain or two of starch with about half a test-tubeful of cold water and a drop or two of sulphuric acid, and boil the mixture for a few minutes; no mucilage is formed, and the liquid, if sufficiently boiled, yields no blue color with iodine; the starch has become converted into *dextrin*. The same effect is produced if the starch is maintained at a temperature of about 320° F. for a short time. Dextrin is now largely manufactured in this way, and a paste of it used by calico-printers as a vehicle for colors; it is termed *British gum*. The change may also be effected by *diastase*, a peculiar ferment existing in malt. Mix two equal quantities of starch with equal amounts of water, adding to one a little ground malt, then heat both slowly to the boiling-point; the mixture without malt thickens to a paste or pudding, that with malt remains thin, its starch having become converted into dextrin.

Diastase is probably the vegetable fibrin of gluten in a state of decomposition; it is so named from διάστασις (*diastasis*), *separation*, in allusion to the separation, or rather alteration, it effects among the constituent atoms of starch.

Malt (the word malt is said to be derived from the Welsh *mall*, soft or "rotten") is simply barley which has been softened by steeping in water, allowed to germinate slightly, and further change then arrested by the application of heat in a kiln. During germination the gluten breaks up and yields a glutinous substance termed vegetable gelatine, diastase, and other matters. To the vegetable gelatine is due much of the "body" of well-malted and slightly-hopped beer; it is precipitated by tannic acid, hence the thinness of ale (pale or bitter) brewed with a large proportion of hop or other materials containing tannic acid. A portion of the diastase reacting on the starch of the barley converts it into dextrin, and, indeed, carries conversion to the further stage of grape-sugar, as will be explained immediately. The temperature to which the malt is heated is made to vary, so that the sugar of the malt may or may not be partially altered to a dark-brown coloring material; if great, the malt is said to be *high-dried*, and is used in porter-brewing; if low, the product is of lighter color, and is used for ale. The diastase remaining in malt is still capable

of converting a large quantity of starch into dextrin and sugar; hence the makers or distillers of the various spirits operate on a mixture of malted and unmalted grain in preparing liquors for fermentation.

Gum is a frequent constituent of vegetable juices, existing in large quantity in several species of acacia. According to Frémy gum is a calcium salt, sometimes partially a potassium salt of the *gummic* or *arabic* radical. The formula of gummic acid is said to be $H_2C_{12}H_{18}O_{10}$, H_2O. Gum differs from dextrin in yielding oxalic acid but no mucic acid when oxidized by nitric acid. *Cerasin* or *cherry-tree gum* is an insoluble modification of acacia gum. *Bassorin* ($C_{12}H_{20}O_{10}$) is a form of gum which is insoluble in water, but absorbs a large quantity of that liquid and forms a gelatinoid mass. It occurs largely in Tragacanth, combined, like arabin, with calcium. *Pectin* or *vegetable jelly* ($C_{32}H_{40}O_{28}$, $4H_2O$) is the body which gives to expressed vegetable juices the property of gelatinizing. It forms the chief portion of Irish or Carrageen moss (*Chondrus crispus*, U. S. P.).

Isomerism. Allotropy. Polymorphism.

The composition of dextrin is represented by the same formula as that of starch, namely $C_6H_{10}O_5$; for it has the same percentage composition as starch. Cellulose (see next page) has also a similar formula. There are many other bodies similar in centesimal composition, but dissimilar in properties; such substances are termed *isomeric* (ἴσος, *isos*, equal, and μέρος, *meros*, part); and their condition is spoken of as one of *isomerism*. There is sometimes good reason for doubling or otherwise multiplying the formula of one of two isomeric bodies. Thus olefiant gas (ethylene), the chief illuminating constituent of coal-gas, is represented by the formula C_2H_4, while amylene, an anæsthetic liquid hydrocarbon, obtained from amylic alcohol, though having the same percentage composition as olefiant gas, is represented by the formula C_5H_{10}: for the latter, when gaseous, is about twice and a half as heavy as the former, and must contain, therefore, in equal volumes, twice and a half as many atoms; its formula is, consequently, for this and other reasons, constructed to represent those proportions. This variety of isomerism is termed *polymerism* (from πολύς, *polūs*, many or much, and μέρος, part). Metastannic acid (*vide* p. 215) is a polymeric variety of stannic acid. An illustration of a second variety of isomerism is seen in the case of cyanate of ammonium and urea, bodies already alluded to in connection with cyanic acid. These and several other pairs of chemical substances have dissimilar properties, yet are similar not only in elementary composition and in the centesimal proportion of the elements, but also in the fact that each molecule possesses the same number of atoms. But the reactions of these bodies indicate the probable nature of their construction; and this is shown in their formula by the disposition of the symbols. Thus cyanate of ammonium is represented by the formula $\dot{N}H_4CNO$, urea by CH_4N_2O. Such bodies are termed *metameric* (from μετά, *meta*, a preposition denoting change, and μέρος), and their condition spoken of as one of *metamerism*. The isomerism of starch and dextrin may be of a polymeric or of a metameric character; but we do not

yet know which, and must therefore at present give them identical formulæ. Substances similar in composition and constitution, yet differing in properties, are termed *allotropic* (ἄλλος, *allos*, another, τρόπος, *tropos*, condition). Thus ordinary phosphorus, kept at a temperature of about 450° Fahr., in an atmosphere from which air is excluded, becomes red, opaque, insoluble in liquids in which ordinary phosphorus is soluble, oxidizes extremely slowly, and only ignites when heated to near 500° Fahr. (red or amorphous phosphorus). Other allotropic varieties of phosphorus are known. Another illustration of *allotropy* is seen in the varieties of tartaric acid, which have different optical properties, but otherwise are identical; they are in neither of the above-mentioned states of isomerism, but are allotropic modifications of the same substance. Occasionally one and the same substance crystallizes in two distinct forms, its state is then described as one of *polymorphism* (πολύς, *polūs*, many, μορφή *morphē*, form). Sulphur is polymorphous. It crystallizes by slow cooling in (1) prismatic crystals of sp. gr. 1.98, while in nature it occurs in (2) octahedra of sp. gr. 2.07. Melted and poured into water, sulphur takes up the form of (3) caoutchouc of sp. gr. 1.96. These differences warrant the statement that sulphur occurs in three distinct allotropic conditions.

Cellulin or *cellulose*, the woody fibre of plants, familiar in the nearly pure state, under the forms of "cotton-wool" (*Gossypium*, B. P. and U. S. P., "hairs of the seed of various species of Gossypium"), paper, linen, and pith, is another substance isomeric, probably polymeric, with starch. Lignin is a closely allied body, lining the interior of woody cells and vessels. By the action of nitric acid of various strengths on cellulin, peroxide of nitrogen (NO_2) is substituted for one, two, or three atoms of hydrogen—mono-, di-, or trinitrocellulin being formed:—

$$\underset{\text{Cellulin.}}{C_6H_{10}O_5} + \underset{\text{Nitric acid.}}{HNO_3} = \underset{\text{Mononitrocellulin.}}{C_6\left\{\begin{matrix}H_9\\NO_2\end{matrix}\right\}O_5} + \underset{\text{Water.}}{H_2O}$$

$$\underset{\text{Cellulin.}}{C_6H_{10}O_5} + \underset{\text{Nitric acid.}}{2HNO_3} = \underset{\text{Dinitrocellulin.}}{C_6\left\{\begin{matrix}H_8\\2NO_2\end{matrix}\right\}O_5} + \underset{\text{Water.}}{2H_2O}$$

$$\underset{\text{Cellulin.}}{C_6H_{10}O_5} + \underset{\text{Nitric acid.}}{3HNO_3} = \underset{\text{Trinitrocellulin.}}{C_6\left\{\begin{matrix}H_7\\3NO_2\end{matrix}\right\}O_5} + \underset{\text{Water.}}{3H_2O}$$

Trinitrocellulin is highly explosive gun-cotton; dinitrocellulin is not sufficiently explosive for use instead of gunpowder; mononitrocellulin is scarcely at all explosive. The three movable atoms of hydrogen in cellulin may be displaced by bodies other than peroxide of nitrogen.

Dinitrocellulin (*Pyroxylin*, B. P.) may be prepared by the following process: Mix 5 fluidounces of sulphuric acid and 5 of nitric in an earthenware mortar, immerse 1 ounce of cotton wool in the mixture, and stir it for three minutes with a glass rod so that it is thoroughly and uniformly

wetted by the acids. Transfer the cotton to a vessel containing a considerable volume of water, stir it rapidly and well with a glass rod, decant the liquid, pour more water upon the mass, agitate again, and repeat the affusion, agitation, and decantation until the washing ceases to give a precipitate with chloride of barium. Drain the product on filtering paper, and dry in a water-bath.

The *Pyroxylin*, U. S. P., is made by macerating half a troy ounce of cotton for fifteen hours in a mixture of four troy ounces of sulphuric acid and three and a half troy ounces of nitric, and washing as above.

Pyroxylin may also be made by soaking 7 parts of white filtering paper, which has been washed in hydrochloric acid and dried, in a mixture of 140 parts of sulphuric acid (sp. gr. 1.82) and 70 of nitric acid (1.37) for three hours, and well washing the product (Guichard).

Mononitrocellulin and *trinitrocellulin* are insoluble in a mixture of alcohol and ether; *dinitrocellulin* or *pyroxylin* is soluble, the solution forming ordinary collodion (*Collodium*, B. P. and U. S. P.). The official proportions are 1 ounce of pyroxylin dissolved in a mixture of 36 fluidounces of ether and 12 of rectified spirit. After digesting for a few days, the liquid is decanted from any insoluble matter and preserved in a well-corked bottle. It is "a colorless, highly inflammable liquid with ethereal odor, which dries rapidly upon exposure to the air, and leaves a thin transparent film, insoluble in water or rectified spirit." Flexible collodion (*Collodium Flexile*, B. P., and U. S. P.) is a mixture of collodion (6 fluidounces), Canada Balsam (120 grains), and castor oil (1 fluidrachm).

QUESTIONS AND EXERCISES.

709. How is wheat-starch or potato-starch isolated?
710. Define gluten and glutin.
711. Enumerate the proximate principles of wheaten flour.
712. Is starch soluble in water?
713. Which is the best chemical test for starch?
714. Distinguish physically between the varieties of starch.
715. Into what compound is starch converted by heat?
716. What occurs when a mixture of starch and water is allowed to flow into hot diluted sulphuric acid?
717. If equal amounts of starch and water be heated, one containing a small quantity of ground malt, what effects ensue?
718. Write a short article on the chemistry of "malting."
719. What is the nature of gum arabic and how is it distinguished from "British Gum"?
720. Explain *isomerism*, as illustrated by starch and dextrin.
721. Give examples of polymeric bodies.
722. State the formula of a body metameric with urea.
723. Define *allotropy* and *polymorphism*, giving illustrations.

724. What form of cellulin is official?
725. Mention the properties of the products of the action of nitric acid of various strengths on cellulin.
726. How is pyroxylin prepared.

SUGARS.

Cane-sugar, $C_{12}H_{22}O_{11}$. Inverted-sugar, $C_6H_{12}O_6$.
Grape-sugar, $C_6H_{12}O_6,H_2O$. Milk-sugar, $C_{12}H_{22}O_{11},H_2O$.

Artificial formation of Grape-sugar from Cane-sugar.—Tests for Sugar.—Dissolve a grain or two of common cane-sugar in water. To a portion of this solution placed in a test-tube add more water, two or three drops of solution of sulphate of copper, a considerable quantity of solution of potash or soda (enough to turn the color of the liquid from a light to a dark-blue), and heat the mixture to the boiling-point; no obvious change occurs. To another portion of the syrup add a drop of sulphuric acid, and boil for ten or twenty minutes, then add the copper solution and alkali, and heat as before; a yellowish-red precipitate of cuprous oxide (Cu_2O) falls. This test is exceedingly delicate.

The above reaction is due to the conversion of the *cane-sugar* ($C_{12}H_{22}O_{11}$) into *inverted-sugar*, or *lævulose*, $C_6H_{12}O_6$ (so-called because its solution causes left-handed rotation of a ray of polarized light, cane-sugar having an opposite effect), and grape-sugar $C_6H_{12}O_6$, H_2O, by the influence of the sulphuric acid, and to the reducing action of the inverted-sugar and the grape-sugar on the cupric solution. The formation of a precipitate immediately, without the action of acid, shows the presence of the latter sugars—its formation only after ebullition with acid indicating, in the absence of starch or dextrin, cane-sugar. In this reduction process the sugar is oxidized and broken up into several substances; the exact nature of the reaction has not been ascertained.

Cane-sugar or *sucrose* (*Saccharum Purificatum*, B. P. and U. S. P.) is a frequent constituent of vegetable juices. Thus it forms the chief portion of cassia-pulp (*Cassiæ Pulpa*, B. P.), is contained in the carrot and turnip, but is most plentiful in the sugar-cane; much, however, is now obtained from the sugar-maple and beetroot. On the evaporation of the juice, common *brown* or *moist sugar* crystallizes out; this, by resolution, filtration through animal charcoal, evaporation to a strong syrup, and crystallization in moulds, yields the compact crystalline conical loaves known in trade as *lump-sugar*. From a slightly less strong syrup, slowly cooled, the crystals termed *sugar-candy* are deposited, white or colored according to the color of the syrup.

Inverted Suyar or *Lævulose* is uncrystallizable. It is found in the grape, fig (*Ficus*, B. P. and U. S. P.), cherry, and gooseberry; both grape-sugar and inverted sugar in the strawberry, peach, plum, etc.

Grape-sugar or *glucose* (from γλυκὺς, *glucūs*, sweet) is often seen in the crystallized state, in dried grapes or raisins and other fruits; it is also the variety of sugar met with in diabetic urine. Its crystalline character is quite distinct from that of cane-sugar, the latter forming large four or six-sided rhomboidal prisms, while grape-sugar occurs in masses of small cubes or square plates. Grape-sugar is also less soluble in water but more soluble in alcohol than cane-sugar.

Lævulose is lævogyrate, while Sucrose and Glucose possess right-handed rotation; the latter twist a ray of polarized light from left to right, to an extent dependent on the amount of sugar present—a fact easy of application in estimating the amount of sugar in syrups or in diabetic urine.

Both cane-sugar and grape-sugar yield alcohol and carbonic acid gas by fermentation, the cane-sugar probably always passing into grape-sugar before the production of alcohol commences.

$$\underset{\text{Grape-sugar.}}{C_6H_{12}O_6} = \underset{\text{Alcohol.}}{2C_2H_5HO} + \underset{\text{Carbonic acid gas.}}{2CO_2}$$

In *bread-making*, some of the starch is converted into dextrin, and this into sugar by the ferment. The above action then goes on, the liberation of gas producing the *rising* or swelling of the mixture of flour, water, and yeast (dough)—the temperature to which the mass is subjected in the oven causing escape of alcohol, and further expansion of the bubbles of carbonic acid gas in every part of the now spongy loaf. The carbonic acid gas gradually evolved when flour is worked up for bread with a mixture of dry bicarbonate of sodium and tartaric acid (best preserved by previous admixture with dried flour and a little carbonate of magnesium)—*baking-powder*—exerts similar influence. The least objectionable method of introducing carbonic acid gas, however, is that of Dauglish, whose patent Aërated Bread is made from flour by mere admixture with carbonic-acid water under pressure. On removal from the cylinder, the resulting dough expands by the natural elasticity of the imprisoned carbonic acid, and the bake-oven completes the process. The crumb of bread is official (*Mica Panis*, B. P.).

Milk-sugar or *lactose* ($C_{12}H_{24}O_{12}$) (*Saccharum Lactis*, B. P. and U. S. P), the sweet principle of the milk of various animals, is not susceptible of alcoholic or vinous fermentation; but it resembles grape-sugar in reducing an alkaline solution of copper with precipitation of suboxide. It is readily obtained from milk by adding a few drops of acid, stirring, setting aside for the *curds* to separate, filtering, evaporating the *whey* to a small bulk, filtering again if necessary, and allowing to cool and crystallize. It usually occurs in trade "in cylindrical masses, two inches in diameter, with a cord or stick in the axis, or in fragments of cakes—grayish-white, crystalline on the surface and in its texture, translucent, hard, scentless, faintly sweet, gritty when chewed." It is soluble in 6 parts of cold and 3

of boiling water; slightly soluble in alcohol; insoluble in ether. Powdered milk-sugar is used in pharmacy as a vehicle for potent solid medicines.

Action of Alkali on Sugar.—To a little solution of grape-sugar add solution of potash or soda, or solution of carbonate of potassium, and warm the mixture; the liquid is darkened in color from amber to brown, according to the amount of sugar present.

Tests.—The copper-reaction, the fermentation process, and the effect of alkalies form three good tests of the presence of grape-sugar, and, indirectly, of cane-sugar. A piece of merino or other woollen material, previously dipped in a solution of stannic chloride and dried, becomes of a brown or black color when dipped in a solution of glucose and heated to about 300° F. by holding before a fire.

Sugar from Starch.—Boil the starch with a little water and a drop of sulphuric acid as for dextrin, but continue the ebullition for several minutes; on testing a portion of the cooled liquid with iodine and another portion with the heated alkaline solution of a copper salt as described on page 361, it will be found that the starch has nearly all become converted into grape-sugar, or *starch-sugar* as it is sometimes termed. When made on a large scale, a warm (131° F.) mixture of starch and water of the consistence of cream is slowly poured into a boiling solution of one part of sulphuric acid in one hundred of water, the whole boiled for some time, the acid neutralized by chalk, the mixture filtered, the liquid evaporated to a thick syrup and set aside; in a few days it crystallizes to a granular mass resembling honey. In this operation a small quantity of dextrin remains with the glucose; but if the process be conducted under pressure, conversion, according to Manbré, is complete.

The sugar in fresh fruits is mainly cane-sugar; but by the action of the acid, or possibly of a ferment in the juice, it is gradually converted into *inverted sugar*, a variety differing from cane-sugar in being uncrystallizable, and in having an inverted or opposite influence on polarized light, twisting the ray from right to left (lævogyrate, having lævo-rotation—hence sometimes termed *levulose*). Ripe Hips (*Rosæ Caninæ Fructus*, B. P.) contain 30 per cent. of such sugar. Fruit-sugar, as gathered in the form of syrup by bees, is probably a mixture of these two varieties. It is gradually altered to a crystalline or granular mass of grape-sugar, as seen in dried fruits, such as Raisins (*Uvæ*, B. P., *Uva Passa*, U. S. P.), and the Prune (*Prunum*, B. P. and U. S. P.) and in solidified honey (*Mel*, B. P. and U. S. P.). This, the common form of grape-sugar, is dextrogyrate, and hence is sometimes termed *dextrose*, to distinguish it

from levulose. Honey often contains flocculent matters which cause it to ferment and yield mannite (Stoddart), alcohol, and acetic acid; hence for use in medicine it is directed (*Mel Depuratum*, B. P. and U. S. P.) to be clarified by melting and straining, while hot, through flannel previously moistened with warm water. A mixture of clarified honey 80 per cent., acetic acid 10 per cent., and water 10 per cent. is official under the name of *Oxymel* (from ὀξὺς, *oxūs*, acid, and μέλι, *meli*, honey). A similar mixture of honey with acetic acid containing the soluble portions of squill-bulbs (*Scilla*, B. P. and U. S. P.) is known as Oxymel of Squill (*Oxymel Scillæ*, B. P.). Honey or sugar-cane are the bases of the official *Confections*.

"*Honey Dew*" is a viscid saccharine matter occasionally met with on the leaves of the lime, maple, black alder, rose, and other trees. Sometimes it is sufficiently abundant to dry and fall on the ground, forming a veritable "shower of manna." It is a mixture of cane-sugar, inverted sugar, and dextrin.

Barley sugar is made by simply heating cane-sugar till it fuses, a change from the crystalline to the uncrystallizable condition occurring. *Treacle* (*Theriaca*, B. P.), *Molasses*, (*Syrupus Fuscus*, U. S. P.), or *Melasses* (from *Mel*, honey), chiefly results from the application of too much heat in evaporating the syrups of the sugar cane; it is a mixture of cane-sugar with uncrystallizable sugar and coloring-matter. Liquorice-root (*Glycyrrhizæ Radix*, B. P.) contains a considerable quantity of uncrystallizable sugar (*Glycyrrhizin*).

Caramel.—Carefully heat a grain or two of sugar in a test-tube until it blackens; the product is *caramel* or *burnt sugar* (the *Saccharum Ustum* of pharmacy). It is used as a coloring agent for gravies, confectioneries, spirits, and similar materials.

Mannite ($C_6H_{14}O_6$).—Boil manna with alcohol, filter, and set aside; mannite separates in colorless shining crystals or acicular masses, to the extent of from 60 to 80 per cent. of the manna.

Manna, B. P. and U. S. P., is "a concrete saccharine exudation from the stem of *Fraxinus Ornus* and *F. rotundifolia;* it is obtained by making incisions in the stem of the trees." It occurs in "stalactiform pieces from one to six inches in length, and one or two inches in width, uneven, porous, and friable, curved on one side, of a yellowish-white color, with a faintly nauseous odor, and a sweetish taste." It is also met with in celery, onions, asparagus, certain fungi and sea-weeds, occurs in the exudations of apple and pear trees, and is produced during the viscous fermentation of sugar.

Mannite is an alcohol, the radical of which is sexivalent $(C_6H_8)^{vi}$ 6HO (Wanklyn). It is closely related to the sugars, glucose becoming mannite by action of nascent hydrogen :—

$$\underset{\text{Glucose.}}{C_6H_{12}O_6} + \underset{\text{Hydrogen.}}{H_2} = \underset{\text{Mannite.}}{C_6H_{14}O_6}$$

Indeed, glucose itself is probably an alcohol of another radical

$(C_6H_6)^{vi}6HO$. Mannite does not undergo vinous fermentation in contact with yeast. It is soluble in 5 times its weight of cold water.

Mucic Acid ($H_2C_6H_8O_8$) and *Saccharic Acid* ($H_2C_6H_8O_8$) are two isomeric bodies formed by the action of dilute nitric acid on gum, sugar, and mannite.

QUESTIONS AND EXERCISES.

727. How are cane-sugar and grape-sugar analytically distinguished?
728. Describe the methods of extracting and purifying cane-sugar.
729. Mention the chief sources of cane-sugar.
730. Give chemical explanations of the different processes of bread-making.
731. How is milk-sugar obtained, and in what respects does it differ from other sugar?
732. By what process may starch be entirely converted into sugar?
733. What is the difference between fruit-sugar and honey?
734. What is Oxymel?
735. Describe the effect of heat on cane-sugar.
736. Describe the source and character of manna.
737. Give the latest view of the constitution of mannite.
738. Whence are mucic and saccharic acids obtained?

THE GLUCOSIDES.

Source.—The Glucosides are certain proximate vegetable principles which, by ebullition with dilute acid, or other method of decomposition, take up the elements of water and yield glucose, accompanied by a second substance, which differs in each case according to the body operated on. Twelve of the glucosides are of pharmaceutical interest, namely: Amygdalin, Cathartic acid, Colocynthin, Convolvulin, Digitalin, Elaterin, Guaiacin, Jalapin, Salicin, Santonin, Scammonin. Tannin, or tannic acid, is also a glucoside; it has been described among the acids.

Note on Nomenclature.—The first syllable of the names of glucosides and neutral principles generally are commonly given in allusion to origin; the last syllable is *in*, which sufficiently distinguishes them as a class.

Amygdalin ($C_{20}H_{27}NO_{11}$, $3H_2O$).—This is a white crystalline substance, existing in the bitter (*Amygdala Amara*, B. P. and U. S. P.), but not in the sweet almond (*Amygdala Dulcis*, B. P. and U. S. P.). It is readily extracted by alcohol from the cake left when the fixed oil has been expressed

from bitter almonds. From the concentrated alcoholic solution ether precipitates the amygdalin.

Make an emulsion of two or three sweet almonds by bruising and rubbing them with water, and notice that it has no odor of essential oil of bitter almonds; add a grain or two of amygdalin, an odor of essential oil of bitter almonds is at once developed. Bruise two or three bitter almonds and rub with water; the volatile oil is again developed (*Oleum Amygdalæ Amaræ*, U. S. P.).

Bitter Almond-water (*Aqua Amygdalæ Amaræ*, U. S. P.) is made by filtering a mixture of 16 minims of the oil with 60 grains of carbonate of magnesium and 2 wine-pints of distilled water.

The source of the hydride of benzoyl, or essential oil of bitter almonds, in these reactions is the amygdalin, which, under the influence of *synaptase* or *emulsin*, a ferment existing in both bitter and sweet almonds, splits up into the essential oil, hydrocyanic acid, and glucose :—

$$\underset{\text{Amygdalin.}}{C_{20}H_{27}NO_{11}} + \underset{\text{Water.}}{2H_2O} = \underset{\text{Hydride of benzoyl.}}{C_7H_5OH} + \underset{\text{Hydrocyanic acid.}}{HCN} + \underset{\text{Glucose.}}{2C_6H_{12}O_6}$$

As each molecule of amygdalin yields one of hydrocyanic acid, a simple calculation shows that 17 grains (mixed with emulsion of sweet almonds) will be required to form one grain of real hydrocyanic acid, a quantity equivalent to 50 minims of the dilute hydrocyanic acid of the British Pharmacopœia.

Test.—The reaction between synaptase and amygdalin is applicable as a test of the presence of one by the addition of the other, even when mixed with much organic matter.

Cherry-Laurel-water (*Aqua Laurocerasi*, B. P., by distillation with water from *Laurocerasi Folia*, B. P.) contains hydrocyanic acid derived from a reaction similar to, if not identical with, that just described. But the proportion of amygdalin or analogous body in cherry-laurel-leaves is most variable; hence the strength of the water is highly uncertain. The preparation is worse than useless.

Caution.—Essential oil of almonds is highly poisonous. The purified oil or hydrate of benzoyl is almost innocuous; it is obtained on distilling the crude oil with milk of lime and ferrous chloride. Artificial oil of bitter almonds or nitrobenzol ($C_6H_5(NO_2)$) when taken in quantity has been known to produce death. The presence of nitrobenzol in oil of bitter almonds is detected by adding a little of the oil to a mixture of zinc and diluted sulphuric acid, shaking well, setting aside for an hour or two, filtering off the clear liquid and adding a little chlorate of potassium; a violet color (actual mauve) is produced.

Arbutin ($C_{12}H_{16}O_7$) is contained in the leaves of *Arctostaphylos uva ursi* and *Chimaphila umbellata*.

Cathartic Acid.—"The glucoside acid that now is known to confer on the Senna of Alexandria (*Senna Alexandriana*, B. P.).

Tinnevely (*Senna Indica*, B. P., *Senna*, U. S. P.), and probably on American Senna (*Cassia Marilandica*, U. S. P.), its purgative property, has been named by its discoverers (Dragendorf and Kubly) Cathartic acid. Its formula has been stated as $C_{180}H_{192}N_4SO_{82}$, which, if true, accounts for its extreme stability. It is insoluble in water, strong alcohol, and ether, but enters readily into watery solution when combined with alkaline and earthy bases, in which state it exists in senna. Its ammonium salts give brownish flocculent precipitates with salts of silver, tin, mercury, copper, and lead. Antimonial salts, tannin, yellow and red prussiates have no effect upon it. Alkalies, aided by heat, act destructively upon it. Boiled with a mineral acid it splits into a peculiar kind of glucose and an acid that has been named Cathartogenic; its formula is said to be $C_{132}H_{116}N_4SO_{44}$. The natural cathartate occurring in senna is prepared by partially precipitating by strong spirit a water infusion of senna, concentrated to a syrupy state by evaporation *in vacuo*. The filtrate is now treated with a much larger bulk of absolute alcohol, and the precipitate thus obtained is purified by repeated solution in water and precipitation by alcohol. To obtain the pure acid, advantage is taken of its colloidal properties; the crude cathartate is dissolved in moderately strong hydrochloric acid, and subjected to dialysis on a diaphragm of parchment paper. The minimum dose of this pure acid was found to be about 1½ grain, which caused several stools with decided griping.

"The carthartic combinations that I have made are, the cathartate of ammonium, prepared from cathartate of lead by my original process, and the mixed cathartates, prepared according to Dragendorf's method as modified by myself. Of the former nearly pure salt, I have found 3¾ grains to purge fairly as to amount, but slowly as to time, and with considerable griping. Of the latter 7½ grains purged violently with much griping and sickness, which continued through the greater part of the day. It obviously would be improper to combine senna with any of its metallic precipitants, should such be desired, which is not likely. It is here satisfactory to observe that the cathartate of magnesium is soluble, and that the old-fashioned black draught agrees with new-fashioned science." (Groves.)

Buckthorn juice (*Rhamni Succus*, B. P.) owes its cathartic properties to a substance apparently identical with cathartic acid.

Chiratin.—The active principle of Chiretta (*Chirata*, B. P. and U. S. P.) is said by Flückiger and Höhn to be due to chiratin, a pale-yellow neutral substance allied to the glucosides.

Colocynthin ($C_{56}H_{84}O_{23}$?).—This substance is the active bitter and purgative principle of colocynth-fruit (*Colocynthidis Pulpa*, B. P., *Colocynthis*, U. S. P.): it is soluble in water and alcohol, but not in ether. By ebullition with acids it furnishes glucose and a resinoid body.

Convolvulin.—See Jalapin.

Digitalin ($C_{27}H_{45}O_{15}$).—This is an active principle of the Foxglove (*Digitalis*, B. P.). Boil a grain of digitalin (*Digitalinum*, B. P. and U. S. P.) with sulphuric acid for

some time; flocks of *digitaliretin* ($C_{15}H_{25}O_5$) separate, and glucose may be detected in the liquid.

$$\underset{\text{Digitalin.}}{C_{27}H_{45}O_{15}} + \underset{\text{Water.}}{2H_2O} = \underset{\text{Digitaliretin.}}{C_{15}H_{25}O_5} + \underset{\text{Glucose.}}{2C_6H_{12}O_6}$$

Properties.—Digitalin occurs "in porous mammillated masses or small scales, white, inodorous, and intensely bitter, readily soluble in spirit, but almost insoluble in water and in pure ether, dissolves in acids, but does not form with them neutral compounds; its solution in hydrochloric acid is of a faint yellow color, but rapidly becomes green. It leaves no residue when burned with free access of air. It powerfully irritates the nostrils, and is an active poison."

Process.—The official process for the preparation of digitalin consists in dissolving the glucoside out of the digitalis leaf (*Digitalis Folia*, B. P. and U. S. P.) by alcohol, removing the alcohol by distillation, dissolving the residue in water by the help of a small quantity of acetic acid, removing much of the color from the solution by animal charcoal, neutralizing most of the acetic acid by ammonia, precipitating the digitalin by tannic acid (with which it forms an insoluble compound), washing the precipitate, rubbing and heating it with spirit and oxide of lead (which removes the acid in the form of insoluble tannate of lead), again decolorizing by animal charcoal, evaporating to dryness, washing out impurities still remaining by ether, and drying the residual digitalin. In this form digitalin is uncrystallizable.

Pure Digitalin.—On treating commercial digitalin with chloroform only an inert substance remains undissolved. The solution yields pure digitalin on evaporation; it may be crystallized from spirit in radiating needles. (Nativelle.) The therapeutic effect of the pure substance is identical with the preparations of digitalis, but, as might be expected, more constant in its action and of course intensely powerful.

ELATERIN ($C_{20}H_{28}O_5$).—Boil elaterium (*Elaterium*, B. P. and U. S. P.), the dried sediment from the juice of the squirting cucumber fruit (*Ecbalii Fractus*, B. P.), in a small quantity of spirit of wine, and filter; fibrous and amylaceous matter remain insoluble, while elaterin and resin are dissolved. The filtrate, concentrated and poured into a warm solution of potash, yields, on cooling, crystals of elaterin, resin being retained by the alkali. It is purified by recrystallization from spirit. Boil elaterium in dilute sulphuric acid for an hour or two, filter, and test the clear liquid for glucose; a reddish precipitate of cuprous oxide falls. This reaction is readily obtained with elaterium, but not always with elaterin; hence probably the latter is not a true glucoside.

Elaterin is the active principle of the so-called elaterium. Elaterium occurs "in light friable slightly incurved cakes, about one line

($\frac{1}{12}$ inch) thick, greenish-gray, acrid and bitter; fracture finely granular." Good specimens of this drug should yield, according to the British Pharmacopœia, not less than 20 per cent. of elaterin by the above process. Elaterium is sometimes adulterated with chalk and other substances.

GUAIACIN.—Resin of guaiacum (*Guaiaci Resina*, B. P. and U. S. P.), an exudation from the wood (*Guaiaci Lignum*, B. P. and U. S. P.) of *Guaiacum officinale*, is probably a mixture of several substances, among which are *Guaiaretinic acid* ($C_{20}H_{26}O_4$) (Hlasiwetz) and *Guaiacin*, a glucoside. On boiling guaiacum-resin with dilute sulphuric acid for some time, glucose is found in the liquid, a green resinous substance (*guaiaretin*) remaining insoluble (Kosmann). Most oxidizing agents, and even atmospheric air, especially under the influence of certain organic substances, produce a blue, then green, and finally a brown color, when brought into contact with an alcoholic solution of guaiacum-resin.

These effects are said to be due to three stages of oxidation (Jonas). They may be observed on adding the solution to the inner surface of a paring of raw potato.

JALAPIN ($C_{31}H_{50}O_{16}$) AND CONVOLVULIN ($C_{34}H_{56}O_{16}$).—According to Keyser and Meyer, jalap-resin contains two distinct substances — convolvulin, chiefly obtained from Mexican male jalap, and jalapin, most largely contained in the true jalap; the former is soluble in ether, the latter insoluble. Boil jalap-resin with dilute sulphuric acid for some time and filter; a substance, which is probably a mixture of *jalapinol* ($C_{13}H_{24}O_3$) and *convolvulinol* ($C_{16}H_{30}O_3$), separates; and glucose may be detected in the clear liquid. (It is to be regretted that the authors transpose the above names, terming the old well-known jalapin convolvulin.)

$$\underset{\text{Jalapin.}}{C_{31}H_{50}O_{16}} + \underset{\text{Water.}}{5H_2O} = \underset{\text{Jalapinol.}}{C_{13}H_{24}O_3} + \underset{\text{Glucose.}}{3C_6H_{12}O_6}$$

Jalapic Acid.—This is contained in the portion of jalap-resin soluble in ether. It may also be obtained from jalapin by ebullition with alkalies:—

$$\underset{\text{Jalapin.}}{2C_{31}H_{50}O_{16}} + \underset{\text{Water.}}{3H_2O} = \underset{\text{Jalapic acid.}}{C_{62}H_{106}O_{35}}$$

Jalap-resin (*Jalapæ Resina*, B. P. and U. S. P.) is obtained by digesting and percolating jalap tubercles (*Jalapa*, B. P. and U. S. P.) with spirit of wine, adding a little water, distilling off the spirit, pouring away the aqueous portion which contains much saccharine matter, and wash-

ing and drying the residual resin. The tincture is sometimes decolorized by animal charcoal, and the evaporated product sold as jalapin.

Jalap-resin is insoluble in oil of turpentine; common resin, or rosin, soluble. If the presence of the latter is suspected, the specimen should be powdered, digested in turpentine, the mixture filtered, and the filtrate evaporated; no residue, or not more than yielded by the turpentine itself, should be obtained.

SALICIN ($C_{13}H_{18}O_7$).—This substance is contained in and easily extracted from willow-bark.

Tests.—1. To a small portion of salicin placed on a white plate or dish add a drop of strong sulphuric acid; a deep-red color is produced.

2. Boil salicin with dilute sulphuric acid for some time; it is converted into *saligenin* ($C_7H_8O_2$) and glucose.

$$\underset{\text{Salicin.}}{C_{13}H_{18}O_7} + \underset{\text{Water.}}{H_2O} = \underset{\text{Saligenin.}}{C_7H_8O_2} + \underset{\text{Glucose.}}{C_6H_{12}O_6}$$

Examine a portion of the solution for grape-sugar by the copper test.

3. To another portion of the liquid, carefully neutralized, add a persalt of iron; a purplish-blue color is produced, due to the reaction of the saligenin and the ferric salt.

4. Heat a mixture of about 1 part of salicin, 1 of red chromate of potassium, $1\frac{1}{2}$ of sulphuric acid, and 20 of water in a test-tube; a fragrant characteristic odor is evolved, due to the formation of hydride of salicyl ($C_7H_5O_2H$), an essential oil identical with that existing in meadow-sweet (*Spiræ ulmaria*) and in heliotrope.

$$\underset{\text{Saligenin.}}{2C_7H_8O_2} + \underset{\text{Oxygen.}}{O_2} = \underset{\text{Hydride of salicyl.}}{2C_7H_5O_2H} + \underset{\text{Water.}}{2H_2O}$$

SANTONIN ($C_{15}H_{18}O_3$).—This substance is a weak acid, insoluble in ammonia, but forming a soluble calcium salt. From a solution of santonate of calcium the santonin is precipitated by acids. Boiled for some time with dilute sulphuric acid it yields 87 per cent. of an insoluble resinous substance (*santoniretin*) and glucose (Kosmann). Santonin (*Santoninum*, B. P. and U. S. P., and *Trochisci Santonini*, U. S. P.) is official. It is soluble in an aqueous solution of twice its weight of carbonate of sodium.

Process.—The process for its preparation consists in boiling *santonica*, B. P. and U. S. P. (the unexpanded flower-heads of an undetermined species of *Artemisia*—*A. cina*, U. S. P.), with milk of lime (whereby santonate of calcium is formed), straining, precipitating the santonin or santonic acid by hydrochloric acid (acetic acid, U. S. P.), washing with ammonia to remove resin, dissolving in spirit and digesting with animal charcoal to get rid of coloring-matter,

setting the spirituous solution aside to deposit crystals of santonin, and purifying by recrystallization from spirit. (Mialhe).

Saponin ($C_{12}H_{20}O_7$?) is a peculiar glucoside occurring in Soapwort, the root of the common Pink, and many other plants: its solution in water, even though very dilute, froths like a solution of soap. Pereira considered *smilacin*, one of the principles of the supposed activity of Sarsaparilla (*Sarzœ Radix*, B. P., *Sarsaparilla*, U. S. P.), to be closely allied to, if not identical with, saponin.

Saponin is also met with in the root of *Polygala Senega* (*Senegœ Radix*, B. P., *Senega*, U. S. P.), though the active principle of senega is said to reside in *polygalic acid*, probably a glucoside derivative of saponin.

Scammonin ($C_{32}H_{52}O_{16}$).—Boil resin of scammony (*Scammoniæ Resina*, B. P. and U. S. P.) with dilute sulphuric acid for some time; glucose may then be detected in the liquid, a resinous acid termed *scammoniol* ($C_{14}H_{13}O_3$?) being produced at the same time.

Natural scammony (*Scammonium*, B. P. and U. S. P.) is an exudation from incisions in the living root (*Scammoniæ Radix*, B. P.) of *Convolvulus Scammonia*. It contains from 10 to 20 per cent. of gum. The British official resin of scammony contains no gum, and is made by digesting the root in spirit, adding water, distilling off the alcohol, and washing the residual resin with hot water till free from gum.

The U. S. P. process consists in exhausting scammony in alcohol, recovering the latter by distillation, treating the residue with water, and drying the separated resin.

Resin of scammony is soluble in all proportions in ether. Sulphuric acid slowly reddens it. It is said to be liable to adulteration with resin of jalap, guaiacum-resin, and common rosin. Resin of jalap is insoluble in ether, guaiacum-resin is distinguished by the color tests mentioned under Guaiacin, and rosin by the action of sulphuric acid.

QUESTIONS AND EXERCISES.

739. Define glucosides, and mention those of pharmaceutical interest.

740. Draw out an equation illustrative of the development of Oil of Bitter Almonds.

741. How much pure amygdalin will yield one grain of real hydrocyanic acid?

742. To what does Cherry-Laurel-water owe activity? Is the preparation trustworthy?

743. Mention the active principle of Senna.

744. By what process is the glucoside of the purple foxglove prepared?

745. State the circumstances under which Guaiacum-Resin and Jalap-Resin yield glucose.

746. Mention a test for guaiacum-resin.

747. How may the adulteration of jalap-resin by rosin be detected?

748. Enumerate the tests for Salicin.

749. How is santonin officially prepared?

750. Name sources of saponin.

751. What is the difference between Scammony and Resin of Scammony?

752. How would you detect resins of turpentine, guaiacum, or jalap, in resin of scammony?

ALCOHOL AND ALLIED BODIES.

ALCOHOL.

Formation of Alcohol.—Ferment two or three grains of sugar by dissolving in a test-tube full of water, adding a little yeast (*Cerevisiæ Fermentum*, B. P., *Fermentum*, U. S. P.), or a piece of the so-called German or dried yeast, and setting the whole aside for several hours in a warm place at a temperature of 70° or 75°; carbonic acid gas is evolved, and, if the tube be inverted in a small dish containing water, may be collected in the upper part of the tube and subsequently tested: the solution contains alcohol. If the experiment be made on larger quantities (four ounces of sugar, one of yeast, and a pint of water) the fermented liquid should be distilled, one-half being collected, shaken with a little lime, soda, or potash, to neutralize any acetic acid, and decompose ethereal salts, and again distilled till one-half has passed over; the product is dilute spirit of wine. It may be still further concentrated or *rectified* by repeating this process of *fractional distillation*.

Both cane-sugar and grape-sugar yield alcohol by fermentation, the cane-sugar probably always passing into grape-sugar before the production of alcohol commences.

$$\underset{\text{Grape-sugar.}}{C_6H_{12}O_6} = \underset{\text{Alcohol.}}{2C_2H_5HO} + \underset{\text{Carbonic acid gas.}}{2CO_2}$$

Traces of several other substances are simultaneously produced (*vide* "*Fousel Oil*" in Index). By this reaction are formed the spirit of the various kinds of wine, beer, and liqueurs, such as Orange Wine (*Vinum Aurantii*, B. P.), made "by the fermentation of a saccharine solution, to which the fresh peel of the bitter orange has been added;" Sherry Wine (*Vinum Xericum*, B. P. and U. S. P.), the fermented juice of the grape; Port Wine (*Vinum Portense*, U. S. P.), Whiskey (*Spiritus Frumenti*, U. S. P.), containing from 48 to 56 per cent. of pure alcohol; *Spirit of Myrcia* or *Bay Rum* (*Spiritus Myrciæ*, U. S. P.), prepared by distilling rum with leaves of *Myrcia acris;* and others.

Varieties of Alcohol.—The weak spirit concentrated by distillation till it contains 84 per cent. by weight of pure alcohol is an

ordinary article of commerce; its specific gravity at 60° is 0.8382. This is common *Spirit of Wine*, the *Spiritus Rectificatus* of the British Pharmacopœia. *Alcohol*, U. S. P., has sp. gr. 0.835; *Alcohol Fortius*, U. S. P., sp. gr. 0.817. The official *Proof Spirit** (*Spiritus Tenuior*, B. P.) contains 49 per cent. by weight of alcohol, and is made by diluting 100 volumes of Rectified Spirit with water until the well-stirred product measures 156 volumes. Sixty volumes of water will be required for this purpose, the liquids occupying less bulk after than before admixture. In the language of the Excise authorities the rectified spirit of the Pharmacopœia would be described as "56 per cent. over proof" (56 per cent. O. P.); that is 100 volumes contain as much alcohol as is present in 156 volumes of proof spirit. Obviously, proof spirit may be made by diluting with water rectified spirit of any other strength than that mentioned above. Thus 100 fluidounces of a spirit of "seventy over proof" may be diluted to 170, or the same quantity of a spirit of "fifty over proof" may be diluted to 150, and so on. The specific gravity of proof spirit at 60° is 0.920. (*Alcohol Dilutum*, U. S. P., has sp. gr. 0.941.)

Empirical Formulæ.—Composition of Alcohol.—Alcohol, by quantitative analysis, is found to contain the elements carbon, hydrogen, and oxygen in the following proportions:—

Composition of Alcohol.

Carbon	52.174 or ÷ 12 =	4.348 or	2.
Hydrogen	13.043 or ÷ 1 =	13.043 or	6.
Oxygen	34.783 or ÷ 16 =	2.174 or	1.
	100.000		

From centesimal numbers a formula is obtained in the usual way. Thus, on dividing these figures by the atomic weights of the respective elements (C = 12, H = 1, O = 16), and reducing the products to the simplest whole numbers, alcohol will be found to contain two atoms of carbon to every six of hydrogen and to every one of oxygen, and its possible or *empirical formula* to be C_2H_6O.

Constitution of Alcohol.—There is good reason to believe that alcohol is the hydrate of a basylous radical *ethyl* (C_2H_5 or Et); hence we derive the *rational formula* C_2H_5HO or EtHO.

Rational Formulæ.—Rational formulæ are deduced by (1) ascertaining how much of the substance will continue with, displace or play the part of, the atomic weight of a well-known element or radical. When this method cannot be applied, or in confirmation of it, processes of (2) reduction, (3) oxidation, (4) substitution, etc., are employed.

* *Proof spirit* is so termed from the fact that in olden times a proof of its strength was supposed to be afforded by moistening a small quantity of gunpowder and setting light to the spirit: if it fired the powder it was said to be "over proof;" if not, "under proof." The weakest spirit that would stand this test was what we should now describe as of sp. gr. 0.920.

Salts of Ethyl.—Alcohol is, then, a body analogous in constitution to hydrate of potassium (KHO); and there are other compounds of ethyl analogous in constitution to ordinary inorganic salts, such as those of potassium. The oxide of ethyl (Et_2O) is common ether; the nitrite of ethyl ($EtNO_2$) is the body which, dissolved in spirit of wine, constitutes "sweet spirit of nitre;" the acid sulphate of ethyl ($EtHSO_4$), or sulphethylic or sulphovinic acid, is a liquid met with in the preparation of ether. The iodide (EtI), hydride (EtH), acetate ($Et\bar{A}$) and other salts are of considerable chemical interest, but not used in medicine.

Absolute or Real Alcohol (C_2H_5HO) may be prepared from spirit of wine by removing the water which the latter contains. This is accomplished, partially, by the agency of carbonate of potassium, and finally and entirely by recently burned quicklime. In operating on, say, one pint, 1½ ounce of dried carbonate of potassium is placed in a bottle that can be well closed, and frequently shaken during two days with the spirit. Meanwhile, about half a pound of good quicklime, if not already at hand, is made from 10 or 11 ounces of slaked lime by heating to redness in a covered crucible for half an hour. The spirit having been decanted from the denser aqueous solution of carbonate of potassium and placed in a quart flask, retort, or tin can, the lime, as soon as cold, is added, and the whole occasionally shaken during a day. The vessel is now placed in a saucepan or other bath containing water, quickly connected with a condenser (in the case of the flask or can by a bent tube and cork previously prepared; for absolute alcohol must not be exposed to air, or water in the form of moisture will be rapidly reabsorbed) and heat applied to the bath. Rejecting the first ounce or ounce and a half, as likely to contain traces of moisture absorbed from the air or apparatus, continue distillation until nothing more passes over, the water in the bath being kept just below the boiling-point (about 200° F.). These details are those of the British Pharmacopœia. Specific gravity 0.7938. Boiling-point 173.6.

Tests.—There are no specific tests for alcohol when mixed with complex matters. It is, however, easily isolated and concentrated by fractional distillation, and is then recognizable by conjoint physical and chemical characters. Thus its odor and taste are characteristic; it is lighter than water, volatile, colorless, and, when tolerably strong, inflammable, burning with an almost non-luminous flame; it readily yields aldehyd (see below) and acetic ether (*vide* p. 268), each of which has a characteristic odor; lastly, in presence of hot acid, alcohol reduces red chromate of potassium to a green salt of chromium.

According to Lieben 1 of alcohol in 2000 of water can be detected by adding to some of the warmed liquid a little iodine, a few drops of solution of soda, again warming gently, and setting aside for a time; a yellowish crystalline deposit of *iodoform* (CHI_3) is obtained. Under the microscope the latter presents the appearance of hexagonal plates or six-rayed and other varieties of stellar crystals.

$$C_2H_6O + 4I_2 + 6NaHO = CHI_3 + NaCHO_2 + 5NaI + 5H_2O.$$

Other alcohols, aldehyds, gum, turpentine, sugar, and several other substances give a similar reaction.

Tests of purity.—Oil of resin is precipitated on diluting spirit of wine with distilled water, giving an opalescent appearance to the mixture. The specific gravity should be 0.838. Fusel oil, aldehyd, and aldehydic acid are detected by nitrate of silver (*vide* Index, "Alcohol," test for purity of). Water in absolute alcohol may be detected by adding to a small quantity a little highly dried sulphate of copper, which becomes blue ($CuSO_4.5H_2O$) if water is present. but retains its yellowish-white anhydrous character ($CuSO_4$) if water be absent.

ALDEHYD (C_2H_4O).—Place together, in a capacious test-tube, or a flask, spirit of wine, black oxide of manganese, sulphuric acid, and water, and gently warm the mixture; aldehyd (*alcohol dehydrogenatus*), a highly volatile liquid, is immediately formed, and its vapor evolved, recognized by its peculiar, somewhat fragrant odor. Adapt a cork and rather long bent tube to the test-tube, and let some of the aldehyd slowly distil over into another test-tube, the condensing-tube being kept as cool as possible. Set the distillate aside for a day or two; the aldehyd will have nearly all disappeared, and acetic acid be found in the tube. Test the exposed liquid by litmus paper; it will be found to have an acid reaction: make it slightly alkaline by a drop or two of solution of carbonate of sodium, then boil to remove any alcohol and aldehyd present, add sulphuric acid, and notice the characteristic odor of the acetic acid evolved.

These experiments will enable the process of acetification described in connection with acetic acid to be more fully understood. Pure diluted alcohol is not oxidized by exposure to air; but in presence of fermentive matter, or vegetable matter undergoing decay or change, it is oxidized first to aldehyd and then to acetic acid.

In the above process the black oxide of manganese and sulphuric acid furnish nascent oxygen:—

$$\underset{\text{Black oxide of manganese.}}{MnO_2} + \underset{\text{Sulphuric acid.}}{H_2SO_4} = \underset{\text{Sulphate of manganese.}}{MnSO_4} + \underset{\text{Oxygen (atom).}}{O} + \underset{\text{Water.}}{H_2O}$$

The nascent oxygen then acts on the alcohol, just as the oxygen of the air acts on the alcohol in fermented infusion of malt, beer, or wine, giving aldehyd:—

$$\underset{\text{Alcohol.}}{C_2H_6O} + \underset{\text{Oxygen (atom).}}{O} = \underset{\text{Aldehyd.}}{C_2H_4O} + \underset{\text{Water.}}{H_2O}$$

The aldehyd rapidly, even when pure (more rapidly when impure), absorbs oxygen and yields acetic acid:—

$$\underset{\text{Aldehyd.}}{2C_2H_4O} + \underset{\text{Oxygen.}}{O_2} = \underset{\text{Acetic acid.}}{2C_2H_4O_2}$$

Tests.—Aldehyd heated with solution of potash gives a brownish-yellow resinous mass of peculiar odor. Its aqueous solution reduces salts of silver, giving a mirror-like coating to the sides of a test-tube.

Spirit of French Wine (*Spiritus Vini Gallici*, B. P. and U. S. P.) or *Brandy* is a colored and flavored variety of alcohol distilled from French wine. Its color is that of light sherry, and is derived from the cask in which it has been kept, but is commonly deepened by the addition of burnt sugar. Its taste is due to the volatile flavoring constituent of the wine, often increased by the addition of artificial essences. It should contain from 48 to 56 per cent. of alcohol.

QUESTIONS AND EXERCISES.

753. Write a few sentences on the formation, purification, and concentration of alcohol, and explain the difference between Rectified Spirit, Proof Spirit, and Absolute Alcohol.

754. What quantity of water must be added to one gallon of spirit of wine, 56 degrees over proof, to convert it into proof spirit.

755. To what volume must 5 pints of spirit of wine of 53 degrees be diluted before it becomes proof spirit?—*Ans.* 7 pints, 13 ounces.

756. State the specific gravity of proof spirit.

757. Show how the formula of alcohol is obtained from its centesimal composition :—

Carbon	52.174
Hydrogen	13.043
Oxygen	34.783
	100.000

758. Give the formulæ of some of the salts of ethyl.

759. By what processes may pure hydrate of ethyl be obtained?

760. Enumerate the characters of alcohol.

761. Mention a chemical test to distinguish rectified spirit from absolute alcohol.

762. From the formula of aldehyd calculate back its composition in 100 parts.

763. What is the relation of aldehyd to alcohol and to acetic acid?

764. Whence is brandy obtained, and to what are due its color and flavor?

ETHER.

Formula $C_4H_{10}O$, or $(C_2H_5)_2O$, or Et_2O.

Experimental Process.—Into a capacious test-tube put a small quantity of spirit of wine and about half its bulk of sulphuric acid, mix, and gently warm; the vapor of ether, recognized by its odor, is evolved. Adapt a cork

and long bent tube to the test-tube and slowly distil over the ether into another test-tube. Half the original quantity of alcohol now placed in the generating-tube will again give ether; and this operation may be repeated many times.

On the large scale, and according to the following official process (*Æther*, B. P. and U. S. P.), the addition of alcohol, instead of being intermitting, is continuous, a tube conveying alcohol from a reservoir into the generating-vessel. Mix 10 fluidounces of sulphuric acid with 12 fluidounces of rectified spirit in a glass flask capable of containing at least two pints, and, not allowing the mixture to cool, connect the flask by means of a bent glass tube with a Liebig's condenser, and distil with a heat sufficient to maintain the liquid in brisk ebullition. If a thermometer be used the temperature may be still more carefully regulated—between 284° and 290° F. As soon as the ethereal fluid begins to pass over, supply fresh spirit in a continuous stream, and in such quantity as to about equal the volume of the fluid which distils. For this purpose use a tube furnished with a stopcock to regulate the supply, connecting one end of the tube with a vessel containing the spirit supported above the level of the flask, and passing the other end through the cork of the flask into the liquid. When a total of 50 fluidounces of spirit has been added, and 42 fluidounces of ether have distilled over, the process may be stopped.

To *partially purify* the liquid, dissolve 10 ounces of chloride of calcium in 13 ounces of water, add half an ounce of lime, and agitate the mixture in a bottle with the impure ether. Leave the mixture at rest for ten minutes, pour off the light supernatant fluid, and distil it with a gentle heat until a glass bead of specific gravity 0.735 placed in the receiver begins to float. The ether and spirit retained by the chloride of calcium and by the residue of each rectification may be recovered by distillation and used in a subsequent operation.

Explanation of Process.—On the addition of sulphuric acid to alcohol in equal volumes, one molecule of each react and give a molecule of sulphethylic acid and one of water :—

$$\underset{\text{Alcohol.}}{EtHO} + \underset{\substack{\text{Sulphuric}\\\text{acid.}}}{H_2SO_4} = \underset{\substack{\text{Sulphethylic}\\\text{acid.}}}{EtHSO_4} + \underset{\text{Water.}}{H_2O}$$

More alcohol then gives ether and sulphuric acid by the reaction of one molecule of the alcohol on one of sulphethylic acid :—

$$\underset{\text{Alcohol.}}{EtHO} + \underset{\substack{\text{Sulphethylic}\\\text{acid.}}}{EtHSO_4} = \underset{\text{Ether.}}{Et_2O} + \underset{\substack{\text{Sulphuric}\\\text{acid.}}}{H_2SO_4}$$

The water of the first reaction and the ether of the second distil over, while the sulphuric acid, as fast as liberated, is attacked by alcohol and reconverted into sulphethylic acid :—

$$\underset{\text{Alcohol.}}{EtHO} + \underset{\substack{\text{Sulphuric}\\\text{acid.}}}{H_2SO_4} = \underset{\substack{\text{Sulphethylic}\\\text{acid.}}}{EtHSO_4} = \underset{\text{Water.}}{H_2O}$$

so that the sulphuric acid originally employed finally remains in the retort in the form of sulphethylic acid. The effect, however, of a small quantity of sulphuric acid in thus converting a large quantity of alcohol into ether is limited, secondary reactions occurring to some extent after a time.

Properties.—Pure ether is gaseous at temperatures above 95° F.; hence the condensing-tubes employed in its distillation must be kept as cool as possible. At all ordinary temperatures it rapidly evaporates, absorbing much heat from the surface on which it is placed. A few drops evaporated consecutively from the back of the hand produce great cold; if blown in the form of spray, the cooling effect is so rapid and intense as to produce local anæsthesia. Its vapor is very heavy, more than twice and one-half that of air and nearly forty times that of hydrogen ($H_2=2$; $C_4H_{10}=74$; or as one to 37). In a still atmosphere therefore it will flow a considerable distance along a table or floor before complete diffusion occurs; the vapor is also highly inflammable; hence the importance of keeping candle and other flames at a distance during manipulations with ether.

Purification.—To imitate the process of partial purification above described, add to the small quantity of ether obtained in the foregoing operation a strong solution of chloride of calcium and a little slaked lime; the latter absorbs any sulphurous acid that may have been produced by secondary decompositions, while the former absorbs water; on shaking the mixture and then setting aside for a minute or two, the ether will be found floating on the surface of the solution of chloride of calcium.

This ether, redistilled until the distillate has a sp. gr. not higher than 0.735 (0.750, U. S. P.) and boiling-point not higher than 105° F., is the ether of the British Pharmacopœia. It still contains about 8 per cent. of alcohol. The latter may be removed by well shaking the ether with half of its bulk of water, setting aside, separating the floating ether and again shaking it with water; alcohol is thus washed out. This washed ether containing water (for water and ether are to some extent soluble the one in the other; 50 measures agitated with an equal volume of water are reduced to 45 by an absorption of 10 per cent.) is next placed in a retort with solid chloride of calcium and a little caustic lime, and once more distilled; pure dry ether (*Æther Purus*, B. P., *Æther Fortior*, U. S. P.) results. Sp. gr. not exceeding 0.720 (0.728, U. S. P.).

Spiritus Ætheris, B. P., is a mixture of common ether (*Æther*, B. P.) with twice its bulk of rectified spirit.

NITROUS ETHER, OR NITRITE OF ETHYL.

Formula $EtNO_2$.

Process.—To a third of a test-tubeful of rectified spirit add about a tenth of its bulk of sulphuric acid, rather more

of nitric acid, and some copper-wire or turnings, and warm the mixture as soon as ebullition commences, the vapor of nitrous ether is evolved, recognized by its odor. A long bent tube, kept cool, may be adapted by a perforated cork to the test-tube, and thus a few drops of impure nitrous ether be condensed and collected.

The above process conducted on a larger scale, with definite quantities of materials, temperature regulated by a thermometer, and a well-cooled condenser, is the official (Redwood's) process for the preparation of a concentrated solution of nitrous ether in spirit; diluted with nearly three times its bulk of rectified spirit it forms the "sweet spirit of nitre" (*Spiritus Ætheris Nitrosi*, B. P. and U. S. P.) of pharmacy.

"Take of

Nitric Acid.	3 fluidounces,
Sulphuric Acid	2 fluidounces,
Copper, in fine wire (about No. 25)	2 ounces,
Rectified Spirit	a sufficiency.

"To one pint of the spirit add gradually the sulphuric acid, stirring them together; then add, in the same way, two and a half ounces of the nitric acid. Put the mixture into a retort or other suitable apparatus, into which the copper has been introduced, and to which a thermometer is fitted. Attach now an efficient condenser, and, applying a gentle heat, let the spirit distil at a temperature commencing at 170° and rising to 175°, but not exceeding 180°, until 12 fluidounces have passed over and been collected in a bottle kept cool, if necessary, with ice-cold water; then withdraw the heat, and, having allowed the contents of the retort to cool, introduce the remaining half ounce of nitric acid, and resume the distillation as before, until the distilled product has been increased to 15 fluidounces. Mix this with two pints of the rectified spirit, or as much as will make the product correspond to the tests of specific gravity and percentage of liquid separated by chloride of calcium (*vide infra*). Preserve it in well-closed vessels.

Disregarding secondary products (including much aldehyd), the following equation probably represents decompositions that occur in the operation. The main point in the reaction is the reduction of the nitric to the nitrous radical by the indirect agency of the copper.

$$\underset{\text{Alcohol.}}{EtHO} + \underset{\text{Nitric acid.}}{HNO_3} + \underset{\text{Sulphuric acid.}}{H_2SO_4} + \underset{\text{Copper.}}{Cu} = \underset{\text{Nitrous ether.}}{EtNO_2} + \underset{\text{Water.}}{2H_2O} + \underset{\text{Sulphate of copper.}}{CuSO_4}$$

Properties.—Spirit of Nitrous Ether "is transparent and nearly colorless, with a very slight tinge of yellow, mobile, inflammable, of a peculiar penetrating apple-like odor, and sweetish, cooling, sharp taste. Specific gravity, 0.845. It effervesces feebly, or not at all, when shaken with a little bicarbonate of soda" (showing absence of appreciable quantities of free nitrous, acetic, or other acids). The aldehyd in it may be detected by the potash test (see page 376).

Test.—The nitrous radical may be detected by adding sulphate of

iron and sulphuric acid to some of the spirit of nitrous ether, a brown or black compound being produced, already explained in connection with nitric acid (p. 256).

Test of Strength.—To some of the official Spirit of Nitrous Ether add twice its bulk of a saturated solution of chloride of calcium and mix the liquids; on setting aside, nitrous ether will rise to the surface. If the spirit of nitrous ether be of official strength, not less than 2 per cent. of its volume will thus separate, indicating the presence of 10 per cent. of the ether, 8 per cent. being said to be still in solution. A graduated tube is obviously most convenient for this purpose.

Spiritus Ætheris Nitrosi, U. S. P., has the specific gravity 0.837, and contains five per cent. of nitrous ether.

Iodide of Ethyl (EtI) may be prepared by mixing amorphous phosphorus with *absolute* alcohol and then adding iodine.

$$\underset{\text{Alcohol.}}{5EtHO} + \underset{\substack{\text{Iodide of}\\\text{phosphorus.}}}{PI_5} = \underset{\substack{\text{Iodide of}\\\text{ethyl.}}}{5EtI} + \underset{\substack{\text{Phosphoric}\\\text{acid.}}}{H_3PO_4} + \underset{\text{Water.}}{H_2O}$$

The reaction at first proceeds rapidly, and is complete after the mixture has been set aside for a few hours. The iodide of ethyl may then be isolated by careful distillation, freed from any excess of iodine by washing with a very small quantity of solution of potash or soda, washed with water, dried over chloride of calcium, and again distilled. It should be kept in a dark place, as light favors decomposition and liberation of iodine.

Ethyl.—This gaseous radical, $(C_2H_5)_2$ or Et_2, is obtained on digesting together at about 250° F., in a strong sealed tube, dry freshly granulated zinc with iodide of ethyl (Frankland).

$$\underset{\text{Zinc.}}{Zn} + \underset{\substack{\text{Iodide of}\\\text{ethyl.}}}{2EtI} = \underset{\substack{\text{Iodide of}\\\text{zinc.}}}{ZnI_2} + \underset{\text{Ethyl.}}{Et_2}$$

On cautiously opening the tube the ethyl escapes, and may be ignited or collected over water. There remains with the iodide of zinc a body termed by Frankland *zinc-ethyl* ($ZnEt_2$); it is a spontaneously inflammable liquid, but may easily be distilled and otherwise manipulated if a few simple precautions be observed. If water be allowed to flow down the tube, the solid compound of iodide of zinc and zinc-ethyl will be decomposed, a gas, *hydride of ethyl*

(EtH), resulting, which also may be inflamed or collected over water:—

$$ZnEt_2 + 2H_2O = Zn2HO + 2EtH.$$

QUESTIONS AND EXERCISES.

765. Describe the official process for the preparation of Ether, giving equations.

766. Offer a physical explanation of the mode of producing local anæsthesia.

767. How is commercial ether purified?

768. Explain Redwood's process for the preparation of "sweet spirit of nitre."

769. Give the properties of spirit of nitrous ether.

770. By what method is the strength of "sweet spirit of nitre" estimated?

771. How is iodide of ethyl made?

772. Adduce evidence of the existence of ethyl.

OTHER ALCOHOL RADICALS AND THEIR SALTS.

What has been stated concerning the chemistry of ethyl and its compounds may be applied to other radicals known to exist, some of the compounds of each of which are of common occurrence. These basylous radicals are closely related to each other, to hydrogen, and to the metals. Starting from hydrogen, their formulæ may be built up by successive additions of CH_2, thus:—

Hydrogen	H	
Methyl	CH_3,	or Me
Ethyl	C_2H_5,	or Et
Propyl (or Trityl)	C_3H_7,	or Pr
Butyl (or Tetryl)	C_4H_9,	or Bu
Amyl	C_5H_{11},	or Ay
Caproyl (or Hexyl)	C_6H_{13},	or Cp

The above list is an illustration of an *homologous* series (from ὁμός, *homos*, the same, and λόγος, *logos*, description) of compounds. It will be observed that the relation of the number of hydrogen atoms to carbon is twice as many with one added; hence the series is often termed the C_nH_{2n+1} series (n = any number). The oxides of these radicals are known as *ethers*, their hydrates *alcohols*, their compounds with the acetic and similar acidulous radicals *ethereal salts*. Every alcohol furnishes a body corresponding to the aldehyd of spirit of wine, the class being termed *aldehyds;* each also yields an acid cor-

responding with acetic acid. Any one of these classes constitutes an homologous series. Or, taking the hydride, oxide, hydrate, acid, of any single radical, we get a *heterologous* (ἕτερος, *heteros*, another) series of compounds. Hydride of methyl (MeH or CH_3H) is ordinary *marsh-gas*, *fire-damp*, or *light carburetted hydrogen;* it is a diluent or non-luminiferous constituent of ordinary coal-gas to the extent of 30 to 40 per cent.;* *formic acid*, the acid of the methyl series; *butyric acid*, the acid of the butyl series; *sulphocyanate of butyl*, the essential oil of horseradish; *valerianic acid*, the acid of the amyl series.

Homologous and Heterologous Series of the C_nH_{2n+1} *Radicals.*

Radicals.	Hydrides.	Oxides (or ethers).	Hydrates (or alcohols).	Aldehyds.	Acids.
$(CH_3)_2$	CH_3H	$(CH_3)_2O$	CH_3HO	CH_2O?	CH_3O_2
$(C_2H_5)_2$	C_2H_5H	$(C_2H_5)_2O$	C_2H_5HO	C_2H_4O	$C_2H_4O_2$
$(C_3H_7)_2$	C_3H_7H	$(C_3H_7)_2O$	C_3H_7HO	C_3H_6O	$C_3H_6O_2$
$(C_4H_9)_2$	C_4H_9H	$(C_4H_9)_2O$	C_4H_9HO	C_4H_8O	$C_4H_8O_2$
$(C_5H_{11})_2$	$C_5H_{11}H$	$(C_5H_{11})_2O$	$C_5H_{11}HO$	$C_5H_{10}O$	$C_5H_{10}O_2$
etc.	etc.	etc.	etc.	etc.	etc.

QUESTIONS AND EXERCISES.

773. Mention several radicals homologous with ethyl, and give their formulæ.

774. Define ethers, hydrides, alcohols, ethereal salts, aldehyds.

775. What is the difference between homologous and heterologous series?

776. Give the systematic name of *fire-damp*.

777. Enumerate the chief constituents of coal-gas.

778. State the formulæ of formic, butyric, and valerianic acids.

779. Write the formulæ of butyl, its hydride, ether, alcohol, aldehyd, and acid.

* *Coal-gas.*—The other diluents, or vehicles for the illuminating constituents, of coal-gas are hydrogen (40 to 50 per cent.) and carbonic oxide (6 to 7 per cent). The illuminating constituents are olefiant gas (p. 394) and its homologues, existing to the extent of from 5 to 7 per cent. The impurities are nitrogen, air, carbonic acid, bisulphide of carbon CS_2 (a volatile liquid easily made from its elements), and other badly smelling sulphur compounds. Upwards of fifty distinct chemical substances have been obtained from the solid, liquid, and gaseous products of the destructive distillation of coal.

MYTHYLIC ALCOHOL.

Methylic Alcohol (CH_3HO, or MeHO), Wood-Spirit, or Pyroxylic Spirit, or Wood-Naphtha, is a product of the destructive distillation of wood. Spirit of wine containing 10 per cent. of wood-spirit constitutes ordinary *methylated spirit*, a spirit issued duty free, for the use of manufacturers, the methylic alcohol not interfering with technical applications. From its nauseous taste and odor, however, it cannot take the place of gin, brandy, or other spirit; hence, while industry is benefited, intemperance is discouraged and the revenue not injured.

Detection of Methylic Alcohol in presence of Ethylic Alcohol.—Three or four methods have been proposed for the detection of methylated spirit in various liquids; that open to least objection is by J. T. Miller. For the application of the test to tinctures and similar spirituous mixtures, some of the spirit is first separated by distilling off a drachm or so from about half an ounce of the liquid placed in a small flask or test-tube having a long bent tube attached. Into a similar apparatus put 30 grains of powdered red chromate of potassium, half an ounce of water, 25 minims of strong sulphuric acid, and 30 or 40 minims of the spirit to be tested. Set the mixture aside for a quarter of an hour, and then distil nearly half a fluidounce. Place the distillate in a small dish, add a very slight excess of carbonate of sodium, boil down to about a quarter of an ounce, add enough acetic acid to impart a distinct but feeble acid reaction, pour the liquid into a test-tube, add a grain of nitrate of silver dissolved in about 30 drops of water, and heat gently for a couple of minutes. If the liquid then merely darkens a little, but continues quite translucent, the spirit is free from methylic alcohol; but if a copious precipitate of dark-brown or black metallic silver separates, and the tube, after being rinsed out and filled with clean water, has a distinct film of silver, which appears brown by transmitted light (best seen by holding it against white paper), the spirit is methylated.

Explanation.—This test depends for its action on the reducing-powers of formic acid. In the above operation the ethylic alcohol becomes oxidized to acetic acid (the natural acid of the ethyl series), which does not reduce silver salts, a minute quantity only of formic acid being produced, while the methylic alcohol yields formic acid (the natural acid of the methyl series) in a comparatively large quantity. Aldehyd, which is also a reducing agent, is simultaneously produced, but removed in the subsequent ebullition with carbonate of sodium.

Methylated Sweet Spirit of Nitre.—The preparation of spirit of nitrous ether from methylated spirit is illegal in Great Britain, but, nevertheless, occasionally practised. For the detection of methylic alcohol in this liquid, Mr. Miller suggests the following modification of the above process.

Shake about an ounce of the sample with 20 or 30 grains of anhydrous carbonate of potassium, and, if needful, add fresh portions of the salt until it ceases to be dissolved, then pour off the supernatant spirit. This serves to neutralize acid and to remove water, in which some samples are remarkably rich. Introduce half a fluidounce of the spirit into a small flask; add 150 grains of anhydrous chloride of calcium in powder, and stir well together; then, having connected the flask with a condenser, place it in a bath of boiling water, and distil a fluidrachm and a half, or continue the distillation until scarcely anything more comes over. The operation is rather slow, but needs little attention, and should be done thoroughly. The distillate contains nearly the whole of the nitrous ether and other interfering substances. Now add to the contents of the flask a fluidrachm of water, and draw over the half drachm of spirit required for testing. Add to it the usual oxidizing solution composed of 30 grains of red chromate of potassium, 25 minims of strong sulphuric acid, and half an ounce of water; let the mixture stand a quarter of an hour, then distil half a fluidounce. Treat the distillate with a slight excess of carbonate of sodium, boil rapidly down to two fluidrachms, and drop in, cautiously, enough acetic acid to impart a faint acid reaction; pour the liquid into a test-tube about three-quarters of an inch in diameter; add two drops of *diluted* acetic acid, and one grain of nitrate of silver in half a drachm of pure water; apply heat, and boil gently for two minutes. If the spirit is free from methylic alcohol the solution darkens and often assumes transiently a purplish tinge, but continues quite translucent, and the test-tube, after being rinsed out and filled with water, appears clean or nearly so. But if the spirit contains only 1 per cent. of methylic alcohol the liquid turns first brown, then almost black and opaque, and a film of silver, which is brown by transmitted light, is deposited on the tube. When the sample is methylated to the extent of 3 or 4 per cent., the film is sufficiently thick to form a brilliant mirror. To insure accuracy, the experiments should be performed by daylight.

CHLOROFORM.

Formula $CHCl_3$.

Process.—Should the necessary appliances be at hand, a small quantity of this liquid may easily be prepared by the official process. One fluidounce and a half of spirit and 24 of water are placed in a retort or flask of at least a quart capacity; 8 oz. of chlorinated lime and 4 of slaked lime are added, the vessel connected with a condenser, and the mixture heated until distillation commences, the source of heat then being withdrawn. The condensed liquid should fall into a small flask containing water, at the bottom of which about a drachm of chloroform will slowly collect.

Explanation of Process.—The hypochlorite of calcium (Ca2ClO) believed to be present in the chlorinated lime (see remarks in connection with hypochlorous acid) readily yields up oxygen and chlorine to organic substances, the calcium being liberated as hydrate, $4(Ca2ClO) + 4H_2O = 4(Ca2HO) + 2O_2 + 4Cl_2$. The alcohol used in making chloroform is thus reduced first to aldehyd:—

$$\underset{\text{Alcohol.}}{2C_2H_6O} + \underset{\text{Oxygen.}}{O_2} = \underset{\text{Aldehyd.}}{2C_2H_4O} + \underset{\text{Water.}}{2H_2O}$$

The action of chlorine on aldehyd then probably gives chloral (*chlor-al*dehyd):—

$$\underset{\text{Aldehyd.}}{C_2H_4O} + \underset{\text{Chlorine.}}{3Cl_2} = \underset{\text{Chloral.}}{C_2HCl_3O} + \underset{\text{Hydrochl. acid.}}{3HCl}$$

The hydrochloric acid being at once neutralized by some of the liberated hydrate of calcium to form chloride of calcium and water, more freed hydrate of calcium and chloral give formate of calcium and chloroform.

$$\underset{\text{Chloral.}}{2C_2HCl_3O} + \underset{\text{Hydrate of calcium.}}{Ca2HO} = \underset{\text{Formate of calcium.}}{Ca2CHO_2} + \underset{\text{Chloroform.}}{2CHCl_3}$$

Or, neglecting the probable steps in the process, and regarding only the materials and the products, 4 molecules of alcohol and 8 of hypochlorite of calcium give 2 of chloroform, 3 of formate of calcium, 5 of chloride of calcium, and 8 of water, thus:—

$$\underset{\text{Alcohol.}}{4C_2H_6O} + \underset{\text{Hypochlorite of calcium.}}{8CaCl_2O_2} = \underset{\text{Chloroform.}}{2CHCl_3} + \underset{\text{Formate of calcium.}}{3(Ca2CHO_2)} + \underset{\text{Chloride of calcium.}}{5CaCl_2} + \underset{\text{Water.}}{8H_2O}$$

The hydrate of calcium placed in the generating-vessels is not essential, but is useful in preventing secondary decompositions, the hydrate of calcium obtainable from the reaction being insufficient for this purpose.

Constitution.—Chloroform is sometimes considered to be the chlo-

ride of a trivalent radical methenyl (CH), the first member of a series C_nH_{2n-1}. Glycerine is the hydrate of another member—*glyceryl* or *propenyl*, C_3H_5 (p. 394).

Chloroform may also be regarded as the chloride of dichlor-methyl; it may be formed from methylic compounds, thus:—

$$\underset{\text{Methylic alcohol.}}{2CH_4O} + 2(\underset{\text{Chlorinated lime.}}{CaCl_2,CaCl_2O_2}) = \underset{\text{Chloroform.}}{2CHCl_3} + \underset{\text{Oxychloride of calcium.}}{CaCl_2,3CaO} + \underset{\text{Water.}}{3H_2O}$$

Chlorine converts it into tetrachloride of carbon, completing a series of *substitution products* of chloride of methyl.

$$C\left\{\begin{matrix}H\\H\\H\end{matrix}\right\}Cl \qquad C\left\{\begin{matrix}H\\H\\Cl\end{matrix}\right\}Cl \qquad C\left\{\begin{matrix}H\\Cl\\Cl\end{matrix}\right\}Cl \qquad C\left\{\begin{matrix}Cl\\Cl\\Cl\end{matrix}\right\}Cl \text{ or } CCl_4$$

Chloride of methyl. | Chloride of mono-chlor-methyl. | Chloride of di-chlor-methyl. | Chloride of tri-chlor- or methyl | Tetrachloride of carbon.

The chloride of mono-chlor-methyl, under the name of dichloride of methylene, has been used as an anæsthetic. It may be obtained by the action of nascent hydrogen on chloroform.

Chloroform is purified by shaking it with pure sulphuric acid containing no trace of nitric acid, which chars and removes hydrocarbons, but does not affect chloroform. It is freed from any trace of acid by agitation with carbonate of sodium and from moisture by distillation with lime.

Properties.—The sp. gr. of purified chloroform is 1.497 (1.480 U. S. P.). It readily and entirely volatilizes with characteristic odor at common temperatures. It has a sweetish taste, is limpid, colorless, soluble in alcohol and ether, and slightly in water, but burns with a sluggish green smoky flame.

Iodoform (*Iodoformum*, U. S. P.) analogous in constitution to chloroform, the iodine taking the place of the chlorine (CHI_3), is prepared by mixing in a retort 2 parts of carbonate of potassium, 2 parts of iodine, 1 part of alcohol, and 5 of water, heating till colorless, and then pouring into a beaker and allowing to settle. The Iodoform is deposited in yellow scales, which are collected on a filter, washed thoroughly with water and dried between filtering paper.

Iodoform appears in the shape of yellow, shining six-sided scales with a saffron-like odor; is volatile at ordinary temperatures, and at a temperature above 250° is decomposed, giving off violet vapors. Almost insoluble in water, but more so in alcohol, ether, and the fixed and volatile oils.

CHLORAL AND CHLORAL HYDRATE.

Process.—Pass a rapid stream of dry chlorine into pure absolute alcohol so long as absorption occurs. During the first hour or two the alcohol must be kept cool, afterwards gradually warmed till ultimately the boiling-point is reached. The preparation of a considerable quantity occupies several days. The crude product is mixed with three times its volume of oil of vitriol and distilled, again mixed

with a similar quantity of oil of vitriol and again distilled, and finally rectified from quicklime.

The formation of chloral would at first sight seem to be due to the production from the alcohol (C_2H_6O) of aldehyd (C_2H_4O), through the removal of hydrogen by the chlorine, and the substitution of chlorine for hydrogen in the aldehyd (C_2H_4O) with formation of chlor-aldehyd or chloral (C_2HCl_3O). But the reactions are far more complicated, being somewhat as follows. Aldehyd and hydrochloric acid are first formed; these with some of the alcohol give monochlorinated ether, $\left.\begin{matrix}C_2H_5\\C_2H_4Cl\end{matrix}\right\}O$, which with more chlorine yields tetrachlorinated ether, $\left.\begin{matrix}C_2H_5\\C_2HCl_4\end{matrix}\right\}O_2$, and this in presence of water furnishes chloral, some alcohol, and some hydrochloric acid (Würtz and Vogt).

Properties.—The formula of chloral is C_2HCl_3O. It is a colorless liquid, of oily consistence. Sp. gr. 1.502. Boiling-point 201.2. Its vapor has a penetrating smell, and is somewhat irritating to the eyes. Mixed with water heat is disengaged, and solid white, crystallizable, *hydrous chloral* (*Chloral*, U. S. P.), or what is more generally, though somewhat irregularly, termed *chloral hydrate* (C_2HCl_3O, H_2O) results. The latter fuses at 110.8 and boils at 293° F. It sublimes as a white crystalline powder. Both chloral and chloral hydrate are soluble in water, alcohol, ether, and oils. The aqueous solution should be neutral, and give no reaction with nitrate of silver. Chloral is said sometimes to undergo a spontaneous change into an opaque white isomeric modification, insoluble in water, alcohol, or ether, but convertible by prolonged contact with water or by distillation into the ordinary condition. By action of weak alkalies chloral first yields formiate of the alkali-metal and chloroform:—

$$C_2HCl_3O + KHO = KCHO_2 + CHCl_3.$$

Chloral, or rather strong aqueous solution of chloral hydrate (3 in 4), injected beneath the skin yields nascent chloroform by action of the alkali of the blood, and produces narcotic effects (Liebreich, Personne). Chloroform itself admits of similar hypodermic use (Richardson). If administered by the stomach, thirty to eighty grains of solid hydrate are required. The final products of the reaction of the chloroform and blood are formiate and chloride of sodium. A spirituous solution of potash effects the same transformation.

$$CHCl_3 + 4KHO = KCHO_2 + 3KCl + 2H_2O$$

Solution of ammonia and moist hydrate of calcium, as well as weak solutions of fixed alkalies, convert hydrate of chloral into formiate of the metal and chloroform. The reaction with the slaked lime being especially definite and complete (Wood), it may be employed in ascertaining the richness of a sample of commercial chloral hydrate in chemically pure chloral hydrate.

$$\underbrace{2(C_2HCl_3O,H_2O)}_{331} + Ca2HO = \underbrace{2CHCl_3}_{239} + Ca2CHO_2 + 2H_2O.$$

From the foregoing equation and molecular weights it is obvious that 100 grains of hydrate of chloral, if quite dry, will yield by distillation with lime and a little water (in a small flask and long bent tube kept cool by moistened paper) 72.2 grains of chloroform, by weight, or (the sp. gr. of chloroform being taken at 1.497) 47.56 grains by measure, or about 52 minims.

Pure Chloral Hydrate.—Liebreich, who first proposed the use of chloral hydrate, gives the following as the characteristics of a pure article: Colorless, transparent. Does not decompose by the action of the atmosphere, does not leave oily spots when pressed between blotting-paper, affects neither cork nor paper. Smells agreeably aromatic, but a little pungent when heated. Taste bitter astringent, slightly caustic. Seems to melt on rubbing between the fingers. Dissolves in water like candy without first forming oily drops. Dissolves in bisulphide of carbon, petroleum, ether, water, alcohol, oil of turpentine, etc. Boiling-point 203° to 205° F. Distilled with sulphuric acid, the chloral should pass over at 205° to 207° F. Melting-point 133° to 136° F. Gives no chlorine reaction on treating the solution in water (acidulated by nitric acid) with nitrate of silver.

Impure Chloral Hydrate.—Yellowish, cloudy. Decomposes; leaves spots by pressing between blotting-paper; decomposes corks and paper of the packing. Smells pungent and irritating; on opening the bottles sticky and often emits fumes. Taste strongly caustic. With water forms oily drops or is partially insoluble. Boils at a higher temperature. On treating it with sulphuric acid turns brown, with formation of hydrochloric acid. Gives chlorine reaction on treating the solution in water (acidulated by nitric acid) with nitrate of silver.

Alcoholates of chloral are obtained on combining alcohols with chloral.

Bromal (C_2HBr_3O), *hydrate of bromal* (C_2HBr_3O, H_2O), and *alcoholates of bromal* are produced when bromine instead of chlorine attacks alcohol.

AMYLIC ALCOHOL.

Amylic Alcohol (*Alcohol Amylicum*, B. P. and U. S. P.) ($C_5H_{11}HO$, or AyHO) is a constant accompaniment of ethylic or common alcohol (C_2H_5HO, or EtHO) when the latter is prepared from sugar which has been derived from starch; hence the name, from *amylum* starch. The sugar of potato-starch yields a considerable quantity; hence the alcohol is often called *potato-oil*. It is also termed *fousel-oil*, or *fusel-oil* (from φύω, *phuō*, to produce), in allusion to the circumstance that the supposed oil is not simply educed from a substance already containing it, as is usually the case with oils, but is actually produced during the operation. It was described as oil probably because it resembled oil in not readily mixing with water; but it is soluble to some extent in water, and is a true spirit, homologous with spirit of wine. It often contains variable proportions of propylic, butylic, and caproylic alcohols. See also Valerianic Acid.

Amylic alcohol is "a colorless liquid with a penetrating and oppressive odor, and a burning taste. When pure its specific gravity is 0.818; boiling-point 279°. Sparingly soluble in water, but soluble in all proportions in alcohol, ether, and essential oils. Exposed to the air in contact with platinum-black, it is slowly oxidized, yielding valerianic acid." Two allotropic varieties of amylic alcohol exist, one dextro-rotating a polarized ray.

Acetate of Amyl ($C_5H_{11}C_2H_3O_2$, or $Ay\overline{A}$). To a small quantity of amylic alcohol in a test-tube add some acetate of potassium and a little sulphuric acid, and warm the mixture; the vapor of acetate of amyl is evolved, recognized by its odor, which is that of the jargonelle pear. If a condensing-tube be attached, the essence may be distilled over, washed by agitation with water to free it from alcohol, and separated by a pipette.

$$\underset{\text{Acetate of potassium.}}{K\overline{A}} + \underset{\text{Amylic alcohol.}}{AyHO} + \underset{\text{Sulphuric acid.}}{H_2SO_4} = \underset{\text{Acetate of amyl.}}{Ay\overline{A}} + \underset{\text{Acid sulphate of potassium.}}{KHSO_4} + \underset{\text{Water.}}{H_2O}$$

Fruit-Essences.

Acetate of amyl, prepared with the proper equivalent proportions of constituents as indicated by the above equation, is largely manufactured for use as a flavoring agent by confectioners. Valerianate of amyl ($C_5H_{11}C_5H_9O_2$) is similarly used under the name of apple-oil. Butyrate of ethyl ($C_2H_5C_4H_7O_2$) closely resembles the odor and

flavor of the pine-apple; œnanthylate of ethyl ($C_2H_5C_7H_{13}O_2$) recalls green-gage; pelargonate of ethyl ($C_2H_5C_9H_{17}O_2$) quince; suberate of ethyl ($Et_2C_8H_{12}O_4$) mulberry; sebacate of ethyl ($Et_2C_{10}H_{16}O_4$) melon. Hydride of salicyl ($C_7H_5O_2H$), or salicylous acid, is the essential oil of meadow-sweet (*Spiræa ulmaria*), and may be prepared artificially by the oxidation of salicin (*vide* p. 370). Salicylate of methyl ($CH_3C_7H_5O_3$), or gaultheric acid (*Oleum gaultheriæ*, U. S. P.), is the essential oil of winter-green (*Gaultheria procumbens*), and may also be prepared artificially from salicin. By mixing these ethereal salts with each other and with essential oils in various proportions, the odor and flavor of nearly every fruit may be fairly imitated.

Nitrite of Amyl ($C_5H_{11}NO_2$).—For the preparation of this substance Maisch recommends a modification of Balard's process. Amylic alcohol is first rectified until pure; that is until its boiling-point is about 270° F. This alcohol, with about an equal bulk of nitric acid, is introduced into a capacious glass retort, and a moderate heat is applied and very gradually increased. As soon as the mixture approaches boiling, the fire is removed, and the reaction allowed to continue. If the application of the heat has been too rapid or too long continued, considerable frothing occurs, and the contents of the retort are apt to foam over. With a moderate and slowly increased heat, the reaction is less violent and the temperature rises gradually after the removal of the fire and the beginning of boiling. As soon as the thermometer, inserted in the tubulus, rises above 212° F., the receiver is changed, the distillate now becoming more and more mixed with ethyl-amylic ether and nitrate of amyl, readily perceived by the change in odor.

The distillate obtained below 212° F. is agitated with an aqueous solution of caustic or carbonate of potassium to remove free acids, and, after separation, the oily liquid is introduced into a clean retort and again slowly heated. The first portion coming over contains amylic aldehyd. When the very slowly increased heat has risen to 205° F., the receiver is again changed and the distillate now collected as nitrite of amyl, until the thermometer reaches 212° F., when the distillation is stopped.

QUESTIONS AND EXERCISES.

780. Name the source of methylic alcohol.

781. What is "methylated spirit?"

782. Describe the method by which methylated spirit is detected in a tincture.

783. In what relation does formic acid stand to methylic alcohol?

784. How would you proceed to ascertain whether or not a specimen of sweet spirit of nitre had been made from methylated spirit?

785. Give details of the production of chloroform from alcohol, tracing the various steps by equations.

786. Is chloroform an ethylic compound? What is its probable constitution?

787. How is chloroform purified?

788. State the character of pure chloroform.

789. Describe the reactions that occur in the manufacture of chloral and chloral hydrate.

790. What is the nature of the action of alkalies on chloral hydrate?

791. Mention the characters of pure and impure chloral hydrate.

792. Whence is amylic alcohol obtained?

793. Has valerianic acid any chemical relation to amylic alcohol?

794. Mention the systematic names of several artificial fruit-essences.

795. What is the formula of nitrite of amyl, and how is it prepared?

SALTS AND DERIVATIVES OF RADICALS OF OTHER SERIES THAN THE C_nH_{2n+1}.

What has been stated regarding radicals having the general formula C_nH_{2n+1} and their salts, may be applied to the radicals of other series.

The series C_nH_{2n-7} includes *phenyl* (C_6H_5), the hydride of which (C_6H_5H, or PhH) is common *benzol* (B. P.), a colorless volatile liquid obtained from coal-tar. *Toluol* (C_7H_8), or methyl-benzol, is one of the products of the distillation of balsam of Peru. The next homologue, *xylol* (C_8H_{10}), or dimethyl-benzol, is contained in crude wood-spirit and in coal-naphtha: it is a colorless fluid, having an odor faintly resembling that of benzol; boiling-point 282° F.; sp. gr. .866. Benzol is a powerful solvent of grease, and under the name of *Benzine Collas* was introduced by M. Collas, in 1848, for cleansing stuffs. By the action of strong nitric acid, benzol yields *nitrobenzol* ($C_6H_5(NO_2)$), a liquid termed, from its odor, *artificial oil of bitter almonds*, or *essence of mirbane*. Its specific gravity is 1.20 to 1.29. The odor of this essence, however, is not exactly that of essential oil of almonds, and its composition is very different; so that it is not truly an artificial volatile oil. The natural oil has a sp. gr. of 1.04 to 1.07, and is a hydride of the negative radical benzoyl (C_7H_5OH), a radical derived from the next higher homologue of phenyl by displacement of hydrogen by oxygen. Nitrobenzol yields aniline (*vide infra*), oil of bitter almonds does not (page 366). The hydrate of phenyl (C_6H_5HO), or *phenic alcohol*, or *phenol*, is the *phenic acid* or *carbolic acid* of commerce (*Acidum Carbolicum*, U. S. P.), a colorless crystalline substance, obtained from coal-tar oil by fractional distillation and subsequent purification. At temperatures above 95° F. it is not an oily liquid. It is only slightly soluble in water, *Aqua Acidi Carbolici*, U. S. P., but readily dissolved by alcohol, ether, and glycerine (*Glyceritum Acidi Carbolici*, U. S. P.). In odor, taste, and solubility (and in appearance when liquefied by heat or by the addition of 5 per cent. of water) it resembles

creasote, a wood-tar product for which carbolic acid is often substituted. Beside hydrate of phenyl (C_6H_5HO) coal-tar oil contains *cresol, hydrate of cresyl*, or cresylic acid (C_7H_7HO); while wood-tar oil furnishes *guaiacol* ($C_7H_8O_2$)—also a product of the destructive distillation of guaiacum-resin—and *creasol* ($C_8H_{10}O_2$), or creasote. Certain coloring-matters may be obtained by the oxidation of carbolic acid; ammonia mixed with it, and then a small quantity of solution of a hypochlorite gives a blue liquid; a similar effect is produced on dipping a chip of deal into carbolic acid (or into creasote), then into hydrochloric acid, and afterwards exposing it to the air. By the following tests carbolic acid may be distinguished from creasote. The former boils only at 370°, while the latter readily dries up at 212°. Carbolic acid does not affect a ray of polarized light; creasote twists it to the right. Carbolic acid is either solid or may be solidified by cooling; creasote is not solidified by the cold produced by a mixture of hydrochloric acid and sulphate of sodium. Creasote from coal (impure or crude carbolic acid) gives a jelly when shaken with collodion; creasote from wood (*Creasotum*, B. P. and U. S. P.) is unaffected by collodion (Rust). Coal-creasote is soluble in solution of potash, wood-creasote insoluble. The coal product is soluble in a large volume of water, and a neutral solution of ferric chloride strikes a blue color with the liquid; wood-creasote is less soluble (*Aqua Creasoti*, U. S. P., is said to contain 1 in 129) and not altered by ferric chloride. An alcoholic solution of the coal-oil is colored brown by ferric chloride, a similar solution of true creasote green. According to Mr. Thomas Morson pure creasote is unaffected when mixed with an equal volume of commercial glycerine (it is soluble in pure anhydrous glycerine—Flückiger), while carbolic acid is miscible in all proportions, and will carry into solution even a considerable quantity of creasote. Carbolic acid is a powerful *antiseptic* (ἀντί, *anti*, against, and σήπω, *sepo*, to putrefy). In large doses it is poisonous, the best *antidote* being olive oil and castor oil, freely administered. *Acidum Carbolicum Impurum*, U. S. P., is the impure carbolic acid obtained from coal-tar oil by treating it first with an alkali, and then with an acid, and finally distilling. It is of a brown shade, and if at first colorless it becomes reddish-brown on exposure. It consists of carbolic and cresylic acids in variable proportion together with impurities derived from coal-tar. 100 measures of warm water on being agitated with one measure of the liquid will dissolve out the two acids and should not leave more than 30 per cent. by measure of impurity. Carbolic acid is soluble in oil of vitriol, *sulpho-carbolic acid* ($HC_6H_5SO_4$) or *sulphophenic acid* being formed. On diluting and mixing with oxides, hydrates, or carbonates, *sulphocarbolates* are formed. The formula of *sulphocarbolate of sodium* is $NaC_6H_5SO_4$; *sulphocarbolate of zinc* $Zn(C_6H_5SO_4)_2H_2O$. Trinitro-carbolic acid ($C_6H_3(NO_2)_3O$) is formed on slowly dropping carbolic acid into fuming nitric acid; it is the yellow dye known as *carbazotic acid* or *picric acid;* most of the picrates are explosive by percussion. Both carbolic acid and benzol are secondary products, obtained in the manufacture of coal-gas; hence, indeed, the word *phenic*, and thence *phenyl* (from φαίνω, *phainō*, I light, in allusion to the use of coal-gas). *Aniline*, or

phenylamine, is a product of the action of nascent hydrogen on nitrobenzol.

$$\underset{\text{Nitrobenzol.}}{C_6H_5NO_2} + \underset{\text{Hydrogen.}}{3H_2} = N\left\{\begin{matrix} C_6H_5 \\ H \\ H \end{matrix}\right. + 2H_2O,$$

the substance whence, by oxidation, &c., aniline-red (magenta), -orange, -yellow, -green, -blue, -violet (mauve), and -black are produced.

Aloins.—The aloes of pharmacy (*Aloe Barbadensis*, B. P., and *Aloe Socotrina*, B. P.) is an evaporated juice, doubtless much altered by the temperature to which it is subjected.

Barbaloin, $C_{34}H_{36}O_{14}H_2O$.—This substance, first obtained by T. and H. Smith, occurs in minute crystals in Barbadoes and Socotrine aloes. It is readily procured from the former by dissolving in boiling water acidified with a little hydrochloric acid, after some hours, pouring off the precipitated resin and evaporating the liquid to a syrup. The aloin crystallizes out in a day or two. Barbaloin yields by the action of bromine and chlorine substitution compounds, $C_{34}H_{30}B_{16}O_{14}$ and $C_{34}H_{30}Cl_6O_{14}6H_2O$. Nitric acid dropped upon it produces a red color, which soon fades. Boiled for some time with strong nitric acid barbaloin gives, together with oxalic and picric acids, a yellow substance, chrysammic acid, $C_{14}H_1(NO_2)_4O_4$, which furnishes beautiful red salts.

Nataloin, $C_{25}H_{28}O_{11}$.—This body was discovered by Flückiger in Natal aloes. It crystallizes readily in rectangular plates, either from spirit or from water. No bromine or chlorine substitution derivatives have yet been formed, but an acetyl compound $C_{25}H_{22}(C_2H_3O)_6O_{11}$ (Tilden) has been analyzed. The existence of this compound serves to corroborate the formula given above. Nataloin moistened with nitric acid gives a red coloration which does not fade. When boiled with nitric acid it yields no chrysammic, but only oxalic and picric acids.

The reactions of these two bodies seem to indicate that they are complex phenols. Phenol being the phenyl hydrate, C_6H_5,HO, and cresol being the methyl-phenol, C_6H_4,CH_3,HO, the aloins may possibly have a similar constitution, that is, they may be the hydrates of radicals in which part of the hydrogen is replaced by groups of atoms. Anthracen, $C_{14}H_{10}$, has been obtained by deoxidation of barbaloin.

In the series C_nH_{2n-1}' we have the univalent radical *allyl* (C_3H_5), whose sulphide ($(C_3H_5)_2S$) is *essential oil of garlic* (*Allium*, U. S. P.) and sulphocyanate (C_3H_5CyS) the *essential oil of mustard*. *Mustard* (*sinapis*, B. P. and U. S. P.) is a powdered mixture of black and white mustard-seeds. The white mustard-seed contains *sinalbin* ($C_{30}H_{44}N_2S_2O_{16}$), a glucoside which, in contact with the aqueous extract of mustard, yields some acrid oil. The black contains a ferment resembling the *emulsin* of almonds (p. 366) and *myronate* of potassium. The latter is the body which, under the influence of the former, yields the chief part of the oil.

$$\underset{\text{Myronate of potassium.}}{K_2C_{20}H_{38}N_2S_4O_{19}} = \underset{\text{Acid sulphate of potassium.}}{2(KHSO_3)} + \underset{\text{Oil of Mustard.}}{2C_3H_5CNS} + \underset{\text{Glucose.}}{2C_6H_{12}O_6} + \underset{\text{Water.}}{H_2O}$$

Allyl compounds are also met with in several other cruciferous and liliaceous plants.

In the C_nH_{2n} series occurs *ethylene* or *olefiant gas* (C_2H_4), the chief illuminating constituent of coal-gas (readily made on heating alcohol with twice its volume of strong sulphuric acid), a bivalent radical, the alcohol of which is *glycol* ($C_2H_4 2HO$). *Etherol*, or *Ethereal Oil* (*Oleum Ethereum*, U. S. P.), or *light oil of wine* ($C_{16}H_{32}$?), a hydrocarbon polymeric with olefiant gas, is one of the products of the action of excess of sulphuric acid on alcohol: its sp. gr. is 0.917. In the C_nH_{2n-1}''' the trivalent hypothetical radical *glyceryl* (C_3H_5) is found, the hydrate of which ($C_3H_5 3HO$) is glycerine. The homologues of glycol are termed *glycols*, the homologues of glycerine *glycerines*. It will be noticed that the chemical composition of the radicals glyceryl and allyl is identical (C_3H_5), but the former is trivalent and the latter univalent; hence they probably differ in physical constitution; they are isomeric, possibly polymeric, with each other. From a glyceryl compound (glycerine), however, an allyl salt (iodide) can be produced. By distilling a mixture of glycerine and diniodide of phosphorus, iodide of allyl (C_3H_5I) is obtained, and on digesting this with sulphocyanate of potassium, the sulphocyanate of allyl, or *artificial oil of mustard*, results; identical with the natural oil.

Glycerine.

Glycerine, or *Glyceric Alcohol* ($C_3H_5 3HO$).—Glycerine is the hydrate of *glyceryl*, *glycyl*, or *propenyl*—the basylous radical of most oils and fats. These latter are mainly oleates, palmitates, and stearates of glyceryl; and when heated with metallic hydrates (even with water—hydrate of hydrogen, HHO—at a temp. of 500° or 600° F.) yield oleate, palmitate or stearate of the metal, and hydrate of glyceryl or glycerine. Hence glycerine is a by-product in the manufacture of soap, hard candles, and lead-plaster (*vide* Index).

Properties.—Glycerine is viscid when pure, specific gravity 1.28 (not below 1.25, B. P.) has a sweet taste, is soluble in water or alcohol in all proportions. It has remarable powers as a solvent, is a valuable *antiseptic* even when diluted with 10 parts of water, and useful as an emollient. In vacuo it may be distilled unchanged but under ordinary atmospheric pressure is decomposed by heat.

Test.—Heat one or two drops of glycerine in a test-tube, alone or with strong sulphuric acid, acid sulphate of potassium, or other salt powerfully absorbent in water; vapors of acrolein (from *acer*, sharp, and *oleum*, oil) are evolved, recognized by their powerfully irritating effects on the eyes and respiratory passages. If the glycerine be in solution in water, it must be evaporated as low as possible before applying this test. Besides glycerine itself (*Glycerinum*,

B. P., *Glycerina*, U. S. P.), there are several official preparations of glycerine—solutions of carbolic, gallic, and tannic acids and borax in glycerine, and a sort of mucilage of starch in glycerine (*Glyceritum Acidi Carbolici*, *Glyceritum Acidi Gallici*, *Glyceritum Acidi Tannici*, *Glyceritum Picis Liquidæ*, and *Glyceritum Sodii Boratis*).

QUESTIONS AND EXERCISES.

796. Give the names and formulæ of compounds of radicals having the general formula C_nH_{2n-7}', C_nH_{2n-1}', C_nH_{2n-1}''', and C_nH_{2n}'',—*e. g.*, benzol, essential oil of mustard, glycerine, and glycol.

797. State the difference in composition of natural and artificial oil of bitter almonds.

798. How is the so-called artificial oil of bitter almonds prepared?

799. What are the uses, composition, source, and properties of Carbolic Acid?

800. State the characters by which carbolic acid is distinguished from Creasote.

801. In what relation does carbolic acid stand to cresylic acid?

802. What is the general formula of sulphocarbolates?

803. Draw out an equation explanatory of the production of aniline.

804. Mention the chief properties of Glycerine.

805. What is the specific gravity of glycerine?

806. By what test is glycerine recognized?

807. Enumerate some official preparations in which glycerine is employed as a solvent.

ALBUMENOID SUBSTANCES.

Albumen.—Agitate thoroughly, white of egg (*Albumen Ovi*, B. P.) with water, and strain or pour off the liquid from the flocculent membranous insoluble matter. One white to 4 ozs. of water forms the "Solution of Albumen," B. P.

Test.—Heat a portion of this solution of albumen to the boiling-point; the albumen becomes insoluble, separating in clots or coagula of characteristic appearance.

Other Reactions.—Add to small quantities of aqueous solution of albumen solutions of corrosive sublimate, nitrate of silver, sulphate of copper, acetate of lead, alum, perchloride of tin; the various salts not only coagulate but form insoluble compounds with albumen. Hence the

value of an egg as a temporary antidote in cases of poisoning by many metallic salts, its administration retarding the absorption of the poison until the stomach-pump or other measures can be applied. Sulphuric, nitric, and hydrochloric acids precipitate albumen; the coagulum is slowly redissolved by aid of heat, a brown, yellow, or purplish-red color being produced. Neither acetic, tartaric, nor organic acids, generally, except gallo-tannic, coagulate albumen. Alkalies prevent the precipitation of albumen.

Yolk or *Yelk of Egg* (*Ovi Vitellus*, B. P.) contains only 3 per cent. of albumen—the white 12½. The yolk also contains only 30 per cent. of yellow fat and 14 of casein. The whole egg (*Ovum*, U. S. P.) is also official.

Albumen is met with in large quantities in the serum of blood, in smaller quantity in chyle and lymph, and in the brain, kidneys, liver, muscles, and pancreas. It is not a normal constituent of saliva, gastric juice, bile, or mucus, but occurs in those secretions during inflammation. It is found in the urine and feces only under certain diseased states of the system.

The cause of the coagulation of albumen by heat has not yet been discovered.

Albumen has never been obtained sufficiently pure to admit of its composition being expressed by a trustworthy formula; Gerhardt regarded it as a sodium compound ($HNaC_{72}H_{110}N_{18}SO_{22},H_2O$).

Fibrin, Casein, Legumin.

Fibrin is the chief constituent of the muscular tissue of animals. It occurs in solution in the blood; and its spontaneous solidification or coagulation is the cause of the *clotting* of blood shortly after being drawn from the body—a phenomenon which cannot at present be explained satisfactorily. Fibrin may be obtained by whipping fresh blood with a bundle of twigs, separating the adherent fibres, and washing in water till colorless.

Average Composition of Blood (in 1000 parts).
(Compiled by Kirkes.)

Water			784
Albumen			70
Fibrin			2.2
Red Corpuscles:	Globulin		123.5
	Hæmatin		7.5
Fatty matters.	Cholesterin	0.08	1.3
	Cerebrin	0.40	
	Serolin	0.02	
	Oleic and margaric acids		
	Volatile and odorous fatty acid		
	Fat containing Phosphorus		

Inorganic salts.	Chloride of sodium	3.6
	Chloride of potassium	.36
	Phosphate of sodium (Na_3PO_4)	.2
	Carbonate of sodium	.84
	Sulphate of sodium	.28
	Phosphates of calcium and magnesium	.25
	Oxide and phosphate of iron	.50
Extractive matters, biliary-coloring-matter, gases, and accidental substances		5.47
		1000.

Percentage proportion of the *chief* constituents of Blood.

Water	78.4
Red corpuscles	13.1
Albumen of serum	7.0
Inorganic salts	.603
Extractive, fatty, and other matters	.677
Fibrin	.22
	100.

Casein occurs in Cow's Milk (*Lac*, B. P.) to the extent of 3 per cent., dissolved by a trace of alkaline salt. Its solution does not spontaneously coagulate like that of fibrin, nor by heat like albumen; but acids cause its precipitation from milk in the form of a curd (cheese) containing the fat (butter)-globules previously suspended in the milk, a clear yellow liquid (or whey) remaining. *Curds and whey* are also produced on adding to milk a piece, or an infusion, of *rennet*, the salted and dried inner membrane of the fourth stomach of the calf. The exact action of rennet is not known.

Average composition of 1000 *parts of Milk.*

	Specific gravity.	Water.	Solid constituents.	Casein and extractive.	Sugar.	Butter.	Salts.
Woman . . .	1.033	889	111	40	44	27	2
Cow	1.034	864	136	55	38	36	7

Specific gravity alone, as taken by the form of hydrometer termed a *lactometer*, or even by more delicate means, is of little value as an indication of the richness of milk, the butter and the other solids exerting an influence in opposite directions. Good cow's milk affords from 11 to 13 per cent. by volume of cream, and 3 to 3½ per cent. of butter. The water of milk seldom or never varies more than from 86½ to 87½ per cent., and the solid constituents from 13½ to 12½. Town milk is commonly 3 and sometimes 2 parts milk and 1 part water. Under the microscope milk is seen to consist of minute cor-

puscles floating in a transparent medium. These corpuscles consist of fatty matter (butter) contained in a filmy albumenoid envelope.

Legumin or *vegetable casein* is found in most leguminous seeds, such as sweet and bitter almonds. Peas contain about 25 per cent. of legumin.

Vegetable albumen is contained in many plant-juices, and is deposited in flocculi on heating such liquids. *Vegetable fibrin* is the name given by Liebig and Dumas to that portion of the gluten of wheat which is insoluble in alcohol and ether (*vide* p. 356).

Albumenoid substances are nearly identical in percentage composition. Albumen (and fibrin) contains 53.5 of carbon, 7 of hydrogen, 15.5 of nitrogen, 22 of oxygen, 1.6 of sulphur, and .4 of phosphorus. Casein contains no phosphorus. These three bodies are often termed the *plastic elements of nutrition*, under the assumption that animals directly assimilate them in forming muscles, nerves, and other tissues, —starch, sugar, and similar matter forming the *respiratory* materials of food, because more immediately concerned in keeping up the temperature of the body by the combustion going on between them, and their products, and the oxygen of the air in the blood.

Musk (*Moschus*, B. P. and U. S. P.), "the inspissated and dried secretion from the preputial follicles of *Moschus moschiferus*" (the Musk-Deer), is a mixture of albumenoid, fatty, and other animal matters with a volatile odorous substance of unknown composition.

GELATIGENOUS SUBSTANCES.

This group of nitrogenous bodies differs from true albumenoid in containing less carbon and sulphur and more nitrogen. They are contained in certain animal tissues, and on boiling with water yield a solution which has the remarkable property of solidifying to a jelly on cooling. The tendons, ligaments, bones, skin, and serous membranes afford *gelatine* proper; the cartilages give *chondrine*, which differs from gelatine in composition and in being precipitated by vegetable acids, alum, and the acetates of lead. The purest variety of gelatine is *isinglass*, B. P. (*Icthyocolla*, U. S. P.), "the swimming-bladder or sound of various species of *Acipenser*, Linn., prepared and cut in fine shreds." Small quantities are more easily disintegrated by a file than a knife. Fifty grains dissolved in 5 ounces of distilled water forms the official "Solution of Gelatine," B. P. *Glue* is an impure variety of gelatine, made from the trimmings of hides; *size* is glue of inferior tenacity, prepared from the parings of parchment and thin skins. "Among the varieties of gelatine derived from different tissues and from the same sources at different ages, much diversity exists as to the firmness and other characters of the solid formed on the cooling of the solutions. The differences between isinglass, size, and glue, in these respects, are familiarly known, and afford good examples of the varieties called weak and strong, or low and high, gelatines. The differences are sometimes ascribed to the quantities of water combined in each case with the pure or anhy-

drous gelatine, part of which water seems to be chemically combined with the gelatine; for no artificial addition of water to glue would give it the character of size, nor would any abstraction of water from isinglass or size convert it into the hard dry substance of glue. But such a change is effected in the gradual process of nutrition of the tissues; for, as a general rule, the tissues of an old animal yield a much firmer or stronger jelly than the corresponding parts of a young animal of the same species." (Kirke's Physiology.) Gelatine appears to unite chemically with a portion of the water in which it is soaked when used for culinary and manufacturing purposes, for a solution of glue in hot anhydrous glycerine does not yield an ordinary jelly on cooling.

PEPSINE.

Pepsine (from *πέπτω, peptō*, to digest) is a nitrogenous substance existing in the gastric juice, and as a viscid matter in the *peptic* glands and on the walls of the stomachs of animals. The mucous membrane of the stomach (of the hog, sheep, or calf, killed fasting) is scraped, and macerated in cold water for twelve hours; the pepsine in the strained liquid is then precipitated by acetate of lead, the deposit washed once or twice by decantation, sulphuretted hydrogen passed through the mixture of the deposit with a little water to remove the whole of the lead, and the filtered liquid evaporated to dryness at a temperature not exceeding 105° F. Pepsine is a powerful promoter of digestion; its solution is hence frequently termed *artificial gastric juice*. As met with in pharmacy its strength varies greatly. It is often prepared by simply mixing with starch the thick liquid obtained on macerating the scraped stomach with water, and evaporating to dryness. (Vide *Pharmaceutical Journal*, 1865–66, p. 112, and 1871–72, pp. 785 and 843.)

QUESTIONS AND EXERCISES.

808. In what form is albumen familiar?
809. Name the chief test for albumen.
810. Why is the administration of albumen useful in cases of poisoning?
811. Mention the points of difference between yolk and white of egg.
812. From what sources other than egg may albumen be obtained?
813. In what respects does fibrin differ from albumen?
814. Enumerate the chief constituents of blood.
815. How may fibrin be obtained from blood?
816. State the difference between casein, fibrin, and albumen.
817. What are the relations of cream, butter, curds and whey, and cheese, to milk?

818. Describe the microscopic appearances of blood and of milk.
819 How much cream should be obtained from good milk?
820. What is the percentage of water in genuine milk?
821. Name sources of vegetable casein and vegetable albumen.
822. Give the percentage of nitrogen in albumenoid substances.
823. Describe the chemical nature of musk.
824. In what lie the peculiarities of gelatine?
825. To what extent do isinglass, glue, and size differ?
826. Whence is pepsine obtained?
827. How is pepsine prepared?

FATTY BODIES.

SOAPS, SOLID FATS, FIXED OILS, VOLATILE OILS, CAMPHORS.

General relations.—Oils and fats are, apparently, almost as simple in constitution as ordinary inorganic salts. Just as acetate of potassium ($KC_2H_3O_2$) is regarded as a compound of potassium (K) with the characteristic elements of all acetates ($C_2H_3O_2$), so soft soap is considered to be a compound of potassium (K) with the elements characteristic of all oleates ($C_{18}H_{33}O_2$), and hence is chemically termed oleate of potassium ($KC_{18}H_{33}O_2$). Olive oil, from which soap is commonly prepared, is mainly oleate of the trivalent radical *glyceryl* (C_3H_5), the formula of pure fluid oil being $C_3H_53C_{18}H_{33}O_2$, and its name *oleine*. The formation of a soap, therefore, on bringing together oil and a moist oxide or hydrate, is a simple case of double decomposition, as seen already in connection with lead plaster (p. 188), or in the following equation relating to the formation of common hard soap:—

$$\underset{\text{Hydrate of sodium (caustic soda)}}{3NaHO} + \underset{\text{Oleate of glyceryl (vegetable oil).}}{C_3H_53C_{18}H_{33}O_2} = \underset{\text{Oleate of sodium (hard soap).}}{3NaC_{18}H_{33}O_2} + \underset{\text{Hydrate of glyceryl (glycerine).}}{C_3H_53HO}$$

Berthelot has succeeded in preparing oil artificially from oleic acid and glycerine; and it is said to be identical with the pure oleine of olive and of other fixed oils. Hard fats chiefly consist of *stearine*—that is, of tristearate of glyceryl ($C_3H_53C_{18}H_{35}O_2$). Mr. Wilson, of Price's Candle Company, obtains stearic and oleic acids and glycerine by simply passing steam, heated to 500° or 600° F., through melted fat. Both the glycerine and fat acids distil over in the current of steam, the glycerine dissolving in the condensed water, the fat-acids floating on the aqueous liquid.

The author finds that oleic acid readily combines with alkaloids and most of the metallic oxides or hydrates, forming oleates which are soluble in fats. In this way active medicines may be administered internally in conjunction with oils, or externally in the form of ointments.

Soaps.—Olive oil boiled with solution of potash yields potassium soap, or *soft soap* (*Sapo Mollis*, B. P.); with soda, sodium soap, or *hard soap* (*Sapo Durus*, B. P. and U.

S. P.); mixed with ammonia, an ammonium soap (*Linimentum Ammoniæ*, B. P. and U. S. P.); and with lime-water, calcium soap (*Linimentum Calcis*, B. P. and—flaxseed oil—U. S. P.),—all oleates, chiefly of the respective basylous radicals. Their mode of formation is indicated in the foregoing equation. The alkali soaps are soluble in alcohol, the others insoluble. The official characters of Hard Soap are: "grayish-white, dry, inodorous; horny and pulverizable when kept in dry warm air; easily moulded when heated; soluble in rectified spirit; not imparting an oily stain to paper; incinerated it yields an ash which does not deliquesce." And of Soft Soap: "yellowish-green, inodorous, of a gelatinous consistence; soluble in rectified spirit; not imparting an oily stain to paper: incinerated it yields an ash which is very deliquescent."

The hard soap met with in trade is made from all varieties of oil, the commoner kinds being simply the product of the evaporated mixture of oil and alkali; while the better sorts have been separated from alkaline impurities and the glycerine by the addition of common salt to the liquors, which causes the precipitation of the pure soap as a curd. Potash soap is not precipitable by salt.

Bile, the gall of the ox (*Bos taurus*, Linn.), freed from mucus by agitating with twice its bulk of rectified spirit (in which mucus is insoluble), filtering, and evaporating, yields the official Purified Ox-Bile (*Fel Bovinum Purificatum*, B. P.): the latter has a resinous appearance, but is chiefly composed of two crystalline substances having the constitution of a soap; the one is *glycocholate*, or simply *cholate, of sodium* ($NaC_{26}H_{42}NO_6$), the other is termed *taurocholate of sodium* ($NaC_{26}H_{44}NO_7S$). Both taurocholates and glycocholates are conjugated bodies readily yielding, the former *cholalic acid* ($H_2C_{14}H_{39}O_5$) and *taurine* ($C_2H_7NO_3S$), the latter cholalic acid and *glycocine* or *glycocoll* ($C_2H_5NO_2$), a body having interesting physiological relations, inasmuch as it is obtainable from gelatine (hence the name glycocoll, from γλυκὺς, *glucūs*, sweet, and κόλλα, *kolla*, glue) and hippuric acid. The presence of bile in a liquid such as urine, is detected by Pettenkofer's test. The fluid is gradually mixed with half its bulk of strong sulphuric acid in a test-tube, rise of temperature being prevented by partial immersion of the tube in water. A small quantity of powdered white sugar is then introduced and well mixed with the acid liquid, and more sulphuric acid then poured in; as the temperature rises a reddish or violet coloration is produced. The cholalic acid liberated in the reaction furnishes the color.

Solid Fats.—1. *Lard* (*Adeps Præparatus*, B. P. and U. S. P.) is the purified internal fat of the abdomen of the hog—the perfectly fresh *omentum* or *flare*, washed, melted, strained, and dried. 2. *Benzoated Lard* (*Adeps Benzoatus*, B. P.) is prepared lard heated over a water-bath with benzoin (10 grains per ounce), which communicates an agreeable odor and prevents or retards rancidity. Purified

lard is a mixture of oleine and stearine; *margarine*, the margarate of glyceryl, was formerly supposed to be a constituent of lard and other soft fats, but is now regarded as a mere mixture of *palmitine* (the chief fat of palm oil) and stearine. 3. *Yellow Wax* (*Cera Flava*, B. P. and U. S. P.), the prepared honeycomb of the Hive-Bee, and the same bleached by exposure to sunlight. 4. *White Wax* (*Cera Alba*, B. P. and U. S. P.), according to Brodie, is chiefly a mixture of *Cerotic Acid* ($HC_{27}H_{53}O_2$), *Palmitate of Melissyl* ($C_{30}H_{61}C_{16}H_{31}O_2$), and about 5 per cent. of *Ceroleine*, the body to which the color, odor, and tenacity of wax are due. 5. *Spermaceti* (*Cetaceum*, B. P. and U. S. P.) is the *palmitate of cetyl* ($C_{16}H_{33}C_{16}H_{31}O_2$), or *cetine;* when saponified it yields not glycerine, the hydrate of glyceryl (C_3H_53HO), but *ethal*, the hydrate of cetyl ($C_{16}H_{33}HO$); it is the solid crystalline fat accompanying *sperm* oil in the head of the spermaceti-whale. 6. *Suet*, the internal fat of the abdomen of the sheep, purified by melting and straining, forms the official *Prepared Suet* (*Sevum Præparatum*, B. P. and U. S. P.); it is almost exclusively composed of stearin ($C_3H_53C_{18}H_{35}O_2$). 7. Expressed oil of *nutmeg* (*Oleum Myristicæ Expressum*, B. P.) is a mixture of a little volatile oil with much yellow and white fat, the latter a myristate of glyceryl ($C_3H_53C_{14}H_{27}O_2$). 8. Oil of *theobroma*, or *Cacao-butter* (*Oleum Theobromæ*, B. P. and U. S. P.), is a solid product of the ground seeds or *cocoa nibs* of the *Theobroma cacao*, which also furnish *cocoa* and *chocolate*. 9. *Cocoa-nut* oil, a soft fat largely contained in the edible portion of the nut of *Cocos nucifera*, or common cocoa-nut of the shops, a body containing glyceryl united with no less than six different univalent acidulous radicals, namely, the caproic ($C_6H_{11}O_2$), caprylic ($C_8H_{15}O_2$), rutic ($C_{16}H_{19}O_2$), lauric ($C_{12}H_{23}O_2$), myristic ($C_{14}H_{27}O_2$), and palmitic ($C_{16}H_{31}O_2$)—radicals which, like some from common resin, when united with sodium, form a soap differing from ordinary hard soap (oleate of sodium) by being tolerably soluble in a solution of chloride of sodium; hence the use of cocoa-nut oil and resin in making *marine soap*, a soap which, for the reason just indicated, readily yields a lather in sea-water.

Fixed Oils.—*Fixed* and *Volatile* oils are naturally distinguished by their behavior when heated; they also differ in chemical constitution, a fixed oil being, apparently, a combination of a basylous with an acidulous radical, while a volatile oil is commonly a neutral hydrocarbon.

Drying and Non-drying Oils.—Among fixed oils, most of which are oleate with a little palmitate and stearate of glyceryl, a few, such as, 1, *linseed* (*Oleum Lini*, B. P. and U. S. P., contained in *Lini Semina*, B. P., *Linum*, U. S. P., or Flaxseed, the ground residue of which, after removal of some of the oil, is *linseed meal*, *Lini Farina*, U. S. P.), and, 2, *cod-liver* (*Oleum Morrhuæ*, B. P. and U. S. P.), and, to some extent, castor and croton, are known as *drying oils*, from the readiness with which they absorb oxygen and become hardened to a resin. Linseed commonly contains 37 or 38 per cent. of oil; 25 to 27 per cent. is obtained by submitting the ground seeds to hydraulic pressure, 10 or 12 per cent. remaining in the residue oil-cake. Among the *non-drying oils* are the following: 3, *Almond*

oil, indifferently yielded by the bitter (*Amygdala Amara*, B. P. and U. S. P.) or sweet seed (*Amygdala Dulcis*, B. P. and U. S. P.); 4, *Croton* oil (*Oleum Crotonis*, B. P., *Oleum Tiglii*, U. S. P.), which seems to contain *crotonate of glyceryl* ($C_3H_5 3C_4H_5O_2$). Geuther, however, states that no such acid as crotonic is obtainable from croton oil, but acetic, butyric, valerianic, and higher members of the oleic series, together with *tiglic acid*, $H_2C_5H_7O_2$. 5, *Olive* oil (*Oleum Olivæ*, B. P. and U. S. P.), already noticed; 6, *Castor* oil (*Oleum Ricini*, B. P. and U. S. P.), a *ricinoleate of glyceryl* ($C_3H_5 3C_{18}H_{33}O_3$) or ricinoleine, a slightly oxidized oleine, soluble, unlike most fixed oils, in alcohol; 7, Oil of *male fern* (*Filix Mas*, B. P. and U. S. P.), a vermifuge obtained by exhausting the rhizome with ether and removing the ether by evaporation—a dark-colored oil containing a little volatile oil and resin, and officially termed an extract (*Extractum Filicis Liquidum*, B. P.); 8, Fixed oil of *mustard*, a bland, inodorous, yellow or amber oil, yielding, by saponification and action of sulphuric acid, glycerine, oleic acid, and *erucic acid*, $HC_{22}H_{41}O_2$ (Darby); 9, *Lycopodium Oil* from the sporules of Club-moss.

Their physical qualities and the formulæ of their acidulous radicals show that the fatty bodies are closely related, and indicate that the natural processes by which they are formed are probably as closely related. The following Table, from Miller's "Elements of Chemistry," well shows the homology of the fat-acids, and gives their names, formulæ, melting-points, boiling-points, and natural and artificial sources. For further information respecting the more commonly occurring of these acids, the reader is referred to the Index, and for others to larger chemical works, or Watts's "Dictionary of Chemistry."

Acids.	Formulæ. Molec. Vol. = 2.	Melting point.		Boiling point.		Whence obtained.
		°F.	°C.	°F.	°C.	
Formic.....	$HC\ H\ O_2$	21	—6	221	105.3	Red ants; distillati oxalic acid; and tion of amylaceou other organic bodie
Acetic.....	$HC_2\ H_3\ O_2$	63	17	243	117	Distillation of wood; oxidation of alcohol, etc.
Propionic....	$HC_3\ H_5\ O_2$	...	...	284	140	Fermentation of glycerin, etc.
Butyric.....	$HC_4\ H_7\ O_2$	below °	—20	314	157	Butter; fermentation of lactic acid, etc.
Valerianic...	$HC_5\ H_9\ O_2$	"	"	347	175	Valerian-root; oxidation of fousel oil.
Caproic.....	$HC_6\ H_{11}O_2$	...	...	392	200	Butter.
Œnanthylic.	$HC_7\ H_{13}O_2$	"	"	298?	148?	Castor oil by distillation, etc.
Caprylic.....	$HC_8\ H_{15}O_2$	59	15	457	236	Butter; cocoa-nut oil.
Pelargonic...	$HC_9\ H_{17}O_2$	...	...	500	260	Leaves of the geranium.
Rutic	$HC_{10}H_{19}O_2$	86	30	...	...	Butter; oil of rue b dation.
Lauric.....	$HC_{12}H_{23}O_2$	110	43	...	...	Cocoa-nut oil; berries bay tree.
Myristic.....	$HC_{14}H_{27}O_2$	129	54	...	...	Nutmeg-butter; cocc oil, etc.
Palmitic	$HC_{16}H_{31}O_2$	143.6	62	...	...	Palm oil; butter; bee etc.
Stearic.....	$HC_{18}H_{35}O_2$	159	70.5	...	...	Most solid animal fat
Arachidic....	$HC_{20}H_{39}O_2$	167	75	...	...	Butter; oil of ground
Cerotic	$HC_{27}H_{53}O_2$	174	79	...	...	Beeswax.
Melissic	$HC_{30}H_{59}O_2$	192	89	...	...	Beeswax.

QUESTIONS AND EXERCISES.

828. Give a sketch of the general chemistry of fixed oils, fats and soaps.

829. What is the difference between Hard and Soft Soap?

830. Which soaps are official?

831. Name the source of lard, and state how "Prepared Lard" is obtained.

832. State the composition of Beeswax.

833. In what does Spermaceti differ from other solid fats?

834. Mention the chief constituent of Suet.

835. Whence is Cacao-Butter obtained?

836. Why is *marine soap* so called, and from what fatty matter is it exclusively prepared?

837. What do you understand by *drying* and *non-drying* oils?
838. In what respect does Castor Oil differ from other oils?
839. How is oil of male fern (*Ex. Filicis Liquidum*) prepared?
840. Mention the sources and formulæ of the following fat-acids: formic, acetic, propionic, butyric, valerianic, caproic, œnanthylic, caprylic, pelargonic, and rutic.

Volatile Oils.—The *Volatile* or *Essential Oils* exist in various parts of plants probably as mere combinations of carbon and hydrogen; but such *hydrocarbons* are prone to change when in contact with oxygen or moisture; hence these liquids as they occur in pharmacy are usually mixtures of liquid hydrocarbons or *elæoptens* with oxidized hydrocarbons, which are commonly solid or camphor-like bodies termed *stearoptens*. On cooling a volatile oil, a stearopten (from στέαρ, *stear*, suet) often crystallizes out; or on distilling an oil, it remains in the retort, being less volatile than an elæopten (from ἔλαιον, *elaion*, oil, and ὄπτομαι, *optomai*, to see). Volatile oils should be preserved in well-closed bottles.

The process by which volatile oils are usually obtained from herbs, flowers, fruits, or seeds, may be imitated on the small scale by placing the material (bruised cloves or caraways for instance) in a tubulated retort, adapting the retort to a Liebig's condenser, and passing steam, generated in a Florence flask, through a glass tube to the bottom of the retort. The steam in its passage upward through the substance will carry the oil over the neck of the retort into the condenser, and thence, liquefied and cooled, into the receiving vessel, where the oil will be found floating on the water. It may be collected by running off the distillate through a glass funnel having a stopcock in the neck, or by letting the water from the condenser drop into an old test-tube which has a small hole in the bottom, or any similar tube placed in a larger vessel, the water and oil being subsequently run off separately from the tube as from a pipette. The water will in most cases be the ordinary official medicated water of the material operated on (*Aqua Aurantii Floris*, *Anethi*, *Carui*, *Cinnamomi*, *Fœniculi*, *Menthæ Piperitæ*, *Menthæ Viridis*, *Pimentæ*, *Rosæ*—from *Rosæ Centifoliæ Petala*, B. P. and U. S. P.—*Sambuci*). Volatile oils, like fixed oils, stain paper, but the stain of the former is not permanent like that of the latter. Oils of lemon and orange are sometimes obtained by mere pressure of the rind of the fruit.

A large number of volatile oils are employed in medicine, either in the pure state, in the form of saturated aqueous solution (medicated waters), solution in spirit of wine, 1 in 5 (*Essentia Anisi* and *Essentia Menthæ Piperitæ*, B. P.) and 1 in 50 (*Spiritus Cajuputi*, *Juniperi*, *Lavandulæ*, *Menthæ Piperitæ*, *Myristicæ*, *Rosmarini*), or

as leading constituents in various barks, roots, leaves, etc. The strength of *Spiritus Anisi*, U. S. P.; *Sp. Cinnamomi*, U. S. P.; *Sp. Menthæ Piperitæ*, U. S. P. and *Sp. Menth. Viridis*, U. S. P., is 1 of oil to 15 of spirit of wine. *Perfumes* ("scents" or "essences," including "Lavender-Water" and "Eau de Cologne") are for the most part solutions of essential oils in spirit of wine, or spirituous infusions of materials containing essential oils. The following oils are, directly or indirectly, official in the British Pharmacopœia. 1. Volatile oil of *Bitter Almond* (p. 366). 2. Oil of *Dill* (*Oleum Anethi*, B. P.), a pale yellow, pungent, acrid liquid distilled from dill-fruit. It contains a hydrocarbon *anethene* ($C_{10}H_{16}$) and an oxidized oil ($C_{10}H_{14}O$) identical with the carvol of oil of caraway (Gladstone). 3. Oil of *Aniseed* (*Oleum Anisi*, B. P.), a colorless or pale yellow liquid, of sweetish warm flavor, distilled in Europe from the Anise-fruit (*Pimpinella anisum*), and in China from the fruit of Star-Anis (*Illicium anisatum*); it is a mixture of a hydrocarbon isomeric with oil of turpentine and a stearopten ($C_{10}H_{12}O$), which crystallizes out at low temperatures. 4. Oil of *Chamomile* (*Oleum Anthemidis*, B. P.), a bluish or, when old, yellow oil, of characteristic odor and taste, distilled from chamomile flowers (*Anthemidis flores*, B. P.): the official variety (*Anthemis nobilis*) yields an oil composed of a hydrocarbon ($C_{10}H_{16}$) and an oxidized portion ($C_{10}H_{16}O_2$ or C_5H_8O), which, heated with potash, gives *angelate of potassium* ($KC_5H_7O_2$), whence is obtained *angelic acid* ($HC_5H_7O_2$); while the flowers of another variety (*Matricaria Chamomilla*, U. S. P.) contain a stearopten ($C_{10}H_{16}O$) having the composition of laurel-camphor. 5. Oil of *Horseradish*-root (*Armoraciæ Radix*, B. P.) is, according to Hofmann, the sulphocyanate of butyl or tetryl (C_4H_9CNS); it is the chief ingredient of *Spiritus Armoraciæ Compositus*, B. P. 6. Oil of Sweet-Orange Peel (*Aurantii Dulcis Cortex*, U. S. P.) and Oil of Bitter-Orange rind (*Aurantii Amari Cortex*, B. P. and U. S. P.), the flavoring constituent of the official syrup of the *peel* (*Syrupus Aurantii*, B. P.), and the oils of, 7, *lemon* (*Oleum Limonis*, B. P. and U. S. P.), from Lemon Peel (*Limonis Cortex*, U. S. P.); 8, *lime*; 9, *bergamot* (*Oleum Bergamii*, U. S. P.); 10, *citron* and a variety of citron termed *cedra*, resemble each other in composition, containing *hesperidine*, a hydrocarbon ($C_{10}H_{16}$) and a small quantity of oxidized hydrocarbons ($C_{10}H_{10}O_5$, $C_{15}H_{10}O_5$, and (Wright and Piesse) $C_{20}H_{30}O_3$). 11. Oil of *Neroli* or *Orange-Flower*, the aqueous solution of which is official in the forms of water (*Aqua Aurantii Floris*, B. P. and U. S. P.) and syrup (*Syrupus Aurantii Floris*, B. P. and U. S. P.), contains a fragrant hydrocarbon ($C_{10}H_{16}$), colorless when fresh, but becoming red on exposure to light, and an inodorous oxidized hydrocarbon. 12. Oil of *Buchu-leaves* (*Buchu Folia*, B. P. and U. S. P.) consists of a hydrocarbon holding in solution a crystalline stearopten. 13. Oil of *Cardamoms*, from the seeds of the capsules (*Cardamomum*, B. P. and U. S. P.), is chiefly a hydrocarbon ($C_{10}H_{16}$) isomeric with oil of turpentine. 14. Oil of *Cajuput* (*Oleum Cajuputi*, B. P. and U. S. P.) is a mobile bluish liquid the composition of which ($C_{10}H_{18}O$) seems to be that of the common hydrocarbon associated with the elements of water. The green coloring matter of most samples of cajuput oil

is organic. Guibourt, and, more recently, Histed, have found copper in many specimens of cajuput oil. 15. Oil of *Caraway*-fruit (*Carum*, U. S. P.) (*Oleum Carui*, B. P., *Oleum Cari*, U. S. P.) is a mixture of *carvene* ($C_{10}H_{16}$) and *carvol* ($C_{10}H_{14}O$). 16. Oil of *Cloves* (*Oleum Caryophylli*, B. P. and U. S. P.) and of *Pimento* (*Oleum Pimentæ*, B. P. and U. S. P.), both heavier than water, contain a liquid hydrocarbon ($C_{10}H_{16}$), *eugenic acid* ($C_{10}H_{12}O_2$), a solid body, *eugenin*, isomeric with eugenic acid, and a second crystalline substance, *caryophyllin* ($C_{10}H_{16}O$), isomeric with common camphor. 17. Oil of *Cascarilla*-bark (*Cascarillæ Cortex*, B. P. and U. S. P.) has not been fully examined. 18. Oil of *Cinnamon*-bark (*Cinnamomi Cortex*, B. P. and U. S. P.) and of *Cassia*-bark is mostly hydride of cinnamyl (C_9H_7OH). Boiled with nitric acid it furnishes hydride of benzoyl (C_7H_5OH) and benzoic acid ($HC_7H_5O_2$), with chloride of lime yields benzoate of calcium($Ca2C_7H_5O_2$), and with caustic potash gives cinnamate of potassium ($KC_9H_7O_2$). The specific gravity of oil of cinnamon (*Oleum Cinnamomi*, B. P. and U. S. P.) varies from 1.025 to 1.050. 19. Oil of *Citronella* is chiefly composed of *citronellol* ($C_{10}H_{16}O$), probably isomeric with the *absinthol* of wormwood (Gladstone). 20. Oil of *Copavia* (*Oleum Copaibæ*, B. P. and U. S. P.) and, 21, of *Cubebs* (*Oleum Cubebæ*, B. P. and U. S. P.) are hydrocarbons having the formula $C_{15}H_{24}$. 22. Oil of *Coriander* (*Coriandri fructus*, B. P., *Coriandrum*, U. S. P., *Oleum Coriandri*, B. P.) seems to have the composition of hydrous oil of turpentine ($C_{10}H_{16}H_2O$). 23. *Eucalyptus globulus* furnishes an oil the more volatile and chief portion of which is *eucalyptol* ($C_{12}H_{20}O$). 24. Oil of *Juniper* (*Oleum Juniperi*, B. P. and U. S. P.), the active constituent of Juniper Tops and Berries (*Juniperus*, U. S. P.), is a hydrocarbon ($C_{10}H_{16}$) which by contact with water yields a white crystalline hydrous compound ($C_{10}H_{16}H_2O$). 25. Oil of *Fennel*-fruit (*Oleum Fœniculi*, U. S. P.) (*Fœniculi Fructus*, B. P. and U. S. P.) differs in odor, but contains the same proximate constituents as oil of anise. 26. Oil of *Lavender* (*Oleum Lavandulæ*, B. P. and U. S. P.) contains a hydrocarbon which by oxidation yields common camphor. 27. Oil or Butter of *Orris* (*Iris Florentina*) is a soft camphor ($C_8H_{16}O_2$), lighter than water. 28. Oil of *Peppermint* (*Oleum Menthæ Piperitæ*, B. P. and U. S. P.) consists of a hydrocarbon, *menthene* ($C_{10}H_{18}$), which differs from that of most volatile oils, and hydrous menthene ($C_{10}H_{18}H_2O$), a crystalline stearopten. 29. Oil of *Spearmint* (*Oleum Menthæ Viridis*, B. P. and U. S. P.) contains a liquid expressed by the formula $C_{10}H_{20}O$; also, according to Gladstone, *menthol* ($C_{10}H_{14}O$) isomeric with carvol. 30. Oil of *Nutmeg* (*Oleum Myristicæ*, B. P. and U. S. P.) and of the arillus of the nutmeg or mace (*Macis*, U. S. P.) is composed of a hydrocarbon *myristicene* ($C_{10}H_{16}$), and *myristicol* ($C_{10}H_{14}O$)—Gladstone. 30*a*. Oil of Origanum (*Oleum origani*, U. S. P.) from *Origanum vulgare*, U. S. P., is of a bright-yellow color, having an odor somewhat like peppermint; it is a mixture of a liquid hydrocarbon and a camphor which is deposited after long standing. 31. Oil or Otto or Attar of *Cabbage-rose petals* (*Rosæ Centifoliæ Petals*, B. P. and U. S. P., *Oleum Rosæ*, U. S. P.) gives the fragrance to Rose water (*Aqua Rosæ*, B. P.). It resembles most

other volatile oils in being composed of a hydrocarbon and an oxidized portion, but differs from all in this respect, that the hydrocarbon is solid and is destitute of odor, while the oxygenated constituent is liquid and the source of the perfume. According to Flückiger the solid hydrocarbon (C_8H_{16}) yields succinic acid as the chief product of its oxidation by nitric acid, and in other respects affords evidence of belonging to the paraffin series of fats. 32. Oil of *Rosemary-tops* (*Oleum Rosmarini*, B. P. and U. S. P.) is a mixture of hydrocarbon, oxygenized oil, and stearopten in variable proportions. 33. Oil of *Rue* (*Oleum Rutæ*, B. P. and U. S. P.) contains a small quantity of hydrocarbon ($C_{10}H_{16}$) with some rutic aldehyd ($C_{10}H_{20}O$), but according to Greville Williams is chiefly euodic aldehyd ($C_{11}H_{22}O$), some lauric aldehyd ($C_{12}H_{24}O$) also being present. Gorup-Besanez and Grimm have obtained oil of rue ($C_{11}H_{22}O$) artificially as one of the products of the destructive distillation of acetate and caprate of calcium. 34. Oil of *Savin* (*Oleum Sabinæ*, B. P. and U. S. P.) is isomeric with oil of turpentine $C_{10}H_{16}$). 35. Oil of *Elder-flowers* (*Sambuci Flores*, B. P. and U. S. P.) occurs in very small quantity; it has a butyraceous consistence. It contains a hydrocarbon, *sambucene* ($C_{10}H_{16}$), and probably a camphor. 36. Oil of *Sassafras-root* (*Oleum Sassafras*, U. S. P.), specific gravity 1.094 (*Sassafras Radix*, B. P. and U. S. P.), yields *safren* ($C_{10}H_{16}$) and large quantities of a stearopten, *sassafrol* ($C_{10}H_{10}O_2$). 37. Oil of *Mustard* (*Oleum Sinapis*, B. P.) is the sulphocyanate of allyl (p. 393). If adulterated with alcohol, its specific gravity is below 1.015. 38. Oil of *Turpentine* (*Oleum Terebinthinæ*, B. P. and U. S. P.). Turpentine itself is really an oleoresin of about the consistence of fresh honey. It flows naturally or by incision from the wood of most coniferous trees, larch (*Larix, Europœa*) yielding *Venice Turpentine*, *Abies balsamea* furnishing *Canadian Turpentine*, Balsam of Fir or *Canada Balsam* (*Terebinthina Canadensis*, B. P. and U. S. P.), *Pistachia terebinthus*, the variety termed *Chian Turpentine*, and the *Pinus palustris*, *Pinus abies*, and *Pinus pinaster* affording American Turpentine (*Terebinthus*, U. S. P.). *Pinus maritima* gives the French or Bordeaux Turpentine. By distillation turpentine is separated into *rosin* or *resin* (which remains in the still), and *essential oil of turpentine*, often termed simply *turpentine*, *spirit of turpentine*, or "*turps*" (which distils over). Mixed with alkali to saturate resinous acids, and redistilled, oil of turpentine furnishes *rectified oil of turpentine*. Under the influence of heat, chemical agents, or both, oil of turpentine ($C_{10}H_{16}$) yields many derivatives of considerable chemical interest. 39. Oil of *Valerian-root* (*Valerianæ Radix*, B. P. and U. S. P.) (*Oleum Valerianæ*, U. S. P.) is a mixture of a hydrocarbon ($C_{10}H_{16}$) and *valerol* ($C_6H_{10}O$). Valerol slowly oxidizes to valerianic acid, known by its smell. A similar change occurs at once if the oil of valerian be allowed to fall, drop by drop, on heated caustic potash: $C_6H_{10}O+3KHO+H_2O=K_2CO_3+KC_5H_9O_2+3H_2$. By the action of sulphuric acid on the valerianate of potassium thus produced, valerianic acid is obtained. 40. Oil of *Ginger* (*Zingiber*, B. P. and U. S. P.) has the composition of hydrous oil of turpentine. 41. *Wormseed* (*Chenopodium*, U. S. P.) contains a volatile oil.

42. Oil of *Thyme* (*Oleum Thymi*, U. S. P.) is a mixture of *thymene* ($C_{10}H_{16}$) and *thymol* ($C_{10}H_{14}O$), a solid white crystalline body. Thymol is also contained in, 43, Oil of Horsemint (*Monarda*, U. S. P.).

Camphors.—In addition to the stearoptens or camphors already mentioned as being contained in or formed from volatile oils, there is one that is a common article of trade. It is obtained from the wood of *Camphora officinarum*, or Camphor-Laurel, in Japan (termed in Europe, Dutch camphor, because imported by the Dutch) and in China (known as Formosa camphor), by a rough process of distillation with water, and is resublimed in this country (*Camphora*, B. P. and U. S. P.). The formula of laurel-camphor is $C_{10}H_{16}O$. The essential oil (*Oleum Camphoræ*, U. S. P.), from which doubtless camphor is derived by oxidation, is easily obtained from the wood, and is occasionally met with in commerce under the name of *liquid camphor* or *camphor oil;* its formula is $C_{20}H_{32}O$; by exposure to air it becomes oxidized and deposits common camphor, $C_{20}H_{32}O+O=2C_{10}H_{16}O$. There is another kind of camphor in European markets less common than laurel-camphor, but highly esteemed by the Chinese; it is obtained from the *Dryobalanops aromatica*, and denominated Sumatra or Borneo camphor. It differs slightly from laurel-camphor in containing more hydrogen, its formula being $C_{10}H_{18}O$. It is accompanied in the tree by a volatile oil ($C_{10}H_{16}$) isomeric with oil of turpentine. This oil *borneène*, is also occasionally met with in trade under the name of *liquid camphor* or *camphor oil*, but differs from laurel-camphor oil in not depositing crystals on exposure to air.

Camphor is soluble to a slight extent in water (40 grains per gallon, Pooley). The official Camphor-water (*Aqua Camphoræ*, B. P. and U. S. P.), or *Camphor mixture*, is such a solution.

Cantharidin ($C_5H_6O_2$?), the active blistering principle of cantharides (*Cantharides*, B. P., *Cantharis*, U. S. P.) and other vesicating insects, has most of the properties of a camphor or stearopten. It slowly crystallizes, from an alcoholic tincture of the beetles, in fusible, volatile, micaceous plates. The following process for the extraction of cantharidin is by Fumouze: Powdered cantharides are macerated with chloroform for twenty-four hours; and this treatment is repeated twice with fresh quantities of solvent, the residue having been well squeezed each time. The collected solutions are then distilled, and the dark-green residue treated with bisulphide of carbon, which dissolves fatty, resinous, and other matters, and precipitates the cantharidin. The precipitate is thrown on a filter, washed with bisulphide of carbon, and recrystallized from chloroform. The same process, omitting the final recrystallization, may be used for the quantitative estimation of cantharidin in cantharides. The average quantity found is from four to five parts in one thousand. Cantharidin is readily soluble in warm glacial acetic acid (Tichborne) and in acetic ether.

Massing and Draggendorf consider cantharidin to be an anhydride ($C_5H_6O_2$), and that with the elements of water it forms *cantharidic acid* ($H_2C_5H_6O_2$). A cantharidate of potassium has the composition $KHC_5H_6O_2$.

QUESTIONS AND EXERCISES.

841. How do volatile oils differ chemically from fixed oils?
842. What are the general chemical characters of volatile oils?
843. Describe the usual process by which volatile oils are obtained.
844. Mention the differences in composition between the volatile oils of *Anthemis nobilis* and *Matricaria chamomilla*.
845. Give the systematic name of oil of horseradish.
846. State the general composition of the oil of lemon, lime, bergamot, citron, and cedra.
847. Name the constituents of oil of cloves.
848. In what respect does oil (or otto) of roses differ from other volatile oils?
849. To what class of substances do the constituents of oil of rue belong?
850. How does natural turpentine differ from the turpentine of trade?
851. With what object is commercial turpentine rectified?
852. How is camphor oil related to camphor?
853. In what respects do Borneo or Sumatra camphor and camphor oil differ from the corresponding products of Japan and China?
854. What is the nature of cantharidin?

RESINOID SUBSTANCES.

RESINS, OLEO-RESINS, GUM-RESINS, BALSAMS.

Resins occur in plants generally in association with volatile oils. They closely resemble camphors or stearoptens, but are not volatile, and differ from oils and fats mainly in being solid and brittle. *Oleo-resins* are mixtures of a resin and a volatile oil. *Gum-resins* are mixtures of a resin or oleo-resins and gum. *Balsams* are commonly described as resins or oleo-resins which yield benzoic or cinnamic acid; but oleo-resins containing neither of these acids are often termed balsams, *e. g.*, balsam of copaiva and Canada balsam.

Resins.—1. *Resin*, *rosin*, or *colophony* (*Resina*, B. P. and U. S. P.) is the type of this class. Its source is the oleo-resin or true turpentine of the conifers, a body which by distillation yields spirit of turpentine and a residuum of rosin. "Brown" and "White" rosin are met with in trade. The former is the residue of American, the latter of Bordeaux turpentine (from *Pinus Abies*, etc., and *Pinus Maritima*) respectively. The chief constituents of brown resin are *pinic acid* ($HC_{20}H_{29}O_2$) and *sylvic acid*, identical in composition, but differing in properties (*vide* Isomerism), the former being soluble and the latter insoluble in cold spirit of wine. White resin or "galipot" is chiefly *pimaric acid*, also isomeric with pinic acid. Pinic acid heated yields *colophonic* or *colopholic acid*. Among the products of the destructive distillation of resin, Tichborne has recently found "*colophonic hydrate*" ($C_{10}H_{22}O_3,H_2O$), a white inodor-

ous crystalline substance, and by depriving this of water obtained white crystalline *colophonine* ($C_{10}H_{20}O_3$). Resin is soluble in oil of turpentine. Contact with sulphuric acid immediately colors it strongly red. It is a constituent of eight of the fourteen Plasters (*Emplastra*) of the British Pharmacopœia. 2. *Arnicin*, the chief acrid if not the only active principle of Arnica (*Arnicæ Radix*, B. P., *Arnicæ Flores*, U. S. P.), is a resin. 3. *Cannabin*, said to be the active principle of *Indian Hemp* (*Cannabis Indica*, B. P., *Extractum Cannabis*, U. S. P.), is usually described as a resin. 4. *Capsicum-fruit* contains resin (p. 351). 5. *Castorin*, a resinous matter, is the name given to the chief constituent of *Castor* (*Castoreum*), B. P. and U. S. P.), the dried preputial follicles and included secretion of the Beaver (*Castor Fiber*). 6. *Ergotin* is a very active resinoid constituent of *Ergot* (*Ergota*, B. P. and U. S. P.), or "the sclerotium (compact mycelium or spawn) of *Claviceps purpurea*, produced within the paleæ of the common rye, *Secale cereale*." 7. *Guaiacum-resin* is a mixture of several substances (p. 369). 8. *Jalap-resin* (p. 369). 9. *Kousso* (*Cusso*, B. P.) is said to owe its anthelmintic property to a neutral bitter acrid resin. 10. *Mastic* (*Mastiche*, B. P. and U. S. P.) is a resinous exudation obtained by incision from the stem of the Mastic or Lentisk tree. Nine-tenths of Mastic is *mastichic acid* ($C_{20}H_{31}O_2$), a resin soluble in alcohol; the remaining tenth, *masticin* ($C_{20}H_{31}O$) a tenacious elastic resin. 11. *Mezereon*, the dried bark (*Mezerei Cortex*, B. P. and U. S. P.) of *Daphne mezereum*, Mezereon, and *Daphne laureola*, Spurge Laurel, owes its acridity to a resin. 12. *Pepper* contains a resin (p. 353). 13. *Burgundy Pitch* (*Pix Burgundica*, B. P. and U. S. P.) is the melted and strained exudation from the stem of the Spruce Fir, *Abies Excelsa*. The term Burgundy is a misnomer, the resin never having been collected at or near Burgundy; Finland, and to a smaller extent Baden, and Austria being the countries whence it is derived. Its constituents closely resemble those of common Resin. It is often adulterated and imitated by a mixture of resin with palm-oil, water, etc., from which it may be readily distinguished by its duller yellow color, highly aromatic odor, greater solubility in alcohol, and almost complete solubility in twice its weight of glacial acetic acid (Hanbury). 14. *Podophyllum-resin* (p. 351). 15. *Pyrethrin* is the name of the acrid resinous active principle of *Pellitory-root* (*Pyrethri Radix*, B. P.). 16. The resins of Rhubarb have already been alluded to in connection with Chrysophanic acid (p. 300). 17. *Rottlerin* is the name given by Anderson to a crystalline resin from Kamala (*Kamala*, B. P.), the minute glands that cover the capsules of *Rottlera tinctoria*: to this, and, apparently, allied resins, Kamala owes its activity as an anthelmintic.

Oleo-resins.—1. *Copaiva* (*Copaiba*, B. P. and U. S. P.) is a mixture of about 40 per cent. of essential oil ($C_{15}H_{24}$), with two or more per cent. of brown soft resin, and 50 or more of a yellow dark resin termed *Copaivic acid* ($C_{20}H_{30}O_2$). Copaiva heated with a fourth of its weight of the official carbonate of magnesium yields a transparent fluid, owing to the formation of copaivate of magnesium and solution of this soap in the essential oil. With an equal weight of the car-

bonate enough soap is produced to take up the whole of the essential oil, and form a mass capable of being rolled into pills. A much smaller quantity of calcined magnesia, as might be expected, effects the same result; but more time, often several days, is required before complete reaction is effected. Quicklime has a similar effect. Perhaps carbonate reacts more quickly because of its fine state of division and admixture of hydrate—in which case hydrates of calcium and magnesium may be expected to act better than the calcined preparations, and in much smaller quantity than carbonate of magnesium. Copaiva is soluble in its own bulk of benzol, and, unlike, 2, Wood-oil, a similar oleo-resin from the *Dipterocarpus turbinatus*, does not become gelatinous when heated to 270° F. Copaiva, also, is not fluorescent. 3. *Elemi* (*Elemi*, B. P.) is an exudation from an unknown tree (probably *Canarium commune*). It consists of volatile oil with 80 or more per cent. of two resins, the one ($C_{20}H_{32}O_2$) soluble in cold alcohol, the other ($C_{20}H_{33}O$) almost insoluble. 4. *Wood-Tar* (*Pix Liquida*, B. P. and U. S. P.) is a mixture of several resinoid and oily bodies (amongst others Creasote, p. 392) obtained by destructive distillation from the wood of *Pinus sylvestris* and other pines. When heated it yields a terebinthinate oil and a residue of *pitch*. 5. *Turpentines*. These oleo-resins have been mentioned in connection with oil of turpentine, their volatile, and resin, their fixed constituent. 6. *Common Frankincense* (*Thus Americanum*, B. P.) is the concrete turpentine of *Pinus tæda*. 7. *Canada Balsam* (*Terebinthina Canadensis*, B. P.) is the turpentine or oleo-resin of the Balm of Gilead Fir (*Abies balsamea*). 8. *Sumbul-root* (*Sumbul Radix*, B. P.) seems to owe its stimulating property to two oleo-resins, one soluble in ether, the other in alcohol. 9. *Oleo-resin of Lupulin* (U. S. P.) is an ethereal extract of the yellow powder (*Lupulina*, U. S. P.) attached to the small nuts at the base of the scales which form the aggregate fruit of the Hop (*Humulus Lupulus*). It contains essential oil of hop and oxidized oil or resin. *Oleoresinæ Capsici*, *Cubebæ*, *Piperis*, and *Zingiberis* are also official in the United States Pharmacopœia. 10. *Pix Canadensis*, U. S. P., is the concrete juice of *Abies Canadensis*.

Gum-resins.—1. *Ammoniacum* (*Ammoniacum*, B. P. and U. S. P.) is an exudation from the *Dorema Ammoniacum*. It contains nearly 20 per cent. of gum and about 70 of resin ($C_{40}H_{30}O_9$—Johnston). 2. *Assafœtida* (*Assafœtida*, B. P.) is a gum-resin obtained, by incision, from the living root of *Narthex assafœtida*. It contains from 50 to 70 per cent. of resin, 25 to 30 per cent. of gum (about two-thirds arabin, one-third bassorin, p. 97), and 3 to 5 per cent. of volatile oil. 3. *Gamboge* (*Cambogia*, B. P. and U. S. P.) is obtained from the *Garcinia morella*. When of best quality it contains from 20 to 25 per cent. of gum, and 80 to 75 per cent. of a resin termed *gambogic acid* ($C_{20}H_{23}O_4$). 4. *Galbanum* (*Galbanum*, B. P. and U. S. P.) contains from 20 to 25 per cent. of gum, and about 65 per cent. of resin ($C_{40}H_{54}O_7$), and 3 or 4 per cent. of volatile oil. 5. *Myrrh* (*Myrrha*, B. P. and U. S. P.), an exudation from the stem of *Balsamodendron myrrha*, contains about half its weight of soluble gum (probably arabin), 10 per cent. of insoluble gum (probably

bassorin), $2\frac{1}{2}$ of volatile oil, and about 25 per cent. of resin (myrrhic acid). 6. *Scammony* (p. 371).

Gum-resins need only be finely powdered and rubbed in a mortar with water to yield a medicial *emulsion*, in which the fine particles of resin are held in suspension by the aqueous solution of gum.

Balsams.—1. *Benzoin* (*Benzoinum*, B. P. and U. S. P.) is obtained from incisions of the bark of *Styrax benzoin*. It contains 12 to 15 per cent. of benzoic acid (p. 298), about 50 per cent. of a resin (α) soluble in ether, 25 to 30 per cent. of a resin (β) soluble in alcohol only, and 3 to 4 per cent. of a resin (γ) soluble in solution of carbonate of sodium. The α resin is considered to be a compound of the β ($C_{40}H_{46}O_9$) and the γ ($C_{30}H_{40}O_5$). The balsams of Peru, Tolu, and Storax differ from benzoin in containing cinnamic (p. 407) in place of benzoic acid; hence they yield, by oxidation, hydride of benzoyl (oil of bitter almonds). 2. *Balsam of Peru* (*Balsamum Peruvianum*, B. P. and U. S. P.), from the *Myroxylon Pereiræ*, is a mixture of 70 per cent. of oily with about 23 of resinous matter, and 6 per cent. of cinnamic acid. The oil, by fractional distillation in an atmosphere of carbonic acid gas and under diminished pressure, furnishes *benzylic alcohol* (C_7H_7HO), *benzoate of benzyl* ($C_7H_7C_7H_5O_2$), and *cinnamate of benzyl* ($C_7H_7C_9H_7O_2$) (Kraut). By action of alcoholic solution of potash it yields benzoate and cinnamate of potassium, and benzylic alcohol; also *cinnamic alcohol* (C_9H_9HO), otherwise known as *peruvine* or *styrone;* it also often holds in solution *metacinnaméin* or *styracin* ($C_{18}H_{16}O_2$), isomeric with hydride of cinnamyl (C_9H_7OH). The resin of balsam of Peru seems to result from the action of moisture on the oil. The constituents of *Vanilla*, U. S. P., the prepared unripe pods of a plant, somewhat resemble those of Balsam of Peru. The crystals often found on vanilla are a weak acid substance having the formula $C_{16}H_{16}O_6$ (Carles). 3. *Balsam of Tolu* (*Balsamum Tolutanum*, B. P. and U. S. P.) is an exudation from incisions in the bark of *Myroxylon toluifera;* it closely resembles balsam of Peru, but is more susceptible of resinification. Old hard balsam of tolu is a convenient source of cinnamic acid, which is extracted by the same process as that by which benzoic acid is obtained from benzoin, namely, ebullition with alkali, filtration, and precipitation by hydrochloric acid. 4. *Storax* is an oleo-resin obtained from the *Liquidambar orientale*. It contains a volatile oil term *styrol* (C_8H_8), cinnamic acid, styracin, and a soft and a hard resin. Styrol differs from similar hydrocarbons in being converted into a polymeric solid termed *metastyrol* or *draconyl* on the mere application of a temperature of about 400° F. For medicinal use, storax (*Styrax Præparatus*, B. P. and U. S. P.) is purified by solution in alcohol, filtration, and removal of the alcohol by distillation.

Caoutchouc or *India-rubber*, and *Gutta Percha*.

Caoutchouc is the hardened juice of *Hevea* (*Siphonia*) *Braziliensis*, *Castilloa elastica*, *Urceola elastica*, *Ficus elastica*, and other plants (Collins). Heated moderately with sulphur it takes up 2 or 3 per cent., and forms *vulcanized India-rubber;* at a higher tem-

perature a hard horny product, termed *ebonite* or *vulcanite*, results. *Gutta Percha* (U. S. P.) is the concrete drop or juice of the *percha* (Malay) tree, the *Isonandra gutta*, and of other Sapotaceous plants. It is soluble in chloroform (*Liquor Gutta-percha*, U. S. P.), benzoyl, and essential oils. White gutta percha is obtained by precipitating a solution of the ordinary gutta percha in chloroform by alcohol, washing the precipitate with alcohol, and finally boiling in water and moulding into desired form while still hot.

These two elastic substances, in the pure state, are hydrocarbons (xC_5H_4), usually slightly oxidized.

QUESTIONS AND EXERCISES.

855. Distinguish between resins and camphors. Mention the points of difference of resins, oleo-resins, gum-resins, and balsams.

856. Name the constituents of common Resin.

857. Enumerate some official articles of which the active constituents are resins.

858. Give the chief distinguishing characters of Burgundy Pitch.

859. What is the average proportion of oil in Copaiva?

860. Explain the effect of magnesia or lime on copaiva.

861. State the nature of Wood-tar.

862. Why do Ammoniacum, Assafœtida, Gamboge, Galbanum, and Myrrh give an emulsion by mere trituration with water?

863. In what respect does Benzoin differ from the Balsams of Peru, Tolu, and Storax?

864. What is the chemical nature of India-rubber and Gutta Percha?

865. How is India-rubber *vulcanized* and converted into *ebonite* or *vulcanite?*

COLORING-MATTERS.

The animal, vegetable, and mineral kingdoms abound in substances or pigments which powerfully decompose light, absorbing certain of its constituent colors, and reflecting some others. Thus, for example, most leaves contain a body termed chlorophyll, which has the property of absorbing red light and reflecting green; these reflected rays entering the eye of an observer, and striking on the retina (the expanded extremity of the optic nerve), always communicate the same impression to the brain; in popular language the leaf is said to be green. Art has added largely to the number of natural coloring-matters.

Yellow.—1. *Chrome-yellow* occurs in more than a dozen shades (see *Lead, chromate of*). 2. *Fustic* or *yellow wood* is the wood of the *Rhus cotinus*. 3. *Gamboge* (see *Gamboge*). 4. *Ochre* is met with of many tints, under the names of *yellow ochre, gold yellow, gold earth* or *ochre, yellow sienna, Chinese yellow.* It is chiefly

a mixture of oxyhydrates of iron with alumina and lime. 5. *Orpiment* is a sulphide of arsenicum (As_2S_3). 6. *Persian berries* or *Avignon grains* contain a principle termed *chrysorhamnin* ($C_{23}H_{22}O_{11}$). They are the product of the *Rhamnus infectorius*. 7. *Purree* or *Indian yellow* is said by Stenhouse to owe its color to *purrate* or *euxanthate of magnesium* ($MgC_{42}H_{34}O_{22}$). 8. *Quercitron* is the bark of *Quercus tinctoria*, U. S. P., or Black Oak. It contains the yellow glucoside, *quercitrin* ($C_{18}H_{18}O_{10},H_2O$). 9. *Rhubarb* (see *Chrysophanic acid*, p. 300). 10 *Saffron* (*Crocus*, B. P. and U.S. P.), the dried stigma and part of the style of *Crocus sativus*, yields *saffranin* or *polychroite*, a yellow principle whose chemistry is but little known. 11. *Turmeric*, the rhizome of *Curcuma longa*, owes its yellow color to *curcumin*, a resinous matter, the formula of which is said by Daube to be $C_{10}H_{10}O_3$, and by Iwanof C_4H_4O. Possibly two yellow pigments are present. 12. *Weld* (*Reseda luteola*) contains a durable yellow matter termed *luteolin* ($C_{20}H_{14}O_3$). 13. *Picric* or *carbazotic acid* (p. 392) is a very powerful yellow dye. 14. Dried and powdered carrots yield to bisulphide of carbon a yellow coloring-matter, "carrotin," which is obtained on evaporating the solvent. It is said to be used in coloring butter.

Red.—1. *Alkanet*, the root of *Alkanna tinctoria*, Tausch, *Anchusa tinctoria*, Desf., yields *anchusin* ($C_{35}H_{40}O_8$), a resinoid matter soluble in oils and fats. 2. *Annato*, *Arnatto*, or *Arnotto*, a paste prepared from the seeds of *Bixa orellana*, contains *bixin*, an orange-red, and *orellin*, a yellow principle. 3. *Brazil-wood* (*Cæsalpinia brasiliensis*) furnishes *brezilin*, the basis of several lakes. *Sapan-wood* and *Cam-wood* probably contain the same substance. 4. *Cinnabar*, Chinese red, Vermilion, or Paris red is mercuric sulphide. 5. *Chrome-red* is an oxychromate of lead. 6. *Cochineal* (p. 300). 7. *Madder*, the root of *Rubia tinctorum*, powdered and treated with sulphuric acid and acidulated water to effect the removal of earthy and other inert matters, furnishes a residual powder termed *garancin*. Garancin yields to pure water *alizarin* ($C_{14}H_{10}O_4$, $3H_2O$), the red, neutral, crystallizable coloring-matter of madder. Alizarin does not exist ready formed in the plant, but is derived, by fermentation, from rubian, a yellowish resinoid substance. Alizarin is now produced artificially from *anthracene*, one of the solid constituents of coal-tar. 8. *Mulberry-juice* (*Mori Succus*, B. P.) contains a violet-red coloring-matter which has not been chemically examined. 9. *Red lead* (p. 187). 10. *Red oxide of iron*, of shades varying from light to brown red, is found native. The common names of it are Armenian bole, Berlin-red, colcothar, English red, red ochre, burnt ochre, red earth, terra di sienna, mineral purple, stone red, and Indian red. 11. *Red Sandal-wood* (*Pterocarpi Lignum*, B. P. and U. S. P.), the billets and chips of *Pterocarpus santalinus*, owes its color to *santalin* ($C_{16}H_{16}O_3$), a resinoid matter. 12. *Red-Poppy Petals* (*Rhœdos Petula*, B. P.), from the *papaver rhœas*, contain a red coloring principle which has not yet been isolated. 13. *Red-Rose Petals* (*Rosæ Gallicæ Petala*, B. P. and U. S. P.) also yield a red substance which has not been analyzed. 14. *Safflower*, *Dyer's Saffron* or *Bastard Saffron*, the florets of *Carthamus tinc-*

torius, contains an unimportant yellow dye, and 5 per cent. *carthamin* ($C_{14}H_{16}O_7$), an uncrystallizable red dye, the pigment of the old *pink saucers*. Carthamin seems to possess acid characters, and (like silicic acid and other substances) to be soluble in water for a certain time after liberation from its alkaline solution; for fabrics are dyed with safflower by immersion in a bath made of an infusion in dilute alkali neutralized by citric acid immediately before use, the carthamin probably penetrating the cells and vessels of the fibres in a soluble form, there becoming insoluble and imprisoned and thus giving permanent color to the wool, silk, or other material. Mixed with French chalk, carthamin is used as a cosmetic under the name of *vegetable rouge—carmine* being *animal rouge*, and *red oxide of iron mineral rouge*. 15. *Lac-dye* is a cheap form of cochineal, and is also yielded by a species of *Coccus*. 16. *Logwood* (*Hæmatoxyli Lignum*, B. P.) contains a yellow substance, *hæmatoxylin* ($C_{16}H_{14}O_6H_2O$ or $3H_2O$), which, under the influence of air and alkali, assumes an intense red color. 17. *Red enamel* colors, for glass-staining and ceremic operations, are produced either by cuprous silicate or purple of Cassius (p. 218).

Blue.—1. *Cobalt oxide* precipitated in combination or admixture with alumina or phosphate of calcium forms *Thénard's blue*, *cobalt-blue*, *Hoffner's blue*, and *cobaltic ultramarine*. 2. *Smalt*, *Saxony blue*, or *King's blue*, is rough cobalt glass in fine powder (p. 207). 3. *Copper-blue*, *mountain-blue*, and *English* or *Hambro' blue* are carbonates or oxycarbonates of copper. 4. *Indigo* (p. 258). 5. *Litmus*, *lichen-blue*, *turnsole*, *orchil* or *archil*, and *cudbear* are products of the action of air and alkalies on certain colorless principles, as *orcin* ($C_7H_8O_2$), derived from different species of lichen—*Roccella*, *Variolaria*, and *Lecanora*. 6. *Prussian blue* (p. 303) and *Turnbull's blue* (p. 304), the ferro- and ferridcyanides of iron, are met with under the names of *Erlangen*, *Louisa*, *Saxon*, *Paris*, *or Berlin blue*. 7. *Ultramarine* is made on a large scale by roasting a mixture of fine white clay, carbonate of sodium, sulphur, and charcoal. Its constitution is not well made out. Acids decompose it, sulphuretted hydrogen escaping.

Green.—1. *Cupro-arsenical* green pigments (p. 152). 2. *Chlorophyll*, *Leaf-green*, or *Chromule*. A method of extracting chlorophyll is given under "Extracts," *vide* Index. It is resinoid, soluble in alcohol and ether, insoluble in water, and, according to Frémy, consists of a blue substance, *phyllocyanin* ($C_{34}H_{68}N_4O_{17}$?), and a yellow, *phylloxanthin;* the yellow tints in fading autumnal leaves, he says, are due to the latter principle, the former being the first to fade. 3. *Sap-green*, *buckthorn-*, *vegetable-*, or *bladder-green* is obtained by evaporating to dryness a mixture of lime and the juice (*Rhamni Succus*, B. P.) of the berries of the Buckthorn (*Rhamnus catharticus*). It is soluble in water, slightly in alcohol, and insoluble in ether and oils. 4. *Green ultramarine* is made by a process similar to that for blue ultramarine. 5. Mixtures of blue and yellow pigments and dyes are common sources of green colors. 6. Glass and earthenware are colored green by oxide of chromium and black oxide of copper.

Brown.—1. *Umber*, *Sienna*, or *Chestnut-brown* is found native. By heat it is darkened in tint, and is then known as *burnt umber*. It is a mixture of oxide of iron, silica, and alumina. 2. *Sepia* is a dried fluid from the ink-bag of cuttlefishes (*Sepiadæ*); by its ejection into adjacent water the animal obtains opportunity of escape from enemies. 3. *Catechu* (p. 318) furnishes a brown coloring-matter.

Black.—1. *Blacklead* (p. 26), *bone-black* (p. 95), or *ivory-black*, and *lampblack*, the latter a deposited soot from incomplete combustion of resin and tar, are varieties of carbon. 2. *Burnt sugar* or *caramel* (p. 364). 3. *Indian ink* is usually a dried mixture of fine lampblack and size, or thin glue. 4. *Black ink* is essentially tannates and gallates of iron suspended in water containing a little gum in solution. 5. *Printer's ink* is well boiled linseed or other oil, mixed with good lampblack, vermilion, or other pigment. 6. *Black dyes* are of the same nature as ink.

White Pigments.—1. *Chalk* or *Whiting* (p. 94). 2. *French chalk*, *steatite*, or *soapstone*, a silicate of magnesium. 3. *Heavy white* (p. 87). 4. *Pearl-white* (p. 224). 5. *Plaster of Paris* (p. 90). 6. *Starch* (p. 355). 7. *White-lead* (p. 185). 8. *Zinc-white* (p. 113). 9. Oxides of tin and zinc and phosphate of calcium are employed for giving a white opacity to glass.

Aniline Colors. *Coal-tar colors.*—Within the last ten years nearly every shade of color seen in the animal or vegetable kingdoms has been successfully imitated by certain dyes and pigments primarily derived from a mineral, coal. Coal distilled for gas furnishes tar or gas-tar. Coal-tar contains some aniline; but especially it contains a liquid convertible into aniline, namely benzol (C_6H_5H), first discovered by Faraday in compressed oil-gas. From aniline, by oxidation, Runge obtained the violet color-reaction, the body producing which Perkin afterwards studied and isolated, and manufactured under the name of *mauve*. *Aniline-red* (*fuchsine*, *magenta*, or *rosaniline*), *aniline-yellow*, *aniline-green*, *aniline-blue*, and, in short, aniline-dyes, lakes, and pigments of every hue of the rainbow, are now common articles of trade. Their application has revolutionized the arts of the dyer and color printer.

QUESTIONS AND EXERCISES.

866. Explain the production of color.
867. Mention the chief yellow coloring-matters.
868. What is annatto?
869. Name the colorific constituent of madder.
870. State the source of Litmus.
871. Distinguish between Prussian blue and Turnbull's blue.
872. How is blue ultramarine obtained?
873. Describe the coloring principle of green leaves.
874. By what agents is glass colored green?
875. Whence is sepia obtained?
876. Describe the chemistry of black ink.
877. Write a few sentences on *aniline colors*.

CHEMICAL TOXICOLOGY.

In cases of criminal and accidental poisoning, the substances presented to the chemical analyst for examination are usually articles of food, medicines, vomited matters, or the liver, kidney, intestines, stomach and contents, removed in course of post-mortem examination. In these cases some special operations are necessary before the poison can be isolated in a state of sufficient purity for the application of the usual tests; for in most instances the large quantity of animal or vegetable, or, in one word, organic matter present prevents or masks the characteristic reactions on which the tests are founded. These operations will now be described;* they form the chemical part of the subject of toxicology (τοξικὸν, *toxicon*, poison, and λόγος, *logos*, discourse).

Substances occurring in the form of an apparently definite salt or unmixed with organic matter need no special treatment, they are analyzed by the ordinary methods already given, attention being restricted to poisonous compounds only.

Examination of an organic mixture suspected to contain: Mercury, Arsenicum, Antimony, Lead, Copper, or Zinc; Sulphuric Acid, Nitric Acid, Hydrochloric Acid, Oxalic Acid, or Hydrocyanic Acid; Caustic Alkalies; Strychnia or Phosphorus; Morphia or other Poisonous Alkaloids.

Preliminary Examination.

Odor, *Appearance*, *Taste*.—Smell the mixture, with the view of ascertaining the presence or absence of any notable quantity of free hydrocyanic acid. Look carefully for any small solid particles, such as arsenic, corrosive sublimate, or verdigris, and for any appearance which may be regarded as abnormal, any character unusual to the coffee, tea, beer, medicine, vomit, coats of stomach, kidney, liver, or other organ, tissue, or solid matter under examination. If liquid or semifluid, taste the mixture, or add to a small portion some solution of carbonate of sodium, with the view of ascertaining by excessive sourness or strong effervescence the presence of any large, poisonous quantity of sulphuric, nitric, or hydrochloric acid. If so excessively alkaline as to require the addition of a very large quantity

* Materials for these experiments are readily obtained for educational purposes by dissolving the poison in infusions of tea, coffee, porter, or in water to which some mucilage of starch or linseed-meal, pieces of bread, potato, and fat have been added.

of acid before neutralization is effected, a noxious quantity of a corrosive or caustic alkali is present.

Special instructions may induce the operator to suspect the presence of one particular poison. Direct examination for the latter may then be made, either at once, if the substance has an aqueous character, or when filtration or treatment with warm hydrochloric or acetic acid has afforded a more or less colorless liquid.

Fluids.—A vomit or the contents of a stomach, if set aside in a long narrow vessel (test-glass or ale-glass), or, better, exposed on a filter during a night, will often yield a more or less clear limpid portion at the bottom or top of the solid matter. This fluid (separated by a pipette or otherwise) will sometimes respond to tests without further preparation, and always requires less preparatory treatment than a semisolid mixture. If none passes through a filter, a portion often collects in the upper part.

General procedure.—If the preliminary examination does not indicate the method to be pursued, proceed as follows, treating a portion (not more than one-fourth) of the mixture for the poisonous metals, another for the acids, and a third for alkaloids, reserving the remainder for any special experiments which may suggest themselves in the course of analysis.

Examination for Mercury, Arsenicum, Antimony, Lead, Copper, Zinc.

If a liquid, acidulate with hydrochloric acid and boil for a short time. If solid or semisolid, cut up the matter into small pieces, add enough water to form a fluid mixture, stir in ten or twenty per cent. of ordinary liquid hydrochloric acid, and boil until, from partial aggregation and solution of the solid matter, filtration can be easily effected.

Heat a portion of the clear liquid with a thin piece of bright copper or copper gauze, about an inch long and a quarter of an inch broad, for about ten or twenty minutes; metallic *mercury*, *arsenicum*, or *antimony* will be deposited on the copper, darkening it considerably in color. Pour off the liquid from the copper, carefully rinse the latter with a little cold water, dry the piece of metal by holding it over or near a flame (using fingers, not tongs, or it may become sufficiently hot for loss of mercury or arsenicum to occur by volatilization), introduce it into a narrow test-tube or piece of glass tubing closed at one end, and heat

the bottom of the tube in a flame, holding it horizontally that the upper part of the tube may be kept cool, and partially closing the mouth with the finger to prevent escape of vapor. Under these circumstances any *Mercury* will volatilize from the copper and condense on the cool part of the tube in a ring or patch of white sublimate, readily aggregating into visible globules on being pressed by the side of a thin glass rod inserted into the tube; *Arsenicum* will volatilize from the copper, and, absorbing oxygen from the air in the tube, condense on the cool part of the glass in a ring or patch of white sublimate of arsenic (gray or even darker if much arsenicum as well as arsenic be present), not running into globules when rubbed, but occurring in small crystals, the characteristic octahedral form of which is readily seen by aid of a good hand lens, or the lower part of a microscope; *Antimony* volatilizes from the copper, if strongly heated, and, absorbing oxygen, immediately condenses as a slight white deposit close to the metal.

Confirmatory Tests.—1. Nothing short of the production of globules should be accepted as evidence of the presence of mercury. It will usually have existed as corrosive sublimate.

2. To confirm indications of the presence of arsenicum, a portion of the acid liquid may be subjected to the hydrogen tests (pp. 149, 151); or the tube containing the white crystalline arsenic may be broken, and the part on which the sublimate occurs boiled for some time in water, and the hydrosulphuric-acid, ammonio-nitrate-of-silver, and ammonio-sulphate-of-copper tests (pp. 151, 153) applied to the aqueous solution.

3. For antimony, a portion of the acid liquid must always be introduced into the hydrogen-apparatus with the usual precautions. (*Vide* p. 160.)

For *Lead* and *Copper*, pass hydrosulphuric acid gas through the clear acid liquid for some time, warming the liquid if no precipitate is produced, or diluting and partially neutralizing the acid by ammonia if much acid has been added. Collect on a filter any black precipitate that may have formed; wash, dissolve in a few drops of aqua regia, dilute, and apply the tests, such as ammonia for copper, sulphuric acid for lead, and any other of the ordinary reagents (pp. 168, 189).

Copper may often be at once detected in a small quantity of acidulated liquid by immersing the point of a penknife or a piece of bright iron wire—a deposit of copper, in its characteristic color, quickly or slowly appearing, according to the amount present (p. 168).

Zinc.—To the acid liquid through which sulphuretted hydrogen has been passed, add excess of ammonia (or to the original acid fluid add excess of ammonia, and then sulphydrate of ammonium); a precipitate falls which may contain alumina, phosphates, and zinc; it is usually blackish from the presence of sulphide of iron. Collect the precipitate on a filter, wash, dissolve in a little hydrochloric acid, add a few drops of nitric acid, boil, pour in excess of ammonia, filter, and test the filtrate with sulphydrate of ammonia—a white precipitate indicates zinc.

Examination for Mineral Acids, Oxalic Acid, or Hydrocyanic Acid.

To detect *Hydrochloric*, *Nitric*, or *Sulphuric Acid* in any liquid containing organic matter, dilute with water and apply to small portions the usual tests for each acid, disregarding indications of small quantities. (*Vide* pp. 240, 256, 277.)

Excessive sourness, copious evolution of carbonic acid gas on the addition of carbonate of sodium, and abundant evidence of acid on applying the various tests to small portions of the fluid presented for analysis, collectively form sufficient evidence of the occurrence of a poisonous amount of either of the three common mineral acids. Small quantities of the hydrochloric, nitric, and sulphuric radicals occurring as metallic salts or acids, are common normal constituents of food, hence the direction to disregard insignificant indications. If the fluid under examination is a vomit or the contents of a stomach, and an antidote has been administered, free acid will not be found, but, instead, a large amount of corresponding salt.

For *Oxalic Acid*, filter or strain a portion of the liquid, if not already clear, and add solution of acetate of lead so long as a precipitate occurs; collect the precipitate, which is partly oxalate of lead, on a filter, wash, transfer it to a test-tube or test-glass, add a little water, and pass hydrosulphuric gas through the mixture for a short time; the lead is thus converted into the insoluble form of sulphide, while oxalic acid is set free in the solution. Filter, boil to get rid of hydrosulphuric gas, and apply the usual tests for oxalic acid (see p. 282) to the clear filtrate.

The contents of a stomach containing oxalic acid are often of a dark-brown color with a tinge of green (altered blood and mucus), and the viscid mixture generally, though slowly, affords some clear, limpid, almost colorless liquid by filtration on standing.

For *Hydrocyanic Acid*, the three chief tests may be ap-

plied at once to the liquid or semiliquid organic mixture, whether it has an odor of hydrocyanic acid or not. First: half fill a small porcelain crucible with the material, add eight or ten drops of strong sulphuric acid, stir gently with a glass rod, and invert ever the mouth of the crucible a watch-glass moistened with a small drop of solution of nitrate of silver; a white film on the silver solution is probably cyanide of silver, formed by the action of the gaseous hydrocyanic acid on the nitrate of silver. Second: prepare a small quantity of the organic mixture as before, slightly moistening the centre of the watch-glass with solution of potash; here again the heat generated by the action of the strong acid is sufficient to volatilize some of the hydrocyanic acid, which, reacting on the potash, forms cyanide of potassium. On removing the watch-glass and stirring into it successively solution of a ferrous salt, a ferric salt, and hydrochloric acid, flocks of prussian blue are produced if hydrocyanic acid is present. Third: proceed as before, moistening the watch-glass with sulphydrate of ammonium; after exposure to the hydrocyanic gas for five or ten minutes, add a drop of solution of ammonia, evaporate to dryness at a low temperature, and add a drop of hydrochloric acid and of solution of perchloride of iron; a blood-red color, due to sulphocyanate of iron, is produced if cyanogen is present.

If the above reactions are not well marked, the organic mixture may be carefully and slowly distilled in a small retort, the neck of which passes into a bottle and dips beneath the surface of a little water at the bottom of the bottle, and the reagents then applied to separate portions of the distillate.

The examination of organic mixtures for hydrocyanic acid must be made without delay, as the poison soon begins to decompose, and in a day or two is usually destroyed.

Examination for Phosphorus.

A paste containing phosphorus is commonly employed for destroying vermin. In cases of poisoning the phosphorus is commonly in sufficient quantity to be recognized by its characteristic unpleasant smell. A stomach in which it occurs not unfrequently exhibits slight luminosity if opened in a dark room. When the phosphorus is too small in quantity or too much diffused to afford this appearance, a portion of the material is placed in a flask, water acidulated by sulphuric acid added, a long wide glass tube fitted to the neck of the flask by a cork, and the mixture gently boiled. If phosphorus is present (even 1 part in 2,000,000, according to De Vry) the top of the column of steam as it condenses in the tube will appear distinctly

phosphorescent when viewed in a dark room. From its liability to oxidation phosphorus cannot be detected after much exposure of an organic mixture to air.

Examination for Strychnia and Morphia.

Strychnia.—If solid or semisolid, digest the matter with water and about 10 per cent. of hydrochloric acid till fluid, filter, evaporate to dryness over a water-bath. If the organic mixture is already liquid, it is simply acidulated with hydrochloric acid and evaporated to dryness. The acid residue is next treated with spirit of wine as long as anything is dissolved, the filtered tincture evaporated to dryness over the water-bath, and the residue digested in water and filtered. This slightly acid aqueous solution must now be rendered alkaline by ammonia, and well shaken in a bottle or long tube with about half an ounce of chloroform, and set by till the chloroform has subsided. The chloroform (which contains the strychnia) is then removed by a pipette, the presence of any aqueous liquid being carefully avoided, and evaporated to dryness in a small basin over a water-bath, the residue moistened with concentrated sulphuric acid, and the basin kept over the water-bath for several hours. (It is highly important that the sulphuric acid used in this operation should be free from nitrous compounds. Test the acid, therefore, by adding powdered sulphate of iron, which becomes pink if nitrous bodies are present. If these are found, the acid should be purified by strongly heating with sulphate of ammonium, seventy or eighty grains to a pint.) The charred material is exhausted with water, filtered, excess of ammonia added, the filtrate shaken with about a quarter of an ounce of chloroform, the mixture set aside for the chloroform to separate, and the chloroform again removed. If, on evaporating a small portion of this chloroform solution to dryness, adding a drop of sulphuric acid to the residue, and warming, any darkening in color or charring takes place, the strychnia is not sufficiently pure for chemical detection; in that case the rest of the chloroform must be removed by evaporation, and the residue redigested in warm sulphuric acid for two or three hours. Dilution, neutralization of acid by ammonia, and agitation with chloroform are again practised, and the residue of a small portion of the chloroform solution once more tested with sulphuric acid. If charring still occurs, the treatment must be repeated a

third time. Finally a part of the chloroform solution is taken up by a pipette, and drop after drop evaporated on one spot of a porcelain crucible-lid until a fairly distinct dry residue is obtained. A drop of sulphuric acid is placed on the spot, another drop placed near, a minute fragment of red chromate of potassium placed in the second drop, and when the acid has become tinged with the chromate, one drop drawn across the other; the characteristic evanescent purple color is then seen, if strychnia is present. Other tests (*vide* p. 248) may be applied to similar spots.

This is Girdwood and Rogers's method for the detection of strychnia when mixed with organic matter. It is tedious but trustworthy, and, though apparently complicated, very simple in principle; thus: strychnia is soluble in acidulated water or alcohol, or in chloroform, readily removed from an alkaline liquid by agitation with chloroform, and not charred or otherwise attacked when heated to 212° F. with sulphuric acid: much of the organic matter of the food is insoluble in water; of that soluble in water, much is insoluble in alcohol; and of that soluble in both menstrua, all is charred and destroyed by warm sulphuric acid in a shorter or longer time.

Morphia, and the Meconic Acid with which it is associated in Opium.—To the liquid or the semifluid mixture warmed for some time with a small quantity of acetic acid, filtered, and concentrated if necessary, add solution of acetate of lead until no further precipitate is produced. Filter and examine the *precipitate* for meconic acid, reserving the *filtrate* for the detection of morphia.

The Precipitate.—Wash the *precipitate* (meconate of lead, etc.) with water, place it in a test-tube or test-glass with a small quantity of water, pass hydrosulphuric acid gas through the mixture for a short time, filter, slightly warm in a small basin, well stirring to promote removal of excess of the gas, and add a drop of neutral solution of perchloride of iron; a red color, due to the formation of meconate of iron, is produced if meconic acid is present. This color is not destroyed on boiling the liquid, as is the case with ferric acetate, nor is it bleached by solution of corrosive sublimate, thus distinguishing it from the ferric sulphocyanate. It is discharged by hydrochloric acid.

The Filtrate.—The solution from which meconic acid has been removed by acetate of lead is evaporated to a small bulk over a water-bath, excess of carbonate of potassium added, and evaporation continued to dryness. The residue is then treated with alcohol, which dissolves the

morphia. The alcoholic solution evaporated similarly may leave the morphia sufficiently pure for the application of the usual tests (*vide* page 341) to small portions of the residue. If no reaction is obtained, add a drop of sulphuric acid and a little water to the residue and shake with ether, in which the salt of morphia is insoluble. The treatment with ether may be repeated until nothing more is removed, the acid aqueous liquid saturated with carbonate of potassium, the mixture evaporated to dryness, the residue digested in alcohol, filtered, and portions of the alcoholic liquid evaporated to obtain spots of morphia for the application of the ordinary tests.

If much organic matter is believed to remain in the filtrate after the acetate of lead treatment, or if a considerable excess of acetate of lead has been employed, the filtered liquid should be subjected to a current of sulphuretted hydrogen until no more sulphide of lead is precipitated, the mixture filtered, and the filtrate, with the washings from the sulphide of lead, evaporated to a small bulk, excess of carbonate of potassium added, the whole well mixed and agitated with twice or thrice its bulk of a mixture of ether and acetic ether (ether alone might not dissolve the morphia). On standing the ethereal liquid rises to the surface; it is carefully removed, evaporated to dryness, and the residue tested or further purified in the manner described in the preceding paragraph.

The examination for morphia must be conducted with great care, and with as large a quantity of material as can be spared: for its isolation from other organic matter is an operation of considerable difficulty, especially when only a minute proportion of alkaloid is present. Fortunately the detection of meconic acid does not include similar difficulties; and, as its reactions are quite characteristic, its presence is held to be strong evidence of the existence of opium in an organic mixture.

Examination for Other Poisonous Alkaloids.

Stas's Process.—Minutely subdivide any solid matter; to this and the liquid portion of the vomit, etc., add about twice their weight of the strongest spirit of wine containing sufficient tartaric acid to fairly acidify the mixture. Digest the whole in a flask at a temperature of 150° or 160° F.; set aside to cool; filter. The solution, which will contain the whole of the alkaloid, should then be evaporated nearly to dryness *in vacuo*, or at all events at a temperature not

exceeding 100° F., lest volatile alkaloids should be dissipated. The residue is next exhausted with cold anhydrous alcohol; filtered; and the filtrate evaporated to dryness with the precautions already stated. The extract is dissolved in a very small quantity of water, treated with excess of powdered bicarbonate of sodium or potassium, and well shaken with five or six times its volume of pure ether (with perhaps a little acetic ether). This ethereal liquid contains the alkaloid. Small portions should be evaporated in watch-glasses and tasted, or tested physically and chemically, according as the knowledge of collateral circumstances by the operator, or his experience, or the reactions recorded on pp. 349–354, may suggest.

If a volatile alkaloid (conia, nicotia, hyoscyamia, lobelina) is indicated, the ethereal solution, which may still contain animal matter, is removed, agitated with aqueous solution of potash, decanted, and shaken with pure diluted sulphuric acid. On standing, the aqueous portion, containing the alkaloid as acid sulphate, subsides; the upper ethereal portion containing the animal matter is rejected; the acid aqueous liquid is made alkaline with caustic potash or soda; ether added; well shaken; the ethereal liquid decanted, evaporated to dryness *in vacuo*, or at a low temperature; and (to get rid of all traces of ammonia) again moistened with ether and dried. The residue is now tested for the suspected alkaloid by taste, smell, and the application of appropriate reagents (pp. 349–354).

If a non-volatile alkaloid (aconitia, atropia, brucia, colchicia, emetia, physostigmia, solania, veratria, as well as morphia, codeia, and strychnia) is indicated, further purification is effected by decanting the ethereal liquid from the lower aqueous solution of bicarbonate of sodium, removing the ether by evaporation, digesting the residue in alcohol, filtering, evaporating the alcohol, treating the residue with dilute sulphuric acid, setting aside for a few hours, filtering, concentrating, adding powdered carbonate of potassium, and finally anhydrous alcohol. The alcoholic liquid, on evaporation, yields the alkaloid in a fit state for testing in the manner already stated.

Sonnenschien's Process.—Digest with diluted hydrochloric acid, evaporate to the consistence of syrup, dilute, set aside for some hours, filter. Add solution of phosphomolybdic acid so long as any precipitate falls or cloudiness occurs; collect the precipitate on a small filter; wash it with water containing phosphomolybdic and nitric acid, and,

while still moist, place it in a flask. Decompose this compound of phosphomolybdic acid and alkaloid by adding caustic baryta until the stirred mixture is distinctly alkaline. Distil off volatile alkaloids, condensing and collecting by help of a long tube, so bent that the apparatus shall act as a retort, the end of the tube being attached to a bulb or a series of bulbs containing dilute hydrochloric acid. The acid liquid evaporated gives a residue of hydrochlorates of alkaloids. The latter will afford characteristic reactions with the tests for the suspected alkaloid, and, on being moistened with baryta-water and warmed, will afford fumes of volatile alkaloids whose odor is usually characteristic. The residue in the flask will contain non-volatile alkaloids. It is treated with carbonic acid gas to neutralize and precipitate the excess of baryta as insoluble carbonate of barium; the mixture is evaporated to dryness over a water-bath; and the residue digested in alcohol. The alcoholic solution evaporated generally yields the alkaloids in a fit state for testing.

Phosphomolybdic acid forms with ammonia, in acid solutions, a remarkably insoluble compound, and it comports itself in a similar manner with those compounds which are analogous to ammonia—the nitrogenized organic bases—consequently forming an excellent reagent for their detection. It may be prepared in the following manner: Molybdate of ammonium is precipitated by phosphate of sodium; the yellow precipitate, having been washed, is diffused through water, and heated with sufficient carbonate of sodium to dissolve it. The solution is then evaporated to dryness, and calcined to drive off the ammonia. In case any of the molybdic compound be reduced by this operation, the residue must be moistened with nitric acid and again calcined. The dry mass is then dissolved in cold water, the solution strongly acidulated with nitric acid, and water added until ten parts of the solution contain one of the dry salt. The liquid, which is of a golden-yellow color, must be preserved from ammoniacal fumes. It precipitates all the alkaloids (with the exception of urea) when a mere trace only is present. The precipitates are yellow, generally flocculent, insoluble in water, alcohol, ether, and the dilute mineral acids, with the exception of phosphoric acid. Nitric, acetic, and oxalic acids, concentrated and boiling, dissolve them. These compounds are decomposed by the alkalies, certain metallic oxides, and the alkaline salts, which separate the alkaloid. To give an idea of the sensibility of this reagent, it may be stated that the 0.000071 gramme of strychnia gives an appreciable precipitate with one cubic centimetre of the solution of phosphomolybdic acid.

ANTIDOTES.

Vide "Antidote" in the Index.

QUESTIONS AND EXERCISES.

878. In examining food and similar matter for poison, why must not the ordinary tests for the poison be at once applied?

879. What preliminary operations should be performed on a vomit in a case of suspected poisoning?

880. How would you proceed in searching for corrosive sublimate in wine?

881. By what series of operations would you satisfy yourself of the presence or absence of arsenic in the contents of a stomach?

882. Describe the treatment to which decoction of coffee should be subjected in testing it for tartar-emetic.

883. State the method by which the occurrence of lead in water is demonstrated.

884. Give a process for the detection of copper in jam.

885. How would you detect zinc in a vomit?

886. How may the presence of a poisonous quantity of sulphuric acid in gin be proved?

887. In examining ale for free nitric acid what reactions would be selected?

888. Show how you would conclude that a dangerous quantity of hydrochloric acid had been added to cider.

889. Describe the manipulations necessary in testing for hydrocyanic acid in the contents of a stomach.

890. By what method is oxalic acid discovered in infusion of coffee?

891. How is the phosphorus detected in organic mixtures?

892. Give the process by which strychnia is isolated from partially digested food.

893. Mention the experiments by which the presence of laudanum in porter is demonstrated.

894. Name the appropriate antidotes in cases of poisoning by: *a*, alkaloids; *b*, antimonials; *c*, arsenic; *d*, barium salts; *e*, copper compounds; *f*, hydrochloric acid; *g*, hydrocyanic acid; *h*, preparations of lead; *i*, corrosive sublimate; *j*, nitric acid; *k*, oxalic acid; *l*, salts of silver; *m*, oil of vitriol; *n*, tin liquors; *o*, zinc solutions; *p*, carbolic acid.

EXAMINATION OF MORBID URINE AND CALCULI.

The various products of the natural and continuous decay of animal tissue and the refuse matter of food are eliminated from the system chiefly as fæces, urine, and expired air. Air exhaled from the lungs carries off from the blood much carbon (about 8 ounces in 24 hours), in the form of carbonic acid gas, and some aqueous vapor—the latter, together with a small amount of oily matter, also escaping by the skin. Directing the breath to a cold surface renders moisture evident; and breathing through a tube into lime-water demonstrates the presence of a considerable quantity of carbonic acid gas. The fæces consist mainly of the insoluble *débris* of the system, the soluble matters and water forming the urine. These excretions vary considerably, according to the food and general habits of the individual and external temperature. But in disease the variations become excessive; their detection by the medical practitioner, or by the pharmacist for the medical practitioner, is therefore a matter of importance.

A complete analysis of fæces, urine, or expelled air cannot be performed in the present state of our knowledge. Nor can any analysis of fæces or air be made with sufficient ease and rapidity to be practically available in medical diagnosis. But with regard to urine, certain abnormal substances and abnormal quantities of normal constituents may be chemically detected in the course of a few minutes by any one having already some knowledge of chemical manipulation.

Healthy human urine contains, in 1000 parts, 957 of water, 14 of urea, 1 of uric acid, 15 of other organic matter, and 13 of inorganic salts. The acidity of urine Thudichum considers to be due to *cryptophanic acid*, $H_2C_5H_7NO_5$.

Examination of Morbid Urine for Albumen, Sugar, Bile, and Excess of Urea; and Urinary Sediment for Urates (or Lithates), Phosphates, Oxalate of Calcium, and Uric Acid.

Albumen.—To detect albumen, acidulate a portion of the clear urine in a test-tube with a few drops of acid (to keep phosphates in solution—nitric is best, acetic not so good) and boil; flocks or coagula will separate if albumen be present.

This experiment should first be made on normal urine containing a drop or two of solution of white of egg. A coagulum of pure albumen is white, greenish if bile pigment is present, and brownish-red if the urine contains blood. The influence of acids and alkalies on the precipitation of albumen is noticed on page 396.

The occurrence of albumen in the urine may be temporary and of but little importance; or it may indicate the existence of a serious affection, known as Bright's disease.

Sugar.—To a portion of the clear urine in a test-tube add five or ten drops of solution of sulphate of copper; pour in solution of potash or soda until the precipitate first formed is redissolved; slowly heat the solution to near the boiling-point; a yellow, yellowish-red, or red precipitate (cuprous oxide) is formed if sugar is present.

This experiment should first be made on urine containing a drop or two of solution of grape-sugar (page 361). The hydrate of copper precipitated by the alkali is insoluble in excess of pure potash or soda, but readily dissolves if organic matter, especially sugar, is present. The copper salt may not contain iron.

Other tests may be applied if necessary (*vide* page 361).

A minute amount of sugar is said to occur in normal urine and a distinct trace is occasionally present. In larger quantities it is a characteristic constituent of the urine of diabetic patients, greatly increasing the specific gravity of the excretion. Small hydrometers (termed urinometers) are commonly employed for quickly and readily ascertaining the specific gravity of urine; they range from 1000 to 1050, the interval of 1015 to 1025 being marked as "H. S.," or healthy state. (*Vide* "Specific Gravity" and "Hydrometers" in Index.)

Bile.—This is best detected by the general test (Pettenkofer's) described on page 401. Or a little of the urine may be placed on a white plate and strong nitric acid dropped on it; a peculiar play of colors—green, yellow, violet, etc.—occurs if (the coloring matter of) bile is present.

Excess of Urea.—Nearly one-half of the solid matter in the urine is urea. Its proportion varies considerably; but $1\frac{1}{2}$ per cent. may be regarded as an average amount. Concentrate urine slightly by evaporation in a small dish, pour the liquid into the test-tube, set the tube aside till cold, or cool it by letting cold water run over the outside, add an equal bulk of strong nitric acid and again set aside; scaly crystals of nitrate of urea are deposited more or less quickly.

With regard to the amount of urea in urine, it is impossible to sharply define excess or deficiency. If nitric acid gives crystals without concentration, excess is certainly present. A rough estimate may be formed by mixing a few drops of the urine and acid on a piece of glass and setting aside; the time which elapses before crystals form is an indication of the quantity in the specimen. The time will vary according to the temperature and state of moisture of the atmosphere; but with care some useful comparative results may in this way be obtained.

Tests.—Urea in solution in water may be detected by the above reaction with nitric acid, and by the readiness with which it yields ammonia on being boiled with alkalies. In putrid urine its conversion into an ammoniacal salt has already been effected.

$$\underset{\text{Urea.}}{CH_4N_2O} + \underset{\text{Water.}}{2H_2O} = \underset{\text{Carb. of ammon.}}{(NH_4)_2CO_3}.$$

Formula of Urea.—The empirical formula of urea is CH_4N_2O. Its rational formula may be thus written :— $\left.\begin{matrix}(CO)'' \\ H_2 \\ H_2\end{matrix}\right\} N_2$; that is, it may be regarded as one of the organic bases already referred to, a primary diamine, in which the bivalent radical CO occupies the place of H_2. The other atoms of hydrogen may be displaced by various radicals, and many *compound ureas* be thus obtained.

Artificial Urea.—Urea may be prepared artificially by Williams's modification of Wöhler's method. Cyanide of potassium, of the best commercial quality (containing about 90 per cent. of real cyanide), is fused at a very low red heat in a shallow iron vessel; red lead is added in small quantities at a time, the temperature being kept down by constant stirring. When the red lead ceases to cause further action the mixture (cyanate of potassium and lead) is allowed to cool, the product finely powdered, exhausted with cold water, nitrate of barium added till no more precipitate (carbonate of barium) falls, the mixture filtered, and the filtrate treated with nitrate of lead so long as cyanate of lead is thrown down. The latter is thoroughly washed, and dried at a low temperature. Equivalent quantities of cyanate of lead and sulphate of ammonium, digested in a small quantity of water at a gentle heat and filtered, yield a solution from which urea crystallizes on cooling.

Another Process.—Basaroff has found that urea is produced when ordinary carbonate of ammonium is heated in hermetically sealed tubes to about 275° F. for a few hours. The same chemist had previously obtained urea by similarly heating pure carbamate of ammonium, so that the source of the urea in the former case is probably the carbamate of ammonium believed to occur in the carbonate (see page 78).

$$NH_4NH_2CO_2 - H_2O = CH_4N_2O.$$

URINARY SEDIMENTS.

Warm the sediment with the supernatant urine and filter.

Insoluble.	*Soluble.*
Phosphates, oxalate of calcium, and uric acid. Warm with acetic acid, and filter.	Urates — of ammonium, calcium, or sodium, chiefly the latter. They are redeposited as the liquid cools, and if sufficient in quantity may be further examined for ammonium, calcium, sodium, and the uric radical by the appropriate tests.

Insoluble.	*Soluble.*
Oxalate of calcium and uric acid. Warm with hydrochloric acid, filter.	Phosphates. Add ammonia, white ppt. = phosphate of calcium, or ammonio-magnesium phosphate, or both.

Insoluble.	*Soluble.*
Uric acid. Apply murexid test (p. 320).	Oxalate of calcium. May be reprecipitated by ammonia.

Notes.—Urinary deposits are seldom of a complex character; the action of heat and acetic and hydrochloric acids generally at once indicates the character of the deposit, rendering filtration and precipitation unnecessary.

The urates are often of a pink or red color, owing to the presence of a pigment termed *purpurine;* hence the common name of *red gravel* for such deposits. *Purpurine* is soluble in alcohol, and may be removed by digesting a red deposit in that solvent. It is seldom necessary to determine whether the urate be that of ammonium, calcium, or sodium (see also Uric Acid, page 320).

The *phosphate of calcium* and the *ammonio-magnesium phosphate* are usually both present in a phosphatic deposit, the magnesium salt forming the larger proportion. They may, if necessary, and if sufficient in quantity, be separated by collecting on a filter, washing, and boiling with solution of carbonate of sodium. The carbonates of calcium and magnesium thus formed are collected on a filter, washed, dissolved in a drop or two of hydrochloric acid—chloride of ammonium, ammonia, and carbonate of ammonium added, the mixture boiled and filtered; any calcium originally present will then remain insoluble as carbonate of calcium, while any magnesium will be reprecipitated from the filtrate as ammonio-magnesium phosphate on the addition of phosphate of sodium, the mixture being also well stirred.——The chief portion of excreted phosphates is carried off by the fæces, that remaining in the urine being kept in solu-

tion by the influence of acid phosphate of sodium, and, frequently, lactic acid.——Occasionally, an hour or two after a hearty meal, the urine becomes sufficiently alkaline for the phosphates to be deposited, and the urine when passed is turbid from their presence.——The ammoniacal constituent of the magnesium salt does not occur normally, but is produced from urea as soon as urine becomes alkaline.

Oxalate of calcium is seldom met with in excessive amounts, but very often in small quantities mixed with phosphates.

Free uric acid is in most cases distinctly crystalline, and nearly always of a yellow, red, or brown color.

Artificial Sediments.—For educational practice, artificial deposits may be obtained as follows: 1. Rub up in a mortar a few grains of serpent's excrement (chiefly urate of ammonium) with an ounce or two of urine; this represents a sediment of urates. 2. Add a few drops of solution of chloride of calcium and of phosphate of sodium to urine; the deposit may be regarded as one of phosphates. 3. To an ounce or two of urine add very small quantities of chloride of calcium and oxalate of ammonium; the precipitate is oxalate of calcium. 4. To urine acidulated by hydrochloric acid add a little serpent's excrement; the sediment is uric acid.

Other deposits than the foregoing are occasionally observed. Thus *hippuric acid* ($HC_9H_8NO_3$), a normal constituent of human urine, and largely contained in the urine of herbivorous animals, is sometimes found associated with uric acid in urinary sediment, especially in that of patients whose medicine contains benzoic acid (p. 301). Its appearance, as observed by the aid of the microscope, is characteristic —namely, slender, four-sided prisms, having pointed ends. *Cystin* ($C_3H_7HSO_2$) (from κύστις, *kūstis*, a bladder, in allusion to its origin) rarely occurs as a deposit in urine. It is not soluble in warmed urine or dilute acetic acid, and scarcely in dilute hydrochloric acid, hence would be met with in testing for free uric acid. It is very soluble in ammonia, recrystallizing from a drop of the solution placed on a piece of glass in characteristic microscopic six-sided plates. *Organized sediments* may be due to the corpuscles of pus, mucus, or blood, fat-globules, spermatozoa, cylindrical casts of the tubes of the kidneys, epithelial cells from the walls of the bladder, or foreign matters, such as fibres of wool, cotton, small feathers, dust; these are best recognized by the microscope, as will be seen by the following paragraphs and figures on the microscopic appearances of both crystalline and organized urinary sediments.

Microscopic Examination of Urinary Sediments.

Urine containing insoluble matter is usually more or less opaque. For microscopical examination a few ounces should be set aside in a conical test-glass for an hour or two, the clear supernatent urine poured off from the sediment as far as possible, a small drop of the residue placed on a slip of glass and covered with a piece of thin glass and examined under the microscope with different magnifying-powers.

The respective appearances of the various crystalline and organized matters are given in the following figures, which were drawn by my friend H. B. Brady, F.L.S., from natural specimens (as seen with a two-third inch objective and No. 1 eye-piece, *i. e.*, magnified 60 diameters) in the collections of St. Bartholomew's Hospital, Dr. Sedgwick, W. W. Stoddart, F.C.S., Mr. Waddington, and the Author.

Uric Acid occurs in many forms, most of which are given in the first two figures. Flat, more or less oval crystals, sometimes attached



Uric Acid.

Uric Acid.

to each other, their outline then resembling an 8, a cross, or a star, are common. Single and grouped quadratic prisms, aigrettes, spicula, and crystals recalling dumb-bells are met with. From urine acidulated by hydrochloric acid, square crystals, two opposite sides smooth and two jagged, are generally deposited: acidulated by acetic acid more typical forms are obtained. A drop of solution of potash or soda placed on a glass slip will dissolve a deposit of uric acid, a drop of any acid re-precipitating it in minute but characteristic crystals.



Cystin.

Cystin is very rarely met with as a urinary deposit; that from which the figure was taken was found in the urine of a patient in St. Bartholomew's Hospital. Lamellæ of cystin always assume an hexagonal character; but the angles are sometimes ill defined and the plates superposed: in the latter case, a drop of solution of ammonia placed on the glass at once dissolves the deposit, well-marked six-sided crystals appearing as the drop dries up.

Triple Phosphate (phosphate of magnesium and ammonium) is deposited as soon as urine becomes alkaline, the ammoniacal constituent being furnished by the decomposition of urea. It occurs in large prismatic crystals, forming a beautiful object when viewed by polarized light—sometimes also in ragged stellate or arborescent crystals, resembling those of snow. Both forms may be artificially prepared by adding a small lump of carbonate of ammonium to a few ounces of urine set aside in a test-glass.



Triple Phosphate.

Amorphous deposits are either *earthy phosphates* (a mixture of phosphates of magnesium and calcium) or *urates* (of calcium, magnesium, ammonium, potassium, or sodium—chiefly the latter). They may be distinguished by the action of a drop of acetic acid placed near the sediment on the glass slip, the effect being watched under the microscope; phosphates dissolve, while urates gradually assume characteristic forms of uric acid. Urates redissolve when warmed with the supernatant urine.

Urates of Sodium and Magnesium, though generally amorphous, occasionally take a crystalline form—bundles or tufts of small needles—as shown in the cut.

Oxalate of Calcium commonly occurs in octahedra requiring high magnifying power for their detection. The crystals are easily overlooked if other matters are present, but are more distinctly seen after phosphates have been removed by acetic acid. In certain aspects the smaller crystals look like square plates traversed by a cross. A dumb-bell form of this deposit is also sometimes seen, resembling certain forms of uric acid and the coalescing spherules of a much rarer sediment—carbonate of calcium. Oxalate of calcium is insoluble in acetic but soluble in hydrochloric acid. The octahedra are frequently met with in the urine of persons who have partaken of garden rhubarb; the crystals may often be deposited artificially (according to Waddington,) by dropping a fragment of oxalic acid into several ounces of urine and setting aside for several hours.



Urates, a, of Sodium, b, of Magnesium.
Oxalate of Calcium.

Carbonate of Calcium is rarely found in the urine of man, but frequently in that of the horse and other herbivorous animals. Human urine containing carbonate of calcium often reddens litmus paper; and it is only after the removal, on standing, of the excess of carbonic acid that the salt is deposited. It consists of minute spherules, varying in size, the smaller ones often in process of coalescence. The dumb-bell form thus produced is easily distinguished from similar groups of uric acid or oxalate of calcium by showing a black cross in each spherule when viewed by polarized light. Acetic acid dissolves carbonate of calcium, liberating carbonic acid gas, with visible effervescence (under the microscope) if the slide has been previously warmed and a group of crystals be attacked.



Carbonate of Calcium. Hippuric Acid.

Hippuric Acid.—The pointed rhombic prisms and acicular crystals are characteristic, and easily recognized. The broader crystals may possibly be mistaken for triple phosphate, and the narrower for certain forms of uric acid; but insolubility in acetic acid distinguishes them from the former, and solubility in alcohol from the latter. These tests may be applied while the deposit is under microscopic observation. An alcoholic solution of hippuric acid evaporated to dryness, and the residue treated with water, gives a solution from which characteristic crystalline forms of hippuric acid may be obtained on allowing a drop to dry upon a slip of glass.

The organized deposits in urine entail greater care in their determination, and usually require a higher magnifying power for their proper examination, than those of crystalline form. The figures are drawn to 230 diameters. The following notes will assist the observer.



Epithelial Cells and Tubuli.

Casts of uriniferous tubuli are fibrinous masses of various forms, and often of considerable length—sometimes delicate and transparent, occasionally granular, and often beset with fat-globules. Epithelial *débris* are frequently present in urine in the form of nucleated cells, regular and oval when full, but angular and unsymmetrical when partially emptied of their contents—sometimes perfect, but more frequently a good deal broken up.

Blood is easily recognized. Urine containing it is high-colored, and the corpuscles appear under the microscope as reddish circular disks, either single or laid together in strings resembling piles of coin. Their color and somewhat smaller size serve to distinguish them from pus-corpuscles. In doubtful cases a drop of blood from the finger should be diluted with water and used for comparison. After urine containing blood has stood for some time, the corpuscles lose their regular outline and become angular. (See *a* in the figure.) Day, of Geelong, tests for blood in urine, or in stains on clothing, by adding a few drops of a recently prepared alcoholic solution of the inner unoxidized portions of guaiacum resin and then a small quantity of Robbins's aqueous or ethereal solution of peroxide of hydrogen, when a blue color results. If the stain is on a dark-colored fabric, the moistened parts may be pressed with white blotting paper, when blue impressions will be obtained. Contact with many substances causes the blue reaction or oxidation of guaiacum; the peculiarity of blood is that it does not produce this effect unless peroxide of hydrogen or a similar antozonic liquid is present. Bodies such as permanganate of potassium, whose oxygen is, apparently, in the form of ozone, also gives rise to a blue color with guaiacum; peroxide of hydrogen and other compounds whose oxygen is in the opposite, positive, or, according to Schönbein, antagonistic condition, produce no such effect. It would seem as if blood or some other constituent of blood has the power of converting positive into negative oxygen, and thus cause an effect which negative oxygen alone is able to produce; for of all substances which, like blood, do not alone cause guaiacum to become blue, blood is the only one that so affects antozonides (themselves inactive) as to enable them to act as ozonides, that is to oxidize the guaiacum. Both the venous and arterial fluid from any red-blooded animal will produce this blue reaction. Fruit stains are darkened by ammonia, which does not alter the color of blood. Iron stains or iron-mould yield no color to water, whereas the red coloring-matter of blood is soluble in water. The peroxide of hydrogen should be free from more than a trace of acid.



Blood Corpuscles.

Pus and Mucus.—Purulent urine deposits, on standing, a light-colored layer, easily diffused through the liquid by shaking. Acetic acid does not dissolve the sediment; and solution of potash, of official strength, converts it into a gelatinous mass. Under the microscope, pus-corpuscles appear rounded and colorless, rather larger than blood-disks, and somewhat granular on the surface. They generally show minute nuclei, which are more distinctly seen after

treatment with acetic acid. (See the portion of the figure marked *a*.) Mucus possesses no definite microscopic characters, but commonly has imbedded in it pus, epithelium, and air-bubbles. Mucus is coagulated in a peculiar and characteristic manner by acetic acid: and this reaction, together with the ropy appearance it imparts to urine, prevents its being confounded with pus. Day's test for pus consists in adding a drop or two of oxidized tincture of guaiacum, to the urine or other liquid, when a clear blue color is produced. It is necessary to moisten dry pus with water before applying the test. The test liquid is made by exposing a saturated alcoholic solution of guaiacum to the air until it has absorbed a sufficient quantity of oxygen to give it the property of turning green when placed in contact with iodide of potassium. Day's test for mucus consists in the application, first, of oxidized tincture of guaiacum, which by itself undergoes no change in the presence of mucus, and then in the addition of carbolic acid or creasote, which quickly changes the color of the guaiacum to a bright blue. Neither carbolic acid nor creasote alone will render guaiacum blue. In testing for mucus on cloths, or when it is mixed with blood, it is necessary to use the carbolic acid pure, but when the mucus is in a liquid state it is better to use carbolic acid diluted with alcohol.



Pus Corpuscles.

Saliva.—Saliva is an aqueous fluid containing less than 1 per cent. of solid matter, of which one-third is an albuminoid substance termed *ptyalin* (from πτύελον, *spittle*), a body that has power of converting starch into dextrin and grape-sugar. Alkaline salts, including a trace of sulphocyanide of potassium, and calcareous compounds, are also present.



Fat Globules.

Day's test for saliva in urine, etc., is similar to that for mucus, with the exception that the blue reaction produced by the oxidized tincture of guaiacum and alcoholic solution of carbolic acid is highly intensified by the addition of Robbins's aqueous or ethereal solution of peroxide of hydrogen.

Fatty matter occurs either as minute globules partially dif-

fused through the urine (as shown at *a*) or in more intimate emulsion (as at *b* in the figure). When present in larger quantity, it collects as a sort of skim on the surface after standing.

Spermatozoa are liable to escape notice, on account of their small size and extreme transparency. Suspected urine should be allowed to settle some hours in a conical test-glass, and the drop at the bottom examined under a high power. The drawing shows their tadpole-like appearance.



Spermatozoa.



Sarcina Ventriculi.

Sarcina ventriculi is an alga of very rare occurrence in urine, though not unfrequent in the matters vomited during certain diseases of the stomach. The upper figures (*a*) are copied from Dr. Thudichum's drawing (from urine); the larger fronds (*b*) are from vomited matter.

Extraneous bodies, such as hair, wool, or fragments of feathers, are often found in urinary deposits; and ludicrous mistakes have been made by observers not on their guard in respect to such casual admixtures.

Examination of Urinary Calculi.

The term *calculus* is the diminutive of *calx*, a lime- or chalk-stone. Knowledge of the composition of a calculus or urinary deposit affords valuable diagnostic aid to the physician; hence the importance of a correct analysis of these substances.

Nature of Calculi.—Urinary calculi have the same composition as unorganized urinary sediments. They consist, in short, of sediments that have been deposited slowly within the bladder, particle on particle, layer on layer, the several substances becoming so compact as to be less easily acted on by reagents than when deposited after the urine has been passed—the urates less readily soluble in warm water, the calcic phosphate insoluble in acetic acid until it has been dissolved in hydrochloric acid and reprecipitated by an alkali.

Preliminary Treatment.—If the calculus is whole, saw it in two through the centre, and notice whether it is built up of distinct layers or apparently consists of one substance. If the latter, use about a grain of the sawdust for the analysis; if the former, carefully

scrape off portions of each layer, and examine them separately. If the calculus is in fragments, select fair specimens of about half a grain or a grain each, and reduce to a fine powder by placing on a hard surface and crushing under the blade of a knife.

Analysis.—Commence the analysis by heating a portion about the size of a pin's head, on platinum foil, in order to ascertain whether organic matter, inorganic matter, or both, are present. If both, the ash is examined for inorganic substances, and a fresh portion of the calculus for uric acid by the murexid test. (In the absence of uric acid any slight charring may be considered to be due to indefinite animal matter.) If composed of organic matter only, the calculus will in nearly all cases be uric acid, the indication being confirmed by applying the murexid test in a watch-glass to another fragment, half the size of a small pin's head. If organic only, the ash on the platinum foil may be examined for phosphates, and a separate portion of the calculus for oxalates. Even a single drop of liquid obtained in any of these experiments may be filtered by placing it on a filter not larger than a sixpence and previously moistened with water, and adding three or four drops of water one after the other as each passes through the paper. If the calculus is suspected to contain more than one substance, boil about half a grain of the powder in half a test-tubeful of distilled water for a few minutes and pour it on a small filter; then proceed according to the following Table:—

<table>
<tr><td colspan="2">Insoluble.
Phosphates, oxalates of calcium, and free uric acid.
Boil with two or three drops of hydrochloric acid and filter.</td><td>Soluble.
Urates.
These will probably be redeposited as the solution cools. Small quantities may be detected by evaporating the solution to dryness. They are tested for ammonium, sodium, calcium, and the uric radical by the appropriate reagents.</td></tr>
<tr><td>Insoluble.
Uric acid. Apply the murexid test (p. 320).</td><td colspan="2">Soluble.
Phosphates and oxalate of calcium.
Add excess of ammonia, and then excess of acetic acid; filter.</td></tr>
<tr><td></td><td>Insoluble.
Oxalate of calcium.</td><td>Soluble.
Phosphates.
They may be reprecipitated by ammonia.</td></tr>
</table>

Varieties of Calculi.—Calculi composed entirely of *uric acid* are common; a minute portion heated on platinum foil chars, burns, and leaves scarcely a trace of ash. The phosphates frequently occur together, forming what is known as the *fusible calculus*, from the readiness with which a fragment aggregates, and even fuses to a bead, when heated on a loop of platinum wire in the blowpipe-flame. The phosphates may, if necessary, be further examined by the method described in connection with urinary deposits. Oxalate of calcium often occurs alone, forming a dark-colored calculus having a very rough surface, hence termed the *mulberry calculus*. Smaller calculi of the same substance are called, from their appearance, *hempseed calculi*. Calculi of *cystin* are rarely met with. *Xanthin* (from ξανθός, *xanthos*, yellow, in allusion to the color it yields with nitric acid) still less often occurs as a calculus. The earthy concretions, or *chalk-stones*, which frequently form in the joints of gouty persons, are composed chiefly of urates, the sodium salt being that most commonly met with. *Gall-stones* or *biliary calculi*, occasionally form in the gall-bladder: they contain *cholesterin* (from χολή, *cholē*, bile, and στερεός, *stereos*, solid), a fatty substance of alcoholoid constitution, soluble in rectified spirit or ether, and crystallizing from such solutions in well-defined, square, scaly crystals. Phosphatic and other calculi of many pounds weight are often found in the stomach and larger intestines of animals.

QUESTIONS AND EXERCISES.

895. In breathing, how much carbon (in the form of carbonic acid gas) is exhaled from the lungs every 24 hours?

896. How may the presence of carbonic acid gas in expired air be demonstrated?

897. Mention an experiment showing the escape of moisture from the lungs during breathing.

898. State the method of testing for albumen in urine.

899. Give the tests for sugar in urine.

900. What is the average composition of healthy urine?

901. Give the tests for urea.

902. Write the rational formulæ of some compound ureas in which methyl or ethyl displace hydrogen.

903. Describe an artificial process for the production of urea, giving equations.

904. Sketch out a plan for the chemical examination of urinary sediments.

905. A deposit is insoluble in the supernatant urine or in acetic acid; of what substances may it consist?

906. Which compounds are indicated when a deposit redissolves on warming it with the supernatant urine?

907. Name the salts insoluble in warmed urine but dissolved on the addition of acetic acid.

908. Mention the chemical characters of cystin. At what stage of analysis would it be recognized?

909. Describe the microscopical appearance of the following urinary deposits:—

Uric Acid.	Tube-casts.
Cystin.	Epithelial *débris*.
Triple phosphate.	Blood.
Earthy phosphates.	Pus.
Urates.	Mucus.
Oxalate of Calcium.	Fat.
Carbonate of Calcium.	Spermatozoa.
Hippuric Acid.	Sarcina.

Extraneous Bodies.

910. How are Day's tests for blood, pus, and saliva applied?

911. What is the general, physical, and chemical nature of urinary calculi?

912. How are urinary calculi prepared for chemical examination?

913. Draw out a chart for the chemical examination of urinary calculi.

914. Why is the "fusible calculus" so called, and what is its composition?

915. State the characters of "mulberry" and "hempseed" calculi.

916. What are the "chalk-stones" of gout and "gall-stones" or "biliary calculi?"

THE GALENICAL PREPARATIONS OF THE BRITISH PHARMACOPŒIA.

The preparation of Confections, Decoctions, Enemas, Extracts, Glycerines, Infusions, Inhalations, Juices, Liniments, Lozenges, Mixtures, Ointments, Pills, Plasters, Poultices, Powders, Spirits, Suppositories, Syrups, Tinctures, and Wines, includes a number of mechanical rather than chemical operations, and belongs to the domain of pure Pharmacy. The medical or pharmaceutical pupil will have had ample opportunity of practically studying these compounds before working at experimental chemistry, and will probably have prepared many of them according to the directions of the Pharmacopœia; if not, he is referred to the pages of the last edition of that work for details.

Among the extracts of the British Pharmacopœia, however, there are five (namely, those of Aconite, Belladonna, Hemlock, Henbane, and Lettuce) which are not simply evaporated infusions, decoctions, or tinctures, like most

others, but are evaporated juices from which vegetable albumen, the supposed source of fermentation and decay, has been removed, and chlorophyll (the green coloring-matter of plant-juice) retained practically unimpaired in tint. In order that attention may be concentrated on the process by which these are prepared, rather than on the extracts themselves, it is advisable to make an extract of some ordinary green vegetable, such as cabbage or turnip-tops. Bruise the green leaves of a good-sized cabbage in a mortar, and press out the juice; heat it gradually to 130°, and remove the green flocks of chlorophyll which separate, by filtration through calico. When the liquor has all passed through the filter, set the chlorophyll aside for a time, heat the strained liquor to 200° to coagulate albumen; remove the latter by filtration and throw away; evaporate the filtrate by a water-bath to the consistence of thin syrup; then add to it the chlorophyll, and, stirring the whole together assiduously, continue the evaporation at a temperature not exceeding 140°, until the extract is of a suitable consistence for forming pills. A higher temperature than that indicated would cause the alteration of the chlorophyll to a dark-brown substance, the extract no longer having the green tint which custom and the British Pharmacopœia demand.

QUESTIONS AND EXERCISES.

917. Enumerate the different classes of official galenical preparations.

918. Describe the general process for the preparation of green extracts:—

Aconite. Hemlock.
Belladonna. Henbane.
Lettuce.

919. Why is vegetable albumen excluded in the preparation of green extracts?

920. How may chlorophyll be removed from vegetable juices, and again be introduced into their evaporated residues, without destroying its color.

921. For what reason is exposure of chlorophyll to heat avoided in the manufacture of green extracts?

THE CHEMICAL PREPARATIONS OF THE PHARMACOPŒIAS.

The process by which every official chemical substance is prepared has already been described, and the strict chemical character of the processes illustrated by experiments and explained by aid of equations. Should the reader, in addition, desire an intimate acquaintance with those details of manipulation on which the successful and economic manufacture of chemical substances depends, he is advised to prepare, if he has not done so already, a few ounces of each of the salts mentioned in the Pharmacopœias or commonly used in Pharmacy. An additional guide in these operations will be the Pharmacopœia itself.

The production of many chemical and galenical substances on a commerical scale can only be successfully carried on in manufacturing-laboratories and with some knowledge of the circumstances of supply and demand, value of raw material, and of by-products. Commercial Chemistry and Pharmacy, however, can best hope for success when founded on the working out of abstract principles. The problem of manufacturing-success is solved with certainty by wisely applied science.

Memorandum.—The next subjects of experimental study will be determined by the nature of the student's future pursuits. In most cases the operations of quantitative analysis will engage attention. These should be of a volumetric and gravimetric character; for details concerning them see the following pages.

QUANTITATIVE ANALYSIS.

INTRODUCTORY REMARKS.

General Principles.—The proportions in which chemical substances unite with each other in forming compounds are definite and invariable (p. 41). Quantitative analysis is based on this law. When, for example, aqueous solutions of a salt of silver and a chloride are mixed, a white curdy precipitate is produced containing chlorine and silver in atomic proportions, that is, 35.5 parts of chlorine to 108 of silver. No matter what the chloride or what the salt of silver, the resulting chloride of silver is invariable in composition. The formula AgCl is a convenient picture of this compound in these proportions. The weight of a definite compound being given, therefore, the proportional amounts of its constituents can be ascertained by simple calculation. Thus, for instance, 8.53 parts of chloride of silver contain 2.11 parts of chlorine and 6.42 of silver: for if 143.5 (the molecular weight) of chloride of silver contain 35.5 (the atomic weight) of chlorine, 8.53 of chloride of silver will be found to contain 2.11 of chlorine:—

$$143.5 : 35.5 :: 8.53 : x$$

$$\begin{array}{r} 8.53 \\ \hline 1.065 \\ 17.75 \\ 284.0 \end{array}$$

$$143.5)\overline{302.815}(2.11$$

$$\begin{array}{r} 287.0 \\ \hline 15.81 \\ 14.35 \\ \hline 1.465 \\ 1.435 \end{array}$$

$$x = 2.11.$$

And if 143.5 of chloride of silver contain 108 of silver, 8.53 of chloride of silver will contain 6.42 of silver. To ascertain, for example, the amount of silver in a substance, containing, say, nitrate of silver, all that is necessary is to take a weighed quantity of the substance, dissolve it, precipitate the whole of the silver by adding hydrochloric acid or other chloride till no more chloride of silver falls, collect the precipitate on a filter, wash, dry, and weigh. The amount of silver in the dried chloride, ascertained by calculation, is the amount of silver in the quantity of substance on which the operation was conducted; a rule-of-three sum gives the quantity per cent.—the form in which the results of quantitative analysis are usually stated.

Occasionally a constituent of a substance admits of being isolated and weighed in the uncombined state. Thus the amount of mercury in a substance may be determined by separating and weighing the mercury in the metallic condition; if occurring as calomel ($HgCl$) or corrosive sublimate ($HgCl_2$), the proportion of chlorine may then be ascertained by calculation ($Hg=200$; $Cl=35.5$).

Nature of Gravimetric Quantitative Analysis.—As above stated, a body may be isolated and *weighed* and its quantity thus ascertained; or it may be separated and weighed in combination with another body whose combining proportion is well known; this is quantitative analysis by the *gravimetric* method.

Nature of Volumetric Quantitative Analysis.—Quantitative analysis by the *volumetric* method consists in noting the volume of a liquid required to be added to the substance under examination before a given effect is produced. Thus, for instance, a solution of nitrate of silver of known strength may be used in experimentally ascertaining an unknown amount of chlorine in any substance. The silver solution is added to a solution of a definite quantity of the substance until flocks of chloride of silver cease to be precipitated: every 108 parts of silver added (or 170 of nitrate of silver: $Ag=108$, $N=14$ $O_3=48$; total 170) indicates the presence of 35.5 of chlorine, or an equivalent quantity of any chloride. The preparation of standard solutions, such as that of nitrate of silver, to which allusion is here made, requires considerable care; but when made, certain analyses can be executed with far more rapidity and ease than by gravimetric processes.

Note.—The quantitative analysis of solids and liquids often involves determinations of temperature and specific gravity. These processes will now be explained, after which an outline of volumetric and gravimetric quantitative analysis will be given. The scope of this work precludes any attempt to describe all the little mechanical details observed by quantitative analysts; essential operations, however, are so fully treated that expert manipulators will meet with little difficulty.

Measurement of Atmospheric Pressure.

The Barometer.—The analysis of gases and vapors involves, also, determinations of the varying pressure of the atmosphere as indicated by the *barometer* (from βάρος, *baros*, weight, and μέτρον, *metron*, measure). The ordinary mercurial barometer is a glass tube 33 or 34 inches long, closed at one end, filled with mercury, and inverted in a small cistern or cup of mercury. The mercury remains in the tube owing to the weight or pressure of the atmosphere on the exposed surface of the liquid, the average height of the column being nearly 30 inches. In the popular form of the instrument, the wheel-barometer, the cistern is formed by a recurvature of the tube; on the exposed surface of the mercury a float is placed, from which a thread passes over a pulley and moves an index whenever the column of mercury rises or falls. As supplied to the public these barometers are usually inclosed in ornamental frames with thermo-

meters attached. In the wheel-barometer the glass tube and contained column of mercury are altogether inclosed, the index alone being visible. In the other variety the upper end of the glass tube and mercurial column are exposed and the height of the mercury is ascertained by direct observation.

The aneroid barometer (from ἀ, *a*, *without*, and νηρὸς, *neros*, fluid) consists of a small, shallow, vacuous metal-drum, the sides of which approach each other when an increase of atmospheric pressure occurs, their elasticity enabling them to recede toward their former position on a decrease of pressure. This motion is so multiplied and altered in direction by levers, etc., as to act on a hand traversing a plate on which is marked numbers corresponding with those showing the height of the mercurial column of the ordinary barometer by which the aneroid was adjusted. *The Bourdon barometer* (from the name of the inventor) is a modified aneroid, containing, in the place of the round metal box, a flattened vacuous tube of metal, bent nearly to a circle. These barometers are also useful for measuring the pressure in steam-boilers, etc. Under the name of *pressure-gauges* they are sold to indicate pressures of 500 pounds and upwards per square inch. From their portability (they can be made of 1 to 2 inches in diameter and 1 inch thick) they are excellent companions for travellers wishing to know the heights of hills, mountains, and other elevations.

For further information concerning the influence of pressure on the volume of a gas or vapor see page 469; and for descriptions of the methods of analyzing gases, refer to Ganot's "Physics" (translated by Atkinson), Miller's "Chemical Physics," and "Analysis of Gases" in Watts's "Dictionary of Chemistry."

MEASUREMENT OF TEMPERATURE.

General Principles.—As a rule, all bodies expand on the addition, and contract on the abstraction of heat, the alteration in volume being constant and regular for equal increments or decrements of temperature. The extent of this alteration in a given substance, expressed in parts or degrees, constitutes the usual method of intelligibly stating, with accuracy, precision, and minuteness, a particular condition of warmth or temperature, that is, of sensible heat. The substance commonly employed for this purpose is mercury, the chief advantages of which are that it will bear a high temperature without boiling, a low temperature without freezing, does not adhere to glass to a sufficient extent to "wet" the sides of any tube in which it may be inclosed, and, from its good conducting-power for heat, responds rapidly to changes of temperature. Platinum, earthenware, alcohol, and air are also occasionally used for thermometric purposes.

The Thermometer.—The construction of an accurate thermometer is a matter of great difficulty; but the following are the leading steps in the operation. Select a piece

of glass tubing having a fine capillary (*capillus*, a hair) bore, and about a foot long; heat one extremity in the blowpipe-flame until the orifice closes, and the glass is sufficiently soft to admit of a bulb being blown; heat the bulb to expel air, immediately plunging the open extremity of the tube into mercury; the bulb having cooled, and some mercury having entered and taken the place of expelled air, again heat the bulb and tube until the mercury boils and its vapor escapes through the bore of the tube; again plunge the extremity under mercury, which will probably now completely fill the bulb and tube. When cold the bulb is placed in melting ice. The top of the column of mercury in the capillary tube should then be within an inch or two of the bulb; if higher, some of the mercury must be expelled by heat; if lower, more metal must be introduced as before. The tube is now heated near the open end and a portion drawn out, until the diameter is reduced to about one-tenth. The bulb is next warmed until the mercurial column rises above the constricted part of the tube, which is then rapidly fused in the blowpipe-flame, and the extremity of the tube removed.

The instrument is now ready for *graduation*. The bulb is placed in boiling-water (a medium having, *cæteris paribus*, an invariable temperature), and, when the position of the top of the mercurial column is constant, a mark is made on the tube by a scratching diamond or a file. This operation is repeated with melting ice (also a medium having an invariable temperature). The space between these two marks is divided into a certain number of intervals termed *degrees*. Unfortunately this number is not uniform in all countries: in England it is 180, as proposed by Fahrenheit; in France 100, as proposed by Celsius (the Centigrade scale), a number generally adopted by scientific men; in some parts of the Continent the divisions are 80 for the same interval, as suggested by Réaumur. Whichever be the number selected, similar markings should be continued beyond the boiling- and freezing-points as far as the length of the stem admits.

Thermometric Scales.—On the Centigrade and Réaumur scales the freezing point of water is made zero, and the boiling point 100 and 80 respectively; on the Fahrenheit scale the zero is placed 32 degrees below the congealing-point of water, the boiling-point of which becomes, consequently, 212. Even on the Fahrenheit system temperatures below the freezing-point of water are often spoken of as "degrees of frost;" thus 19 degrees as marked on the thermom-

eter would be regarded as "13 degrees of frost." It is to be regretted that the freezing-point of water is not universally regarded as the zero-point, and the number of intervals between that and the boiling-point everywhere the same.

The degrees of one scale are easily converted into those of another, if their relations be remembered, namely: 180 (F.), 100 (C.), 80 (R.); or 18, 10, and 8; or, best, 9, 5, and 4.

Formulæ for the conversion of degrees of one thermometric scale into those of another.

F=Fahrenheit. C=Centigrade.
R=Réaumur. D=The observed degree.

If above the freezing-point of water (32° F; 0° C; 0° R),

F into C . . . . . (D—32)÷9×5.
F " R . . . . . (D—32)÷9×4.
C " F . . . . . D÷ 5 ×9+32.
R " F . . . . . D÷ 4 ×9+32.

If below freezing, but above 0° F (—17°.77 C; —14°.22 R),

F into C . . . . . .—(32—D)÷9×5.
F " R . . . . . .—(32—D)÷9×4.
C " F . . . . . 32—(D÷5×9).
R " F . . . . . 32—(D÷4×9).

If below 0° F (—17°.77 C; —14°.22 R),

F into C . . . . . .—(D+32)÷9 ×5.
F " R . . . . . .—(D+32)÷9 ×4.
C " F . . . . . .—(D÷ 5 ×9)—32.
R " F . . . . . .—(D÷ 4 ×9)—22.

For all degrees:—

C into R . . . . . D÷5×4.
R " C . . . . . D÷4×5.

In ascertaining the temperature of a liquid, the bulb of a thermometer is simply inserted and the degree noted. In determining the boiling-point, also, the bulb is inserted in the liquid, if a pure substance. In taking the boiling-point of a liquid which is being distilled from a mixture, the bulb of the thermometer should be near to but not beneath the surface.

The following are the boiling points of a few substances met with in pharmacy:—

	Centigrade.	Fahrenheit.
Alcohol, absolute	78.3	173
" 84 per cent.	79.5	175
" 49 per cent. (proof spirit)	81.4	178.5
" amylic	132.2	270
Benzol	80.6	177
Bromine	63.0	145.4
Benzoic acid	239.0	462
Carbolic acid	187.8	370

	Centigrade.	Fahrenheit.
Chloroform	61	142
Ether (B. P.) (below)	40.5	105
" pure	35	95
Mercury *in vacuo* (as in a thermometer)	304	580
" in air (barom. at 30 inches)	350	662
Water (barom. at 29.92 inches)	100	212
" (" 29.33 ")	99.5	211
" (" 28.74 ")	99	210
Saturated solutions of—		
Cream of tartar	101	214
Common salt	106.6	224
Sal ammoniac	113.3	236
Nitrate of sodium	119	246
Acetate of sodium	124.4	256
Chloride of calcium	179.4	355

By "gentle heat," U. S. P., is meant any temperature between 90° and 100° F.

To Determine Melting-points of Fat.—Heat a fragment of the substance (spermaceti or wax for example) till it liquefies, and then draw up a small portion into a thin glass tube, about the size of a knitting-needle. Immerse the tube in cold water contained in a beaker, and slowly heat the vessel till the thin opaque cylinder of solid fat melts and becomes transparent: a delicate thermometer placed in the water indicates the point of change to the fifth of a degree. Remove the source of heat, and note the congealing-point of the substance; it will be identical with or close to the melting-point.

Pyrometers.—Temperatures above the boiling-point of mercury are determined by ascertaining to what extent a bar of platinum or porcelain has elongated. The bar is inclosed in a cavity of a suitable case, a plug of platinum or porcelain placed at one end of the bar, and the whole exposed in the region whose temperature is to be found. After cooling, the distance to which the bar has forced the plug along the cavity is accurately measured and the corresponding degree of temperature noted. The value of the distance is fixed for low temperatures by comparison with a mercurial thermometer, and the scale carried upwards through intervals of equivalent length. Such thermometers are conventionally distinguished from ordinary instruments by the name *pyrometer* (from πῦρ, *pūr*, fire, and μέτρον, *metron*, measure).

The following melting-points of official substances are given in the British Pharmacopœia:—

	In degrees Centigrade.	In degrees Fahrenheit.
Acetic acid, glacial	8.9	48
" " congeals at	1.1	34
Benzoic acid	120	248
Carbolic acid	35	95
Oil of theobroma	50	122
Phosphorus	43.3	110
Prepared lard (about)	38	100
" suet	39.5	103
Spermaceti	38	100
White wax (not under)	65.5	150
Yellow wax	60	140

The order of fusibility of a few of the metals is as follows:—

	In degrees Centigrade.	In degrees Fahrenheit.
Mercury	— 39.4	— 39
Potassium	+ 62.5	+144.5
Sodium	97.6	207.7
Tin	227.8	442
Bismuth	264	507
Lead	325	617
Zinc	411.6	773
Antimony	621	1150
Silver	1023	1873
Copper	1091	1996
Gold	1102	2016
Cast iron	1530	2786

QUESTIONS AND EXERCISES.

922. On what fundamental laws are the operations of quantitative analysis based?

923. What is the general nature of *gravimetric* quantitative analysis?

924. Describe the general principle of *volumetric* quantitative analysis.

925. How are variations in atmospheric pressure quantitatively determined?

926. Explain the construction and mode of action of a mercurial barometer.

927. In what respect does a wheel-barometer differ from an instrument in which the readings are taken from the top of the column of mercury?

928. Describe the principle of action of an aneroid barometer.

929. On what general principles are thermometers constructed?

930. What material is employed in making thermometers?

931. Why is mercury selected as a thermometric indicator?
232. Describe the manufacture of a mercurial thermometer.
933. How are thermometers graduated?
934. Give formulæ for the conversion of the degrees of one thermometric scale into those of another, (*a*) when the temperature is above the freezing-point of water, (*b*) below 32° F. but above 0° F., and (*c*) below 0° F.
935. Name the degree C. equivalent to 60° F.
936. What degree C. is represented by —4° F.?
937. Mention the degree F. indicated by 20° C.
938. Convert 100° R. into degrees C. and F.
939. State the boiling-points of alcohol, chloroform, ether, mercury, and water on either thermometric scale.
940. Describe the details of manipulation in estimating the melting-point of fats.
941. In what respect do pyrometers differ from thermometers?
942. Mention the melting-points of glacial acetic acid, oil of theobroma, lard, suet, and wax.
943. Give the fusing-points of tin, lead, zinc, copper, and cast-iron.

ESTIMATION OF WEIGHT.

DEFINITIONS.

All bodies, celestial and terrestrial, attract each other, the amount of attraction being in direct proportion to the quantity of matter of which they consist, and in inverse proportion to the squares of their distances. This is *gravitation*. When gravitation in certain directions is exactly counterbalanced by gravitation in opposite directions, a body (*e. g.* the earth) remains suspended in space. Such a body, in relation to other bodies, has gravity but not weight. *Weight* is the effect of gravity, being the excess of gravitation in one direction over and above that exerted in the opposite direction. Weight, truly, in any terrestrial substance, is the excess of attraction which it and the earth have for each other over and above the attraction of each in opposite directions by the various heavenly bodies. But, practically, the weight of any terrestrial substance is the effect of the attraction of the earth only. *Specific* weight is the definite or precise weight of a body in relation to its bulk; it is more usually but not quite correctly termed *specific gravity*—gravity belonging to the earth, not to the substance.

QUESTIONS.

944. What is understood by gravitation?
945. State the difference between weight and gravity.
946. Mention a case in which a body has gravity but no apparent weight.
947. Practically, what causes the weight of terrestrial substances?

Weights and Measures.

The Balance.—The balance used in the quantitative operations of analytical chemistry must be accurate and sensitive. The points of suspension of the beam and pans should be polished steel or agate knife-edges, working on agate planes. It should turn easily and quickly, without too much oscillation, to $\frac{1}{3000}$ or $\frac{1}{6000}$ of a grain, or $\frac{1}{10}$ of a milligramme, when 1000 grains, or 50 or 60 grammes, are placed in each scale. (Grammes are weights of the metric system, a description of which is given on the next two or three pages.) The beam should be light and strong, capable of supporting a load of 1500 grains or 100 grammes; its oscillations are observed by help of a long index attached to its centre, and continued downward for some distance in front of the supporting pillar of the balance. The instrument should be provided with screws for purposes of adjustment, a mechanical contrivance for supporting the beam above its bearing when not in use or during the removal or addition of weights, spirit levels to enable the operator to give it a horizontal position, and be inclosed in a glass case to protect from dust. It should be placed in a room the atmosphere of which is not liable to be contaminated by acid fumes, in a situation free from vibration; and a vessel containing lumps of quicklime should be placed in the case to keep the inclosed air dry and prevent the formation of rust on the steel knife-edges or other parts. During weighing, the doors of the balance should be shut, in order that currents of air may not unequally influence the pans.

The Weights.—These should be preserved in a box having a separate compartment for each. They must not be lifted directly with the fingers, but by a small pair of forceps. If grain-weights, they should range from 1000 grs. to $\frac{1}{10}$ gr., a $\frac{1}{10}$ weight being fashioned of gold wire to act as a "rider" on the divided beam, and thus indicate by its position 100ths and 1000ths of a grain. From $\frac{1}{10}$ to 10 grs. the weights may be of platinum; thence upward to 1000 grs. of brass. The relation of the weights to each other should be decimal. Metric decimal weights may range from 100 grammes to 1 gramme, of brass, and thence downward to 1 centigramme, of platinum, a gold centigramme rider being employed to indicate milligrammes and tenths of a milligramme.

Weights and Measures of the U. S. Pharmacopœia.—The weights and measures used by physicians and apothecaries in the United States, when prescribing and preparing medicines, are the following—as stated in the U. S. Pharmacopœia.

Weights.—These are derived from the *troy pound*, and are exhibited in the following table, with their signs annexed:—

One pound,	℔	=	12 ounces	= 5760 grains.
One ounce,	℥	=	8 drachms	= 480 grains.
One drachm,	ʒ	=	3 scruples	= 60 grains.
One scruple,	℈	. . . . .		= 20 grains.
One grain	gr.	. . . . .		= 1 grain.

In order to avoid the danger of mistakes from confounding the troy and avoirdupois pounds, the term *pound* is disused in the for-

mulæ of the U. S. Pharmacopœia, and the desired weight is expressed in ounces, each containing four hundred and eighty grains. This ounce is always printed *troyounce*, to guard against the error of substituting for it the avoirdupois ounce, consisting of four hundred and thirty-seven and a half grains. The drachm and scruple are also disused, and replaced by their equivalents in grains.

It is highly important that persons engaged in preparing medicines should be provided with troy weights. But those who are not so provided can make their avoirdupois weights available as substitutes for troy weights, by bearing in mind that 42.5 grains, added to the avoirdupois ounce, will make it equal to the troy ounce; and that 1240 grains, deducted from the avoirdupois pound, will reduce it to the troy pound.

Measures.—These are derived from the *wine gallon*, and are given in the following table, with their signs annexed:—

One gallon,	C	=	8 pints	=	61,440 minims.
One pint,	O	=	16 fluidounces	=	7,680 minims.
One fluidounce,	f℥	=	8 fluidrachms	=	480 minims.
One fluidrachm,	fℨ	.	. . . . .	=	60 minims.
One minim,	♏	.	. . . . .	=	1 minim.

In this work the term *gallon* is not used, that measure being always expressed in pints.

At the temperature of 60°, a pint of distilled water weighs 7291.2 grains, a fluidounce 455.7 grains.

The Metric System of weights (the word *metric* is from the Greek μέτρον, *metron*, measure) is greatly to be preferred to all others, the relation of the metric weights of all denominations to measures of length, capacity, and surface being so simple as to be within the perfect comprehension of a child; while under the British and American plans the weights have no such relation, either with each other or with the various measures. Moreover the metric system is in perfect harmony with the universal method of counting; it is a decimal system.

[It is perhaps impossible to realize, much more express, the advantages we enjoy from the fact that in every country of the world the system of numeration is identical. That system is the decimal. Whatever language a man speaks, his method of numbering is decimal; his talk concerning number is decimal; his written or printed signs signifying number are decimal. With the figures 1, 2, 3, 4, 5, 6, 7, 8, 9, 0 he represents all possible variation in number, the position of a figure in reference to its companions alone determining its value, a figure on the left hand of any other figure in an allocation of numeral symbols (for example, 1871) having ten times the value of that figure, while the figure on the right hand of any other has a tenth of the value of that other. When the youngest pupil is asked how many units there are in 1871, he smiles at the simplicity of the question, and says 1871. How many tens? 187, and 1 over. How many hundreds? 18, and 71 over. How many thousands? 1, and 871 over. But if he is asked how many scruples there are in 1871 grains, how many drachms, how many ounces—he first inquires which drachms or which ounces are meant, avoirdupois ounces, troy ounces,

or wine ounces, and then brings out his slate and pencil. And so with the pints or gallons in 1871 fluidounces, or the feet and yards in 1871 inches, or the pence, shillings, and pounds in 1871 farthings; to say nothing of cross questions, such as the value of 1871 articles at 2 dollars and 20 cents per dozen, or of the perplexity caused by the varying values of several individual weights or of measures of length, capacity, and surface in different parts of the country. What is desired is, that there should be an equally simple decimal relation among weights and measures and coins as already universally exists among numbers. This condition of things having already been introduced into most other countries, there is no good reason why it should not be accomplished in the United States and Great Britain.]

The Metric System of weights and measures is founded on the metre. The engraving represents a pocket folding measure, the tenth part of a metre in length, divided into 10 centimetres, and each centimetre into 10 millimetres.



The Decimetre.

The units of the system with their multiples and submultiples are as follows:—

Units.

Length.—The *Unit of Length* is the Metre, derived from the measurement of the Quadrant of a Meridian of the Earth. (Practically it is the length of certain carefully preserved bars of metal, from which copies have been taken.)

Surface.—The *Unity of Surface* is the Are, which is the Square of Ten Metres.

Capacity.—The *Unity of Capacity* is the Litre, which is the Cube of a Tenth Part of a Metre.

Weight.—The *Unit of Weight* is the Gram, which is the Weight of that quantity of distilled water, at its maximum density (4° C.), which fills a Cube of the One-hundredth part of the Metre.

Table.

Note.—Multiples are denoted by the Greek words "Deka," Ten, "Hecto," Hundred, "Kilo," Thousand.
Subdivisions, by the Latin words, "Deci," One-tenth, "Centi," One-hundredth, "Milli," One-thousandth.

Quantities.	Length.	Surface.	Capacity.	Weight.
1000	Kilo-metre	. . .	Kilo-litre	Kilo-gram
100	Hecto-metre	Hectare	Hecto-litre	Hecto-gram
10	Deka-metre	. . .	Deka-litre	Deka-gram
1 (Units)	**METRE**	**ARE**	**LITRE**	**GRAM**
.1	Deci-metre	. . .	Deci-litre	Deci-gram
.01	Centi-metre	Centiare	Centi-litre	Centi-gram
.001	Milli-metre	. . .	Milli-litre	Milli-gram

When the metric method is exclusively adopted these Units and Table, comprising the entire System of Weights and Measures, represent all that will be essential to be learned in lieu of the numerous and complicated Tables hitherto in use. Adopting the style of elementary books on Arithmetic, the Table may be expanded in the following manner :—

10 Milligrams make 1 centigram.
10 Centigrams " 1 decigram.
10 Decigrams " 1 gram.
10 Grams " 1 dekagram.
10 Dekagrams " 1 hectogram.
10 Hectograms " 1 kilogram.

10 Millilitres make 1 centilitre,
etc.

10 Millimetres make 1 centimetre,
etc.

The following approximate equivalents of metrical units should be committed to memory :—

1 Metre = 3 feet 3 inches and 3 eighths.
1 Are = a square whose side is 11 yards.
1 Litre = $1\frac{3}{4}$ pint.
1 Gramme = $15\frac{1}{2}$ grains.

The Metric Ton of 1000 Kilo-grammes = 19 cwt. 2 qrs. 20 lbs. 10 ozs.

The Kilo-gramme = 2 lbs. $3\frac{1}{4}$ ozs. nearly.

The Hect-are = $2\frac{1}{2}$ acres nearly.

For *exact* equivalents, in many forms, see pages 461 and 462. (The word *gramme* is, in English, usually written *gram.*)

Decimal Coinage.—In most countries where the metric system of weights and measures is employed, a decimal division of coins is also adopted. This course, conjoined with the ordinary decimal method of enumerating, which fortunately is in universal use, renders calculations of all kinds most simple—easy to an extent which cannot be conceived in countries like England, where the operations of weighing, measuring, paying, and counting have only the most absurdly intricate relations to each other.

The General Council under whose authority the British Pharmacopœia is issued encourages medical practitioners and pharmacists in the adoption of the metric system, and gives the annexed statement of metric weights and measures.

WEIGHTS AND MEASURES OF THE METRICAL SYSTEM.

(From the British Pharmacopœia, of 1867.)

WEIGHTS.

1 Milligramme	= the thousandth part of one grm.	or 0.001	grm.
1 Centigramme	= the hundredth "	0.01	"
1 Decigramme	= the tenth "	0.1	"
1 Gramme	= weight of a cubic centimetre of water at 4° C.	1.0	"
1 Decagramme	= ten grammes	10.0	"
1 Hectogramme	= one hundred grammes	100.0	"
1 Kilogramme	= one thousand grammes	1000.0	(1 kilo.).

MEASURES OF CAPACITY.

1 Millilitre	=	1	cub. centim.	or the mea. of	1	gram. of	water.
1 Centilitre	=	10	"	"	10	"	"
1 Decilitre	=	100	"	"	100	"	"
1 Litre	=	1000	"	"	1000	"	(1 kilo.).

MEASURES OF LENGTH.

1 Millimetre	= the thousandth part of one metre	or 0.001	metre.
1 Centimetre	= the hundredth "	0.01	"
1 Decimetre	= the tenth "	0.1	"
1 Metre	= the ten-millionth part of a quarter of the meridian of the earth.		

The National Convention for revising the Pharmacopœia of the United States also recognizes the claims of the metric system of weights and measures by giving, in the recent (fifth) edition of the Pharmacopœia, Tables of the units of the metrical system with their multiples and submultiples, similar to the foregoing, and the following Tables showing the relation to each other of the metrical and official or Troy systems.

RELATION OF WEIGHTS OF THE U. S. PHARMACOPŒIA TO METRICAL WEIGHTS.

Fraction of a grain in Milligrammes.			Grains in equivalent Metrical weights.			Drachms, Ounces, and Pounds in equivalent metrical weights.		
Grain.		Milligramme.	Grains.		Centigrammes.	Drachms.		Grammes.
$\frac{1}{64}$	=	1.012	1	=	6.479	1	=	3.887
$\frac{1}{60}$	=	1.079			Decigrammes.	2	=	7.775
$\frac{1}{50}$	=	1.295	2	=	1.295			Decagrammes.
$\frac{1}{48}$	=	1.349	3	=	1.943	3	=	1.166
$\frac{1}{40}$	=	1.619	4	=	2.591	4	=	1.555
$\frac{1}{36}$	=	1.799	5	=	3.239	5	=	1.943
$\frac{1}{30}$	=	2.159	6	=	3.887	6	=	2.332
$\frac{1}{25}$	=	2.591	7	=	4.535	7	=	2.721
$\frac{1}{24}$	=	2.699	8	=	5.183	Ounces.		
$\frac{1}{20}$	=	3.239	9	=	5.831	1	=	3.1103
$\frac{1}{16}$	=	4.049	10	=	6.479	2	=	6.2206
$\frac{1}{15}$	=	4.319	12	=	7.775	3	=	9.3309
$\frac{1}{12}$	=	5.399	15	=	9.718			Hectogrammes.
$\frac{1}{10}$	=	6.479			Grammes.	4	=	1.2441
$\frac{1}{8}$	=	8.098	16	=	1.036	5	=	1.5551
$\frac{1}{6}$	=	10.798	20	=	1.295	6	=	1.8661
$\frac{1}{5}$	=	12 958	24	=	1.555	7	=	2.1772
$\frac{1}{4}$	=	16.197	25	=	1.619	8	=	2.4882
$\frac{1}{3}$	=	21.597	30	=	1.943	9	=	2.7992
$\frac{1}{2}$	=	32.395	40	=	2.591	10	=	3.1103
			50	=	3.239	11	=	3.4213
			60	=	3.887	Pounds.		
						1	=	3.7324
						2	=	7.4648
								Kilogrammes.
						3	=	1.1197

RELATION OF METRICAL WEIGHTS TO WEIGHTS OF THE U. S. PHARMACOPŒIA.

Metrical Weights.		Exact equivalents in grains.	Approximate equivalents in grains.
Milligrammes.			
1	=	.0154	$\frac{1}{65}$
2	=	.0308	$\frac{1}{32}$
3	=	.0463	$\frac{1}{22}$
4	=	.0617	$\frac{1}{16}$
5	=	.0771	$\frac{1}{13}$
6	=	.0926	$\frac{1}{11}$
7	=	.1080	$\frac{1}{9}$
8	=	.1234	$\frac{1}{8}$
9	=	.1389	$\frac{1}{7}$
Centigrammes.			
1	=	.1543	$\frac{1}{6}$
2	=	.3086	$\frac{1}{3}$
3	=	.4630	$\frac{6}{13}$
4	=	.6173	$\frac{7}{11}$
5	=	.7717	$\frac{3}{4}$
6	=	.9260	$\frac{9}{10}$
7	=	1.0803	1
8	=	1.2347	$1\frac{1}{4}$
9	=	1.3890	$1\frac{1}{3}$
Decigrammes.			
1	=	1.543	$1\frac{1}{2}$
2	=	3.086	3
3	=	4.630	$4\frac{1}{2}$
4	=	6.173	6
5	=	7.717	$7\frac{1}{2}$
6	=	9.260	9
7	=	10.803	11
8	=	12.347	$12\frac{1}{2}$
9	=	13.890	14

Metrical Weights.		Exact equivalents in grains.	Approximate equivalents in Troy Weight.
Grammes.			
1	=	15.434	gr. xv.
2	=	30.868	ʒss.
3	=	46.302	℈ij.
4	=	61.736	ʒi.
5	=	77.170	℈iv.
6	=	92.604	ʒiss.
7	=	108.038	℈vss.
8	=	123.472	ʒij.
9	=	138.906	℈vij.
Decagrammes.			
1	=	154.340	ʒiiss.
2	=	308.680	ʒv.
3	=	463.020	ʒviiss.
4	=	617.360	ʒx.
5	=	771.701	ʒxiij.
6	=	926.041	ʒxv.
7	=	1,080.381	ʒxviij.
8	=	1,234.721	ʒxx.
9	=	1,389.062	ʒxxiij.
Hectogrammes.			
1	=	1,543.402	ʒiij ℈v.
2	=	3,086.804	ʒvj ʒiij.
3	=	4,630.206	ʒix ʒv.
4	=	6,173.609	℔i ʒvij.
5	=	7,717.011	℔i ʒiv.
6	=	9,260.413	℔i ʒvij.
7	=	10,803.816	℔i ʒx ʒiv.
8	=	12,347.218	℔ij ʒi ʒv.
9	=	13,890.620	℔ij ʒv.
Kilogramme.			
1	=	15,434.023	℔ij ʒviij.
Myriogramme.			
1	=	154,340.23	℔xxvi ʒix. ʒiv.

The following Tables, from the British Pharmacopœia, the United States Pharmacopœia, and the Diary of Messrs. De La Rue, will be found useful for reference:—

WEIGHTS AND MEASURES OF THE BRITISH PHARMACOPŒIA OF 1867.

WEIGHTS.

1 Grain	gr.			
1 Ounce	oz.		=	437.5 grains.
1 Pound	lb.	= 16 ounces	=	7000 "

MEASURES OF CAPACITY.

1 Minim	min.		
1 Fluidrachm	fl. dr.	=	60 minims.
1 Fluidounce	fl. oz.	=	8 fluidrachms.
1 Pint	O.	=	20 fluidounces.
1 Gallon	C.	=	8 pints.

MEASURES OF LENGTH.

1 line $= \frac{1}{12}$ inch.

1 inch $= \frac{1}{39.1393}$ seconds-pendulum.

12 " = 1 foot.

36 " = 3 feet = 1 yard.

Length of pendulum vibrating seconds of mean time in the latitude of London, in a vacuum at the level of the sea. . . . . } 39.1393 inches.

(1 cubic inch of distilled water at 62° F. and 30 inch Barom. = 252.458 grains.)

RELATION OF MEASURES TO WEIGHTS.

1 Minim	is the measure of		0.91	grain of water.
1 Fluidrachm	"		54.68	grains of water.
1 Fluidounce	"	1 ounce or	437.5	"
1 Pint	"	1.25 pound or	8750.0	"
1 Gallon	"	10 pounds or	70,000.0	"

RELATION OF WEIGHTS AND MEASURES OF THE U. S. PHARMACOPŒIA TO EACH OTHER.

In distilled water at a temperature of 60°.

One Pound	=	0.7900031 Pint	=	6067.2238 Minims.
One Ounce	=	1.0533376 Fluidounce	=	505.6019 Minims.
One Drachm	=	1.0533376 Fluidrachm	=	63.2002 Minims.
One Scruple		. . . . .	=	21.0667 Minims.
One Grain		. . . . .	=	1.0533 Minim.
One Gallon	=	10.1265427 Pounds	=	58328.8862 Grains.
One Pint	=	1.2658178 Pound	=	7291.1107 Grains.
One Fluidounce	=	0.9493633 Ounce	=	455.6944 Grains.
One Fluidrachm	=	0.9493633 Drachm	=	56.9618 Grains.
One Minim		. . . . .	=	0.9493 Grain.

RELATION OF MEASURES OF THE U. S. PHARMACOPŒIA TO CUBIC MEASURE.

One Gallon	=	231.	Cubic Inches.
One Pint	=	28.875	Cubic Inches.
One Fluidounce	=	1.80468	Cubic Inch.
One Fluidrachm	=	0.22558	Cubic Inch.
One Minim	=	0.00375	Cubic Inch.

Metrical Measures of Length.

	In English inches.	In English feet = 12 inches.	In English yards = 3 feet.	In Eng. fathoms = 6 feet.	In English miles = 1760 yards.
Millimetre	0.03937	0.003281	0.0010936	0.0005468	0.0000006
Centimetre	0,39371	0.032809	0.0109363	0.0054682	0.0000062
Decimetre	3.93708	0.328090	0.1093633	0.0546816	0.0000621
Metre	**39.37079**	3.280899	1.0936331	0.5468165	0.0006214
Decametre	393.70790	32.808992	10.9363310	5.4681655	0.0062138
Hectometre	3937.07900	328.089920	109.3633100	54.6816550	0.0621382
Kilometre	39370.79000	3280.899200	1093.6331000	546.8165500	0.6213824
Myriometre	393707.90000	32808.992000	10936.3310000	5468.1655000	6.2138244

1 inch = 2.539954 centimetres. 1 yard = 0.9143835 metre.
1 foot = 3.0479449 decimetres. 1 mile = 1.6093149 kilometre.

Metrical Measures of Surface.

	In English square feet.	In Eng. sq. yards = 9 square feet.	In English poles = 272.25 sq. feet.	In English roods = 10890 sq. feet.	In English acres = 43560 sq. feet.
Centiare or square metre	10.764299	1.196033	0.0395383	0.0009885	0.0002471
Are or 100 square metres	1076.429934	119.603326	3.9538290	0.0988457	0.0247114
Hectare or 10,000 square metres	107642.993418	11960.332602	395.3828959	9.8845724	2.4711431

1 square inch = 6.4513669 square centimetres. 1 square yard = 0.83609715 square metre or centiare.
1 square foot = 9.2899683 square decimetres. 1 acre = 0.40467102 hectare.

Metrical Measures of Capacity.

	In cubic inches.	In cubic feet = 1728 cubic inches.	In pints = 34.65923 cubic inches.	In gallons = 8 pints = 277.27384 cubic inches.	In bushels = 8 gallons = 2218.19072 cubic inches.
Millilitre, or cubic centimetre .	0.06103	0.000035	0.00176	0.0002201	0.0000275
Centilitre, or 10 cubic centimetres	0.61027	0.000353	0.01761	0.0022010	0.0002751
Decilitre, or 100 cubic centimetres	6.10271	0.003532	0.17608	0.0220097	0.0027512
Litre, or cubic decimetre . .	61.02705	0.035317	**1.76077**	0.2200967	0.0275121
Decalitre, or centistere . .	610.27052	0.353166	17.60773	2.2009668	0.2751208
Hectolitre, or decistere . .	6102.70515	3.531658	176.07734	22.0096677	2.7512085
Kilolitre, or stere, or cubic metre	61027.05152	35.316581	1760.77341	220.0966767	27.5120846
Myriolitre, or decastere . .	610270.51519	353.165807	17607.73414	2200.9667675	275.1208459

1 cubic inch = 16.386176 cubic centimetres. 1 cubic foot = 28.315312 cubic decimetres. 1 gallon = 4.543358 litres.

Metrical Measures of Weight.

	In English grains.	In troy ounces = 480 grains.	In avoirdupois lbs. = 7000 grains.	In cwts. = 112 lbs. = 784000 grains.	Tons = 20 cwts. = 15680000 grains.
Milligramme	0.01543	0.000032	0.0000022	0.0000000	0.0000000
Centigramme	0.15432	0.000322	0.0000220	0.0000002	0.0000000
Decigramme	1.54323	0.003215	0.0002205	0.0000020	0.0000001
Gramme	**15.43235**	0.032151	0.0022046	0.0000197	0.0000010
Decagramme	154.32349	0.321507	0.0220462	0.0001968	0.0000098
Hectogramme	1543.23488	3.215073	0.2204621	0.0019684	0.0000984
Kilogramme	15432.34880	32.150727	2.2046213	0.0196841	0.0009842
Myriogramme	154323.48800	321.507267	22.0462126	0.1968412	0.0098421

1 grain = 0.064799 gram. 1 troy oz. = 31.103496 grams. 1 lb. avd. = 0.453593 kilgr. 1 cwt. = 50.802377 kilogrs.

QUESTIONS AND EXERCISES.

948. Mention some advantages of a decimal system of weights and measures.
949. What is the name of the chief unit of the metric decimal system of weights and measures?
950. Mention the names of the metric units of surface, capacity, and weight, and state how they are derived from the unit of length.
951. How are multiples of metric units indicated?
952. State the designations of submultiples of metric units.
953. How many metres are there in a kilometre?
954. How many millimetres in a metre?
955. How many grams in 5 kilograms?
956. How many milligrams in $13\frac{1}{2}$ grams?
957. In 1869 centigrams how many grams?
958. In a metre measure 5 centimetres wide and 1 centimetre thick how many cubic centimetres?
959. How many litres are contained in a cubic metre of any liquid?
960. State the British equivalent of the metre.
961. How many square yards in an are?
962. How many fluidounces in a litre?
963. How many ounces in a kilogram?
964. Give the relation of a metric ton (1000 kilos.) to a British ton.
965. How many grains are there in 1 ton?
966. How many ounces in 1 ton?
967. How many grains of water in 1 fluidrachm?
968. How many minims in 1 pint?
969. How many grains in 1 pint of water?
970. Whence is the British unit of length derived.

Specific Weight or Specific Gravity.

The *specific weight* of a substance is its weight in comparison with weights of similar bulks of other substances. This comparative heaviness of *solids and liquids* is conventionally expressed in relation to water: they are considered as being lighter or heavier than water. Thus, water being regarded as unity = 1, the relative weight, or specific weight, of ether is represented by the figures .720 (it is nearly three-fourths, .750, the weight of water), oil of vitriol by 1.843 (it is nearly twice, 2.000, as heavy as water). The specific weight of substances is, moreover, the weight of similar volumes *at sixty degrees* (60° F.); for the weight of a definite volume of any substance will vary according to temperature, becoming heavier when cooled, and lighter when heated, different bodies (gases excepted) differing in their rate of contraction and expansion. While, then, specific weight, or conventionally *specific gravity*, is truly the comparative weight of equal bulks, the numbers which in America and Great Britain commonly represent specific gravities are the

comparative weights of equal bulks at 60° F., water being taken as unity.* The standard of comparison for gases was formerly air, but is now usually hydrogen.

Specific Gravity of Liquids.

Procure any small bottle holding from 100 to 1000 grains, and having a narrow neck; counterpoise it in a delicate balance; fill it to about halfway up the neck with pure distilled water having a temperature of 60° F.; ascertain the weight of the water, and, for convenience, add or subtract a drop or two, so that the weight shall be a round number of grains; mark the neck by a diamond or file-point at the part cut by the lower edge of the curved surface of the water. Consecutively fill up the bottle to the neck-mark with several other liquids, cooled or warmed to 60° F., first rinsing out the bottle once or twice with a small quantity of each liquid, and note the weights; the respective figures will represent the relative weights of equal bulks of the liquids. If the capacity of the bottle is 10, 100, or 1000 grains, the resulting weights will, without calculation, show the specific gravities of the liquids; if any other number, a rule-of-three sum must be worked out to ascertain the weight of the liquids as compared with 1 (or 1.000) of water. Bottles conveniently adjusted to contain 250, 500, or 1000 grains, or 100 or 50 grammes of water, when filled to the top of their perforated stopper, and other forms of the instrument, are sold by all chemical apparatus makers.

The following are the stated specific gravities of official liquids:—

Acid, acetic, B. P.	1.044
" " U. S. P.	1.047
" " diluted, B. B. and U. S. P.	1.006
" " glacial	1.065 to 1.066
" carbolic	1.065
" hydriodic, diluted	1.112

* The true weight of the body is its weight in air plus the weight of an equal bulk of air and minus the weight of a bulk of air equal to the bulk of brass or other weights employed; or, in other words, its weight *in vacuo* uninfluenced by the buoyancy of the air; but such a correction of the weight of a body is seldom necessary or, indeed, desirable. *Density* is sometimes improperly regarded as synonymous with *specific gravity*. It is true that the density of a body is in exact proportion to its specific gravity; but the former is more correctly the comparative bulk of equal weights, while specific gravity is the comparative weight of equal bulks.

Acid, hydrochloric, B. P. and U. S. P.	1.160
" " diluted, B. P.	1.052
" " " U. S. P.	1.038
" hydrocyanic, B. P. and U. S. P.	0.997
" lactic, U. S. P.	1.212
" Nitric, B. P. and U. S. P.	1.420
" " diluted, B. P.	1.101
" " " U. S. P.	1.068
" nitro-hydrochloric	1.074
" phosphoric diluted, B. P.	1.080
" " " U. S. P.	1.056
" sulphuric, B. P. and U. S. P.	1.843
" " aromatic	0.927
" " diluted, B. P.	1.094
" " U. S. P.	1.082
" sulphurous, solution of, B. P.	1.040
" " " U. S. P.	1.035
Alcohol, U. S. P.	0.835
" absolute	0.795
" (rectified spirit, 84 per cent.)	0.838
" (proof spirit, 49 per cent.)	0.920
" dilutum, U. S. P.	0.941
" fortius, U. S. P.	0.817
" amylic, B. P. and U. S. P.	0.818
Ammonia, aromatic spirit of, B. P.	0.870
" stronger water of, U. S. P.	0.900
" solution of, B. P.	0.959
" strong solution of, B. P.	0.891
Antimony, solution of chloride of, B. P.	1.470
Arsenic, hydrochloric solution of, B. P.	1.009
Arsenical solution (*Liquor Arsenicalis*), B. B.	1.009
Benzol, B. P.	0.850
Bismuth and ammonia, solution of citrate of, B. P.	1.122
Bromine	2.966
Chlorine solution of, B. P.	1.003
Chloroform, B. P. and U. S. P.	1.490
" spirit of, B. P.	0.871
Cinchona, liquid extract of yellow, B. P. (about)	1.100
Creasote, U. S. P.	1.046
"	1.071
Ether, B. P.	0.735
" U. S. P.	0.750
" pure, B. P.	0.720
" fortior, U. S. P.	0.728
Glycerine, B. P. and U. S. P.	1.250
Iron, solution of pernitrate of, B. P.	1.107
" " " " " U. S. P.	1.065
" " " persulpate of, B. P.	1.441
" " " " " U. S. P.	1.320
" strong solution of perchloride of, B. P.	1.338
" tincture of perchloride of, B. P. and U. S. P.	0.992

Lead, solution of subacetate of, B. P.	1.260
" " " " " U. S. P.	1.267
Lime, saccharated solution of, B. P.	1.052
" solution of chlorinated, B. P.	1.035
Mercury (at 0° C. = 32° F.)	13.596
" (at 15°.55 C. = 60° F.)	13.560
" acid solution of nitrate of	2.246
" " " " " U. S. P.	2.165
Nitre, sweet spirit of	0.845
" " " " U. S. P	0.837
Oil of mustard, B. P.	1.015
Potash, solution of, B. P.	1.058
" " " U. S. P.	1.065
Soda, " " B. P.	1.047
" " " U. S. P.	1.071
" " " chlorinated, B. P.	1.103
" " " " U. S. P.	1.045
Squill, oxymel of, B. P.	1.320
Syrup, B. P.	1.330
" U. S. P.	1.317
" of buckthorn, B. P.	1.320
" of ginger	
" of hemidesmus, B. P.	1.335
" of iodide of iron, B. P.	1.385
" of lemons, B. P	1.340
" of mulberries, B. P.	1.330
" of orange-flower, B. P.	1.330
" of " peel, B. P	
" of phosphate of iron, B. P.	
" of poppies, B. P.	1.320
" of red poppy, B. P.	1.330
" of " roses, B. P.	1.335
" of rhubarb, B. P.	
" of senna, B. P.	1.310
" of squill, B. P.	
" of tolu, B. P.	1.330
Treacle, B. P. (about)	1.400

Hydrometers.—The specific gravity of liquids may be ascertained, without scales and weights, by means of an *hydrometer*—an instrument usually of glass, having a graduated stem and a bulb or bulbs at the lower part. The specific gravity of a liquid is indicated by the depth to which the hydrometer sinks in the liquid, the zero of the scale marking the depth to which it sinks in pure water. Hydrometers constructed for special purposes are known under the names of saccharometer, galactometer, elæometer, urinometer, alcohometer. Hydrometers require a considerable quantity of liquid to fairly float them, and specific gravities observed with them are less delicate and trustworthy than those obtained by the balance, nevertheless they are exceedingly useful for many practical purposes where the employment of a delicate balance would be inadmissible.

Specific Gravity of Solids in Mass.

Weigh a piece (50 to 250 grains) of any solid substance heavier than water in the usual manner. Then weigh it in water, by suspending it from a shortened balance pan by a fine thread or hair and immersing in a vessel of water. The buoyant properties of the water will cause the solid to apparently lose weight; *this loss in weight is the exact weight of an equal bulk of water.* The weight of the substance and the weight of an equal bulk of water being thus ascertained, a rule-of-three sum shows the proportional weight of the substance to 1.000 of water. To express the same thing by rule, divide the weight in air by the loss of weight in water, the resulting number is the specific gravity in relation to 1 part of water, the conventional standard of comparison.

Verify some of the following specific gravities:—

Aluminium	2.56
Antimony	6.71
Bismuth	9.83
Coins, English, gold	17.69
" " silver	10.30
" " bronze	8.70
Copper	8.95
Gold	19.34
Iron	7.84
Lead	11.36
Magnesium	1.74
Marble	2.70
Phosphorus	1.77
Platinum	21.53
Silver	10.53
Sulphur	2.05
Tin	7.29
Zinc	7.14

Specific gravities of solid substances should be taken in water having a temperature of about 60° F. The body should be immersed about half an inch below the surface of the water; adhering air-bubbles must be carefully removed; the body must be quite insoluble in water.

Specific Gravity of Solids in Powder or Small Fragments.

Weigh the particles; place them in a counterpoised specific-gravity bottle of known capacity, and fill up with water, taking care that the substance is thoroughly wetted;

again weigh. From the combined weights of water and substance subtract the amount due to the substance; the residue is the weight of the water. Subtract this weight of water from the quantity which the bottle normally contains; the residue is the amount of water displaced by the substance. Having thus obtained the weights of equal bulks of water and substance, a rule-of-three sum shows the relation of the weight of the substance to 1 part of water, the specific gravity.

Or, suspend a cup, short glass tube, or bucket from a shortened balance-pan; immerse in water; counterpoise; place the weighed powder in the cup, and proceed as directed for taking the specific gravity of a solid in mass.

This operation may be conducted on fragments of any of the substances the specific gravities of which are given in the foregoing Table, or on the powdered piece of marble the specific gravity of which has been taken in mass. The specific gravity of one piece of glass, first in mass then in powder, may be ascertained; the result should be identical. The specific gravity of shot is about 11.350; sand, 2.600; mercury, 13.56.

Specific Gravity of Solids Soluble in Water.

Weigh a piece of sugar or other substance soluble in water; suspend it from a balance in the usual manner, and weigh it in turpentine, benzol, or petroleum, the specific gravity of which is known or has been previously determined; the loss in weight is the weight of an equal bulk of the turpentine. Ascertain the weight of an equal bulk of water by calculation.

Sp. gr. of turpentine	:	sp. gr. of water	::	observed bulk of turp.	:	equal bulk of water.

The exact weights of equal bulks of sugar and water being obtained, the weight of a bulk of sugar corresponding to one of water is shown by a rule-of-three sum; in other words, divide the weight of sugar by that of the equal bulk of water, the quotient is the specific gravity of sugar. The specific gravity of sugar ranges from 1.067 to 1.090.

Specific Gravity of Solids Lighter than Water.

This is obtained in a manner similar to that for solids heavier than water; but the light body is sunk by help of a piece of heavy metal, the bulk of water which the latter displaces being deducted from the bulk displaced by both;

the remainder is the weight of a bulk of water equal to the bulk of the light body. For instance, a piece of wood weighing 12 grammes (or grains) is tied to a piece of metal weighing 22 grammes, the loss of weight of the metal in water having been previously found to be 3 grammes. The two, weighing 34 grammes, are now immersed, and the loss in weight found to be 26 grammes. But of this loss 3 grammes have been proved to be due to the buoyant action of the water on the lead; the remaining 23, therefore, represent the same effect on the wood; 23 and 12, therefore, represent the weights of equal bulks of water and wood. As 23 are to 12 so is 1 to .5217. Or, shortly, as before, divide the weight in air by the weight of an equal bulk of water; .5217 is the specific gravity of the wood. Another specimen of wood may be found to be three-fourths (.750) the weight of water, and others heavier. Cork varies from .100 to .300.

Specific Gravity of Gases.

This operation is similar to that for liquids. A globe exhausted of air and holding from 1 to 4 litres (or quarts) is suspended from the arm of a balance, and counterpoised by a similar flask. Gases are introduced in succession and their weights noted. A rule-of-three sum shows their specific gravity in relation to air or hydrogen, whichever be taken as a standard.

Correction of the Volume of Gases for Pressure.—The height of the barometer at the time of manipulation is noted. Remembering the fact that "the bulk of a gas is inversely as the pressure to which it is subjected" (Boyle and Mariotte), a simple calculation shows the volume which the gas would occupy at 760 millimetres (or 29.922 inches), the standard pressure. (30 inches is sometimes adopted as the standard in England.*) Thus, 40 volumes of a gas at 740 millimetres pressure are reduced to 39 when the pressure becomes 760 millimetres (or 90 vols. at 29 ins. barom. become 87 vols. at 30 inches).

Correction of the Volume of Gases for Temperature.—This is done in order to ascertain what volume the gas would occupy at 0° C. (32° F.) or 15°.5 C. (60° F.), according to the standard taken.

* In France the conventional standard height of the barometer is 760 millimetres at 0° C. (32° F.); in England it is 30 inches, the temperature of the mercurial column being 60° F. 760 millims. is equivalent to 29.922 inches; but the expansion of the metal between 32° F. and 60° F. increases the length of the column to 30.005 inches. The standards are, therefore, almost identical, difference in true length being counterbalanced by the temperature at which the length is observed.

Gases expand about 0.3665* per cent. ($\frac{1}{273}$) of their volume *at the freezing-point of water* for every C. degree (0.2036, or $\frac{1}{491}$ for every F. degree) (Regnault). Thus 8 volumes of gas at 0° C. will become 8.293 at 10° C.; for if 100 become 103.665 on being increased in temperature 10° C., 8 will become 8.293 (or if 100 become 102.036 on being increased 10° F., 8 will become 8.1629).

Vapor-density.—Vapors are those gases which condense to liquids at common temperatures. By the density of a vapor is meant its specific gravity. The density of a vapor is the ratio of any given volume to a similar volume of air or hydrogen at the same temperature and pressure. But, for convenience of comparison, this experimental specific gravity is referred, by calculation as just described for permanent gases, to a temperature of 0° C., and 760 millimetres barom. A teaspoonful or so of liquid is placed in a weighed flask of about the capacity of a common tumbler and having a capillary neck; the flask is heated in an oil-bath to a temperature considerably above the boiling-point of the liquid; at the moment vapor ceases to escape, the neck is sealed by a blowpipe-flame, and the temperature of the bath noted; the flask is then removed, cooled, cleaned, and weighed; the height of the barometer is also taken. The neck of the flask is next broken off beneath the surface of water or mercury (which rush in and fill it), and again weighed, by which its capacity in cub. centims. is found. From these data the volume of vapor yielded by a given weight of liquid is ascertained by a few obvious calculations. The capacity of the globe having been ascertained, the weight of an equal bulk of air† is obtained by a rule-of-three sum. This weight of air is deducted from the original weight of the flash, which gives the true weight of the glass. The weight of the glass is next subtracted from the weight of the flask and contained vapor (now condensed), which gives the weight of material used in the experiment. The volume which this weight of material occupied at the time of experiment is next corrected for temperature (to 0°C.) and pressure (760 millimetres) in the manner just described. The weight of a similar volume of hydrogen is next found.‡ The weights of equal volumes of hydrogen and vapor being thus determined, the amount of vapor corresponding to 1 of hydrogen (the specific gravity

* Corrected for the difference between the mercurial and air thermometers the coefficient of expansion of air is 0.003656 (Miller). Gases vary slightly.

† 1 cub. centim. of air at 0° C. and 760 millims. weighs 0.001293 gramme.

‡ 1 litre (1000 cub. centims.) of hydrogen at 0° C. and 760 millimetres (the barometer being at 0°C.) weighs 0.0896 gramme—a volume sometimes termed a *crith* (from κριθή, *krithē*, a barley-corn—figuratively, a small weight); thus a litre of oxygen weighs 16 criths, chlorine 35.5 criths, etc. 100 cubic inches of hydrogen at 32° F. weigh 2.265 grains; at 60° F. 2.143 grains (the barometer being 30 ins. at 60° F. in both cases). 100 cubic inches of air at 32° F. weigh 32.698 grains; at 60° F, 30.935 (barom. 30 ins. at 60° F). 1 cubic inch of water weighs 252.5 (252.458 at 62° F, and 30 in bar.) grains. 1 gallon of water contains 277¼ (277,274 at 62° F) cubic inches.

or vapor-density) is shown by a short calculation. This process of finding the weight of a given volume of vapor is by Dumas. Gay-Lussac's consists in determining the volume of a given weight.

Experiment shows that the specific gravities of many gases and vapors on the hydrogen scale and the proportions in which they combine by weight are identical. Thus, chlorine is 35.5 times as heavy as hydrogen, and 35.5 parts unite with 1 of hydrogen to form hydrochloric acid gas. Hence, if the specific gravity of a gas or vapor is known, its combining proportion may be predicated with reasonable certainty, and *vice versâ*. In applying this rule to gaseous or vaporous compounds, attention must be paid to the extent to which their constituent gases contract at the moment of combination or expand at the moment of decomposition. Thus, steam is found to be composed of two volumes of hydrogen and one of oxygen, the three volumes of constituents condensing to two at the moment of combination. Hence, steam may be expected to be nine times as heavy as hydrogen, which experiment confirms.

These relations may be so expressed as to include both elementary and compound gases and vapors, thus: *molecular weights and specific weights are identical.* Molecular weights represent two volumes of a gas; specific gravity conventionally represents the relative weight of a gas compared with *one* volume of hydrogen or air; hence the specific gravity of a gas or vapor on the H scale is found by calculation on simply dividing the molecular weight by 2; on the air-scale by dividing the hydrogen numbers by 14.44. For example,—

Name.	Molecular formula.	Molecular weight.	Specific gravity. H = 2.	H = 1.	Air = 1.
Hydrogen,	H_2	2	2	1	.069
Chlorine,	Cl_2	71	71	35.5	2.460
Oxygen,	O_2	32	32	16	1.108
Nitrogen,	N_2	28	28	14	.970
Steam,	H_2O	18	18	9	.624
Ammonia gas,	NH_3	17	17	8.5	.589
Carbonic acid gas,	CO_2	44	44	22	1.524
Alcohol (vapor),	C_2H_6O	46	46	23	1.593
Air,	.....	....	28.88	14.44	1.000

These specific gravities closely correspond with those obtained by actual experiment. The specific gravity of any gas or vapor may therefore be calculated if the following data are at hand: (*a*) formula, (*b*) atomic weight of constituent elements; these give the molecular weight, and *the molecular weight divided by* 2 *is the specific gravity* on the hydrogen-scale. Specific gravity on the air-scale is then deducible, if (*c*) the specific gravity of air (14.44) in relation to hydrogen be remembered. The absolute weight of any volume of a gas or vapor on the metric system is then obtainable if (*d*) the weight of a litre of hydrogen (0.0896 gramme) be known, or on the English plan by remembering (*e*) that 100 cubic inches of hydrogen at 60° F. weigh 2.143 grains (100 cubic inches of air at 60° F. weigh 30.935 grains).

In confirmation of these statements regarding the mutual relation

of specific gravity and atomic weight, a remarkable fact may be mentioned. Regnault several years ago found the weights of 1 litre of hydrogen and oxygen to be respectively .089578 and 1.429802 gramme. The latter number divided by the former gives 15.96 as the specific gravity of oxygen. Stas, in recent experimental researches on combining-proportion, finds the atomic weight of oxygen to be not 16, but 15.96.

Exceptions to the law occur in a few compounds and in arsenicum and phosphorus, whose vapor-densities are twice that indicated by the rule.

Relation of the Specific Heat of Elements to their Atomic Weights.—Reference may here appropriately be made to a physical fact of great importance as regards molecular and atomic weights. In the earlier pages of this manual it was stated that elements do not combine chemically in haphazard proportions, but in fixed weights; and abundant evidence of the truth of the statement has already been afforded, and will also be found in this section on quantitative analysis. Secondly, it has been shown that elements do not combine in haphazard proportions by volume, but in certain constant bulks; and the weights of these bulks have been found to be identical with the combining weights themselves. Thirdly (and this is the point to which attention is drawn), if equal amounts of heat be given to elements in the solid state (that is, to solid elements or solid compounds of volatile elements), and the quantity of the element be increased or diminished until each is thus heated through an equal number of degrees, it will be found that the different weights of elements required are (in relation to a common standard) identical with the combining weights of the elements, and with the weights of the combining volumes of the elements. Thus, where 108 parts of silver would be employed, 207 of lead would be necessary. Hence, in the determination of (*a*) combining-proportion, (*b*) specific gravity in gaseous state, and (*c*) specific heat, three distinct methods of ascertaining atomic weight are available. In cases where one method is inapplicable recourse is had to either or, if practicable, both of the others, and thus the trustworthiness of observations and generalizations placed more or less beyond question. The specific heat of a solid element is the same in the free as in the combined condition; therefore the specific heat of a molecule is the sum of the specific heats of its constituent atoms. From the specific heat of a solid compound of a volatile element (chlorine, for example) can thus be calculated the specific heat of an element in the solid state, even though the free element cannot itself be solidified. For the processes by which experimentally to determine specific heat the reader is referred to books on physics.

QUESTIONS AND EXERCISES.

971. Define specific weight, or as it is commonly termed, specific gravity.

972. In speaking of light and heavy bodies especially, what standard of comparison is conventionally employed?

973. How are specific gravities expressed in figures?

974. Why should specific gravities be taken at one constant temperature?

975. How does the buoyancy of air affect the real weight of any material?

976. Describe the difference between density and specific gravity.

977. Give a direct method for the determination of the specific gravity of liquids.

978. A certain bottle holds 150 parts, by weight, of water, or 135.7 of spirit of wine; what is the specific gravity of the latter? *Ans.* 0.9046.

979. Equal volumes of benzol and glycerine weigh 34 and 49 parts respectively, and the sp. gr. of the benzol is 0.850; what is the specific gravity of the glycerine? *Ans.* 1.225.

980. Explain the process employed in taking the specific gravity of solid substances in mass and in powder.

981. State the method by which the specific gravity of a light body, such as cork, is obtained.

982. What modifications of the usual method are necessary in ascertaining the specific gravity of substances soluble in water?

983. How is the specific gravity of gases determined?

984. By what law can the volume of a gas, at any required pressure, be deduced from its observed volume at another pressure?

985. To what extent will 78 volumes of a gas at 29.3 inches barometer alter in bulk when the pressure, as indicated by the barometer, is 30.2 inches?

986. Write a short account of the means by which the volumes of gases are corrected for temperature.

987. At the temperature of 15° C. 40 volumes (litres, pints, ounces, cubic feet, or other quantity) of a gas are measured. To what extent will this amount of gas contract on being cooled to the freezing-point of water (0° C.)?

Answer. As 1 vol. of any gas *at zero* expands or contracts .003665 of a vol. for each rise or fall of 1° C., 1 vol. at 0° C. if heated to 15° C. will become increased by .054975 (that is .003665 multiplied by 15), 1 vol. will expand to 1.054975. Conversely, 1.054975 vol. will contract to 1 vol. if cooled from 15° C. to 0° C. And if 1.054975 becomes 1 in cooling through 15° C., 40 vols. will (as found by rule-of-three) contract to 37.916.

(The following five problems and solutions are from Williamson's "Chemistry.")

988. 10 litres of oxygen are measured off at 14° F. Required the volume of the gas at 15° C.

Answer. The first operation must be to reduce the temperature quoted in Fahrenheit's degrees to an equivalent value on the Centigrade scale. 14° F. is 18° below 32° F., the freezing-point of water; and a range of 9° on the Fahrenheit's scale is equal to a range of 5° on the Centigrade scale, so that the temperature at which the oxygen is measured off is—10° C. The rise of temperature up to 0° expands the gas in such proportion that its volume at 0° is to its volume at —10° as 1 is to 1—0.03665, *i. e.* as 1 to 0.96335. The further rise

of temperature from 0° C. to 15° expands the gas in the proportion of 1 to $1+15\times0.003665$; *i. e.* 1 to 1.054975. The total rise of temperature therefore expands the gas in the proportion of 0.96335 to 1.054975.

$$0.96335 : 1.054975 : : 10 : x;$$

$$\therefore x = \frac{10 \times 1.054975}{0.96335} = 10.95.$$

989. 230 cubic centimetres of oxygen are measured off at 14° C. and 740 millimetres mercurial pressure. Required the volume of the gas at the normal temperature and pressure (0°C. and 760 millimetres).

Answer. Let the reduction for change of temperature be made first. The proportion

$$1 + 14 \times 0.003665 : 1 : : 230 : x$$

gives

$$x = \frac{230}{1.05131} = 218.774$$

To reduce this volume at 740 millimetres pressure to the volume corresponding to the pressure of 760 millimetres, we have the proportion

$$38 : 37 : : 218.77 : x;$$

whence

$$x = \frac{37 \times 218.77}{38} = 213.02.$$

990. A litre of oxygen is confined in a glass flask at 10° C. by the atmospheric pressure, added to that of a column of mercury 60 millimetres high. The flask must be heated to 300° C. without any increase of volume taking place in the oxygen. How high must the column of mercury then be which presses on the gas, supposing the atmospheric pressure to remain constant at 760 millimetres?

Answer. The oxygen is given at 10° C. and 820 millimetres pressure. If the pressure remained constant, the rise of temperature from 10° C. to 300° C. would expand the gas in such proportion that 1.03665 volume would expand to 2.0995 volumes. In order to prevent any expansion the pressure must be increased in the same proportion, whence

$$1.03665 : 2.0995 : : 820 : x;$$

$$\therefore x = \frac{820 \times 2.0995}{1.03665} = 1660.6.$$

From this total pressure the atmospheric pressure of 760 millimetres has to be deducted, leaving 900.6 millimetres as the height of the required mercurial column.

991. A litre of oxygen is required of the density of 100 at 0° C. What weight of potassic chlorate must be used for its preparation, and what total pressure must be applied to it?

Answer. The pressure required to compress oxygen from the density of 16 to that of 100 is found by the proportion

$$16 : 100 :: 760 : x;$$

$$\therefore x = \frac{76000}{16} = 4750.$$

At the pressure of 4750 millimetres of mercury the weight of a litre of oxygen (16 grammes measure 11.2 litres at 0° C. and 760 millims. pressure) is found by the proportion

$$760 : 4750 :: \frac{16}{11.2} : x;$$

whence

$$x = \frac{16 \times 4750}{11.2 \times 760} = 8.93 \text{ grammes.}$$

The weight of chlorate required for the evolution of 8.93 grammes of oxygen is found from the proportion

$$48 : 122.5 :: 8.93 : x;$$

$$\therefore x = 22.8 \text{ grammes.}$$

992. What is the volume of 12 grammes of hydrogen at 15° C.?

Answer. One gramme of hydrogen measures 11.2 litres at 0° C., therefore 12 grammes measure $12 \times 11.2 = 134.4$ litres at 0°. To find their volume at 15° C. we have the proportion

$$1 : 1 + 15 \times 0.003665 :: 134.4 : x;$$

whence

$$x = 134.4 \times 1.054975 = 141.788 \text{ litres.}$$

993. What interest for chemists have the specific heats of substances?

VOLUMETRIC ANALYSIS.

(*See the Introductory Remarks to Quantitative Analysis.*)

APPARATUS.

The only special vessels necessary in volumetric quantitative operations are: 1. *A litre flask*, which, when filled to a mark on the neck, contains one litre (1000 cubic centimetres, *i. e.*, 1000 grammes of water*); it serves for preparing solutions in quantities of one litre. 2. A tall, cylindrical *graduated litre jar* divided into 100 equal parts; it serves for the measurement and admixture of decimal or centesimal parts of a litre. 3. A graduated tube or *burette*, which, when filled to 0, holds 100 cubic centimetres (a decilitre), and

* A cubic centimetre is, strictly speaking, the volume occupied by one gramme of distilled water at its point of greatest density, namely, 4° C.; metrical measurements, however, are uniformly taken at 15°.55 C. (60° F.).

is divided into 100 equal parts; it is used for accurately measuring small volumes of liquids.

The best form of a burette is Mohr's. It consists of a glass tube about the width of a little finger and the length of an arm from the elbow, contracted at the lower extremity and graduated. To the contracted portion is fitted a small piece of vulcanized caoutchouc tubing, into the other end of which a small spout made of narrow glass tube is tightly inserted. A strong wire clamp effectually prevents any liquid from passing out of the burette unless the knobs of the clamp are pressed by the finger and thumb of the operator, when a stream or drop flows at will. The accurate reading of the height of a solution in the burette is a matter of great importance; it should be taken from the bottom of the curved surface of the liquid. It may be still more exactly measured in operations of special delicacy by the employment of a hollow glass float or bulb (Erdmann's float), of such a width that it can move freely in the tube without undue friction, and so adjusted in weight that it shall sink to more than half its length in any ordinary liquid. A fine line is scratched round the centre of the float; this line must be always regarded as marking the height of the fluid in the burette. In charging the burette, a solution is poured in, not until its surface is coincident with 0, but until the mark on the float is coincident with 0.

ESTIMATION OF ALKALIES, ETC.

An equation represents much more than the formation of certain substances from others. Thus

$$\underset{\text{Ammonia.}}{2NH_4HO} + \underset{\substack{\text{Crystallized}\\\text{oxalic acid.}}}{H_2C_2O_4, 2H_2O} = \underset{\substack{\text{Oxalate of}\\\text{ammonium.}}}{(NH_4)_2C_2O_4, H_2O} + \underset{\text{Water.}}{3H_2O}$$

not only shows that oxalate of ammonium is produced when ammonia and crystallized oxalic acid are mixed together, but among other facts, that 70 parts of ammonia and 126 of oxalic acid yield 142 of crystallized oxalate of ammonium and 54 of water. For formulæ represent molecules; the weight of a molecule is the sum of the weights of atoms; and atomic weights are represented by definite invariable numbers (see the Table of atomic weights in the Appendix).

As 126 parts (= 1 molecule) of oxalic acid combine with 70 parts (= 2 molecules) of ammonia, 63 (half of 126) of oxalic acid will unite with 35 (= 1 molecule) of ammonia (NH_4HO); 63 parts of oxalic acid will also unite with 56 of caustic potash ($KHO = 56$), 40 of caustic soda ($NaHO = 40$), 100 of acid carbonate of potassium ($KHCO_3 = 100$), 69 of anhydrous carbonate of potassium ($K_2CO_3 = 138$), 84 of acid carbonate of sodium ($NaHCO_3 = 84$), 53 of anhydrous carbonate of sodium ($Na_2CO_3 = 106$), or 143 of crystallized carbonate of sodium ($Na_2CO_3, 10H_2O = 286$). And if 63 parts of oxalic acid be dissolved in 100 volumes of water, the stated weights of these various salts should be exactly neutralized by such a solution. 143 parts of crystallized carbonate of sodium, for instance,

should, if pure, be exactly neutralized by the 100 volumes of the oxalic acid solution; and if a less number of volumes is required, the salt is so much per cent. impure. 143 parts by weight of a commercial sample of carbonate of sodium (common washing "soda") requiring only 97 of the standard oxalic acid solution is thus shown to contain 97 per cent. of pure carbonate of sodium, the remainder being impurities. Further, the strength of solutions of ammonia, soda, potash, and lime may be accurately determined by adding to any definite quantity of them gradually, from a burette, a solution containing oxalic acid in known quantity, until exact neutralization is effected. If the quantity of oxalic acid required be 63 parts by weight (or 100 volumes of solution of oxalic acid containing 63 parts, by weight, of the crystals), then the quantities of alkaline solutions employed contain, of potash (KHO) 56 parts by weight, of soda (NaHO) 40, of ammonia (NH_4HO) 35 parts, of slaked lime (Ca2HO) 37, anhydrous lime (CaO) 28, etc. The strength of an alkaline solution, or, in other words, the proportion required to effect neutralization of 100 volumes of the oxalic acid solution, having once been determined and decided by authority (B. P. *e. g.*), that quantity may always be expected to take 100 volumes of the oxalic acid liquid; if less is required, the alkaline liquid is so much per cent. weak.

The exact point of neutralization of acid or alkaline liquids is experimentally ascertained by litmus paper, or, more generally, infusion of litmus, which is turned red by the slightest amount of free acid, and blue by alkali.

Standard Solution of Oxalic Acid.

(Crystallized Oxalic Acid, $H_2C_2O_4$, $2H_2O$=126.)

On account of the bivalent character of the oxalic radical and the univalent character of most of the metals contained in the salts which are estimated by oxalic acid, it is convenient to take half the molecular weight of the acid for experiments, with the whole of the molecular weights of salts of univalent basylous radicals. The oxalic acid must be pure, leaving no ash when a gramme or so is heated to redness in a porcelain or platinum crucible; it must also be quite dry, but not effloresced.

Place 63 grammes of the crystals in a litre flask, add distilled water and shake till dissolved, diluting until the solution, at about 60° F., has an exact volume of 1 litre. Preserve in a stoppered bottle.

100 cubic centimetres of this solution contain $\frac{1}{20}$ of the molecular weight of oxalic acid in grammes, and will neutrallize $\frac{1}{20}$ of the molecular weight in grammes, of a salt containing one atom of certain bivalent metals (as Ca2HO), or a salt (Na_2CO_3 *e. g.*) containing two atoms of univalent metals, or $\frac{1}{10}$ of the molecular weight in grammes

of salts containing one atom of univalent radicals (such as $KHCO_3$).

The following official substances are tested with this solution. In those which are fluid there is commonly a slight variation in strength according as they are made by formulæ of the British or U. S. Pharmacopœia.

	Grammes of substance.		C. c. of vol. sol.
*Ammonia, solution of	17.00	=	100.0
" strong solution of	5.23	=	100.0
Ammonium, carbonate of, B. P. and U. S. P.	5.90	=	100.0
Borax, B. P. and U. S. P.	19.10	=	100.0
Lead, acetate of, B. P. and U. S. P.	9.50	=	50.0
" sol. of subacetate of, B. P. and U. S. P.	51.02	=	100.0
Lime, aqueous solution of, B. P. and U. S. P.	438.00	=	20.0
" saccharated sol. of,	45.30	=	25.0
Potash, caustic, B. P. and U. S. P.	5.60	=	90.0 to 100.0
" solution of	48.02	=	50.0
" water, effervescing	292.00	=	10.0
Potassium, bicarbonate of, B. P. and U. S. P.	5.00	=	50.0
" acid tart. of, B. P. and U. S. P.	18.80	=	100.0
" carbonate of, B. P. and U. S. P.	8.30	=	98.0 to 100.0
" citrate of, B. P. and U. S. P.	10.20	=	100.0
" tartrate of, B. P. and U. S. P.	11.30	=	100.0
Soda, caustic, B. P. and U. S. P.	4.00	=	90.0 to 100.0
" solution of	48.72	=	50.0
" water, effervescing	246.07	=	10.0
Sodium, bicarbonate of, B. P. and U. S. P.	8.40	=	100.0
" and potassium, tart. of, B.P. and U.S.P.	14.10	=	100.0
" carbonate of, B. P. and U. S. P.	14.30	=	96.0 to 100.0

Note 1.—The several substances diluted or dissolved, as described in the following paragraphs, are conveniently placed in a beaker, and the solution of acid run in cautiously from the burette.

Note 2.—A smaller number of c. c. of volumetric solution than 100, and a corresponding amount of substance to be tested, may be employed in any case. But to ascertain percentage of impurity in the substance, the amount corresponding to 100 c. c. of the vol. sol. must be considered to have been used, the number of c. c. then wanting to make up 100 is the percentage of impurity.

The solutions of ammonia require only the addition of solution of litmus, and the acid cautiously added until the last drop turns the liquid red. The amount of acid used previously to the addition to the portion that reddened the litmus indicates the proportional purity of the alkaline liquid. Thus, if only 50 c. c. are required, the solution is

* The reading of the Table may be amplified thus: 17 grammes of the official Solution of Ammonia (*Liquor Ammoniæ*, B. P.), carefully weighed, will require, for complete neutralization, if of full strength, 100 cubic centimetres of the official volumetric solution of oxalic acid.

only half as strong as it ought to be; if 93 c. c. are needed, the sol. of ammonia is 7 per cent. too weak, and so on. The actual quantity of ammonia (NH_4HO) or ammoniacal gas (NH_3) in the solutions is readily ascertained by calculations, thus: 100 c. c. of the acid solution have been employed; these contain $\frac{1}{20}$ of the molecular weight of oxalic acid in grammes = 6.3, and have neutralized $\frac{1}{10}$ of the molecular weight of ammonia in grammes = 3.5 (or 1.7 of NH_3); 5.23 parts, by weight, of strong solution of ammonia (the amount employed in the experiment) contain, therefore, 3.5 of ammonia, NH_4HO, or 1.7 of ammoniacal gas NH_3; now if 5.23 parts of a solution contain 3.5 of real ammonia (NH_4HO), 100 parts will contain (by rule-of-three calculation) 67, and if the 5.23 contain 1.7 part of ammonia gas (NH_3), 100 will contain 32.5; hence the Strong Solution of Ammonia, supposed to have been under examination, contains 67 per cent. of the hydrate or 32.5 per cent. of the gas. The formulæ and molecular weights representing this process are as follows:—

$$\underbrace{2NH_4HO}_{70} \quad \underbrace{(\text{or } 2NH_3)}_{34} \quad + \quad \underbrace{H_2C_2O_4,2H_2O}_{126}$$

The carbonate of ammonium should be dissolved in 30 or 40 c. c. of distilled water, infusion of litmus added, the standard oxalic acid solution allowed to flow in until the well-stirred liquid assumes a purple hue (due to the influence of carbonic acid on the litmus), the whole gently warmed to promote evolution of carbonic acid gas, more standard acid then dropped in until the liquid again becomes purple, heat once more applied, and the operation continued until the last drop of acid turns the solution red; the height of the column of liquid in the burette before the last drop escapes represents the true amount of standard solution used, and hence the percentage of real carbonate of ammonium (of official quality) in the specimen on which the experiment was performed. The solution must be heated with care, or ammonia will escape. (Practised analysts usually add excess of the standard acid and thus fix every trace of ammonia; then gently boil to get rid of carbonic acid gas; bring back the liquid to neutrality by an observed volume of standard alkaline solution, and deduct an equivalent volume of acid from the quantity first added.) The formulæ and molecular weights representing the process are as follows:—

$$\underbrace{N_4H_{16}C_3O_8}_{236} + \underbrace{2(H_2C_2O_4,2H_2O)}_{252}$$

(*vide* p. 78) (2 molecules)

As 252 parts of oxalic acid neutralize 236 of the so-called carbonate of ammonium, 6.3 of acid (or 100 vols. of its solution) will neutralize 5.9 of carbonate. If 5.9 grammes of carbonate be the quantity employed, and it does *not* require 100 c.c. of the volumetric solution, it is so much per cent. weak. Thus, if say 94 c. c. neutralize the salt, the latter is 6 per cent. weak (some ammonia gas has escaped, and, consequently, an abnormal amount of acid carbonate NH_4HCO_3, is present). Any smaller quantity of salt than 5.9 grammes may be used; in that case a rule-of-three sum must be worked to show how many c.c. of vol. sol. would have been employed if 5.9 grammes had actually been the amount under experiment.

The borax should be dissolved in several ounces of distilled water. The formulæ and molecular weights representing the process are as follows:—

$$\underbrace{2NaBO_2,B_2O_3,10H_2O}_{382} + \underbrace{H_2C_2O_4,2H_2O}_{126}$$

The solutions of the acetates of lead in distilled water may be rendered clear by the addition of a few drops of acetic acid. They must be well stirred after each addition of the solution of oxalic acid. The action is complete when the last drop of acid produces no more precipitate (oxalate of lead).

$$\underbrace{Pb2C_2H_3O_2,3H_2O}_{379} + \underbrace{H_2C_2O_4,2H_2O}_{126}$$

$$\underbrace{Pb_2O2C_2H_3O_2}_{548} + \underbrace{2(H_2C_2O_4,2H_2O)}_{252}$$

The solutions of lime require similar treatment.

$$\underbrace{Ca2HO}_{74} \quad \underbrace{(\text{or } CaO)}_{56} + \underbrace{H_2C_2O_4,2H_2O}_{126}$$

Solid caustic potash or soda is never met with in a state of chemical purity, but should contain not less than 90 per cent. of the hydrate of potassium or sodium. The standard acid is added to an aqueous solution of the hydrate,

the termination of the action between the alkali and acid being observed by aid of litmus.

If carbonic acid be present, the mixture must be gently boiled before a final reading of the amount of acid added is taken.

$$\underbrace{2KHO}_{112} \text{ or } \underbrace{2NaHO}_{80} + \underbrace{H_2C_2O_4, 2H_2O}_{126}$$

The alkaline carbonates are often moist, and include traces of sulphates, chlorides, and silicates, but are sufficiently pure if containing, in the case of carbonate potassium 98 per cent., and carbonate of sodium 96 per cent., of the respective crystalline salts. The volumetric manipulations with these salts are similar to those for carbonate of ammonium. The strength of soda-ash is often reported in terms of "soda," that is, oxide of sodium ($Na_2O=62$). The old molecular weight of carbonate of sodium, 54 (it should have been 53), derived from that of "soda," 32 (it should have been 31), is still employed in Great Britain in reporting the strength of soda-ash. The true amount of soda equivalent to 54 parts of carbonate is 31.41 parts. A modern analyst having found the true amount of soda in a sample of soda-ash is expected by some manufacturers to report 31.41 parts for every 31, and 54 of carbonate instead of 53, and other quantities in proportion to these figures.

$$\underbrace{2KHCO_3}_{200} + \underbrace{H_2C_2O_4, 2H_2O}_{126} \qquad \underbrace{2NaHCO_3}_{168} + \underbrace{H_2C_2O_4, 2H_2O}_{126}$$

$$\underbrace{K_2CO_3}_{138} + \underbrace{H_2C_2O_4, 2H_2O}_{126} \qquad \underbrace{Na_2CO_3}_{106} + \underbrace{H_2C_2O_4, 2H_2O}_{126}$$

$$\underbrace{K_2CO_3 \text{ of } 84\%}_{164.285} + \underbrace{H_2C_2O_4, 2H_2O}_{126} \qquad \underbrace{Na_2CO_3, 1QH_2O}_{286} + \underbrace{H_2C_2O_4, 2H_2O}_{126}$$

One molecule of tartrate of potassium, or two of the *acid tartrate*, yields one of carbonate when burnt, two molecules of *citrate* yielding three of carbonate under the same circumstances. Two molecules of *tartrate of potassium and sodium* yield one of potassium carbonate and one of sodium carbonate. A volumetric estimation of the amount of carbonate thus produced affords indirect means of quantitatively determining the purity of the original salts.

$$\underbrace{K_2C_4H_4O_6}_{226} \text{ eq. to } \underbrace{H_2C_2O_4, 2H_2O}_{126}$$

$$\underbrace{2KHC_4H_4O_6}_{376} \text{ eq. to } \underbrace{H_2C_2O_4, 2H_2O}_{126}$$

$$\underbrace{2K_3C_6H_5O_7}_{612} \text{ eq. to } \underbrace{3H_2C_2O_4, 2H_2O}_{378}$$

$$\underbrace{NaKC_4H_4O_6, 4H_2O}_{282} \text{ eq. to } \underbrace{H_2C_2O_4, 2H_2O}_{126}$$

Alkalimetry.—The foregoing processes are often spoken of as those of *alkalimetry* (the measurement of alkalies).

Notes.

Neutral solution of litmus is prepared by digesting the commercial fragments in about fifteen or twenty times their weight of water for a few hours, decanting, dividing into two equal portions, adding acid to one till it is faintly red, then pouring in the other, and mixing. The solution may be kept in a stoppered bottle, but occasionally exposed to the air. It should never be filtered, but gradually allowed to deposit.

Standard sulphuric acid may be used in the place of oxalic acid if the latter cannot readily be obtained in a state of purity, 100 c. c. of the liquid containing $\frac{1}{2}\frac{1}{0}$ of the molecular weight of the pure acid in grammes. It is prepared by diluting oil of vitriol with from three to four times its bulk of distilled water, ascertaining how much of the acid liquid is required to exactly neutralize $\frac{1}{2}\frac{1}{0}$ of the molecular weight of pure carbonate of sodium, taken in grammes (5.3), and adding water until the observed volume of acid is increased to 100 c. c. Pure anhydrous carbonate of sodium (Na_2CO_3) is obtained by heating the pure bicarbonate to dull redness in a platinum or porcelain crucible for about a quarter of an hour. The commercial bicarbonate should be tested for chlorides and sulphates, which are usually present in small quantities. Two or three hundred grammes may be purified by washing first with a saturated solution of bicarbonate of sodium and then cold distilled water until all trace of impurity has disappeared, drying over a water-bath, and then igniting to convert into carbonate.

Other quantities of salts than those stated in the foregoing and following Tables may be employed in volumetric determinations, calculation giving any desired form to the experimental results, an expert analyst thus saving much time and material. In the case of substances which are liable to alter by exposure to air, it is important that a selected quantity should be quickly weighed, rather than selected weights be accurately balanced by material, the former operation occupying much the shorter time.

Salts other than the official may be quantitatively analyzed by the volumetric solutions, slight modifications of manipulation even enabling the processes to be adapted to fresh classes of salts. Ample instructions for extending operations in this manner will be found in Sutton's "Handbook of Volumetric Analysis."

QUESTIONS AND EXERCISES.

994. Describe the various pieces of apparatus used in volumetric determinations.

995. One hundred cubic centimetres of solution of oxalic acid contain 6.3 grammes of the crystallized salt; what weights of bicarbonate of potassium and anhydrous carbonate of sodium will that volume saturate?—*Ans.* 10 grammes and 5.3 grammes.

996. What weight of hydrate of potassium is contained in solution of potash 48.02 grammes of which are saturated by 50 c. c. of the standard solution of oxalic acid?—*Ans.* 5.83 per cent.

997. State the percentage of hydrate of calcium in lime-water 438 grammes of which are neutralized by 20 c. c. of the volumetric solution of oxalic acid.—*Ans.* .1689.

998. Eight grammes of a sample of Rochelle salt, after appropriate treatment, require 54.3 c. c. of the oxalic acid solution for complete saturation; what is the centesimal proportion of real salt present?—*Ans.* 95.7.

ESTIMATION OF ACIDS.

In the previous experiments a known amount of an acid has been used in determining unknown amounts of alkalies. In those about to be described a known amount of an alkali is employed in estimating unknown amounts of acids. The alkaline salt selected may be a hydrate or a carbonate; but the former is to be preferred; for the carbonic acid, set free when a strong acid is added to a carbonate, interferes to some extent with the indications of alkalinity, acidity, or neutrality afforded by litmus. The alkali most convenient for use is soda, a solution of which has probably already been made the subject of experiment in operations with the standard solution of oxalic acid. It should be kept in a stoppered bottle and exposed to air as little as possible.

Standard Solution of Soda.

(Hydrate of Sodium, NaHO = 40.)

100 c. c. of the standard solution of oxalic acid are placed in a beaker with a little litmus, the tube or burette

in which the acid was measured rinsed out, and the washings poured into the beaker. A little strong solution of caustic soda is poured through the burette to rinse out water adhering to the tube and float (these rinsings thrown away), and the tube then filled to 0 with more of the alkaline liquid. The solution of soda is cautiously allowed to flow into the beaker until exact neutrality is obtained, the quantity noted, and, to every similar quantity of the whole bulk of the solution of soda, water added until the liquid measures 100 parts. If, for example, 93 c. c. of solution of soda have neutralized the 100 c. c. of acid, then 7 c. c. of distilled water must be added to 93 c. c. of the soda solution, or 70 to 930 to make a litre. A sum of simple proportion will show to what extent any other quantity is to be diluted. Thus, if the bulk of soda solution remaining measures, say, 900 c. c., its volume must be augmented to 967.7 c. c.; for if 93 are to be diluted to 100, 900 must be diluted to 967.7.

100 c. c. of the soda solution contain $\frac{1}{10}$ of the molecular weight (= 4), taken in grammes, of pure hydrate of sodium, and will neutralize an equivalent quantity of any acid. That is, 100 c. c. will neutralize $\frac{1}{10}$ of the molecular weight in grammes of an acid containing one atom of any univalent acidulous radical, $\frac{1}{20}$ of the molecular weight in grammes of an acid containing one atom of any bivalent acidulous radical, or $\frac{1}{30}$ of the molecular weight in grammes of an acid containing one atom of any trivalent acidulous radical.

The following official acids are tested with this solution :—

	Grammes of substance.		C. c. of vol. sol.
Acid, acetic	18.20	=	100.0
" " diluted, B. P. and U. S. P.	70.29	=	50.0
" " glacial	6.00	=	99.0
" citric, B. P. and U. S. P. . . .	7.00	=	100.0
" hydrochloric, B. P. and U. S. P.	11.48	=	100.0
" " diluted	34.50	=	100.0
" nitric, B. P. and U. S. P. . . .	9.00	=	100.0
" " diluted	36.13	=	100.0
" nitro-hydrochloric, diluted . . .	38.30	=	100.0
" sulphuric, B. P. and U. S. P. .	5.06	=	100.0
" " aromatic	36.65	=	100.0
" " diluted	35.90	=	100.0
" tartaric, B. P. and U. S. P. . .	7.50	=	100.0

Notes.—1. In volumetrically estimating the strength of acids by an alkali, the indicator of neutrality is the same as that used in testing alkalies by an acid, namely, litmus.

2. Pure acetates, citrates, tartrates, and some other organic salts have an alkaline action on litmus, but not to an important extent. If the soda solution be added to acetic, citric, or tartaric acids, containing litmus, until the liquid is fairly blue, the operator will obtain trustworthy results. In delicate experiments turmeric may be used instead of litmus.

3. Six grammes of *pure* glacial acetic acid are neutralized by 100 c. c. of the standard solution of soda. But acid of this degree of purity is extremely difficult to prepare. The commercial acid contains only 1 per cent. of water, and is sufficiently pure for use in medicine.

Acidimetry.—The operations for the quantitative analysis or measurement of acids are often collectively spoken of under the name of *acidimetry.* They admit of considerable extension. (See the work previously cited.)

Percentage strength of Acids.—The percentage strength of the several acids and their official solutions is readily ascertained by calculation in a manner similar to that given for alkalies. Thus the volumetric operation with the liquid commonly termed acetic acid is based on the reaction expressed in the following equation:—

$$\underset{\text{Acetic acid.}}{HC_2H_3O_2} + \underset{\text{Soda.}}{NaHO} = \underset{\text{Acetate of sodium.}}{NaC_2H_3O_2} + \underset{\text{Water.}}{H_2O}.$$

This equation, translated into parts by weight, means that 60 parts (the molecular weight) of true acetic acid are exactly neutralized by 40 parts (the molec. wt.) of soda. Supposing the quantity of "acetic acid" employed in the experiment to have been that recommended in the Table (18.2 grammes), and that to neutralize it 100 c. c. of the soda solution have been used, and remembering that 100 c. c. of the soda solution contain 4 grammes of soda, it follows that the 18.2 grammes of the liquid called acetic acid contain 6 grammes of real acetic acid; for if 40 (the molec. wt.) of soda neutralize 60 (the molec. wt.) of real acetic acid, 4 will neutralize 6. Lastly, if 18.2 contain 6, 100 will contain 33; the so-called acetic acid (really an aqueous solution) contains 33 per cent. of true acetic acid ($HC_2H_3O_2$).

If the 18.2 grammes have taken, say, 93 instead of 100 c. c., the acid liquid is 7 per cent. weak; in other words, it contains only 30.7 per cent. of real acid; for (by rule-of-three) if 100 c. c. added to 18.2 grammes indicate 33 per cent., 93 c. c. added to 18.2 grammes indicate 30.7 per cent.

The remaining acids react with the alkaline salts in the manner and to the extent indicated by the following formulæ and molecular weights:—

$$\underbrace{H_3C_6H_5O_7,\ H_2O}_{210} + \underbrace{3NaHO}_{120}$$

$\underbrace{HCl}_{36.5} + \underbrace{NaHO}_{40}$	$\underbrace{HNO_3}_{63} + \underbrace{NaHO}_{40}$
$\underbrace{H_2SO_4}_{98} + \underbrace{2NaHO}_{80}$	$\underbrace{H_2C_4H_4O_6}_{150} + \underbrace{2NaHO}_{80}$

QUESTIONS AND EXERCISES.

999. What percentage of real acid is present in diluted sulphuric acid 30 grammes of which are neutralized by 84 c. c. of the official volumetric solution of soda?—*Ans.* 13.72.

1000. How much real nitric acid is contained in a solution 36 grammes of which are saturated by 94 c. c. of the standard solution of soda?—*Ans.* 16.45 per cent.

ESTIMATION OF ACIDULOUS RADICALS PRECIPITATED BY NITRATE OF SILVER.

The purity of many salts, and the strength of their solutions, may be determined by this process; but at present only three official substances (namely, diluted hydrocyanic acid, bromide of potassium, and arseniate of sodium) are quantitatively analyzed by standard solution of nitrate of silver. The reactions on which the success of the process depends are expressed in the following equations:—

$$\left\{\begin{array}{l} AgNO_3+2NaCy=NaCyAgCy+NaNO_3, \\ NaCyAgCy+AgNO_3=2AgCy+NaNO_3; \end{array}\right.$$
$$KBr+AgNO_3=AgBr+KNO_3;$$
$$Na_2HAsO_4+3AgNO_3=Ag_3AsO_4+2NaNO_3+HNO_3.$$

Standard Solution of Nitrate of Silver.

(Nitrate of Silver, $AgNO_3 = 170$.)

Dissolve 17 grammes of crystals of pure nitrate of silver in 1 litre of water. 100 c. c. of this solution contain $\frac{1}{100}$ of the molecular weight in grammes of nitrate of silver, and will decompose an equivalent quantity of a salt of any acidulous radical yielding silver compounds insoluble in water.

	Grammes of substance.	C. c. of vol. sol.
Acid, hydrocyanic, diluted, B. P. and U. S. P.	27.00	= 100.0
Potassium, bromide of, B. P. and U. S. P.	1.19	= 100.0
Sodium, arseniate of (dry)	.62	= 100.0

Diluted hydrocyanic acid is converted into cyanide of sodium by adding caustic soda until, after stirring, litmus shows that the liquid has an alkaline reaction. The nitrate-of-silver solution is then allowed to flow in gradually, until, after thorough agitation, a slight permanent turbidity remains. When this occurs, the quantity of nitrate of silver added represents exactly half the amount of real hydrocyanic acid present in the diluted preparation. Thus the 100 c. c. of standard solution contains $\frac{1}{100}$ of the molecular weight, in grammes, of nitrate of silver (= 1.7); this would ordinarily correspond, in a case of complete decomposition, to $\frac{1}{100}$ of the molecular weight in grammes of hydrocyanic acid (= .27); 27 grammes of the diluted acid, the quantity employed in the experiment, apparently contain therefore .27 grammes of real acid, equal to 1 per cent. A glance at the equation shows that at the moment cyanide of silver begins to be precipitated, only half of the cyanogen has been converted into cyanide of silver; the quantity of acid indicated by the amount of nitrate added must therefore be doubled for the correct percentage (= 2).

$$\underbrace{2HNC}_{54} \text{ eq. to } \underbrace{AgNO_3}_{170}$$

Bromide of potassium is dissolved in distilled water in a beaker, and the standard solution added until, after agitation of the liquid and subsidence of the bromide of silver, a drop of the solution of nitrate of silver gives no more precipitate.

$$\underbrace{KBr}_{119} + \underbrace{AgNO_3}_{170}$$

Arseniate of sodium ($Na_2HAsO_4,7H_2O$) must be dried at 300° F. before weighing. It is thus reduced to a definite anhydrous salt (Na_2HAsO_4), losing, if pure, 40.38 per cent. of water. Of the weighed residue .62 gramme is dissolved in distilled water, 3.3 c. c. of the vol. sol. of soda added, and the whole treated as described in the previous paragraph.

$$\underbrace{Na_2HAsO_4}_{186} + NaHO + \underbrace{3AgNO_3}_{510} = Ag_3AsO_4 + 3NaNO_3 + H_2O$$

Spirit of Wine (*Spiritus Rectificatus*, B. P.) may contain traces of amylic alcohol and aldehyd; these may be detected by nitrate of silver, which is reduced by them to the metallic state. Any quantity beyond a mere trace of such bodies renders spirit of wine too impure

for use in medicine. "Four fluidounces with thirty grain-measures (about two cub. cent.) of the volumetric solution of nitrate of silver exposed for twenty-four hours to bright light, and then decanted from the black powder which has formed, undergoes no further change when again exposed to light with more of the test."

QUESTIONS AND EXERCISES.

1001. Explain the volumetric method of estimating the strength of aqueous solutions of hydrocyanic acid.

1002. How much nitrate of silver will indicate, by the official volumetric process, the presence of 1 part of real hydrocyanic acid? —*Ans.* 3.148 parts.

ESTIMATION OF SUBSTANCES READILY OXIDIZED.

Any deoxidizer, that is, any substance which quickly absorbs a definite amount of oxygen or is susceptible of any equivalent action, may be quantitatively tested by ascertaining how much of an oxidizing agent of known power must be added to a given quantity before complete oxidation is effected. The oxidizing agents employed for this purpose in the British Pharmacopœia are iodine and the red chromate of potassium; permanganate of potassium is often used for the same purpose. Iodine acts indirectly, by taking hydrogen from water and liberating oxygen; the red chromate of potassium directly, by the facility with which it yields three-sevenths of its oxygen—as indicated by the equations and statements given on page 491; permanganate of potassium by affording five-eighths of its oxygen in presence of acid, $2K_2Mn_2O_8 + 6H_2SO_4 = 2K_2SO_4 + 4MnSO_4 + 6H_2O + 5O_2$.

Standard Solution of Iodine.

(Iodine, I = 127.)

Prepare pure iodine by mixing the commercial article with about a fourth of its weight of iodide of potassium and subliming. Sublimation may be effected by gently warming the mixture in a beaker, the mouth of which is closed by a funnel; the iodine vapor condenses on the funnel; while fixed impurities are left behind, and any chlorine which the iodine may contain is absorbed by the iodide of potassium, an equivalent quantity of iodine being liberated. Small quantities may be similarly treated between two watch-glasses, placed edge to edge. Any trace of moisture in the resublimed iodine is removed by ex-

posure for a few hours under a glass shade near a vessel containing oil of vitriol.

Place 12.7 grammes of pure iodine and about 18 grammes of pure iodide of potassium (an aqueous solution of which is the best solvent of iodine; the salt plays no other part in these operations) in a litre flask, add a small quantity of water, and agitate until the iodine is dissolved, dilute to 1 litre. 100 c. c. of this solution contain $\frac{1}{2\,0\,0}$ of the molecular weight of free iodine in grammes, and, water being present, will cause the oxidation of $\frac{1}{2\,0\,0}$ of the molecular weight of sulphurous acid (H_2SO_3) in grammes (=.41), or $\frac{1}{2\,0\,0}$ (=.32) of sulphurous acid gas (SO_2), sulphuric acid being formed. 100 c. c. will also oxidize $\frac{1}{2\,0\,0}$ of the molecular weight of arsenious acid (H_3AsO_3) in grammes, or $\frac{1}{4\,0\,0}$ of the molecular weight of common white arsenic (As_2O_3) in grammes (=.495), arsenic acid (H_3AsO_4) being produced. The reactions are expressed in the following equations:—

$$I_2 + H_2O + H_2SO_3 = 2HI + H_2SO_4.$$
$$I_2 + 2H_2O + SO_2 = 2HI + H_2SO_4.$$
$$I_2 + H_2O + H_3AsO_3 = 2HI + H_3AsO_4.$$
$$2I_2 + 5H_2O + As_2O_3 = 4HI + 2H_3AsO_4.$$
$$I_2 + 2(Na_2S_2O_3, 5H_2O) = 2NaI + Na_2S_4O_6 + 10H_2O.$$

The following official substances are tested with the standard solution of iodine:—

	Grammes of substance.		C c. of vol. sol.
Acid, solution of sulphurous	3.47	=	100
Arsenic, in mass, B. P. and U. S. P. . .	0.495	=	100
" in alkaline sol. (*Liq. Arsenicalis*)	54.64	=	100
" in acid sol. (*Liq. Arsen. Hydrochl.*)	54.64	=	100
Sodium, hyposulphite of	2.48	=	100

The solution of sulphurous acid is diluted with three-fourths of a litre of cold water, and the iodine solution added until a slight permanent brown tint is produced, showing the presence of free iodine. A better indication of the termination of the action is afforded by mucilage of starch, which gives a blue color with the slightest trace of iodine. As already stated, 100 c. c. of this volumetric solution contain an amount of free iodine sufficient to cause the oxidation of $\frac{1}{2\,0\,0}$ of the molecular weight of either sulphurous acid or sulphurous acid gas. Now $\frac{1}{2\,0\,0}$ of the molecular weight of sulphurous acid (H_2SO_3) in grammes is 0.41; if 3.47 grammes of the solution contain

0.41 of the acid, 100 of the solution will be found to contain 11.8. By a similar calculation the official solution may be shown to contain, or, rather, yield 9.22 per cent. of sulphurous acid gas (SO_2).

If the sulphurous acid be diluted to a less degree than .04 or .05 per cent., there will be some risk of the sulphuric acid formed being again reduced to sulphurous acid, with liberation of iodine. In delicate experiments the distilled water used for dilution should previously be freed from air by boiling, to prevent the small amount of oxidizing action which dissolved air would exert.

$\underbrace{H_2SO_3}_{82}$ eq. to $\underbrace{I_2}_{254}$	$\underbrace{SO_2}_{64}$ eq. to $\underbrace{I_2}_{254}$

The solid arsenic is dissolved in boiling water by help of about two grammes of bicarbonate of sodium. When the liquid is quite cold, mucilage of starch is added, and the iodine solution allowed to flow in until, after well stirring, a permanent blue color is produced.

$\underbrace{H_3AsO_3}_{126}$ eq. to $\underbrace{I_2}_{254}$	$\underbrace{As_2O_3}_{198}$ eq. to $\underbrace{2I_2}_{508}$

The arsenical solution already containing some carbonate of potassium requires only about one and a half gramme of bicarbonate of sodium for neutralization of the arsenious acid. After boiling and cooling, starch and the iodine solution are added as before.

The solution of arsenic in dilute hydrochloric acid requires about three grammes of acid carbonate of sodium, if 54 or 55 grammes of solution is the quantity employed. After boiling for a few minutes and cooling, the starch and iodine are added.

These arsenical solutions contain .9 per cent. of arsenic.

The *Hyposulphate of sodium* is dissolved in water, starch mucilage added, and the iodine solution slowly run in, the whole being frequently stirred, until a permanent blue color is produced.

In the previous reactions iodine has acted as an indirect oxidizing agent by uniting with the hydrogen and thus liberating the oxygen of water. In the present case it unites with an analogue of hydrogen, namely, sodium.

QUESTIONS AND EXERCISES.

1003. Give equations illustrative of the reactions on which the use of a standard volumetric solution of iodine is based.

1004. From what point of view may iodine be regarded as an oxidizing agent?

1005. What reagent indicates the termination of the reaction between deoxidizing substances and moist iodine?

1006. How much sulphurous acid gas will cause the absorption of 2.54 parts of iodine in the volumetric reaction? *Ans.* .64.

1007. What quantity of iodine will be required, under appropriate conditions, to oxidize 5 parts of arsenic? *Ans.* 12.828.

1008. Find by calculation the amount of hyposulphite of sodium equivalent to 13 parts of iodine in volumetric analysis. *Ans.* 25.389.

Standard Solution of Red Chromate of Potassium.

(Red Chromate of Potassium, $K_2CrO_4, CrO_3 = 295$.)

One molecule of red chromate of potassium in presence of an acid, under favorable circumstances, yields four atoms of oxygen to the hydrogen of the acid, leaving three available either for direct oxidation or for combination with the hydrogen of more acid, an equivalent proportion of acidulous radical being liberated for any required purpose.

When used as a volumetric agent, the red chromate always yields the whole of its oxygen to the hydrogen of the accompanying acid, a corresponding quantity of acidulous radical being set free—four-sevenths of this radical immediately combining with the potassium and chromium of the red chromate, three-sevenths becoming available. Ferrous may thus be converted into ferric salts with sufficient rapidity and exactitude to admit of the estimation of an unknown quantity of iron by a known quantity of the red chromate. As one atom of the liberated acidulous radical will convert two molecules of ferrous into one of ferric salt, one molecule of red chromate causes six of ferrous to become three of ferric, as shown in either of the following equations:—

$$K_2CrO_4, CrO_3 + 7H_2SO_4 + 6FeSO_4 = K_2SO_4, Cr_2 3SO_4 + 7H_2O + 3(Fe_2 3SO_4);$$

$$K_2CrO_4, CrO_3 + 14HCl + 6FeCl_2 = 2KCl + Cr_2Cl_6 + 7H_2O + 3Fe_2Cl_6.$$

These equations indicate that, in presence of excess of acid, 295 parts (the molecular weight) of red chromate of potassium will convert 1668 parts of crystallized ferrous sulphate, $6(FeSO_4,7H_2O = 278)$, or an equivalent quantity of ferrous chloride ($6FeCl_2 = 762$), ferrous carbonate ($6FeCO_3 = 696$), ferrous arseniate ($2Fe_3As_2O_8 = 892$), ferrous phosphate ($2Fe_3P_2O_8 = 716$), or iron itself ($3Fe_2 = 336$), into ferric salt. If these parts be taken in grammes, $\frac{1}{100}$ or less of the stated amounts will be found to be convenient quantities for experiment.

Dissolve 14.75 grammes of red chromate of potassium in one litre of distilled water. 100 c. c. of this solution contain $\frac{1}{200}$ of the molecular weight of the salt in grammes, and will cause the conversion of $\frac{1}{200}$ of the weight of 6 atoms of iron in grammes, or an equivalent quantity of the lower salts of iron, from the ferrous to the ferric state. The solution is used in determining the strength of the following official ferrous preparations. It is known that the whole of the ferrous has been converted to ferric salt when a small drop of the liquid placed in contact with a drop of a very dilute solution of ferridcyanide of potassium, on a white plate, ceases to strike a blue color.

	Grammes of substance.		C. c. of vol. sol.
Iron, arseniate of	2.94	=	25
" magnetic oxide of	2.41	=	10
" phosphate of, B. P. and U. S. P .	2.00	=	25
" saccharated carbonate of . . .	4.70	=	50

The several compounds are dissolved in excess of hydrochloric acid diluted with water, and the standard solution then dropped in. The ferrous liquid must not be exposed to the air for more than a few seconds after solution has been effected, or oxygen will be absorbed and a corresponding amount of ferric salt formed before the volumetric oxidizing agent is added: in most cases diluted sulphuric acid may be used as a solvent of the ferrous salt, ferrous sulphate absorbing oxygen from the air far less rapidly than ferrous chloride. It will be found that the proportion of carbonate of iron in the saccharated compound, as indicated by the above numbers, is, 37 in 100. Trade samples yield from 20 to 30, and sometimes 35 per cent., according to the care with which oxidation has been prevented. The theoretical percentage obtainable from the ingredients is 45.5, the quantity that would be present if the compound were anhydrous and unoxydized, conditions never obtained in practice. The 2 grammes of phosphate of iron should contain .895 of real ferrous phosphate or nearly 45 per cent.

The use of these two volumetric solutions in quantitative analysis admits of great extension.

QUESTIONS AND EXERCISES.

1009. Write equations explanatory of the oxidizing power of red chromate of potassium.

1010. One hundred cubic centimetres of an aqueous solution of red chromate of potassium contain $\frac{1}{20}$ of the molecular weight of the salt in grammes; what weight of metallic iron, dissolved in hydrochloric acid, will this volume oxidize?—*Ans.* 1.68 gramme.

1011. If 8.34 grammes of a specimen of crystallized ferrous sulphate require 93 c. c. of the standard solution of chromate for complete oxidation, what percentage of real salt is present?—*Ans.* 93.

1012. How much red chromate of potassium is required for the conversion of 10 parts of ferrous sulphate into ferric salt?—*Ans.* 1.768.

1013. What quantity of pure ferrous carbonate is indicated by 1.475 part of red chromate as applied in volumetric analysis?—*Ans.* 3.48.

1014. State the amount of official saccharated carbonate of iron equivalent to .7375 part of red chromate in the volumetric reaction. —*Ans.* 4.7.

ESTIMATION OF SUBSTANCES READILY DEOXIDIZED.

Any substance which quickly yields a definite amount of oxygen may be quantitatively tested by ascertaining how much of a deoxidizing agent of known power must be added to a given quantity before complete deoxidation is effected. The chief compounds which may be used as absorbers of oxygen (deoxidizers or reducing agents, as they are commonly termed) are hyposulphite of sodium, sulphurous acid, ferrous sulphate,* oxalic acid, arsenious acid. The first-named is officially employed; it is only used in the estimation of free iodine, and, indirectly, of chlorine and chlorinated compounds. Iodine and chlorine are regarded as oxidizing agents, because their great affinity for hydrogen enables them to become powerful indirect oxidizers in presence of water.

Standard Solution of Hyposulphite of Sodium.

(Crystallized Hyposulphite of Sodium, $Na_2S_2O_3,5H_2O=248$.)

Dissolve about 30 grammes of hyposulphite of sodium in a litre or less of water. Fill a burette with this solution, and allow it to flow into a beaker containing exactly 100 c. c. of the volumetric solution of iodine until the brown color of the iodine is just discharged—or, starch

* "Five grains of Permanganate of Potassium dissolved in water require for decoloration a solution of forty-four grains of granulated sulphate of iron acidulated with two fluidrachms of diluted sulphuric acid."—B. P.

being added, until the blue iodide of starch is decolorized. Note the number of c. c. of hyposulphite solution required, and to the bulk of the solution add water, so that 2.48 grammes of hyposulphite of sodium shall be contained in every 100 c. c.

When iodine and hyposulphite of sodium react, two atoms of iodine remove two of sodium from two molecules of the hyposulphite, tetrathionate of sodium being formed, as indicated in the following equation :—

$$I_2 + 2Na_2S_2O_3 = 2NaI + Na_2S_4O_6.$$

As, therefore, 100 c. c. of the iodine solution contain $\frac{1}{100}$ of the atomic weight of iodine in grammes, 100 c. c. of the standard solution of hyposulphite of sodium will contain $\frac{1}{100}$ of the molecular weight of the salt in grammes, and will show the existence of $\frac{1}{100}$ of the atomic weight of iodine in grammes in any quantity of a liquid normally containing free iodine, or iodine liberated by an equivalent quantity of free chlorine.

This solution is employed for quantitatively testing the following substances :—

	Grammes of substance.		C. c. of vol. sol.
Chlorine, solution of	29.26	=	50
Iodine, B. P. and U. S. P.	1.27	=	100
Lime, chlorinated	1.17	=	100
" solution of chlorinated . . .	6.00	=	50
Soda, solution of chlorinated . . .	7.00	=	50

Note.—Owing to the volatility of chlorine and iodine, and the readiness with which they attack the metals of which balances are made, it is not desirable to experiment on stated weights of substances containing these elements. A small stoppered bottle or tube containing the material may be counterpoised, and a convenient quantity removed for analysis, the precise amount taken being ascertained by again weighing the bottle.

The iodine may be dissolved in water containing about a gramme and a half of iodide of potassium, a salt giving no reaction with hyposulphite of sodium.

$$\underbrace{I_2}_{254} \text{ eq. to } \underbrace{2(Na_2S_2O_3, 5H_2O)}_{496}$$

It is assumed in this operation that the iodine has been shown by qualitative analysis to be free from chlorine and bromine. These elements resemble iodine in reacting with

hyposulphite of sodium, hence would reckon as iodine in a volumetric assay.

The solution of chlorine is added to water containing excess of iodide of potassium (about a gramme and a third); a quantity of iodine, equivalent to the amount of chlorine present, is thus liberated. The hyposulphite solution is then dropped in.

$$\underbrace{Cl_2}_{71} \text{ eq. to } \underbrace{2(Na_2S_2O_3, 5H_2O)}_{496}$$

The chlorinated lime ("chloride of lime" or "bleaching-powder") is mixed with about a fifth of a litre of water containing excess of iodide of potassium (3.5 grms.) and acidulated with hydrochloric acid. The available oxygen of the chlorinated lime liberates chlorine from an equivalent quantity of hydrochloric acid; and this, with the available chlorine of the chlorinated lime, sets free an equivalent amount of iodine from the iodide of potassium. The hyposulphite and iodine reacting show the direct and indirect oxidizing power of the chlorinated lime; it should correspond to 30 per cent. of chlorine. For example, as 248 (1 molecule) of hyposulphite indicate the presence of 35.5 (1 atom) of chlorine, 2.48 of hyposulphite (the quantity in 100 c. c.) indicate the presence of .355 of chlorine. If 100 c. c. have been used, therefore, .355 of chlorine is obtainable from the quantity of bleaching-powder employed (1.17). And if 1.17 of bleaching-powder yield .355 of chlorine, 100 will yield about 30 ($30\frac{1}{2}$ nearly).

The solution of chlorinated lime is mixed with about a fifth of a litre of water containing a couple of grammes of iodide of potassium, and ten or twelve c. c. of hydrochloric acid. The hyposulphite solution is then added from a burette until the color of the liberated iodine is just discharged. The solution of chlorinated soda is similarly treated.

Note.—1. In these experiments the blue color formed on the addition of mucilage of starch to the liquids will be found to be a more delicate indicator of the termination of reactions than the brown tint of the iodine.

Note.—2. Standard solutions used in volumetric analysis are often described as normal, decinormal, and centinormal. A normal solution (N) contains in every litre the molecular weight of the salt, *taken in grammes;* a decinormal solution is one-tenth ($\frac{N}{10}$), and a centinormal ($\frac{N}{100}$) one-hundredth the strength of such a normal solution.

QUESTIONS AND EXERCISES.

1015. For what purposes is the official volumetric solution of hyposulphite of sodium used?

1016. On what reaction is based the quantitative employment of hyposulphite of sodium?

1017. How much hyposulphite of sodium is required to show the presence of 10 parts of iodine?—*Ans.* 19.527.

1018. To what amount of chlorine is 4.96 parts of hyposulphite of sodium equivalent in volumetric analysis?—*Ans.* 0.71.

1019. Describe the operations included in the estimation of the strength of bleaching-powder.

1020. By what reagent is the complete absorption of free iodine by hyposulphite of sodium indicated?

MISCELLANEOUS PROBLEMS.

1021. How much bicarbonate of potassium is contained in an eight-ounce bottle of medicine, seven fluidrachms of which are saturated by two and a half grains of crystallized oxalic acid?—*Ans.* 18.1 grains.

1022. A sample of soda-ash is said to contain 78 per cent. of pure anhydrous carbonate of sodium; if the statement is true, how much of the official volumetric solution of oxalic acid will saturate 5 grammes of the specimen?—*Ans.* 73.6.

1023. 2.69 grammes of common brown sulphuric acid are saturated by 43.5 cubic centimetres of the official volumetric solution of soda; how much acid of 96.8 per cent. is present?—*Ans.* The 2.69 contain 2.2.

1024. Four grammes of a litre and a half of concentrated hydrocyanic acid are neutralized by 89 cubic centimetres of volumetric solution of nitrate of silver of official strength; to what volume must the bulk of the acid be diluted for the production of acid of pharmacopœial strength?—*Ans.* 9 litres.

1025. 3.18 grammes of a powder containing arsenic require for complete reaction 84 cubic centimetres of a volumetric solution of iodine, which is 1.43 weaker than the standard solution of the British Pharmacopœia; what percentage of pure arsenic is contained in the powder?—*Ans.* 12.86.

1026. How much pure metal is present in a sample of iron 1.68 gramme of which dissolved in dilute sulphuric acid, is exactly attacked by 95.7 cubic centimetres of a semi-decinormal volumetric solution of red chromate of potassium which is 6 per cent. too strong?

GRAVIMETRIC ANALYSIS.

ESTIMATION OF METALS.

POTASSIUM.

Outline of the Process.—This element is usually estimated in the form of double chloride of potassium and platinum. Qualitative analysis having proved the presence of potassium and other elements in a substance, a small quantity of the material is accurately weighed, dissolved, and the other elements removed by appropriate reagents; the precipitates are well washed, in order that no trace of the potassium salt shall be lost, the resulting liquid concentrated over a water-bath (to avoid loss that would occur mechanically during ebullition), hydrochloric acid added if necessary, solution of perchloride of platinum poured in, and evaporation continued to dryness; excess of the perchloride is then dissolved by adding spirit of wine containing half its bulk of ether (a liquid in which the double chloride is insoluble), the mixture carefully poured on to a tared and dried filter, washed with the spirit till every trace of free perchloride of platinum is removed, the whole dried and weighed; from the resulting amount the proportion of potassium, or equivalent quantity of a salt of potassium, is ascertained by calculation.

> *Note.*—From this short description it will be seen, first, that the chemistry of quantitative is the same as that of qualitative analysis; the second, that the principle of gravimetric is the same as that of volumetric quantitative analysis—the combining-proportions being known, unknown quantities of elements may be ascertained by calculation from known quantities of their compounds.

Apparatus.—In addition to a delicate balance and weights and the common utensils, a few special instruments are used in quantitative manipulation; some of these may be prepared before proceeding with the estimation of potassium.

Filtering-paper may be of the kind known as "Swedish," the texture of which is of the requisite degree of closeness, and its ash small in amount. A large number of circular pieces of one size, six to eight centimetres in diameter, should be cut ready for use. In delicate experiments, where a precipitate on a filter has to be heated and the paper consequently burnt, the weight of the ash of the filter must be deducted from the weight of the residue. The ash is estimated by burning ten or twenty of the cut filters. These are folded into a small compass, a portion

of a piece of platinum wire twisted a few times round the packet, so as to form a cage, the whole held by the free end of the wire over a weighed porcelain crucible placed in the centre of a sheet of glazed paper, the bundle ignited by a spirit-lamp or smokeless gas-flame, the flame allowed to impinge against the charged mass till it falls into the crucible below, any stray fragments on the sheet carefully shaken into the crucible, the latter placed over a flame till carbon has all burnt off and nothing but ash remains, the whole cooled, weighed, and the weight of the crucible deducted; the weight of the residue divided by the number of pieces used gives the average amount of ash in each filter.

A pair of Weighing-tubes, for holding dried filters during operations at the balance, may be made from two test-tubes, one fitting closely within the other. About five centimetres of the closed end of the outer and seven of the inner are cut off, by leading a crack round the tube with a pencil of incandescent charcoal, and the sharp edges fused in the blowpipe-flame. A filter, after drying, is quickly folded and placed in the narrower tube, the mouth of which is then closed by the wider tube. This prevents reabsorption of moisture from the air.

The Washing-bottle, holding the *spirit of wine and ether*, is a common bottle, through the cork of which a short straight tube passes. The outer end of the tube should be sufficiently narrowed to enable it to deliver a very fine stream of the liquid. The bottle being inverted, the warmth of the hand expands the air and vapor to a sufficient extent to force out the liquid.

The Ordinary Washing-bottle for quantitative operations should be formed of a flask in which water may be boiled, fitted up as usual (*vide* p. 93).

A Water-oven is the best form of drying-apparatus. It is a small square copper vessel, jacketed on five sides and having a door on the sixth; water is poured into the space between the inner and outer casing, and the whole placed over a gas-lamp or source of heat, moist air and steam escaping by appropriate apertures. Desiccation at higher temperatures than the boiling-point of water may be practised by using oil or paraffin instead of water, inserting a thermometer in the fat. The apparatus may be purchased of any maker of chemical instruments.

Pure distilled water must be used in all quantitative determinations.

Note.—In practising the operations of quantitative analysis, experiments should at first be conducted on definite salts of known composition, for the accuracy of results may then be tested by calculation.

Estimation of Potassium in the form of double chloride of potassium and platinum.—Select two or three crystals of pure nitrate of potassium, powder them in a clean mortar, dry the powder by gently heating in a porcelain crucible over a flame for a few seconds, place about a couple of decigrammes (0.2 grm.) of the powder in a counterpoised watch-glass, accurately weigh the selected quantity, transfer to a small dish, letting water from a wash-bottle flow over the watch-glass and run into the dish, warm the dish till the nitrate is dissolved, acidulate with hydrochloric acid, add excess of aqueous solution of perchloride of platinum (a quantity containing about 0.4 of solid salt), evaporate to dryness over a water-bath. While evaporation is going on, place a filter and the weighing-tubes in the water-oven, exposing them to a temperature of 212° F. for about half an hour; fold the filter and insert it in the tubes, place them on a plate under a glass shade, and when cold accurately note their weight. Arrange the weighed filter in a funnel over a beaker. Transfer the dried and cooled platinum salt from the dish to the filter by moistening the residue with the mixture of alcohol and ether, and, when the salt is loosened, pouring the contents of the dish into the paper cone. Any salt still adhering may be freed by the finger, which, together with the dish, should be washed in the stream of spirit, the rinsings at once flowing into the filter. The filtrate should have a yellowish-brown color, due to the excess of perchloride of platinum. If it is colorless, an insufficient amount of perchloride has been added, and the whole operation must be repeated. The washed precipitate and filter are finally dried in the water-oven, folded and placed in the weighing-tubes, the drying continued until the whole, after repeated weighing when cold, ceases to alter; the final weight is noted.

Note.—If filters are not freed from all trace of acid by thorough washing, the paper will be brittle when dry, falling to pieces on being folded.

Analytical memoranda in the note book may have the following form:—

Watch-glass and substance	
Watch-glass	
Substance . .	
Weighing-tubes, filter, and Pt salt . .	
Weighing-tubes and filter	
$PtCl_4,2KCl$. .	

The calculations are simple:—

$$\text{As } \left\{\begin{matrix}\text{PtCl}_4.2\text{KCl} \\ =489\end{matrix}\right\} \text{ are equivalent to } \left\{\begin{matrix}2\text{KNO}_3 \\ =202\end{matrix}\right\}$$

$$\text{so } \left\{\begin{matrix}\text{the weight of} \\ \text{double chloride} \\ \text{obtained}\end{matrix}\right\} \text{ is equivalent to } x. \quad x \text{ will be the}$$

amount of *pure* nitrate of potassium in the quantity of substance operated on. x should, in the present instance, be identical with the weight of substance taken, because, for educational purposes, pure nitre is under examination. Only after analyses of pure substances have yielded the operator results identical with those by calculation, can analyses of substances of unknown degree of purity be undertaken with confidence. A table of atomic weights, from which to find molecular weights, is given in the Appendix.

A *Water-bath* for the evaporation of liquids or for drying moist solids at temperatures below 212° F. is an iron, tin, or earthenware pan, the mouth of which can be narrowed by iron or tin diaphragms of various sizes and having orifices adapted to the diameters of evaporating-dishes or plates. In the British Pharmacopœia, "when a *water-bath* is directed to be used, it is to be understood that this term refers to an apparatus by means of which water or its vapor, at a temperature not exceeding 212°. is applied to the outer surface of a vessel containing the substance to be heated, which substance may thus be subjected to a heat near to, but necessarily below, that of 212°. In the *steam-bath* the vapor of water at a temperature above 212°, but not exceeding 230°, is similarly applied."

Evaporation *in vacuo* is performed by simply placing the vessel of liquid over or by the side of a small reservoir of strong sulphuric acid or other absorbent of moisture, on the plate of an air-pump, covering with a capacious receiver, and exhausting.

Platinum residues should be preserved, and the metal recovered from them from time to time (*vide* p. 221).

Hot alcohol sometimes reduces perchloride of platinum, the metal being thrown out of solution in a finely divided form, known as *platinum black;* only aqueous solutions, therefore, of the salt should be used where heat is employed. Hence, also, in washing out excess of perchloride of platinum from the double chloride of platinum and potassium by spirit, the application of heat should be avoided.

Effervescing Potash-water (*Liquor Potassæ Effervescens*, B.P.) is most easily estimated volumetrically (p. 481). Any adulteration by an equivalent amount of bicarbonate of sodium would, however, by that process be undetected; hence the Pharmacopœia directs that "five fluidounces, evaporated to one-fifth, and 12 grains of tartaric acid added, yield a crystalline precipitate, which, when dried, weighs not less than 12 grains." Five fluidounces of this preparation should contain 7.5 grains of bicarbonate, convertible into 14.1

grains of acid tartrate of potassium by 11.25 grains of tartaric acid. The method is somewhat rough, but quite efficient for "potash-water" containing nothing but bicarbonate of potassium.

Proportional weights of equivalent quantities of potassium and its salts.

Metal	K_2	78
Oxide ("potash")	K_2O	94
Hydrate ("caustic potash")	$2KHO$	112
Carbonate (anhydrous)	K_2CO_3	138
Carbonate (crystalline)	K_2CO_3+16% aq.	164.285
Bicarbonate	$2KHCO_3$	200
Nitrate	$2KNO_3$	202
Platinum salt	$PtCl_4, 2KCl$	489

SODIUM.

Sodium is usually estimated as sulphate. Accurately weigh a porcelain crucible and lid, place within about .3 of pure rock-salt, and again weigh, making a memorandum of the weights in a note-book. Add rather more strong sulphuric acid than may be considered sufficient to convert the chloride into acid sulphate of sodium. Heat the crucible gradually, the flame being first directed against the side of the crucible to avoid violent ebullition, until fumes of acid cease to be evolved, towards the end of the operation dropping in one or two fragments of carbonate of ammonium to facilitate complete expulsion of all excess of acid. When cold, weigh the crucible and contents. The weight of the crucible having been deducted, the amount of sulphate obtained should be the exact equivalent of the quantity of chloride of sodium employed.

$$\underbrace{2NaCl}_{117} + H_2SO_4 = \underbrace{Na_2SO_4}_{142} + 2HCl.$$

Proportional weights of equivalent quantities of sodium and its salts.

Metal	Na_2	46
Oxide ("soda")	Na_2O	62
Hydrate ("caustic soda")	$2NaHO$	80
Carbonate (anhydrous)	Na_2CO_3	106
Carbonate (crystals)	$Na_2CO_3, 10H_2O$	286
Bicarbonate	$2NaHCO_3$	168
Chloride	$2NaCl$	117
Sulphate (anhydrous)	Na_2SO_4	142
Sulphate (crystals)	$Na_2SO_4, 10H_2O$	322

AMMONIUM.

Salts of ammonium are, for purposes of quantitative analysis, generally converted into the double chloride of ammonium and platinum ($PtCl_4 2NH_4Cl$), the details of manipulation being the same as those observed in the case of potassium. About 0.15 grm. of pure, white, dry chloride of ammonium may be taken for experiment.

COMPOSITION OF THE PLATINUM SALT.

		In 1 molecule.	In 100 parts.
Pt	198	198	44.30
Cl_6	35.5×6	213	47.64
N_2	14.0×2	28	6.27
H_8	1.0×8	8	1.79
		447	100.00
or, $PtCl_4$	340	340	76.06
$2NH_4Cl$	53.5×2	107	23.94
		447	100.00

The proportion of nitrogen, ammonium, or chloride of ammonium in the double chloride may also be ascertained from the weight of platinum left on igniting the double chloride; for this purpose heat must be applied slowly, or platinum will be mechanically carried off with the gaseous products of decomposition

Proportional weights of equivalent quantities of ammoniacal compounds.

Ammonia (gas)	$2NH_3$	34
Ammonium	$(NH_4)_2$?	36
Chloride of ammonium	$2NH_4Cl$	107
Platinum salt	$PtCl_4,2NH_4Cl$	447
"Carbonate of ammonium"	$(N_4H_{16}C_3O_8) \div 2$	118
Sulphate of ammonium	$(NH_4)_2SO_4$	132

BARIUM.

Barium is estimated in the form of anhydrous sulphate of barium ($BaSO_4$).

Process.—Dissolve 0.3 or 0.4 of pure crystallized and dried chloride or nitrate of barium in about half a litre of water in a beaker, heating to incipient ebullition, and slightly acidulating with hydrochloric or nitric acid. Add

diluted sulphuric acid (prepared some days previously, so that sulphate of lead may have deposited) so long as a precipitate forms, keep the mixture hot for some time, set aside for half an hour, pass the supernatant liquid through a filter, gently boil the residue two or three times with more water; finally collect the precipitate on the filter, removing adherent particles from the beaker by the finger, and cleansing by a stream of hot water from the wash-bottle. The precipitate must be washed with hot water until the filtrate ceases to turn litmus paper red, or give any cloudiness when tested with chloride of barium. The filter and sulphate of barium, having thoroughly drained, is dried in a warm place, commonly by supporting the funnel in an inverted bottomless beaker over a sand-bath or hot plate.

The sulphate of barium is now removed from the filter, heated to drive off every trace of moisture, and weighed. This is accomplished by placing a weighed porcelain crucible (and cover) on a sheet of glazed paper, holding the filter over it, and carefully transferring the precipitate; the sides of the filter are then gently rubbed together and detached powder dropped into the crucible, the paper folded, encased in two or three coils of one end of a platinum wire and burnt over the crucible, ash and any particles in the sheet of paper dropped into the sulphate of barium, the open crucible exposed over a flame till its contents are quite white, covered, cooled, and weighed.

	Formulæ.	Molecular weights.
Chloride of barium	$BaCl_2$	208
Nitrate of barium	$Ba2NO_3$	261
Sulphate of barium	$BaSO_4$	233

Composition of Sulphate of Barium.

		In one molecule.	In 100 parts.
Ba	137	137	58.80
S	32	32	13.73
O_4	16×4	64	27.47
		233	100.00

In these experiments it is unnecessary to take filter-ash into account. Faults of manipulation cause far greater errors.

CALCIUM.

Calcium is usually thrown out of solution in the form of oxalate, the precipitate ignited, and the resulting carbonate weighed.

Process.—Dissolve 0.3 or 0.4 of dried colorless crystals of calc-spar in about a third of a litre of water acidulated with hydrochloric acid, heat the solution to near the boiling-point, add excess of solution of oxalate of ammonia, then ammonia until, after stirring, the liquid smells strongly ammoniacal; set aside in a warm place for twelve hours. Carefully pour off the supernatant liquid, passing it through a filter; add hot water to the precipitate, set aside for half an hour, again decant, and, after once more washing, transfer the precipitate to the filter, allowing all contained fluid to pass through before a fresh portion is added. Wash the precipitate with hot water, avoiding a rapid stream, or the precipitate may be driven through the pores of the paper. Dry, transfer to a weighed crucible, and incinerate, as described for sulphate of barium, and slowly heat the precipitate till the bottom of the crucible is just visibly red when seen in the dark. As soon as the residue is white, or only faintly gray, remove the lamp, cool, and weigh.

The resulting carbonate of calcium should have the same weight as the calc-spar from which it was obtained. If loss has occurred, carbonic acid gas has probably escaped. In that case moisten the residue with water, and after a few minutes test the liquid with red litmus or turmeric paper; if an alkaline reaction is noticed, it is due to the presence of caustic lime. Add a small lump of carbonate of ammonium, evaporate to dryness over a water-bath, and again ignite, this time being careful not to go beyond the prescribed temperature. The treatment may, if necessary, be repeated.

Proportional weights of equivalent quantities of calcium salts.

Oxide (quicklime)	CaO	56
Hydrate (slaked) lime	$Ca2HO$	74
Carbonate	$CaCO_3$	100
Sulphate (anhydrous)	$CaSO_4$	136
Sulphate (crystalline or precipt'd)	$CaSO_4, 2H_2O$	172
Chloride	$CaCl_2$	111
Phosphate (of bone)	$(Ca_32PO_4)310 \div 3$	103.3
Superphosphate	CaH_42PO_4	234

MAGNESIUM.

Process 1.—*The light or heavy carbonate of magnesium* of pharmacy may be estimated by heating a weighed quantity to redness in a porcelain crucible. If it has the composition indicated by the formula given in the British Pharmacopœia ($3MgCO_3$, $Mg2HO,4H_2O$), it will yield 42 per cent. of magnesia (MgO). According to that work, the purity of even sulphate of magnesium ($MgSO_4$, $7H_2O$) may be determined by boiling a weighed quantity with excess of carbonate of sodium, collecting the precipitate, washing, drying, igniting, and weighing the resulting magnesia (MgO). The crystallized sulphate should afford 16.26 per cent. of oxide. The official solution of carbonate of magnesium in carbonic acid water (*Liquor Magnesiæ Carbonatis*, B. P.) should yield five grains of pure oxide of magnesium per fluidounce.

Process 2.—*The general form in which magnesium is precipitated* is as phosphate of ammonium and magnesium ($MgNH_4PO_4$, $6H_2O$); this, by heat, is converted into pyrophosphate of magnesium ($Mg_2P_2O_7$). Accurately weigh a small quantity (0.4 to 0.5) of pure dry crystals of sulphate of magnesium, dissolve in two or three hundred cubic centimetres of cold water in a beaker, add chloride of ammonium, ammonia, and phosphate of sodium or ammonium, agitate with a glass rod (without touching the sides of the vessel, or crystals will firmly adhere to the rubbed portions), and set aside for twelve hours. Collect on a filter, wash the precipitate with water containing a tenth of its volume of the strongest solution of ammonia, until the filtrate ceases to give a precipitate with an acidulated solution of nitrate silver. Dry, transfer to a crucible, burn the filter in the usual way, heat slowly to redness, cool, and weigh.

Proportional weights of equivalent quantities of magnesium salts.

Pyrophosphate . .	$Mg_2P_2O_7$	222
Sulphate	$2(MgSO_4, 7H_2O)$	492
Oxide	$2(MgO)$	80
Official carbonate .	$(3MgCO_3, Mg2HO, 4H_2O) \div 2$.	191

ZINC.

Zinc is usually estimated as oxide (ZnO), occasionally as sulphide (ZnS).

Process.—Dissolve a weighed quantity (0.5 to 0.6) of sulphate of zinc in about half a litre of water in a beaker, heat to near the boiling-point, add carbonate of sodium in slight excess, boil, set aside for a short time; pass the supernatant liquid through a filter, gently boil the precipitate with more water, again decant; repeat these operations two or three times; collect the precipitate on the filter, wash, dry, transfer to a crucible, incinerate, ignite, cool, and weigh. 287 (=molec. weight) of sulphate should yield 81 (=molec. weight) of oxide.

MANGANESE.

To ascertain its value for evolving chlorine from hydrochloric acid a weighed quantity of finely powdered black oxide of manganese is heated in a small flask with pure hydrochloric acid, and the resulting chlorine conveyed into a U-tube containing solution of iodide of potassium. The amount of iodine thus freed is estimated by the volumetric solution of hyposulphite of sodium. 127 of iodine indicate 35.5 of chlorine.

ALUMINIUM.

Aluminium is always precipitated as hydrate ($Al_2 6HO$) and weighed as oxide (Al_2O_3).

Process.—Dissolve about two grammes of pure dry ammonium-alum in half a litre of water, heat the solution, add chloride of ammonium and a slight excess of ammonia, boil gently till the odor of ammonia has nearly disappeared, set aside for the hydrate to deposit, pass the supernatant liquid through a filter, wash the precipitate three or four times by decantation, transfer to the filter, finish the washing, dry, burn the filter, ignite in a covered crucible, and weigh.

$Al_2 3SO_4$, $(NH_4)_2SO_4$, $24H_2O$	907
Al_2O_3	103
Per cent. of Al_2O_3 yielded by ammonium-alum .	11.356

QUESTIONS AND EXERCISES.

1027. Give details of the manipulations observed in gravimetrically estimating salts of potassium or ammonium.

1028. What quantity of chloride of sodium is contained in a sample of rock-salt 0.351 gramme of which yields 0.44 of sulphate of sodium? —*Ans.* 100 per cent. (It is absolutely pure.)

1029. To what amount of the official alum is 0.894 of a gramme of the double chloride of platinum and ammonium equivalent?—*Ans.* 1.814 gramme.

1030. Find the weight of sulphate of barium obtainable from 0.522 of nitrate.—*Ans.* 0.466.

1031. Describe the usual method by which salts of calcium are estimated.

1032. By what quantitative processes may the official salts of magnesium be analyzed?

1033. Calculate the proportion of pure sulphate of zinc in a sample of crystals 0.574 of which yield 0.161 of oxide —*Ans.* 99.3 per cent.

1034. Ascertain the weight of alumina (Al_2O_3) which should be obtained from 1.814 gramme of ammonium-alum.

IRON.

Iron and its salts are gravimetrically estimated in the form of ferric oxide (Fe_2O_3).

Compounds containing organic acidulous radicals are simply incinerated, and the resulting oxide weighed. Thus 1 gramme of the official citrate of iron and ammonium (*Ferri et Ammoniæ Citras*, B. P.) incinerated, with exposure to air, leaves not less than .27 of ferric oxide. A small quantity of the salt is weighed in a tared covered porcelain crucible, flame cautiously applied until vapors cease to be evolved, the lid then removed, the crucible slightly inclined and exposed to a red heat until all carbonaceous matter has disappeared. The residual ferric oxide is then weighed. The tartrate of potassium and iron ((*Ferrum Tartaratum*, B. P.) is treated in the same manner, except that the ash must be washed and again heated before weighing, in order to remove carbonate of potassium produced during incineration; 5 grammes should yield 1.5 gramme of ferric oxide.

From other compounds of iron, soluble in water or acid, the metal is precipitated in the form of hydrate (Fe_26HO) by solution of ammonia, and converted into oxide (Fe_2O_3) by ignition. Dissolve a piece (about 0.2) of the purest iron obtainable (piano wire), accurately weighed, in water

acidulated with hydrochloric acid; add a few drops of nitric acid and gently boil; pour in excess of ammonia, stir, set aside till the ferric hydrate has deposited, pass the supernatant liquid through a filter, treat the precipitate three or four times with boiling water; transfer to the filter, wash till the filtrate yields no trace of chlorine (for chloride of ammonium will decompose ignited ferric oxide, with volatilization of ferric chloride), dry and ignite as usual, and weigh. Iron in the official solutions (*Liquor Ferri Perchloridi Fortior*, *Liquor Ferri Pernitratis*, and *Liquor Ferri Persulphatis*) may be estimated by this general process.

The proportion of metallic iron in a mixture of iron and oxides of iron may be determined by digestion in a strong solution of iodine in iodide of potassium, which attacks the metal only. The reduced iron of pharmacy (*Ferrum Redactum*) is in good condition so long as it contains, as shown by this method, half its weight of free metal.

Proportional weights of equivalent quantities of iron and its salts.

Metal	Fe_2 112
Ferric oxide	Fe_2O_3 160
Ferric hydrate . . .	$Fe_2 6HO$ 214
Ferric chloride . . .	Fe_2Cl_6 325
Ferric sulphate . . .	$Fe_2 3SO_4$ 400
Ferrous sulphate . .	$2(FeSO_4, 7H_2O)$ . . 556

ARSENICUM.

Arsenic (As_2O_3) is usually estimated volumetrically (*vide* p. 489). With certain precautions arsenicum may also be precipitated and weighed as sulphide (As_2S_3).

Process.—The pure, white, massive arsenic (about 0.2) is dissolved in a flask in a small quantity of water containing bicarbonate of sodium or potassium, the liquid being heated. A slight excess of hydrochloric acid is then added, and sulphuretted hydrogen gas passed through the solution so long as a precipitate falls, the mouth of the flask being stopped by a plug of cotton-wool (to prevent undue access of air and consequent decomposition of the gas, resulting in precipitation of sulphur). The mixture is warmed in the flask and carbonic acid gas passed through it until the odor of sulphuretted hydrogen has nearly disappeared; the precipitate collected on a tared filter, washed

as quickly as possible with hot water containing a little sulphuretted hydrogen, dried in a water-oven and weighed. 198 parts of arsenic should yield 246 of sulphide of arsenicum.

ANTIMONY.

The metal is precipitated in the form of sulphide (Sb_2S_3), with the precautions observed in estimating arsenicum—a small quantity of tartaric acid, as well as hydrochloric, being added, to prevent the precipitation of an oxysalt. If the sulphuretted hydrogen be passed through a hot solution, the particles of precipitate aggregate better, and the latter may be more quickly filtered out and washed. The experiment may be performed on about half a gramme of pure tartar-emetic: the salt should yield nearly half its weight (49.56 per cent.) of sulphide. According to Fresenius, the sulphide dried at 100° C. still contains 2 per cent. of water, and must be heated, in a current of carbonic acid gas, until it turns from an orange to a black color, before all moisture is expelled. In the British Pharmacopœia the purity of tartar-emetic (*Antimonium Tartaratum*), and the strength of solution of chloride of antimony (*Liquor Antimonii Chloridi*), are determined by the above process.

COPPER.

Copper is precipitated from its solutions and weighed either (1) as metal (Cu_2), or (2) as oxide (CuO).

Process 1.—Dissolve about half a gramme of dry crystallized sulphate of copper in a small quantity of water, in a tared porcelain crucible or beaker, acidulate with hydrochloric acid, introduce a fragment or two of pure zinc, cover the vessel with a watch-glass, and set aside till evolution of hydrogen has ceased and the still acid liquid is colorless. The copper is then washed with hot water by decantation until no trace of acid remains, the precipitate drained, rinsed with strong spirit of wine, dried in the water-oven, and weighed.

Process 2.—About three-fourths of a gramme of sulphate of copper is accurately weighed, dissolved in half a litre of water, the liquid boiled; dilute solution of potash or soda is then added till no more precipitate falls, ebullition continued for a short time, and the beaker set aside; the supernatant liquid is decanted, the precipitate boiled with water

twice or thrice, collected on a filter, washed, dried, transferred to a crucible, the filter incinerated, and its ash moistened with a drop of nitric acid; the whole is finally heated strongly, cooled, and weighed.

249.5 parts of sulphate of copper yield 79.5 of oxide, or 63.5 of metal.

BISMUTH.

Dissolve 0.3 or 0.4 of pure oxycarbonate of bismuth ($2Bi_2O_2CO_3,H_2O$) (*Bismuthi Carbonas*, B. P.) in a small quantity of hydrochloric acid, dilute with water slightly acidulated by hydrochloric acid, pass excess of sulphuretted hydrogen through the liquid, collect the precipitate on a tared filter, wash, dry at 100° C., and weigh. The sulphide must not be exposed too long in the water-oven, or it will increase in weight owing to absorption of oxygen; hence it should be tested in the balance every half-hour during desiccation. 517 of oxycarbonate should yield 512 of sulphide (Bi_2S_3). The strength of the official solution of citrate of bismuth and ammonium (*Liquor Bismuthi et Ammoniæ Citratis*, B. P.) is determined by this process. "Three fluidrachms of the solution, mixed with an ounce of distilled water, and treated with sulphuretted hydrogen in excess, yield a black precipitate, which, collected, washed, and dried, weighs 9.92 grains. One fluidrachm yields three grains of oxide of bismuth." The atomic weight of bismuth is 208.

MERCURY.

This element may be (1) isolated and estimated in the form of metal, or precipitated and weighed as (2) mercurous chloride, or (3) mercuric sulphide.

Process 1.—The process by which the metal itself is separated is one of distillation, into a bulb surrounded by water. About half a metre of the difficultly fusible German glass known as *combustion-tubing* is sealed at one end after the manner of a test-tube; a mixture of bicarbonate of sodium and dry chalk is then dropped into the tube to the height of two or three centimetres, and, next, several small fragments of quicklime so as to occupy another centimetre; a mixture of about a gramme of pure calomel or corrosive sublimate with enough powdered quicklime to occupy 10 or 12 centimetres of the tube is added, then the lime-rinsings of the mixing-mortar, a layer of a few centi-

metres of powdered quicklime, and finally a plug of *asbestos* (a fibrous mineral unaffected by heat). The whole powder should occupy two-thirds of the length of the tube. The part of the tube just above the asbestos is now softened in the blowpipe-flame and drawn out about a decimetre to the diameter of a narrow quill; it is again drawn out to the same extent at a point about two or three centimetres nearer the mouth, and any excess of tubing cut off. The bulb thus formed may be enlarged by softening and blowing. The tube is next softened at a point close to but anterior to the asbestos, and bent nearly to a right angle; the tube is then softened close to the bulb and slightly bent so that the bulb may be parallel with the large tube; then softened on the other side of the bulb, and the narrow terminal tube bent to a right angle, so that, the tube being held in a horizontal position, the bulb may be sunk in water, and the terminal tube point upwards. The long tube is now laid in the gas-furnance found in most laboratories, a basin so placed that the bulb of the apparatus may be cooled by being surrounded by water, the part of the tube occupied by asbestos heated to redness, and the flame slowly lengthened until the whole tube is red-hot. Under these circumstances the mercurial compound volatilizes, is decomposed by the lime, and its acidulous radical fixed, the mercury carried in vapor to and condensed in the bulb, the carbonic acid gas evolved from the bicarbonate of sodium and chalk washing out the last portions of mercury-vapor from the tube. When the distillation is considered to be complete, the dish of water is removed, the bulb dried, and then detached by help of a file at a point beyond any sublimate of mercury. The bulb is lastly weighed, the mercury shaken, or dissolved out, and the tube again dried and weighed.

Process 2.—The process by which mercury is separated in the form of calomel consists in adding hydrochloric and phosphorous acids (*vide* p. 312) to an aqueous or even acid solution of a weighed quantity of the mercurial compound, setting the mixture aside for twelve hours, collecting the precipitate on a tared filter, washing, drying at 100° C., and weighing (Rose). The experiment may be tried on half a gramme to a gramme of corrosive sublimate.

Process 3.—Two or three decigrammes of corrosive sublimate are dissolved in water, the solution acidulated with hydrochloric acid, excess of sulphuretted hydrogen passed, the precipitate collected on a tared filter, washed with cold water, dried at 100° C., and weighed.

Proportional weights of equivalent quantities of mercury and its salts.

Metal	Hg	200
Mercurous chloride . .	HgCl . . .	235.5
Mercuric chloride . . .	$HgCl_2$ . . .	271
Mercuric sulphide . . .	HgS	232

LEAD.

Lead is generally estimated either as (1) oxide, (2) sulphate, or (3) chromate.

Process 1.—Weigh out one or two grammes of pure acetate of lead in a covered crucible, previously tared, and heat slowly until no more vapors are evolved. Remove the lid, stir down the carbonaceous mass with a clean iron wire, and keep the crucible in the flame so long as any carbon remains unconsumed. Introduce some fragments of fused nitrate of ammonium, and again ignite until no metallic lead remains, and all excess of the nitrate has been decomposed. Cool and weigh the resulting oxide (PbO).

Process 2.—Dissolve 0.4 or 0.5 of a gramme of acetate of lead in a small quantity of water, drop in diluted sulphuric acid, add to the mixture twice its bulk of methylated spirit of wine, and set aside. Decant the supernatant liquid, collect the sulphate on a filter, wash with spirit, dry, transfer to a porcelain crucible, removing as much of the sulphate as possible from the paper, incinerate on the crucible-lid (not in a platinum coil, for the particles of reduced lead would unite with the platinum by fusion), ignite, cool, and weigh.

Process 3.—About half a gramme of acetate of lead is dissolved in two or three hundred c. c. of water, acetic acid added, and then solution of red chromate of potassium. Collect the precipitate on a tared filter, wash, dry at 100° C., and weigh.

Molecular weights of salts of lead.

Metal	Pb	207
Acetate . . .	$Pb2C_2H_3O_2, 3H_2O$.	379
Oxide . . .	PbO	223
Sulphate . .	$PbSO_4$	303
Chromate . .	$PbCrO_4$	323.5

SILVER.

Compounds of silver which are readily decomposed by heat are estimated in the form of (1) metal, others usually as (2) chloride (AgCl), but sometimes as (3) cyanide (AgNC).

Process 1.—Heat about a gramme of oxide of silver (Ag_2O) in a tared crucible, cool, and weigh. 232 of oxide yield 216 of metal. "29 grains heated to redness yield 27 grains of metallic silver."—*Brit. Pharm.*

Process 2.—Dissolve 0.4 or 0.5 of pure dry crystals of nitrate of silver in water, acidulate with two or three drops of nitric acid, slowly add hydrochloric acid, stirring rapidly, until no more precipitate falls. Pour off the supernatant liquid through a filter, wash the chloride of silver once or twice with hot water, transfer to the filter, complete the washing, and dry. After removing as much as possible of the precipitate from the paper to the crucible, burn the filter, letting its ash fall on the inverted lid of the crucible, moisten with a drop of nitric acid, warm, add a drop of hydrochloric acid, evaporate to dryness, replace the lid on the crucible, ignite the whole until the edges of the mass of chloride begin to fuse; cool and weigh. 170 of nitrate yield 143.5 of chloride. According to the British Pharmacopœia, 10 parts of nitrate should thus yield 8.44 of chloride, and the filtrate from the chloride evaporated to dryness should leave no residue, indicating absence of nitrates of potassium or sodium and other similar adulterants.

Process 3.—Cyanide of silver may be collected on a tared filter and dried at 100° C. 170 of nitrate yield 134 of cyanide.

Silver and its salts may be volumetrically estimated by a standard solution of chloride of sodium.

Cupellation.—The amount of silver in an alloy may be also determined by a dry method. The metal is folded in a piece of thin sheet lead, placed on a *cupel* (*cupella*, little cup, made of compressed bone-earth) and heated in a furnace, the cupel being protected from the direct action of flame by a muff-shaped, or, rather, oven-shaped case termed a muffle. The metals melt, the baser become oxidized, the oxide of lead fusing and dissolving the other oxides; the fluid oxides are absorbed by the porous cupel, a button of pure silver remaining. An alloy suspected to contain 95 per cent. of silver requires about 3 times its weight of lead for successful cupellation; if 92½ per cent. (English silver coin), between 5 and 6 times as much lead is necessary.

QUESTIONS AND EXERCISES.

1035. Explain the gravimetric process by which the strength of the official solutions of ferric chloride, nitrate, and sulphate are determined.

1036. Mention the various amounts of ferrous and ferric salts equivalent to 100 parts of metal.

1037. State the precautions necessary to be observed in estimating arsenicum or antimony in the form of sulphide.

1038. In what form are the official compounds of bismuth weighed for quantitative purposes?

1039. Give an outline of the process by which mercury may be isolated from its official preparations and weighed in the metallic condition.

1040. Describe three methods for the quantitative analysis of salts of lead; and the weights of the respective precipitates, supposing 0.56 of crystallized acetate to have been operated on in each case.

1041. Describe the process by which silver is estimated in the forms of metal, chloride, and cyanide.

1042. What proportions of nitrate of silver are indicated, respectively, by 15 of metal, 9.8 of chloride, and 8.1 of cyanide?

1043. Define cupellation.

ESTIMATION OF THE ACIDULOUS RADICALS OF SALTS.

CHLORIDES.

Free chlorine (chlorine-water) and compounds which by action of acids yield free chlorine (Chlorinated Lime, Chlorinated Soda, and their official Solutions) are estimated volumetrically by a standard solution of hyposulphite of sodium (*vide* p. 493). The amount of combined chlorine in pure chlorides (HCl, NaCl) may also be determined by volumetric analysis with a standard solution of nitrate of silver (p. 486).

Combined chlorine is gravimetrically estimated in the form of chloride of silver, the operations being identical with that just described for silver salts; 58.5 parts of pure, colorless, crystallized chloride of sodium (rock-salt) yield 143.5 of chloride of silver.

IODIDES.

Free iodine is estimated volumetrically by solution of hyposulphite of sodium (*vide* p. 493)..

Combined iodine is determined gravimetrically in the form of iodide of silver, the operations being conducted as

with chloride of silver. Iodide of potassium may be used for an experimental determination: KI=166 should yield AgI=235. Of the official iodide of cadmium (*Cadmii Iodidum*, B. P.) it is stated that "ten grains dissolved in water, and nitrate of silver added in excess, give a precipitate which, when washed with water and afterwards with half an ounce of solution of ammonia, and dried, weighs 12.5 grains."

In presence of chlorides and bromides the iodine in iodides may be precipitated and weighed as iodide of palladium.

BROMIDES.

Free bromine may be estimated by shaking with excess of solution of iodide of potassium, and then determining the equivalent quantity of liberated iodine by a standard solution of hyposulphite of sodium (p. 493).

The bromine in bromides may be precipitated and weighed as bromide of silver, the manipulations being the same as those for chloride of silver: 0.2 to 0.3 of pure bromide of potassium may be used for an experimental analysis.

CYANIDES.

The hydrogen cyanide (hydrocyanic acid) is usually estimated volumetrically (*vide* p. 487).

From all soluble cyanides, cyanogen may be precipitated by nitrate of silver, after acidulating with nitric acid, the cyanide of silver collected on a tared filter, dried at 100° C., and weighed.

Of the official Diluted Hydrocyanic Acid, it is stated that one hundred grains (or 110 minims) precipitated by solution of nitrate of silver yield ten grains of dry cyanide of silver.

Cyanide of Silver.

		In 1 molecule.	In 100 parts.
Silver	Ag	107.93	80.59
Cyanogen	CN	26.00	19.41
		133.93	100.00

NITRATES.

Nitrates cannot be estimated by direct gravimetric analysis, none of the baysylous radicals yielding a definite nitrate insoluble in water. With some difficulty they may be determined by indirect volumetric methods.

Process.—The best method is that by Crum, as modified by Frankland and Armstrong. It consists in agitating with mercury a concentrated solution of the nitrate with a large excess of concentrated sulphuric acid—the whole of the nitrogen being then involved as nitric oxide. From the volume of the latter the weight of nitrate whence obtained is easily calculated. No chlorides must be present. For educational purposes the experiment may be conducted on 3 or 4 c. c. of a solution of one gramme of pure nitrate of potassium in 100 c. c. of distilled water. From 1 to 10 c. c. of such a solution will very well represent the nitrates in half a litre of well-water.

The following is the mode in which this process is applied to the estimation of nitrogen existing as nitrates and nitrites in potable waters. The solid residue from half a litre of water used for determination of total solid constituents* is treated with a small quantity of distilled water, a very slight excess of sulphate of silver is added to convert the chlorides present into sulphates, and the filtered liquid is then concentrated by evaporation in a small beaker until it is reduced in bulk to two or three cubic centimetres. The liquid must now be transferred to a glass tube (about as long as the hand) (see fig.) previously filled with mercury at the mercurial trough, and furnished at its upper extremity with a cup and stopcock, the beaker being rinsed out once or twice with a very small volume of recently boiled distilled water, and finally with pure and concentrated sulphuric acid in somewhat greater volume than that of the concentrated solution and rinsings. (For a method of purifying the acid *vide* p. 276.) By a little dexterity it is easy to introduce successively the concentrated liquid, rinsings, and sulphuric acid by means of the cup and stopcock, without the admission of any trace of air. Should, however, air inadvertently gain admittance, it is

* If the water contains nitrites, a separate half litre should be taken for this determination, otherwise there is a risk of loss of nitrogen during evaporation. The nitrites in this half litre of water must be transformed into nitrates by the cautious addition of potassic permanganate to the slightly acidified water before the evaporation is commenced. Immediately after the action of the permanganate the water must be again rendered slightly alkaline.

readily removed by depressing the tube in the mercury trough, and then momentarily opening the stopcock. If this be done within a minute or two after the introduction of the sulphuric acid, no fear need be entertained of the loss of nitric oxide, as the evolution of this gas does not begin until a minute or so after the violent agitation of the contents of the tube.

The acid mixture being thus introduced, the lower extremity of the tube is to be firmly closed by the thumb, and the contents violently agitated by a simultaneous vertical and lateral movement, in such a manner that there is always an unbroken column of mercury, at least an inch long, at the bottom part of the glass tube. From the description, this manipulation may appear difficult; but in practice it is extremely simple, the acid liquid never coming in contact with the flesh. In about a minute from the commencement of the agitation a strong pressure begins to be felt against the thumb of the operator, and mercury spurts out in minute streams, as nitric oxide gas is evolved. The escape of the metal should be gently resisted, so as to maintain a considerable excess of pressure inside the tube, and thus prevent the possibility of air gaining access to the interior during the shaking. In from three to five minutes the reaction is completed, and the nitric oxide may then be transferred to a suitable measuring-apparatus, where its volume is to be determined over mercury. As half a litre of water is used for the determination, and as nitric oxide occupies exactly double the volume of the nitrogen which it contains, the volume of nitric oxide read off expresses the volume of nitrogen existing as nitrates and nitrites in one litre of the water. From the number so obtained, the weight of nitrogen in these forms in 100,000 parts of water is easily calculated. (1 litre of H weighs .0896, and N. is 14 times as heavy as H: 101 of KNO_3 contains 14 of N.)

SULPHIDES.

Process 1.—Soluble sulphides (H_2S, NaHS, *e.g.*) may be determined volumetrically by adding to the aqueous liquid a measured excess of an alkaline solution of arsenic of known strength, neutralizing by hydrochloric acid, diluting to any given volume, filtering off the sulphide of arsenicum precipitated, taking a portion of the filtrate equal to half or a third of the original volume, and, after neutralizing by acid carbonate of sodium, estimating the residual arse-

nic by the standard iodine solution (*vide* p. 488). The process may be tried on a measured volume of sulphuretted hydrogen (the weight of which is easily calculated; 1 litre of hydrogen = 0.0896 gramme) absorbed by a strong solution of soda or potash.

Process 2.—Sulphur and sulphides may also be quantitatively analyzed by oxidizing to sulphuric acid and precipitating in the form of sulphate of barium. A couple of decigrammes of a pure metallic sulphide may be decomposed by careful deflagration with a mixture of chlorate of potassium and carbonate of sodium, the product dissolved in water, acidulated with hydrochloric acid, solution of chloride of barium added, and the precipitated sulphate of barium purified and collected as described in connection with the estimation of barium (p. 502). Many sulphides may be oxidized in a flask by chlorate of potassium and hydrochloric acid, and then precipitated by chloride of barium. Experimental determinations may also be made on a weighed fragment of sulphur, about 0.1, cautiously fused with a solid caustic alkali, and the product oxidized while hot by the slow addition of powdered nitrate or chlorate of potassium, or, when cold, by treatment with chlorate of potassium and hydrochloric acid, and subsequent precipitation by chloride of barium.

Note.—Fusions performed by help of a gas-lamp must be carefully conducted; for any alkali that may creep over the side of a crucible will certainly absorb sulphurous acid from the products of combustion of the gas, and error result.

Process 3.—Soluble sulphides may also be treated with excess of an alkaline arseniate, arsenious sulphide be then precipitated by the addition of hydrochloric acid, and the precipitate collected and weighed with the usual precautions (*vide* p. 508).

Weights of equivalent quantities of sulphur and its compounds.

Sulphur	S	32
Sulphuretted hydrogen . .	H_2S	34
Sulphate of barium . . .	$BaSO_4$	233
Arsenious sulphide . . .	$(As_2S_3) \div 3$ . . .	82
Bisulphide of iron . . .	$(FeS_2) \div 2$ . . .	60
Sulphide of lead	PbS	239

SULPHITES.

Sulphites are usually estimated volumetrically by a standard solution of iodine (*vide* p. 488). Sulphites insoluble in water are diffused in that menstruum, hydrochloric acid added, and the iodine solution then dropped in.

If necessary, sulphites may be estimated gravimetrically by oxidation and precipitation in the form of sulphate of barium.

SULPHATES.

These salts are always precipitated and weighed as sulphate of barium, the manipulations being identical with those performed in the determination of barium by means of sulphates (*vide* p. 502). The purity of Sulphate of Sodium (*Sodæ Sulphas*, B. P.), and the presence of not more than a given amount of sulphuric acid in Vinegar (*Acetum*, B. P.), are directed, in the British Pharmacopœia, to be ascertained by this process. Ten grains of sulphate of sodium yield 7.236 of sulphate of barium. Five ounces of vinegar should yield not more than about one-third of a gramme of sulphate of barium.

Proportional weights of equivalent quantities of sulphates.

The sulphuric radical . . .	SO_4	96
Sulphuric acid	H_2SO_4	98
Sulphate of barium	$BaSO_4$	233

CARBONATES.

Carbonates are usually estimated by the loss in weight they undergo on the addition of a strong acid.

Process 1.—A small light flask is selected—of such a size that it can be conveniently weighed in a delicate balance. Two narrow glass tubes are fitted to the flask by a cork; the one straight, extending from about two or three centimetres above the cork to the bottom of the flask; the other cut off close to the cork on the inside and curved outwards so as to carry a thin drying-tube horizontally above the flask. The drying-tube may be a short narrow test-tube, the bottom of which is constricted so as to form a narrow tube open at the end; it is nearly filled with small pieces of chloride of calcium, a plug of cotton-wool preventing escape of any fragments at either end, and is attached by a pierced cork to the free extremity of the curved tube of the flask. A weighed quantity of any pure

soluble carbonate is placed in the flask, a little water added, a miniature test-tube containing sulphuric acid lowered into the flask by a thread and supported so that the acid may not flow out, the cork inserted, the outer end of the piece of the straight glass tubing closed by a fragment of cork or wax, and the whole weighed. The apparatus is then inclined so that the oil of vitriol and carbonate may slowly react; carbonic acid gas is evolved and escapes through the horizontal tube, any moisture being retained by the chloride of calcium. When effervescence has ceased, the gas still remaining in the vessel is sucked out; this is accomplished by adapting a piece of India-rubber tubing to the end of the drying-tube, removing the small plug from the straight tube, and aspirating slowly with the mouth for a few minutes. If the heat produced by the action of the oil of vitriol and solution is considered insufficient to expel all the carbonic acid from the liquid, the plug is again inserted in the tube and the contents of the flask gently boiled for some seconds. When the apparatus is cold, more air is again drawn through it, and the whole finally weighed. The loss is due to carbonic acid gas (CO_2), from the weight of which that of any carbonate is ascertained by calculation. Carbonates insoluble in water may be attacked by hydrochloric instead of sulphuric acid; granulated mixtures of carbonates and powdered tartaric or citric acids by inclosing the preparation in the inner tube and placing water in the flask, or *vice versâ*. The apparatus also may be modified in many ways to suit the requirements, convenience, or taste of the operator.

Process 2.—Carbonates from which carbonic acid gas is evolved by heat may be estimated by the loss they experience on ignition.

Process 3.—Free carbonic acid gas may be absorbed by a solid stick of potash or a strong alkaline solution, the loss in volume of the gas or mixture of gases indicating the amount originally present.

Weights of equivalent quantities of carbonic acid gas and certain carbonates.

Carbonic acid gas	CO_2 . . .	44
Carbonic acid	H_2CO_3 . .	62
Anhydrous carbonate of sodium . .	Na_2CO_3 . .	106
Anhydrous carbonate of potassium .	K_2CO_3 . .	138
Carbonate of calcium	$CaCO_3$ . .	100

OXALATES.

Process 1.—The oxalic radical is usually precipitated in the form of oxalate of calcium, and weighed as carbonate, the manipulations being identical with those observed in the estimation of calcium (*vide* p. 504). The experiment may be performed on 0.3 or 0.4 of pure crystallized oxalic acid, 126 parts of which should yield 100 of carbonate of calcium.

Process 2.—Oxalates may also be determined by conversion of their acidulous radical into carbonic acid gas, and observation of the weight of the latter. The oxalate, water, and excess of black oxide of manganese are placed in the carbonic acid apparatus, a tube full of oil of vitriol lowered into the flask, the whole weighed, and the operation completed as for carbonates. From the following equation it will be seen that every 88 parts of carbonic acid gas evolved indicate the presence of 126 parts of crystallized oxalic acid or an equivalent quantity of other oxalate:—

$$Na_2C_2O_4 + MnO_2 + 2H_2SO_4 = MnSO_4 + Na_2SO_4 + 2H_2O + 2CO_2.$$

The black oxide of manganese used in this experiment must be free from carbonates. The amount of materials employed is regulated by the size of the vessels.

PHOSPHATES.

Process 1.—*From phosphates dissolved in water*, the phosphoric radical may be precipitated and weighed in the form of pyrophosphate of magnesium, the details of manipulation being similar to those observed in estimating magnesium (*vide* p. 505). Half a gramme or rather more of pure dry crystallized phosphate of sodium may be employed in experimental determinations. The official phosphate of ammonium (*Ammoniæ Phosphas*, B. P.) is quantitatively analyzed by this method. "If twenty grains of this salt be dissolved in water, and solution of ammonio-sulphate of magnesia added, a crystalline precipitate falls, which, when well washed upon a filter with solution of ammonia diluted with an equal volume of water, dried, and heated to redness, leaves 16.8 grains." Half a gramme or less is a more convenient quantity, if the operations be conducted with care. Solution of am-

monio-sulphate of magnesium (B. P.) is prepared by dissolving 2 parts of sulphate of magnesium, 1 of chloride of ammonium, and 1 of solution of ammonia (20.6 per cent. NH_4HO) in 18 or 20 of distilled water; such a solution is of considerable use if several phosphoric determinations are about to be made.

Process 2.—*Free phosphoric acid* is most readily determined as phosphate of lead ($Pb_3 2PO_4$). Of the official solution of phosphoric acid it is stated that "355 grains by weight poured upon 180 grains of oxide of lead in fine powder leave, by evaporation, a residue (principally phosphate of lead) which, after it has been heated to dull redness, weighs 215.5 grains." One-tenth of these quantities may be used for experimental purposes; one to two grammes will give good results. The oxide of lead must be quite pure; it should be prepared by digesting red lead in warm dilute nitric acid, washing, drying, and heating the resulting puce-colored plumbic oxide in a covered porcelain crucible. The increase in weight obtained on evaporating a given amount of solution of phosphoric acid with a known weight of perfectly pure oxide of lead (PbO) may be regarded as entirely due to phosphoric anhydride (P_2O_5),

$$3PbO + P_2O_5 = Pb_3 2PO_4,$$

the actual reaction being,

$$3PbO + 2H_3PO_4 = Pb_3 2PO_4 + 3H_2O.$$

From these equations, and the table of atomic weights (*vide* Appendix), the percentage of phosphoric acid (H_3PO_4) in any specimen of its solution may be easily calculated.

Process 3.—*The strength of pure solution of phosphoric acid* may be ascertained by specific gravity and reference to Tables.

Process 4.—Bone-earth, "superphospate," the *Calcis Phosphas* of pharmacy, and other forms of phosphate of calcium known to be tolerably free from iron or aluminium, may be estimated by treating about half a gramme with hydrochloric acid somewhat diluted, filtering if necessary, warming, precipitating with excess of ammonia, collecting the precipitate ($Ca_3 2PO_4$) washing, drying, igniting, and weighing. "*Calcis phosphas*," if pure, will, in this process, lose no weight.

Process 5.—*Insoluble phosphates* in ashes, manures, etc.,

are treated as follows: a weighed quantity of the material (1.0 to 10.0) is digested in hydrochloric acid diluted with three or four times its bulk of water; filtered (insoluble matter and filter being thoroughly exhausted by water); ammonia added to the filtrate and washings until, after stirring, a faint cloudy precipitate is perceptible; solution of oxalic acid dropped in until, after agitation for a few minutes, the opalescence is removed; oxalate of ammonium next added, the whole warmed, oxalate of calcium removed by filtration, and the filtrate concentrated if very dilute; the liquid treated with citric acid in such quantity that ammonia when added in excess gives a clear *lemon-yellow* solution (Warington), magnesian mixture poured in (as in Process 1), and the precipitate of ammonio-magnesian phosphate collected, washed, dried, and weighed as already described in connection with the estimation of magnesium.

Relative weights of equivalent quantities of phosphoric compounds.

Phosphoric acid	H_3PO_4	98
Pyrophosphate of magnesium	$(Mg_2P_2O_7=222)\div 2=$	111
Phosphate of lead	$(Pb_3 2PO_4=811)\div 2=$	405.5
Phosphoric anhydride . . .	$(P_2O_5=142)\div 2=$	71
Phosphate of calcium . . .	$(Ca_3 2PO_4=310)\div 2=$	155
Superphosphate of calcium	$(CaH_4 2PO_4=234)\div 2=$	117

QUESTIONS AND EXERCISES.

1044. What quantity of pure rock-salt is equivalent to 4.2 parts of chloride of silver?—*Ans.* 1.712.

1045. State the percentage of real iodide of potassium contained in a sample of which 8 parts yield 10.9 of iodide of silver.—*Ans.* 96.25.

1046. What is the strength of a solution of hydrocyanic acid 10 parts of which, by weight, yield .9 of cyanide of silver?—*Ans.* 1.81 per cent.

1047. How are nitrates quantitatively estimated?

1048. By what processes may the strength of sulphides be determined?

1049. How much real sulphate of sodium is contained in a specimen 10 parts of which yield 14.2 of sulphate of barium?—*Ans.* 86.34 per cent.

1050. Give details of the operations performed in the quantitative analysis of carbonates.

1051. What amount of carbonic acid gas should be obtained from 10 parts of acid carbonate (or bicarbonate) of potassium?—*Ans.* 4.4 parts.

1052. To what operation and what quantities of materials does the following equation refer?

$$Na_2C_2O_4 + MnO_2 + 2H_2SO_4 = MnSO_4 + Na_2SO_4 + 2H_2O + 2CO_2.$$

1053. Explain the lead process for the estimation of phosphoric acid in the official solution.

1054. State the amount of superphosphate of calcium equivalent to 7.6 parts of pyrophosphate of magnesium.—*Ans.* 8.01 parts.

SILICATES.

Silica (SiO_2) may be separated from alkaline silicates, or from silicates decomposable by hydrochloric acid, by digesting the substance in hydrochloric acid at a temperature of 70° or 80° C., until completely disintegrated, evaporating to dryness, heating in an air-bath, again moistening with acid, diluting with hot water, filtering, washing, drying, igniting, and weighing.

ESTIMATION OF WATER.

Water, being readily volatilized, is most usually estimated by the loss in weight which a substance undergoes on being heated to a proper temperature. Thus, in the British Pharmacopœia, crystalline gallic acid ($H_3C_7H_3O_5$, H_2O) is stated to lose 9.5 per cent. of its weight at a temperature of 100° C., oxalate of cerium (CeC_2O_4, $3H_2O$) 52 per cent. on incineration, carbonate of potassium about 16 per cent. on exposure to a red heat, sulphate of quinine ($2C_{20}H_{24}N_2O_2$, H_2SO_4, $7H_2O$) 14.4 per cent. at 100° C., arseniate of sodium (Na_2HAsO_4, $7H_2O$) 40.38 per cent. at 149° C., carbonate of sodium (Na_2CO_3, $10H_2O$) 63 per cent., phosphate of sodium (Na_2HPO_4, $12H_2O$) 63 per cent., and sulphate of sodium (Na_2SO_4, $10H_2O$) 55.9 per cent. at a low red heat.

Process.—One or two grammes of substance is sufficient in experiments on desiccation, the material being placed in a watch-glass, covered or uncovered porcelain crucible, or other vessel, according to the temperature to which it is to be exposed. Rapid desiccation at an exact temperature may be effected by introducing the substance into a tube having somewhat the shape of the letter U, sinking the lower part of the tube into a liquid kept at a definite temperature by aid of a thermometer, and drawing or forcing

a current of dry air slowly through the apparatus. Substances liable to oxidation may be desiccated in a current of dried carbonic acid gas. The weights of the U-tube before and after the introduction of the salt, and after desiccation, give the amount of water sought. In all cases the material must be heated until it ceases to lose weight. Occasionally it is desirable to estimate water directly by conveying its vapor in a current of air through a weighed tube containing chloride of calcium and re-weighing the tube at the close of the operation; the increase shows the amount of water.

Note.—Highly dried substances rapidly absorb moisture from the air; they must therefore be weighed quickly, inclosed, if possible, in tubes (p. 498), a pair of clamped watch-glasses, or a crucible having a tightly fitting lid.

CARBON, HYDROGEN, OXYGEN, NITROGEN.

The quantitative analysis of animal and vegetable substances is either *proximate* or *ultimate*. Proximate analysis includes the estimation of water, oil, albumen, starch, cellulose, gum, resin, alkaloids, acids, glucosides, ash. It requires the application of much theoretical knowledge and manipulative skill, and cannot well be studied except under the guidance of a tutor. The best published work on the subject is by Rochleder, a translation of whose monograph will be found in the Pharmaceutical Journal, vol. i. 2d ser. pp. 562, 610; vol. ii. 2d ser. pp. 24, 129, 160, 215, 274, 420, 478.

Ultimate organic analysis can only be successfully accomplished with the appliances of a well-appointed laboratory—a good balance, a gas-furnace giving a smokeless flame (7 or 8 centimetres wide and 70 or 80 centimetres long), special forms of glass apparatus, etc. *The theory of the operation* is simple: a weighed quantity of a substance is burnt to carbonic acid gas ($CO_2=44$) and water ($H_2O=18$), and these products collected and weighed; 12 parts in every 44 of carbonic acid gas ($=\frac{3}{11}$) are carbon, 2 in every 18 of water ($=\frac{1}{9}$) are hydrogen; nitrogen if present escapes as gas. If nitrogen be a constituent, more of the substance is strongly heated with a mixture of the hydrates of sodium and calcium; these bodies then split up into oxides, oxygen, and hydrogen; the oxygen burns the carbon of the substance to carbonic acid gas, its hydrogen and nitrogen appearing as water and ammonia respectively; the carbonic acid and water are disregarded, the ammonia collected and weighed in the form of a double chloride of platinum and ammonium ($PtCl_4 2NH_4Cl$ $=447$), of which 28 parts in every 447 ($=\frac{1}{16}$) are nitrogen. The difference between the sum of the weights of hydrogen and carbon, and the weight of substance taken, is the proportion of oxygen in the body, supposing nitrogen to be absent. If nitrogen is present, the difference between the sum of the percentages of carbon, hydrogen, and nitrogen, and 100, is the percentage of oxygen. Shortly, carbon

is estimated in the form of carbonic acid gas, hydrogen as water, nitrogen as ammonia, and oxygen by loss.

The following is the outline of the necessary manipulations. The source of the oxygen for the combustion of carbon and hydrogen is black oxide of copper in coarse powder. 200 or 300 grammes of this material are heated in a crucible to low redness for a short time to expel every trace of moisture; then transferred to tubes (store-tubes) resembling test-tubes, half a metre long, and having a slightly narrowed mouth, the tube being held in a cloth to protect the hand while the hot oxide is being directly introduced into the mouth of the tube by a scooping motion. As soon as the well-corked tube is cool, the oxide is poured, portion by portion, into a similar tube (the combustion tube), somewhat longer, drawn out to a quill (bent upwards nearly to a right-angle) at one end, not constricted at the mouth, and containing a few decigrammes of fused chlorate of potassium. After ten or fifteen centimetres of oxide have been poured in, about a decigramme of the substance to be analyzed is dropped down the tube, then a few grammes of oxide, then another decigramme of substance, then more oxide, until three or four decigrammes of the body under examination have been added. The fifteen or twenty centimetres of alternate layers are next thoroughly mixed by a long copper wire having a short helix, more oxide is introduced, the wire cleansed by twisting the helix about in the pure oxide, and a plug of asbestos finally placed on the top of the oxide at about five centimetres from the mouth of the tube; the tube is then securely corked and set aside. The substance operated on may be pure white sugar, powdered and dried; the tube in which it is contained is weighed before and after the removal of a portion for combustion, the loss is the quantity employed in the experiment. If the combustion-furnace is powerful, or the combustion-tube not of the hardest glass, the tube should be inclosed in wire gauze the elasticity of which has been destroyed by heating to redness. In the combustion of substances containing nitrogen, the plug of asbestos must be displaced by one of copper turnings, which serve to reduce any oxides of nitrogen, and thus insure the escape of nitrogen itself. The *water* produced when the prepared tube is heated, is collected in a small U-tube containing pieces of chloride of calcium, or pumice-stone moistened with sulphuric acid; the *carbonic acid gas* in a series of

bulbs containing solution of potash (sp. gr. about 1.27). These bulbs may be purchased at any apparatus-shop. The chloride-of-calcium tube is fitted by a good cork to the combustion-tube, the potash-bulbs by a short piece of India-rubber tubing to the chloride-of-calcium tube. The potash-bulbs may carry a short light tube containing a rod of caustic potash three or four centimetres long; this serves to arrest any moisture that might be carried away from the solution of potash by the dried expanded air which escapes during the operation. The combustion-tube having been placed in the furnace, and the drying-tube and potash-bulbs weighed and attached, the gas is lit under the asbestos, and, when the tube is red-hot, the flame slowly extended until nearly the whole tube is at the same temperature, the operation being conducted at such a rate that bubbles of gas escape through the bulbs at about the rate of one per second. When no more gas passes, the extremity of the tube containing the chlorate of potassium is gently heated until oxygen ceases to be evolved; the quilled extremity of the combustion-tube is then broken, and air drawn slowly through the apparatus by suction through an India-rubber tube fixed on the free end of the potash-bulbs, perfect combustion of carbon and removal of all carbonic acid gas is thus insured. The drying-tube and bulbs are disconnected and weighed; the increase in weight due to carbonic acid gas and water respectively noted, and the percentages of carbon, hydrogen, and (by loss) oxygen calculated. This method is that of Liebig, with modifications by Bunsen; good combustion-furnaces are those known as Hofmann's and Griffin's.

The general manipulations for substances containing nitrogen resemble the foregoing so far as the use of a combustion-tube and furnace and collection of the ammoniacal gas are concerned. The combustion-tube must be quilled at one end, and about a third of a metre long. The soda-lime is made by slaking quicklime with a solution of soda, of such a strength that about two parts of quicklime shall be mixed with one of hydrate of sodium, drying the product, heating to bright redness, and finely powdering; it should be preserved in a well-closed bottle. Some of the soda-lime is introduced into the tube, then layers of substance and soda-lime, mixture effected by a wire, more soda-lime added, and lastly a plug of abestos. Bulbs, known as those of Will and Varrentrapp (the originators of the method), containing hydrochloric acid of about 25 per cent.,

are then fitted by a cork, and the tube heated in the furnace. When gas ceases to pass, the quill is broken, and aspiration continued slowly until ammoniacal gas may be considered to have been all removed. The bulbs are disconnected, their contents and rinsings poured into a small dish, solution of perchloride of platinum added, and the operation completed as in the estimation of ammonium and potassium salts (*vide* pages 502 and 499).

Liquids are analyzed by a similar method to that adopted for solids, volatile liquids being inclosed in small bulbs having a long quill. These are weighed previously to and after the introduction of the liquid; just before being dropped into the combustion tube the quill is broken.

Formulæ.—From the percentage composition of an organic substance an empirical formula may be deduced by dividing the weight of each constituent by its atomic weight, and converting the product into the simplest whole numbers; a rational formula by ascertaining the proportion in which the substance unites with a radical or body having a known combining proportion, etc. (*vide* p. 373).

Chlorine, *bromine*, or *iodine* contained in an organic substance is usually estimated by heating to redness a given weight of the material with ten times as much pure lime in a combustion-tube. Chloride, bromide, or iodide of calcium is thus produced. While still hot the tube is plunged into water, the mixture of broken glass and powder treated with pure diluted nitric acid in very slight excess; the filtered liquid precipitated by nitrate of silver, and the chloride, bromide, or iodide of silver collected, washed, dried, and weighed.

Sulphur, *phosphorus*, and *arsenicum* in organic salts may be estimated by gradually heating in a combustion-tube 1 part of the substance with a mixture of 10 parts nitre, 2 dried carbonate of sodium, and 30 chloride of sodium (in order to moderate deflagration). The product is dissolved in water acidulated by nitric acid, the sulphuric radical precipitated and estimated as sulphate of barium, the phosphoric and arsenic radicals as ammonio-magnesian phosphate or arseniate.

QUINIA OR QUININE.

A quantitative determination of the purity of commercial sulphate of quinia may be made by De Vry's process. 2 grammes of the salt are dissolved in 12 c. c. of distilled

water and 1.6 c. c. of diluted sulphuric acid (B. P.). 8 c. c. of solution of hydrate of sodium (1 to 12) and 30 c. c. of pure dry ether are added, the whole well shaken and laid aside for twelve hours. The ethereal solution decanted and evaporated gives the quinia. The aqueous solution, carefully neutralized by acetic acid and strong solution of iodide of potassium (1 in 4) added, gives a white precipitate of hydriodate of quinidia, the mother-liquor containing any cinchonia and cinchonidia that may be present. The precipitate is collected on a tared filter, washed, dried, and weighed; it contains 71.68 per cent. of pure quinidia. The filtrate and washings are rendered alkaline by solution of soda; cinchonia and cinchonidia are precipitated, and may be collected, washed, dried, and weighed.

Note.—If the quinia in drying assumes a resinoid character it should be redissolved in ether, and the solution, when concentrated, allowed to evaporate very slowly or spontaneously.

De Vry's method for the separation and quantitative determination of all the different cinchona alkaloids. This is based upon the following facts (nomenclature after De Vry):—

1. The great solubility of quinine and amorphous alkaloid in ether, and the *relative* insolubility of quinidine, cinchonidine, and cinchonine in this liquid.

2. The great solubility of the iodo-sulphate of the amorphous alkaloid in alcohol, and the very small solubility of the iodo-sulphate of quinine (herapathite) in this liquid.

3. The great difference in solubility between the tartrate of cinchonidine and the tartrates of cinchonine and quinidine—the first being soluble in 1265 parts of water at 10° C., the second in 35.6 parts of water at 16° C., and the third in 38.8 parts of water at 15° C.

4. The great difference in solubility between the hydriodate of quinidine and the hydriodates of cinchonidine and cinchonine in water and alcohol.

1 part of hydriodate of quinidine requires 1250 parts of water at 15° C., or 110 parts of alcohol.

1 part of hydriodate of cinchonidine requires 110 parts of water, or 3 parts of alcohol.

1 part of hydriodate of cinchonine requires 128 parts of water, or 3 parts of alcohol.

These facts are applied to the separation and determination of the different cinchona alkaloids in the following manner:—

Five to ten grammes of the pulverized mixed alkaloids are mixed with 50 grammes of ether, and the mixture, after well shaking, left at rest till the next day. By this operation the alkaloids are separated into two parts, viz., one (A) soluble in ether, and another (B) insoluble in that liquid. The part soluble in ether contains the quinine and the amorphous alkaloid, together with traces of quinidine or cinchonidine, whilst the insoluble part contains the cinchonidine, cinchonine, and quinidine. These two parts are separated by a filter, the insoluble part washed with some ether, and the ethereal solution either evaporated or distilled.

A. *Part soluble in Ether.*—The residue left by the evaporation of the ether is dissolved in 10 parts of proof spirit acidulated by one-twentieth of sulphuric acid. To this solution is carefully added an alcoholic solution of iodine till a precipitate is no longer formed. This part of the process is the most difficult, and requires some experience. If the mixed alkaloids contain a large amount of quinine, there appears immediately a black precipitate of quinine-herapathite, whereby the addition of the solution of iodine is regulated; but if the amount of quinine is only very small, it may happen that the precipitate of herapathite does not appear immediately. In such a case only a small quantity of iodine must be added, and the liquid, after having been stirred by a glass rod, left till the next day. If quinine is really present, it will then be precipitated in the form of herapathite. The chief desideratum of this part of the process is to add enough and not too much iodine. The herapathite is collected upon a filter, washed with strong alcohol, dried upon blotting-paper, and heated in a water-bath. One part of the herapathite, thus dried, represents 0.565 part of pure quinine.

The liquid separated from the herapathite is mixed with an alcoholic solution of sulphurous acid, whereby the iodosulphate of amorphous alkaloid is converted into hydriodate, and the red-brown color disappears. The solution is then carefully neutralized by caustic soda, and heated on a water-bath to expel the alcohol, after which it is precipitated by a slight excess of soda. The precipitate consists of the amorphous alkaloid, containing traces of quinidine or cinchonidine, if these alkaloids were contained in the mixed alkaloids.

B. *Part Insoluble in Ether.*—This part is mixed with 40 parts of hot water, and converted into neutral sulphate by

careful addition of diluted sulphuric acid, so that a solution is obtained having a slight alkaline reaction upon red litmus paper. To this solution a solution of tartrate of potash and soda is added in sufficient quantity to convert the sulphates into tartrates, and, after stirring with a glass rod, it is left till the next day. If cinchonidine be present in appreciable quantity, its tartrate will be found separated in crystalline form, whilst the other tartrates remain dissolved; if only traces of cinchonidine be present striæ will be observed on every spot of the glass which has been rubbed by the glass rod. The tartrate of cinchonidine is collected upon a filter, washed with a little water, and dried on a water-bath. One part of this tartrate represents 0.804 part of cinchonidine.

The liquor separated from this tartrate is mixed with a solution of iodide of potassium, and well stirred by a glass rod. If quinidine is present in appreciable quantity, a sandy crystalline powder of hydriodate of quinidine will be precipitated, which is collected upon a filter, washed with a little water, and dried on a water-bath. One part of this hydriodate represents 0.718 part of anhydrous quinidine. If only a trace of quinidine be present, no precipitate will appear, but only striæ on every spot of the glass which has been rubbed by the glass rod.

The liquor separated from the hydriodate of quinidine is precipitated by caustic soda, whereby the cinchonine is obtained. It is collected upon a filter, washed with water, and dried on a water-bath.

Dr. de Vry states that he is aware that this process is far from perfect. For instance, the tartrate of cinchonidine and the hydriodate of quinidine, although difficultly soluble in cold water, are not insoluble; and therefore the quantities of the alkaloids determined by this process are too small, whilst, consequently, that of the cinchonine found is too large. The best part of the process is the accurate determination of the *real* quinine contained in a bark, and the impossibility of overlooking one of the mentioned five alkaloids which may be contained in a bark.

Carles's Process for the Valuation of Cinchona-barks.—An average sample of the bark is reduced to fine powder and passed through a sieve without residue. Twenty grammes are then taken and intimately mixed in a mortar with 8 grammes of slaked lime previously mixed with 35 grammes of water. This mixture, spread on a plate, is dried in the air in summer, or on a water-bath at other times.

When all the moisture has evaporated, the lumps are broken up, and the powder packed in a percolator with a piece of lint at the bottom. Chloroform is then passed through in successive portions till the mass is exhausted. This is ascertained by receiving the last drops in a watch-glass, evaporating to dryness, and pouring on the residue water acidulated with sulphuric acid, then solution of chlorine, and lastly ammonia. When a green color is no longer produced, it is known that all the quinine has been removed. When the operation is well conducted, about 150 grammes of chloroform suffice for this purpose. The menstruum retained by the mass is displaced by water, and the whole of the chloroform solution is either distilled or evaporated to dryness. To separate the alkaloids from the residue, it is treated several times in the cold with diluted sulphuric acid (1 to 10). 10 to 12 cubic centimetres are sufficient. This solution thrown upon a moistened filter passes through colorless, and free from resinous matter; it is raised to the boiling-point, and ammonia cautiously added, so as to leave the liquid with a *slightly acid* reaction. The sulphate of ammonia thus formed appears to prevent the mother-liquors from retaining sulphate of quinine in solution. All the quinine crystallizes out in the state of sulphate. After some time it is collected on a double filter, the mother-liquors displaced by a little water, and the crystals dried and weighed. It is preferable to dry completely at 100° C., and after weighing in this state to add the 12 per cent. of water which is lost by this treatment. The other alkaloids retained in the mother-liquors are separated by precipitation.

Of the Citrate of Iron and Quinia (*Ferri et Quiniæ Citras*, B. P. and U. S. P.) it is officially stated that "fifty grains dissolved in a fluidounce of water and treated with a slight excess of ammonia give a white precipitate which, when collected on a filter, washed, and dried (at 260 F.) weighs eight grains. The precipitate is almost entirely soluble in two or three fluidrachms of pure ether," and the ethereal solution set aside for twelve hours in a small well-corked bottle yields no crystalline deposit (of quinidia).

MORPHIA.

The official process for the estimation of this alkaloid in opium is conducted in the following manner:—

Take of opium 100 grains, slaked lime 100 grains, dis-

tilled water 4 ounces. Break down the opium, and steep it in an ounce of the water for twenty-four hours, stirring the mixture frequently. Transfer it to a displacement-apparatus, and pour on the remainder of the water in successive portions, so as to exhaust the opium by percolation. To the infusion thus obtained, placed in a flask, add the lime, boil for ten minutes, place the undissolved matter on a filter, and wash it with an ounce of boiling water. Acidulate the filtered fluid slightly with diluted hydrochloric acid, evaporate it to the bulk of half an ounce, and let it cool. Neutralize cautiously with solution of ammonia, carefully avoiding an excess; remove by filtration the brown matter which separates, wash it with an ounce of hot water, mix the washings with the filtrate, concentrate the whole to the bulk of half an ounce, and add now solution of ammonia in slight excess. After twenty-four hours collect the precipitated morphia on a weighed filter, wash it with cold water, and dry it at 212° F. It ought to weigh at least from six to eight grains.

Of Hydrochlorate of Morphia it is stated that "twenty grains of the salt dissolved in half an ounce of warm water, with ammonia added in the slightest possible excess, give on cooling a crystalline precipitate which, when washed with a little cold water and dried by exposure to the air, weighs 15.18 grains."

Testing Opium.—Professor Schneider has proposed, in the 6th revised edition of the Pharmacopœia Austriaca, the following method for testing the quality of opium. Ten grammes of previously dried and powdered opium are treated with a mixture of 150 grammes of distilled water, to which 20 grammes of pure hydrochloric acid, sp. gr. 1.12, are added; the residue, after extraction, should not exceed 4.5 grammes weight; to the acid fluid 20 grammes of common salt are added, and the precipitate thereby caused is collected, after twenty-four hours, on a filter, and the latter washed with a solution of common salt; to the filtrate ammonia is added, and the fluid left standing again for twenty-four hours; the crystals which have separated are collected, redissolved in acetic acid, and precipitated with ammonia; the precipitate so obtained is washed, dried, and weighed; its weight should not be less than 1 gramme.

SUGAR.

The qualitative test of sugar, by means of an alkaline copper solution (*vide* p. 347), may be applied in the estimation of sugar in saccharifeous substances.

Process.—34.64 grammes of pure dry crystals of ordinary sulphate of copper are dissolved in about 250 c. c. of distilled water, 173 grammes of pure crystals of the double tartrate of potassium and sodium are dissolved in 480 c. c. of solution of caustic soda of sp. gr. 1.14. The solutions are mixed and water added to one litre. 100 c. c. of this solution represent 3.464 grammes of sulphate of copper, and correspond to 0.5 of a gramme of pure anhydrous grape-sugar, 0.475 of cane-sugar, or 0.45 of starch. It must be preserved in a well-stoppered bottle to prevent absorption of carbonic acid, and be kept in a dark place. If it give a precipitate on boiling, a little solution of soda may be added in making experiments.

Dissolve 0.475 of pure dry powdered cane-sugar in about 50 c. c. of water, convert into grape-sugar by acidulating with sulphuric acid, and boiling for an hour or two, neutralize with carbonate of sodium, and dilute to 100 c. c. Place 10 c. c. of the copper solution in a small flask, dilute with three or four times its bulk of water, and gently boil. Into the boiling liquid drop the solution of sugar from a burette, one cubic centimetre, or less, at a time, until, after standing for the precipitate to subside, the supernatant liquid has just lost its blue color; 10 c. c. of the solution of the sugar should be required to produce this effect, = 0.475 of cane-sugar or 0.5 of grape-sugar. Experiments on pure cane-sugar must be practised until accuracy is attained; syrups, diabetic urine, and saccharated substances containing unknown quantities of sugar may then be analyzed.

Starch is converted into grape-sugar by gentle ebullition with dilute acid for eight or ten hours, the solution being finally diluted so that one part of starch, or rather sugar, shall be contained in about 150 of water.

Saccharimetry.—A generic term for certain volumetric operations undertaken with the view of ascertaining the quantity of sugar present in any matter in which it may be contained.

Saccharimetry is frequently performed upon common syrup (*Syrupus*, B. P.) and solutions which are known to

contain nothing but cane- (ordinary) sugar, the object being merely to ascertain the amount present. In such a case it is only necessary to take the specific gravity of the liquid at 60° F., and then refer to a previously prepared Table of densities and percentages.

Specific gravity.	Sugar per cent.	Specific gravity.	Sugar per cent.	Specific gravity.	Sugar per cent.
1.007 . .	1.8	1.100 . .	23.7	1.210 . .	46.2
1.014 . .	3.5	1.108 . .	25.6	1.221 . .	48.1
1.022 . .	5.2	1.116 . .	27.6	1.231 . .	50.0
1.029 . .	7.0	1.125 . .	29.4	1.242 . .	52.1
1.036 . .	8.7	1.134 . .	31.5	1.252 . .	54.1
1.044 . .	10.4	1.143 . .	33.4	1.261 . .	56.0
1.052 . .	12.4	1.152 . .	35.2	1.275 . .	58.0
1.060 . .	14.4	1.161 . .	37.0	1.286 . .	60.1
1.067 . .	16.3	1.171 . .	38.8	1.298 . .	62.2
1.075 . .	18.2	1.180 . .	40.6	1.309 . .	64.4
1.083 . .	20.0	1.190 . .	42.4	1.321 . .	66.6?
1.091 . .	21.8	1.199 . .	44.3	1.330 (B.P.)	66.6?

The sp. gr. may be taken by an hydrometer, technically termed a *saccharometer*. (The above spec. gravs. = 1° to 35° Baumé.)

If a liquid contains other substances besides cane-sugar, the test of specific gravity is of little or no value. Advantage may then be taken of the fact that syrup causes right-handed twisting of a ray of plane polarized light to an extent exactly proportionate to the amount of sugar in solution. The saccharine fluid is placed in a long tube having opaque sides and transparent ends; and a ray of homogeneous light, polarized by reflection from a black-glass mirror or otherwise, is sent through the liquid and optically examined by a plate of tourmaline, Nicol's prism, or other polarizing eyepiece. Attached to the eyepiece is a short arm which traverses a circle divided into degrees. The eyepiece and arm are previously so adjusted that when the ray is no longer visible the arm points to the zero of the scale of degrees. The saccharine solution, however, so twists the ray as to again render it visible; and the number of degrees which the eyepiece has to be rotated before the ray is once more invisible is exactly proportionate to the strength of the solution. The value of the degrees having been ascertained by direct experiment and the results tabulated, a reference to the Table at once indicates the percentage of sugar in the liquid under examination.

Grape-sugar also possesses the property of dextro-rotation, but less powerfully than cane-sugar; moreover the former variety does not, like cane-sugar, suffer inversion of the direction of rotation on the addition of hydrochloric acid to its solution—an operation that furnishes data for ascertaining the amounts of cane- and of grape-sugar, or of crystallizable and non-crystallizable sugar, present in a mixture. In using the polariscope-saccharometer, it is convenient to employ tubes of uniform size, and always to operate at the same temperature.

ALCOHOL.

Mulder's process for the determination of the amount of alcohol in wines, beer, tinctures, and other alcoholic liquids containing vegetable matter is as follows: Take the specific gravity and temperature of the liquid, and measure off a certain quantity (100 cubic centimetres); evaporate to one-half or less, avoiding ebullition in order that particles of the material may not be carried away by the steam. Dilute with water to the original bulk, and take the specific gravity at the same temperature as before. Of the figures representing this latter specific gravity, all over 1.000 show to what extent dissolved solid matter affected the original specific gravity of the liquid. Thus, the specific gravity of a sample of wine at 15°.5 C. is 0.9951; evaporated till all alcohol is removed and diluted with water to the original bulk, the specific gravity at 15°.5 C. is 1.0081: 0.0081 represents the gravitating effect of dissolved solid matter in 0.9951 parts of original wine. 0.0081 subtracted from 0.9951 leaves 0.987, which is the specific gravity of the water and alcohol of the wine. On referring to a Table of the strengths of diluted alcohol of different specific gravities (p. 550), 0.987 at 15°.5 C. is found to indicate a spirit containing 8 per cent. of real alcohol. If the foregoing operation be conducted in a retort, the liquid being boiled and the steam carefully condensed, the distillate, diluted with water to the original bulk of wine operated on, will still more accurately represent the amount of water and alcohol in the wine—its specific gravity showing the percentage of real alcohol present.

DIALYSIS.

Dialysis (from διά, *dia*, through, and λύσις, *lusis*, a loosing or resolving) is a term applied by Graham to a process of analysis by diffusion through a septum. The apparatus used in the process is called a *dialyzer*, and is constructed and employed in the following manner. The most convenient septum is the commercial article known as *parchment paper*, made by immersing unsized paper for a short time in sulphuric acid; it is sold by most dealers in chemical apparatus. A piece of this material is stretched over a gutta-percha hoop, and secured by a second external hoop. Dialyzers of useful size are one or two inches deep and five to ten inches wide. Liquids to be dialyzed are poured into the dialyzer, which is then floated in a flat dish containing distilled water.

The practical value of dialysis depends upon the fact that certain substances will diffuse through a given septum far more rapidly than others. Uncrystallizable bodies diffuse very slowly. Of such matters as starch, gum, albumen, and gelatine, the last named is perhaps least diffusive; hence substances of this class are termed *colloids*, or bodies like *collin*, which is the soluble form of gelatine. Substances which diffuse rapidly are mostly crystalline; hence bodies of this class are termed *crystalloids*.

Solutions of two parts of the following named substances in 100 parts of distilled water were dialyzed by Graham for twenty-four hours. The amounts of each substance which passed through the septum bore the following relations to one another:—

Chloride of sodium	1000
Ammonium	847
Theine	703
Salicin	503
Cane-sugar	472
Amygdalin	311
Extract of logwood	168
Catechu	159
Extract of cochineal	51
Gallo-tannic acid	30
Extract of litmus	19
Purified caramel	5

Ten-per-cent. solutions, under similar circumstances, gave the following results:—

Gum Arabic	4
Starch-sugar	266
Cane-sugar	214
Glycerine	440
Alcohol	476
Chloride of sodium	1000

The phenomena of dialysis show that crystalloids are superior to colloids in affinity for water. If a solution of chloride of sodium be placed at the bottom of a jar, and covered by a hot solution of gelatine of sufficient strength to solidify on cooling, the chloride of sodium will diffuse up into the solid jelly, because the water of the solid jelly has a greater affinity for the salt than it has for the gelatine. The solid jelly may obviously be reduced in thickness, and saline liquids placed above it; indeed the conditions would then be still more favorable for diffusion. Replace the stratum of jelly by a permanent colloid, such as parchment paper; the result is the same, but the permanent character of the septum admits of its practical application.

Further researches on dialysis will probably throw much light on several important points in connection with physiological chemistry; for there is little doubt that alimentary matter passes through the cell-walls of animals and plants by this process.

QUESTIONS AND EXERCISES.

1055. Carbonate of potassium is said to lose 16 per cent. of water on exposure to a red heat; give the details of manipulation observed in verifying this statement.

1056. Write a few paragraphs descriptive of the process of ultimate organic analysis.

1057. In what forms are carbon, hydrogen, and nitrogen weighed in quantitative analysis?

1058. In the combustion of .41 of a gramme of sugar, what weights of products will be obtained?—*Ans.* .632 of carbonic acid gas (CO_2) and .237 of water (H_2O).

1059. Describe De Vry's process for the assay of commercial quinia.

1060. Give the official method for the estimation of morphia in opium.

1061. Mention the operations necessary for the estimation of the proportion of sugar in saccharated carbonate of iron, or in a specimen of diabetic urine.

1062. What is understood by *saccharimetry?*

1063. Give two processes for the estimation of the percentage of alcohol in tinctures, wines, or beer.

1064. Define dialysis.

Conclusion.

Detailed instructions for the quantitative analysis of potable water, articles of food, general technical products, special minerals, soils, manures, air, illuminating agents (including solid fats, oils, spirits, petroleum, and gas), dyes, and tanning-materials, would scarcely be in place in this volume.

The course through which the reader has been conducted will, it is hoped, have taught the principles of the science of chemistry, and given special knowledge concerning the applications of that science to medicine and pharmacy, as well as have imparted sufficient manipulative skill to meet the requirements of manufacture or analysis. The author would venture to suggest that this knowledge be utilized, not only in the way of personal advantage, but in experimental researches on chemical subjects connected with therapeutics and pharmacy. The discovery and publication of a new truth, great or small, is the best means whereby to aid in advancing the calling in which we may be engaged, benefit our fellow creatures, and unveil the laws of the Creator of all things.

APPENDIX.

TABLE OF OFFICIAL TESTS FOR IMPURITIES IN PHARMACOPŒIAL PREPARATIONS.*

Name of Preparation.	Impurities.	Tests.	Page.
Acaciæ Gummi	Starch	Iodine	245
Acetum	More than one thousandth of Sulphuric acid	Quantitative analysis	519
Acidum Aceticum	Traces of Lead or Copper	Sulphuretted Hydrogen	197
	Sulphuric acid	Chloride or Nitrate of Barium	277
	Hydrochloric acid	Nitrate of Silver	240
	Sulphurous acid	Nascent Hydrogen	274
Acid. Acetic. Glaciale	Sulphurous acid	Nascent Hydrogen	274
Acidum Boracicum	Alkaline salts	Insolubility in Alcohol	296
Acidum Carbolicum	Creasote	Oxidation, etc. See Creasotum	392
Acidum Citricum	Traces of Copper or Lead	Sulphuretted Hydrogen	197
	Tartaric acid	Acetate of Potassium	28
	Tartaric acid	Excess of Lime-water	291
	Sulphuric acid	Chloride or Nitrate of Barium	277
	Mineral matter	Incineration	86
Acidum Gallicum	Tannic acid	(Isinglass) Gelatine	317
Acidum Hydrochloricum	Sulphuric acid	Chloride or Nitrate of Barium	277
	Arsenic	Sulphuretted Hydrogen, Copper	148
	Sulphurous acid	Nascent Hydrogen	274
Acidum Hydrocyanicum Dilutum	Sulphuric acid	Chloride or Nitrate of Barium	277
	Hydrochloric acid	Ppt. by Nitr. silver, insol. in nitric acid	240
Acidum Nitricum	Mineral matter	Evaporation and ignition.	86
	Sulphuric acid	Chloride or Nitrate of Barium	277
	Hydrochloric acid	Nitrate of Silver	240
	Mineral matter	Incineration	86
Acidum Oxalicum	Lead or Platinum	Sulphuretted Hydrogen	229
Acidum Phosphoricum Dilutum	Sulphuric acid	Chloride or Nitrate of Barium	277
	Hydrochloric acid	Nitrate of Silver and Nitric acid	240
	Metaphosphoric acid	Albumen	311
	Nitric acid	Ferrous Sulphate and Sulphuric acid	256
	Phosphorous acid	Corrosive sublimate	313

* The manipulations necessary to be observed in testing for impurities will be found described in the paragraphs treating of those substances. The Table also includes references to processes for ascertaining deficiency in strength of official articles.

The other "characters and tests" of pharmacopœial compounds have been given in connection with the respective synthetical and analytical reactions.

Name of Preparation.	Impurities.	Test.	Page.
Acidum Sulphuricum	Mineral matter	Evaporation and ignition.	86
	Nitric acid	Ferrous Sulphate	256
	Arsenic or Lead	Sulphuretted Hydrogen	197
Acidum Sulphurosum.	Sulphuric acid	Chloride or Nitrate of Barium	277
Acidum Tannicum	Mineral matter	Incineration	86
Acidum Tartaricum	Metallic matter, as Lead	Sulphuretted Hydrogen	197
	Oxalic acid	Sulphate of Calcium	282
	Calcium (tartrate or sulphate).	Oxalate of Ammonium	98
	Mineral matter	Incineration	86
Aconitia	Mineral matter	Incineration	86
Adeps præparatus	Chloride (of sodium)	Nitrate of Silver	240
	Starch (flour)	Iodine	245
Æther	Alcohol	Boiling point, sp. gravity.	378
Æther Purus	Alcohol, Water	Specific gravity	378
Alcohol	Resin or oil	Opalescence on dilution	375
	Water	Anhydrous Sulphate of Copper.	168
Alcohol Amylicum	Other spirituous matter	Boiling point, sp. gravity.	389
Alum	Iron (sulphate)	Yellow or red prussiate	136
Ammonii Benzoas	Fixed salts	Non-volatility	85
Ammonii Bromidum	Free Bromine	Odour	241
	Iodide (of Ammonium).	Chlorine water and starch	245
Ammonii Carbonas	General	Quantitative analysis(446)	493
	Fixed salts	Non-volatility	85
	Sulphate (of Ammonium).	Chloride or Nitrate of Barium	277
	Chloride (of Ammonium).	Nitrate of Silver	240
Ammonii Chloridum	Fixed salts	Non-volatility	85
Ammonii Nitras	Sulphate (of Ammonium).	Chloride of Barium	277
	Chloride (of Ammonium).	Nitrate of Silver	240
Amylum	Alkaline matter	Red Litmus	83
	Acid matter	Blue Litmus	83
Antimonium Nigrum	Silica	Insolubility in HCl	315
Antimonii Oxidum	Higher oxides of antimony	Insolubility in sol. of acid tartrate of potassium	156
Antimonium Tartaratum.	General	Quantitative analysis	509
Aqua Aurantii Floris	Metallic matter (Pb, Cu, Sn)	Sulphuretted Hydrogen	229
Aqua Destillata	Fixed salts	Evaporation and ignition.	86
	Tin, Lead, or Copper	Sulphuretted Hydrogen	229
	Calcium salts	Oxalate of Ammonium	98
	Chlorides	Nitrate of Silver	240
	Sulphates	Chloride of Nitrate of Barium	297
	Carbonates	Lime-water	280
Argenti Nitras	Other nitrates, etc.	Quantitative analysis, etc.	513
Argenti Oxidum	Metallic silver	Effervescence with Nitric acid	191
	General	Quantitative analysis	513
Argentum Purificatum	Copper	Ammonia to the Nitric solution	169
Atropia	Mineral matter	Incineration	86
Atropiæ Sulphas	Mineral matter	Incineration	86
Balsamum Peruvianum	Fixed oil	Immiscibility with Alcohol	402
	Alcohol	Non-diminution of volume when mixed with water	374
Beberiæ Sulphas	Mineral matter	Incineration	86
Bismuthi Carbonas	Nitrates (of Bismuth or Ammonium).	Sulphate of Indigo	258
	Lead (carbonate)	Diluted Sulphuric acid	189
	Chloride (oxychloride of bismuth).	Nitrate of Silver	240
Bismuthi Subnitras	Lead (oxynitrate)	Diluted Sulphuric acid	179
	Chlorides (oxychloride of bismuth).	Nitrate of Silver	240

Name of Preparation.	Impurities.	Tests.	Page.
Bismuthum Purificatum.	Copper	Ammonia to Nitric solut'n	169
Bromum	General	Specific gravity (465) and boiling point	449
	Iodine	Starch	245
Cadmii Iodidum	Zinc (iodide)	Potash in excess, then Sulphydrate of Ammonium	222
	General	Quantitative analysis	514
Calcii Carbonas Præcipitata	Alumina, Oxide of Iron, and Phosphates.	Sacc. solution of lime to sol. in nitric acid	92
	Chlorides	Nitrate of Silver	240
Calcii Chloridum	Hypochlorite of Calcium	Hydrochloric acid	260
	Carbonic acid	Lime-water	280
Calcii Phosphas	Carbonates (of Calcium)	Effervescence with acids	280
	Alumina	Solution of potash	118
	Sand	Insolubility in acid	315
Calx	Carbonate of Calcium	Effervescence with acids	286
	Alumina, Oxide of Iron, etc.	Sacc. sol. of lime, to sol. in acids	92
Calx Chlorata	General	Quantitative analysis	495
Cambogia	Starch	Iodine (Green)	245
Camphora	Fixed salts	Non-volatility	83
Carbo Animalis Purificatus.	Earthy salts	Incineration (by help of red ox. of mercury)	86
Carbo Ligni	More than 2 per ct. of ash	Incineration	86
Catechu Pallidum	Starch	Iodine	245
Cera Alba	Soft Fats	Melting-point	451
Cera Flava	Soft Fats	Melting-point	451
	Resin	Solubility in Alcohol	410
	Flour	Insolubility in Turpentine, Iodine	245
Cerii Oxalas	Carbonates and other oxalates.	Ash sol. in acids with effervescence	280
	Alumina	Insolubility of Hydrate in Ammonia	203
	General	More or less than 48 per cent. of ash	203
Cetaceum	Soft Fats	Melting-point	451
Chloral	Chlorine	Nitrate of silver	388
	General	Quantitative analysis	388
Chloroform	General	Specific gravity	450
	Hydrocarbons	Sulphuric acid	386
	Non-volatile matter	Residue on evaporation	86
Copaiba	Wood-oil	Gelatinization at 270° F.	412
		Incomplete solubility in Benzol	412
Creasotum	Carbolic acid	Oxidation	392
		Non-volatility at 212° F.	392
		Dextro-rotation of polarized ray	392
		Crystallization on cooling	392
Cupri Sulphas	Iron (ferrous sulphate)	Nitric acid and ammonia	137
Elaterium	Carbonates (chalk)	Effervescence with acids	280
	General	Quantitative analysis	368
Fel Bovinum Purificatum.	Mucus, crude bile	Incomplete solubility in spirit	411
Ferri Arsenias	Sulphate of (sodium)	Chloride or Nitrate of Barium	297
	General	Quantitative analysis	492
Ferri Carbonas Saccharata	Sulphate (of ammonium)	Chloride or Nitrate of Barium	297
	General	Quantitative analysis	492
Ferri et Ammonii Citras	Tartrate (of iron and ammonium)	Ebullition with potash and saturation with Acetic acid ($=KHC_4H_4O_6$)	287
	General	Quantitative analysis	507
	Potassium or Sodium, salts	Alkalinity of ash	83

Name of Preparation.	Impurities.	Test.	Page.
Ferri et Quiniæ Citras	Potassium or Sodium, salts	Alkalinity of ash	83
	General	Quantitative analysis	507
	Alkaloids other than Quinia.	Insolubility of pptd. alkaloid in ether	344
Ferri Oxidum Magneticum	Metallic iron	Effervescence with acids	134
	General	Quantitative analysis	492
Ferri Peroxidum Humidum	Ferrous hydrate	Red prussiate to acid solution	136
	Ferric oxyhydrate	Insolubility in cold dil. Hydrochloric acid	129
Ferri Phosphas	Arsenicum (ferri arsenias)	Slip of Copper in acid solution	148
	General	Quantitative analysis	492
Ferri Sulphas	Ferric oxysulphate	Insolubility in Water	122
Ferri Sulphas Granulata	Ferric compounds	Ppt. of S in aqueous sol. by H_2S	137
	Copper, etc.	Sulphuretted Hydrogen	229
Ferrum Redactum	Less than 50 per cent.	Quantitative analysis	508
Ferrum Tartaratum	Ferrous compounds	Red prussiate to acid solution	136
	Ammoniacal salts	Soda	82
	General	Quantitative analysis	507
Glycerina	General	Specific gravity	394
Hydrargyri Iodidum Rubrum.	Fixed salts	Non-volatility	184
Hydrargyri Iodidum Viride.	Red Iodide	Insolubility in ether	172
Hydrargyri Oxidum Flavum	Fixed Salts	Non-volatility	184
Hydrargyri Oxidum Rubrum	Fixed Salts	Non-volatility	184
	Nitrates (of mercury)	Orange vapor on heating in a tube	179
Hydrargyri Subchloridum	Corrosive Sublimate	Treatment with ether	178
	Fixed salts	Non-volatility	184
Hydrargyri Sulphas	Fixed salts	Non-volatility	184
Hydrargyrum	Fixed metals (Pb, Sn, Zn, Bi, Cu).	Non-volatility	184
Hydrargyrum Ammoniatum.	Fixed salts	Non-volatility	184
Hydrargyrum cum Creta.	Mercuric oxide	Stannous chloride to sol. in HCl	183
Iodum	Fixed salts	Non-volatility	243
	Cyanide of Iodine	Physical characters	243
	General	Quantitative analysis	494
Jalapæ Resina	Resin	Solubility in Turpentine	369
Limonis Succus	Deficiency of Citric acid	Quantitative analysis	290
Liquor Ammoniæ	General	Specific gravity	465
		Quantitative analysis	476
Liquor Ammoniæ Fortior	General impurity or deficiency.	Specific gravity (449) and Quantitative analysis	476
	Carbonate of Ammonium.	Lime-water	280
	Calcium salts (chloride etc.)	Oxalate of Ammonium	98
	Iron salts (ferrous hydrate).	Sulphydrate of Ammonium	136
	Sulphur salts (AmHS)	Ammonio-sulphate of Copper	272
	Chloride of Ammonium	Nitrate of Silver to acidified sol.	240
	Sulphate of Ammonium	Chloride of Barium to acidified sol.	297
Liq. Antimonii Chloridi			489
Liq. Arsenicalis			509
Liq. Arsenici Hydrochloricus	General impurity or deficiency	Specific gravity	489
		Quantitative analysis	
Liq. Bismuthi et Ammonii Cit.			510

Name of Preparation.	Impurities.	Test.	Page.
Liq. Calcis	Deficiency in strength	Quantitative analysis	478
Liq. Calcis Chloratæ	General impurity or deficiency	Specific gravity	466
Liq. Calcis Saccharatus		Quantitative analysis(507)	478
Liquor Chlori	General quality	Specific gravity	465
	Fixed matter	Residue on evaporation	86
	Deficiency in strength	Quantitative analysis	495
Liq. Ferri Perchloridi Fort.	Ferrous salts	Red Prussiate	137
Liq. Ferri Pernitratis	General impurity or deficiency	Specific gravity	465
Liq. Ferri Persulphatis		Quantitative analysis	507
Liq. Hydrargyri Nit. Acid	Deficiency in strength	Specific gravity	466
	Mercurous salts (nitrate)	Hydrochloric acid	183
Liq. Lithii Effervescens	General impurity or deficiency.	Quantitative analysis, etc.	201
Liq. Magnesii Carbonatis	Other magnesian salts	Bitter taste ($MgCl_2MgSO_4$)	101
	General impurity or deficiency.	Quantitative analysis	505
Liq. Plumbi Subacetatis	General impurity or deficiency	Specific gravity	466
		Quantitative analysis	478
Liquor Potassæ	General impurity or deficiency	Specific gravity	466
		Quantitative analysis	478
	Carbonate(of potassium)	Effervescence with acids	277
		Lime-water	280
	Calcium salts	Oxalate of Ammonium	98
	More than traces of Silica	Insol.in acid after evap.etc.	315
	More than traces of Sulphates	Chloride of Barium to acid sol.	276
	More than traces of Chlorides	Nitrate of silver to acid sol.	240
	More than traces of Alumina	Ammonia to acid sol.	117
Liq. Potassæ Effervescens	Deficiency in strength	Quantitative analysis	478
	Bicarbonate of sodium	Tartaric acid, etc.	500
Liquor Sodæ	General impurity or deficiency	Specific gravity	466
		Quantitative analysis	478
	Calcium salts	Oxalate of Ammonium	98
	Carbonate (of sodium)	Effervescence with acids	280
		Lime-water	280
	More than traces of Silica	Insol. in acids after evap	315
	More than traces of Sulphates	$BaCl_2$ to acid sol.	276
	More than traces of Chlorides	$AgNO_3$ to acid sol.	240
	More than traces of Alumina	Ammonia to acid sol.	117
Liquor Sodæ Chloratæ	Salts of Potassium or Ammonium	Perchloride of Platinum to acid sol.	83
	General impurity or deficiency.	Quantitative analysis (65)	494
	Calcium salts	Oxalate of Ammonium	98
Liq Sodæ Effervescens	Deficiency in strength	Quantitative analysis	478
Lithii Carbonas	General impurity or deficiency.	Quantitative analysis	201
	Calcium salts	Oxalate of Ammonium,etc.	201
	Alumina	Lime-water, etc.	201
Lithii Citras	Deficiency in strength	Quantitative analysis	201
Magnesia	Carbonate (of magnesium)	Effervescence with acids	102
Magnesia Levis	Calcium (hydrate or carbonate).	Oxalate of Ammonium to acet sol.	98
	Sulphates (of magnesium or sodium).	Chloride of Barium to acid sol.	276
Magnesii Carbonas	Alumina	Ammonia to acid sol.	117
Magnesii Carb. Levis	Sulphates (of magnesium or sodium).	Chloride of Barium to acid solution	276
	Calcium (carbonate)	Oxalic acid to Ammoniacal solution	98
	Iron, Lead, etc.	Sulph. hydrogen to sol. in acid + excess of Ammon.	229
	General impurity or deficiency.	Quantitative analysis	505

Name of Preparation.	Impurities.	Test.	Page.
Magnesii Sulphas	Calcium (sulphate)	Oxalate of Ammonium	98
	Iron (sulphate)	Chlorinated Lime or Soda	100
	General impurities	Quantitative analysis	505
Manna	Deficiency of mannite	Quantitative analysis	364
Mel	Starch (flour)	Iodine	245
MorphiæHydrochloras	General impurities	Quantitative analysis	533
Olea Destillata	Fixed oil	Permanent greasy stain on paper	..
	Alcohol	Loss in volume on shaking with water	..
Opium	Deficiency in morphia	Quantitative analysis	532
Plumbi Acetas	General	Quantitative analysis	478
Plumbi Carbonas	Sulphate of Lead or Barium or Silicates	Insolubility in Acetic acid (190, 88, 172)	215
	Calcium (chalk)	Oxal. Ammonium after removing Lead	98
Plumbi Oxidum	Carbonates	Effervescence with acids	280
	Copper (oxide)	Ammonia to acid solution	169
Potassa Caustica	More than traces of Chloride	Nitrate of silver to acid solution	246
	More than traces of Sulphates	Chloride of Barium to acid solution	276
	General impurities (water etc.).	Quantitative analysis	478
Potassa Sulphurata	Excess of Carbonate or Sulphate	More than 25 per cent. insol. in spirit	57
Potassii Acetas	Iron and other metallic impurities	Sulphydrate of Ammonium	229
	Carbonate of Potassium	Effervescence with acids; alkalinity; insolubility in spirit	280
Potassii Bicarbonas	General	Quantitative analysis	57
			478
Potassii Bromidum	Free bromine	Odor	241
	Iodide (of potassium)	Chlorine-water and starch	246
	General	Quantitative analysis (487)	515
Potassii Carbonas	More than traces of Silicate	Insol. in acid after evap. etc.	315
	More than traces of Sulphate	Chloride of Barium to acid solution	276
	More than traces of Chloride	Nitr. of Silver to acid sol.	240
	General	Quantitative analysis	478
Potassii Chloras	Chloride (of potassium)	Nitrate of Silver	240
	Calcium (chloride)	Oxalate of Ammonium	98
Potassii Citras	General	Quantitative analysis	481
Potassii Ferridcyanidum	Ferrocyanide (of potassium).	Ferric salt	303
Potassii Iodidum	Iodate (of potassium)	Tartaric acid and starch	62
	Chloride (of potassium)	Nitrate of Silver, etc.	240
	Carbonate (of potassium)	Sacc. solution of Lime	92
Potassii Nitras	Sulphate (of potassium)	Chloride of Barium	276
	Chloride (of potassium)	Nitrate of Silver	240
Potassii Permanganas	General	Quantitative analysis	493
Potassii Sulphas	Acid Sulph. of Potassium	Test-paper	83
	Calcium (sulphate)	Oxalate of Ammonium	98
Potassii Sulphis	Hyposulphite (of potassium).	Sulphuric acid	308
Potassii Tartras Potassii Tartr. Acida	General	Quantitative analysis	481
Quiniæ Sulphas	Salicin	Sulphuric acid	370
	General	Quantitative analysis	529
Rhei Radix	Turmeric	Boracic acid	297
Santoninum	Mineral matter	Incineration	86
Sapo Durus	Earthy soaps, etc.	Insolubility in spirit	401
	Oil	Oily stain to paper	401
	Potassium compounds	Deliquescence of ash	401
Sapo Mollis	Earthy soaps, etc.	Insolubility in spirit	401
	Oil	Oily stain to paper	401

Name of Preparation.	Impurities.	Test.	Page.
Scammoniæ Resina	Resin of guaiacum	Inner surface of Potato-paring	369
	Resin of Jalap	Insolubility in ether	369
Scammonium	Carbonate (of calcium and magnesium).	Effervescence with acids	280
	Starch (flour)	Solution of Iodine	245
Sinapis	Starch (flour)	Solution of Iodine	245
Soda Caustica	More than traces of { Chloride / Sulphate	Nitr. of Silver to acid sol.	240
		Chloride of Barium to acid sol.	276
	General impurities (water etc.).	Quantitative analysis	478
Soda Tartarata	General	Quantitative analysis	481
Soda Acetas	Acid or alkaline matter	Test-paper	83
	Sulphates (sodium or calcium).	Chloride of Barium to acid sol.	276
	Chlorides (sodium or calcium).	Nitrate of Silver to acid sol.	240
Sodii Arsenias	Excess or deficiency of water of crystallization.	Quantitative analysis	487
	General	Quantitative analysis	487
Sodii Bicarbonas	Neutral Carbonate (of sodium).	Mercuric chloride	184
	More than traces of { Chloride / Sulphate	Nitr. of Silver to acid sol.	240
		Chloride of Barium to acid sol.	276
	General	Quantitative analysis	478
Sodii Boras	General	Quantitative analysis	478
Sodii Carbonas	Excess or deficiency of water of cryst. etc.	Quantitative analysis	525
	More than traces of { Chlorides / Sulphates	Nitr. of Silver to acid sol.	240
		Chloride of Barium to acid sol.	276
Sodii Hyposulphis	General	Quantitative analysis	489
Sodii Nitras	Chloride (of sodium)	Nitrate of Silver	240
	Sulphate (of sodium)	Chloride or Nitrate of Barium	276
Sodii Phosphas	More than trace of Sulphate.	Chloride or Nitrate of Barium to acid sol.	276
	Deficiency or excess of water of cryst.	Quantitative analysis	525
Sodii Sulphas	Ammonium salts	Solut'n of potash heated	81
	Ferric salts		137
	General	Quantitative analysis	519
	Excess or deficiency of water of cryst.	Quantitative analysis	525
Sodii Valerianas	Free soda or carbonate	Test-papers	83
		Insolubility in spirit	321
Spiritus Ætheris Nitrosi	General	Specific gravity	466
	More than trace of acid	Effervescence with bicarbonate of sodium	280
	Free acid	More than "feeble" effervescence with bicarbonate of sodium	280
	Deficiency of nitrite of [ethyl.	Quantitative analysis	380
Spiritus Ammonio-Aromat	General	Specific gravity	465
Spiritus Chloroformi			
Spiritus Rectificatus	General (excess of water)	Specific gravity	465
	Resin or oil	Opalescence on dilution	375
	More than traces of fusil oil, etc.	Nitrate of Silver	487
Spiritus Tenuior	General (excess of water).	Specific gravity	373
Strychnia	Brucia	Nitric acid	248
	Mineral matter	Incineration	86
Sulphur Præcipitatum	Sulphate of calcium	Appearance under microscope	271
		Residue on ignition	271

Name of Preparation	Impurities.	Test.	Page.
Sulphur Sublimatum	Earthy matter	Incineration	86
	Trace of Acid (H_2SO_4 or H_2SO_3).	Litmus-paper	83
	Sulphide of Arsenicum	Ammonia	152
Sulphuris Iodidum	Deficiency of Iodine	Quantitative analysis	244
Syrupi	Deficiency of Sugar	Specific gravity	466
Tamarindus	Traces of Copper	Iron	168
Veratria	Mineral matter	Incineration	86
Zinci Acetas	Sulphates	Chloride or Nitrate of Barium	276
	Chlorides	Nitrate of Silver	240
	Metals (As, Cd, Cu, Pb)	Sulphuretted Hydrogen	229
	Iron (acetate)	Nitric Acid: Ammonia	139
	Copper (acetate)	Ammonia	169
Zinci Carbonas	Sulphates	Chloride or Nitrate of Barium to acid sol.	276
	Chlorides	Nitr. of Silver to acid sol.	240
	Copper (carbonate)	Ammonia to acid solution	169
Zinci Chloridum	Metals (As, Cd, Cu, Pb)	Sulphuretted Hydrogen	229
	Sulphates	Chloride or Nitrate of Barium	276
	Calcium (chloride)	Oxalate of Ammonium	98
	Ferrous salts (chloride)	Ferridcyanide of Potass'm	137
	Ferric salts (chloride)	Ferrocyanide of Potass'm	137
Zinci Oxidum	Carbonate (of zinc)	Effervescence with acids	280
	Sulphates (sodium or zinc)	Chloride or Nitrate of Barium to acid sol.	276
	Chlorides	Nitr. of Silver to acid sol.	240
	Copper (oxide)	Ammonia to acid solution	169
Zinci Sulphas	Metal (As, Cd, Cu, Pb)	Sulphuretted hydrogen	229
	Iron (sulphate)	Tincture of galls	318
		Nitric acid: Ammonia	139
	Copper (sulphate)	Ammonia	169
Zinci Valerianas	Sulphate (of zinc)	Chloride or Nitrate of Barium	276
	Butyrate (of zinc)	Acetate of Copper, etc.	322

Equivalent weights of Citric Acid, Tartaric Acid, Carbonate of Potassium, Bicarbonate of Potassium, Carbonate of Sodium, Bicarbonate of Sodium, Carbonate of Ammonium, and Carbonate of Magnesium; repeated (in **black**) for 20 parts of each, and incidentally (in roman) for other proportions. (Exact to two places of decimals.)

Citric Acid ($H_3C_6H_5O_7, H_2O$) ÷ 3 × 2 = 140 . . .	**20.00**	18.66	**16.96**	**14.00**	**9.78**	**6.66**	**23.72**	**29.31**
Tartaric Acid $H_2C_4H_4O_6$ = 150	21.43	**20.00**	**18.26**	**15.00**	**10 49**	**17.85**	**25.42**	**31.41**
Carbonate of Potassium K_2CO_3+16 % Aq.=164.285	**23 47**	**21.90**	**20.00**	16.43	11.48	19.52	27.87	34.40
Bicarbonate of Potassium $2(KHCO_3)$ = 200 . . .	**28 57**	**26.66**	24.34	**20.00**	13.98	23.81	33.89	41.90
Carbonate of Sodium Na_2CO_3, $10H_2O$ = 286 . . .	**40.08**	**38.13**	34.81	28.60	**20.00**	34.04	48 47	59.98
Bicarbonate of Sodium $2(NaHCO_3)$ = 168	**24.00**	**22.40**	20.45	16.80	11.74	**20.00**	28.47	35.18
Carbonate of Ammonium $(N_4H_{16}C_3O_8)$ ÷ 2 = 118 .	**16.85**	**15.73**	14.36	11.80	8.25	14.04	**20.00**	24.71
Carb. of Magnes.$((MgCO_3)_3, Mg2HO, 4H_2O)$÷4=95.5	**13.64**	**12.73**	11.62	9.55	6.68	11.37	16.18	**20.00**

The amount of acid given in any column will saturate the amount of carbonate in the same column, and *vice versâ*.

The amounts of carbonate in any column are equal to each other in chemical power.

Lemon-juice (sp. gr. 1039) contains, on an average, 7 per cent. by weight of citric acid.

The same Table in round numbers, for purposes of prescribing and dispensing.

(The old names in Latin.)

Citric Acid	**20**	19	**17**	**14**	**10**	**17**	**24**	**30**
Tartaric Acid	22	**20**	**18**	**15**	**11**	**18**	**26**	**32**
Carbonate of Potassium (Potassæ Carbonas)	**24**	**22**	**20**	16	12	20	28	35
Bicarbonate of Potassium (Potassæ Bicarbonas) . .	**29**	**27**	24	**20**	14	24	34	42
Carbonate of Sodium (cryst.) (Sodæ Carbonas) . . .	**40**	**38**	35	28	**20**	34	49	60
Bicarbonate of Sodium (Sodæ Bicarbonas)	**24**	**22**	20	17	12	**20**	29	36
Carbonate of Ammonium (Ammoniæ Carbonas) . .	**17**	**16**	14	12	8	14	**20**	25
Carbonate of Magnesium (Magnesiæ Carbonas) . . .	**13**	**13**	11	9	7	11	16	**20**

The Table is read thus: 20 grains of Citric Acid will saturate 29 grains of Bicarbonate of Potassium; 20 grains of Bicarbonate of Sodium will saturate, or be saturated by, 18 grains of Tartaric Acid; 11 grains of Tartaric Acid = 8 grains of Carbonate of Ammonium; 20 grains of Bicarbonate of Sodium are equivalent to, or will do as much work as, 34 grains of Carbonate of Sodium; 14 grains of Citric Acid are as strong as 15 of Tartaric Acid. It is occasionally convenient to double the numbers, halve them, or take some other proportion; also to employ them in weights other than grains.

Lemon-juice contains, on an average, 32½ grains of citric acid in 1 fluidounce, or 4 grains per fluidrachm.

THE PROPORTION BY WEIGHT OF ABSOLUTE OR PLAIN ALCOHOL (C_2H_5HO) IN 100 PARTS OF REAL SPIRITS OF DIFFERENT SPECIFIC GRAVITIES (FOWNES).

Sp. gr. at 60° (15° 5 C.).	Per-centage of real alcohol.	Sp. gr. at 60° (15° 5 C.).	Per-centage of real alcohol.	Sp. gr. at 60° (15° 5 C).	Per-centage of real alcohol.
0.9991	0.5	0.9511	34	0.8769	68
0.9981	1	0.9490	35	0.8745	69
0.9965	2	0.9470	36	0.8721	70
0.9947	3	0.9452	37	0.8696	71
0.9930	4	0.9434	38	0.8672	72
0.9914	5	0.9416	39	0.8649	73
0.9898	6	0.9396	40	0.8625	74
0.9884	7	0.9376	41	0.8603	75
0.9869	8	0.9356	42	0.8581	76
0.9855	9	0.9335	43	0.8557	77
0.9841	10	0.9314	44	0.8533	78
0.9828	11	0.9292	45	0.8508	79
0.9815	12	0.9270	46	0.8483	80
0.9802	13	0.9249	47	0.8459	81
0.9789	14	0.9228	48	0.8434	82
0.9778	15	0.9206	49	0.8408	83
0.9766	16	0.9184	50	0.8382	84
0.9753	17	0.9160	51	0.8357	85
0.9741	18	0.9135	52	0.8331	86
0.9728	19	0.9113	53	0.8305	87
0.9716	20	0.9090	54	0.8279	88
0.9704	21	0.9069	55	0.8254	89
0.9691	22	0.9047	56	0.8228	90
0.9678	23	0.9025	57	0.8199	91
0.9665	24	0.9001	58	0.8172	92
0.9652	25	0.8979	59	0.8145	93
0.9638	26	0.8956	60	0.8118	94
0.9623	27	0.8932	61	0.8089	95
0.9609	28	0.8908	62	0.8061	96
0.9593	29	0.8886	63	0·8031	97
0.9578	30	0.8863	64	0.8001	98
0.9560	31	0.8840	65	0.7969	99
0.9544	32	0.8816	66	0.7938	100
0.9528	33	0.8793	67		

THE ELEMENTS.

	Symbols and atomic value.	Atomic weight.
Aluminium (Al_2^{VI})	Al^{IV}	27.5
Antimony (Sb^{III})	Sb^{V}	122
Arsenicum (As^{III})	As^{V}	75
Barium	Ba^{II}	137
Beryllium (Glucinum)	Be^{II}	9.5
Bismuth (Bi^{III})	Bi^{V}	210
Boron	B^{III}	11
Bromine (79.75, Stas)	Br^{I}	80
Cadmium	Cd^{II}	112
Cæsium	Cs^{I}	133
Calcium	Ca^{II}	40
Carbon (C^{II})	C^{IV}	12
Cerium (Ce^{II})	Ce^{VI}	92
Chlorine (35.368, Stas)	Cl^{I}	35.5
Chromium (Cr_2^{VI})	Cr^{VI}	52.5
Cobalt (Co^{II})	Co^{VI}	58.8
Copper	Cu^{II}	63.5
Didymium	D^{II}	96
Erbium?	Eb^{II}	112.6
Fluorine	F^{I}	19
Glucinum. *See* Beryllium.		
Gold (Au^{I})	Au^{III}	196.7
Hydrogen	H^{I}	1
Indium	In^{VI}	75.6
Iodine (126.533, Stas)	I^{I}	127
Iridium	Ir^{IV}	197
Iron (Fe^{II} & Fe_2^{VI})	Fe^{VI}	56
Lanthanium	L^{II}	92
Lead ($^{II}Pb^{II}$)	Pb^{IV}	207
Lithium (7.004, Stas)	Li^{I}	7
Magnesium	Mg^{II}	24
Manganese (Mn^{II} & Mn^{IV})	Mn^{VI}	55
Mercury	Hg^{II}	200
Molybdenum	Mo^{VI}	96
Nickel (Ni^{II})	Ni^{VI}	58.8
Niobium	Nb^{V}	97.6
Nitrogen (N^{I} & N^{III}) (14.009, Stas)	N^{V}	14
Osmium	Os^{IV}	199
Oxygen (15.96, Stas)	O^{II}	16
Palladium	Pd^{IV}	106.5
Phosphorus (P^{III})	P^{V}	31

	Symbols and atomic value.	Atomic weight.
Platinum (197.88, Andrews)	Pt^{IV}	198
Potassium (39.04, Stas)	K^{I}	39
Rhodium	Rh^{IV}	104.3
Rubidium	Rb^{I}	85.3
Ruthenium	Ru^{IV}	104.2
Selenium	Se^{VI}	79.5
Silicon	Si^{IV}	28
Silver (107.66, Stas)	Ag^{I}	108
Sodium (22.98, Stas)	Na^{I}	23
Strontium	Sr^{II}	87.5
Sulphur (S^{II} & S^{IV})	S^{VI}	32
Tantalum	Ta^{V}	182
Tellurium	Te^{VI}	129
Thallium (203. Crookes)	Tl^{III}	204
Thorinum or Thorium	Th^{II}	238
Tin (Sn^{II})	Sn^{IV}	118
Titanium	Ti^{IV}	50
Tungsten	W^{VI}	184
Uranium	U^{VI}	120
Vanadium	V^{V}	51.3
Yttrium	Y^{II}	61.7
Zinc	Zn^{II}	65
Zirconium	Zi^{IV}	89.5
Total	63	

The quantivalence or atomic value of some elements is, apparently, variable; in the above Table the full coefficients are given in the column of symbols, other common values in brackets.

Atomic weights are sometimes obscurely termed *equivalents*.

INDEX.

Abies balsamea, 411
excelsa, 411
canadensis, 412
Absinthin, 355
Absinthium, 355
Absinthol, 407
Absolute alcohol, 374, 449
Acaciæ gummi, 97
gummi, impurities in, 541
Acetate of ammonium, solution of, 78
amyl, 389
ethyl, 268
copper, 168
iron, 117
lead, 186
morphia, 340
potassium, 57
sodium, 69
zinc, 112
Acetates, 265
analytical reactions of, 265
decomposition of aqueous solution of, 266
volumetric estimation of, 484
Acetic acid, 265, 266, 404
ether, 268
glacial, 266, 451
volumetric estimation of free, 484
Acetone, 268
Acetonitrate of barium, 108
Acetum, 265
cantharidis, 265
colchici, 265
destillatum, 265
impurities in, 267, 541
lobeliæ, 265
opii, 265
sanguinariæ, 265
scillæ, 265
Acetyl, 266
Acid, acetic, 265, 266, 404
acetic, glacial, 266, 451
aconitic, 289
arabic, 358
angelic, 406
arachidic, 404
arsenic, 146
arsenious, 144
benzoic, 298, 413, 451
boracic, 295
bromic, 263
butyric, 322, 404
cantharidic, 409
caproic, 404
caprylic, 404
carbazotic, 394
carbolic, 391, 451
carbolic, impure, 394
carbonic, 27, 278
carminic, 300
cathartic, 366
cathartogenic, 366
cerotic, 404
cetraric, 300
chloric, 259, 261
cholalic, 401
chromic, 211
chrysophanic, 300
chrysammic, 393
cinnamic, 413
citric, 289
colopholic, 410
colophonic, 410
copaivic, 411
cresylic, 392
cryptophanic, 429
cyanic, 300
dextroracemic, 285
dextrotartaric, 285
dithionic, 307
erucic, 403
eugenic, 407

Acid—
equisetic, 289
fluoric, 304
formic, 300, 404
gallic, 301, 318
gambogic, 412
gaultheric, 390
glacial acetic, 266, 451
guaiaretinic, 369
gummic, 258
hemidesmic, 301
hippuric, 301, 433, 436
hydriodic, 243
hydrobromic, 241
hydrochloric, 26, 238
common, 238
dilute, 238
hydrocyanic, 247, 249
dilute, 249
hydroferridcyanic, 303
hydroferrocyanic, 302
hydrofluoric, 304
hydrosulphuric, 269
hypochlorous, 260
hypophosphorous, 304
hyposulphurous, 307
iodic, 263
jalapic, 369
lactic, 309
lauric, 404
lithic, 320
lævoracemic, 285
lævotartaric, 285
malic, 309
mastichic, 411
meconic, 310, 424
melissic, 404
metaboracic, 295
metagummic, 258
metantimonic, 157
metaphosphoric, 310
metastannic, 215
mimotannic, 318
mucic, 365
muriatic, 238
myristic, 402
myrrhic, 412
naphthalic, 298
nitric, 252, 254
dilute, 255
nitrohydrochloric, 162, 255
dilute, 162, 255
nitromuriatic, 255
nitrous, 311

Acid—
œnanthylic, 404
oleic, 400
orthophosphoric, 312
oxalic, 282
palmitic, 404
paratartaric, 285
pelargonic, 404
pentathionic, 307
perchloric, 262
phenic, 391
phosphomolybdic, 426, 427
phosphoric, 22, 293, 312
dilute, 293
glacial, 294
phosphorous, 312
phthalic, 299
picric, 394
pimaric, 410
pinic, 410
polygallic, 371
propionic, 404
prussic, 247
pyrogallic, 319
pyroligneous, 365
pyrophosphoric, 311, 312, 313
racemic, 285
rheic, 300
rhubarbaric, 300
rutic, 404
saccharic, 365
salicylous, 390
sarcolactic, 309
silicic, 314
stannic, 215
stearic, 400, 404
succinic, 315, 407
sulphethylic, 374
sulphindigotic, 258
sulphindylic, 258
sulphocarbolic, 392
sulphocyanic, 316
sulphophenic, 392
sulphovinic, 374
sulphuric, 275
sulphuric, aromatic, 276
dilute, 276
sulphurous, 272
sulphydric, 269
sylvic, 410
tannic, 316
tartaric, 284, 315
tetrathionic, 307
tiglic, 402

Acid—
trinitrocarbolic, 392
trithionic, 307
uric, 320
valerianic, 320, 404
Acid carbonate of potassium, 58, 408
carbonate of sodium, 69
salts, 61, 269
solution of arsenic, 145
tartrate of potassium, 52, 65
tartrate of sodium, 66
Acidimetry, 265
Acids, analytical detection of, 336
antidotes to, 237
definition of, 235
of chlorine, 262
quantitative estimation of, 443
volumetric estimation of official, 445
Acidulous radicals, formulæ and quantivalence of, 55, 104, 236, 237
radicals, qualitative detection of, 323
radicals, quantitative estimation of salts of, 514
radicals, tables to aid in the detection of, 325, 326
Acidum, aceticum, 266
aceticum, impurities in, 541
aceticum dilutum, 266
aceticum glaciale, 266
aceticum glaciale, impurities in, 541
arseniosum, 144
benzoicum, 298
boracicum, impurities in, 541
carbolicum, 392
carbolicum impurum, 392
chromicum, 211
citricum, 289
citricum, impurities in, 541
gallicum, 318
gallicum, impurities in, 541
hydrochloricum, 26, 239
hydrochloricum, impurities in, 541
hydrochloricum dilutum, 239
hydrocyanicum dilutum, 239
hydrocyanicum dilutum, impurities in, 541
lacticum, 309
nitricum, 255
Acidum—
nitricum, impurities in, 541
nitricum dilutum, 255
nitro-hydrochloricum dilutum, 255
nitro-muriaticum, 255
oxalicum, 282
oxalicum, impurities in, 541
phosphoricum dilutum, 293
phosphoricum dilutum, impurities in, 541
sulphuricum, 276
sulphuricum, impurities in, 542
sulphuricum aromaticum, 276
sulphuricum dilutum, 276
sulphurosum, 273
sulphurosum, impurities in 542
tannicum, 317
tannicum, impurities in, 542
tartaricum, 285
tartaricum, impurities in, 542
valerianicum, 322
Aconiti folia, 349
radix, 349
Aconitia, 349
impurities in, 542
Aconitic acid, 289
Aconitina, 349
Aconitine, 349
Aconitum napellus, 349
Acrolein, 394
Adeps benzoatus, 401
præparatus, 401
præparatus, impurities in, 542
Ægle marmelos, 318
Aërated bread, 362
water, 71
Æther, 376
fortior, 378
impurities in, 542
purus, 378
purus, impurities in, 542
Affinity, chemical, 34
Agate, 314
Air, composition, 24
influence of animals and plants on, 18
nitrogen in the, 23
oxygen in the, 15
relative weight of the, 24
weight of 1 cubic cent., 470
weight of 100 cub. inch, 470
Alabaster, 90

Albumen, 395
detection of in urine, 429
vegetable, 398
Albumen ovi, 395
Albumenoid substances, 395
Alchemy, 13
Alcohol, 372
absolute, 374, 449
amylic, 389, 449
and allied bodies, 372 *et seq.*
benzylic, 413
butylic, 322
cinnamic, 413
dilutum, 373
ethylic, 373
fortius, 373
from sugar, 362
glyceric, 394
in 100 parts of spirits of different densities, Table showing the proportion of, 550
methylic, 383
phenic, 391
quantitative estimation of, 536
radicals, 382
real, 374
test for impurities in, 542
test for purity of, 375, 487
Alcohol amylicum, 389
amylicum, impurities in, 542
Alcoholates of chloral, 389
Alcohols, 381
Alcohometer, 466
Aldehyd, 375
benzoic, 299
euodic, 408
lauric, 408
rutic, 408
Aldehyds, 382
Ale, 357
Alexandrian senna, 366
Algaroth's powder, 156
Alizarin, 415
Alkalies, analytical separation of the, 85
antidotes to, 237
quantitative estimation of the, 478
Alkalimetry, 482
Alkaline carbonates, volumetric estimation of the, 478
earths, 108
solution of arsenic, 144
Alkaloids, 338
antidotes to the, 340
distinguished, 339
nomenclature of, 339
poisonous, examination for, 423 *et seq.*
Alkanet, 415
Alkanna tinctoria, 415
Allium, 393
Allotropic bodies, 258
Allotropy, 258
Alloxan, 320
Alloy, 172
Alloys, analysis of, 334
Allyl, 393
sulphide of, 393
sulphocyanate of, 394
Almond-oil, 402, 403
Almonds, oil of bitter, 366, 391
oil of bitter, test for nitrobenzol in, 299
Aloe barbadensis, 393
socotrina, 393
Aloins, 393
Althæa, 310
Alum cake, 116
Alum, 116
chrome-, 116
dried, 117
-flour, 116
iron-, 117
potash-, 116
roche or rock, 117
soda-, 116
Alumen, 116
impurities in, 542
exsiccatum, 117
Alumina, 117
Aluminium, 115, 506
analytical reactions of, 117
and ammonium, sulphate of, 106
and sodium, double chloride of, 116
bronze, 116
derivation of word, 29
detection of in presence of iron and zinc, 139
hydrate of, 117
oxide of, 117
quantitative estimation of, 501
separation of from chromium and iron, 213

Aluminium—
silicate of, 116
sulphate of, 116
Amalgam, 172
ammonium, 76
Amber, 315
oil of, 315
American senna, 367
turpentine, 408
Amianth, 314
Amido-chloride of mercury, 181
Amines, 339
Ammonia, 76
fetid spirit of, 79
gas, composition of, 77
preparation of, 77
solution of, 77
volcanic, 76
volumetric estimation of solutions of, 478
Ammoniacal liquor, 76
salts, sources of, 76
Ammoniacum, 412
Ammoniated mercury, 181
varieties of, 181
Ammoniæ (*vide Ammonii*)
Ammonii acetatis liquor, 78
aromaticus, spiritus, 79
benzoas, 79, 299
benzoas, impurities in, 498
bromidum, 80
carbonas, 78
carbonas, impurities in, 542
chloridum, 76
chloridum, impurities in, 542
citratis, liquor, 79
fœtidus, spiritus, 79
fortior, liquor, 77
iodidum, 80
liquor, 77
nitras, 257
nitras, impurities in, 542
phosphas, 79
sulphas, 76
Ammonio-chloride of mercury, 181
-citrate of iron, 130
-ferric sulphate, 117
-magnesian phosphate, 103, 294
-nitrate of silver, 153, 182
-sulphate of copper, 153, 182
-sulphate of magnesium, 481
-tartrate of iron, 130
Ammonium, 75
acetate of, 78
-amalgam, 76
analytical reactions of, 82
and magnesium, phosphate of, 103
and magnesium, arseniate of, 103
and platinum, double chloride of, 88, 220
arseniate, 146
bicarbonate, 78
benzoate of, 79, 299
bromide of, 80
carbamate, 78
carbonate of, 78
carbonate, solution of, 79
chloride of, 76
citrate of, 79
cyanate of, 301
derivation of word, 28
derivatives, 182
hydrate of, 77
nitrate, 257
oxalate of, 80
phosphate of, 79
potassium, and sodium, separation of, 85
quantitative estimation of, 502
salts, source of, 75
salts, volatility of, 84
sulphate, 76
sulphide of, 81
sulphydrate of, 80
tartrate of, 84
volumetric estimation of carbonate of, 478
Amorphous, meaning of, 160
phosphorus, 293
Amygdala amara, 365, 403
dulcis, 365, 403
Amygdalin, 365
Amyl, 381
acetate of, 389
valerianate of, 389
Amylaceous substances, 355
Amylamine, 339
Amylic alcohol, 289, 449
Amylum, 355
impurities in, 542
Analogies between chlorine, bromine, and iodine, 244
of sodium and potassium salts, 73

Analogy of salts, 73
Analysis, 84
aided by sifting, 330
blowpipe, 331
gas-, 319, 336
gravimetric, 446, 497
meaning of word, 53
organic, 525
practical, 84
proximate, 525
qualitative, 84
quantitative, 445
spectrum-, 336
and synthesis, 53
systematic, for the detection and separation of the metals, 85, 106, 139, 162, 165, 195, 333
ultimate, 525
volumetric, 446, 475
of gases and vapors, 336
of insoluble salts, 334 *et seq.*
of medicines, 336
of salts, 323
of substances having unknown properties, 335
Analytical chemists, 14, note.
detection of the acidulous radicals of salts soluble in water, 323
memoranda, 230, 237
Analytical reactions of
acetates, 267
albumen, 395
alcohol, 374
aldehyd, 376
aluminium, 117
ammonium, 82
amygdalin, 366
antimony, 159, 419
arsenicum, 148, 419
atropia, 350
barium, 88
beberia, 350
benzoates, 300
berberia, 351
bile, 401
bismuth, 225
borates, 297
bromides, 242
brucine, 348
cadmium, 222
caffeia, 353
calcium, 97
Analytical reactions of—
carbonates, 280
chloral hydrate, 387
chlorates, 262
chlorides, 240, 421
chromates, 211
chromium, 212
citrates, 291
cobalt, 207
conia, 352
copper, 168, 419
cyanides, 250
ferric salts, 137
ferridcyanides, 304
ferrocyanides, 303
ferrous salts, 136
fluorides, 304
formates, 301
gallic acid, 319
glucosides, 365
glycerine, 394
gold, 218
guaiacin, 369
hippurates, 302
hydrocyanic acid, 250, 421
hypochlorites, 260
hypophosphites, 306
hyposulphites, 308
iodides, 245
iron, 136
lactates, 309
lead, 189, 419
lithates, 320
lithium, 201
magnesium, 102
malates, 309
manganese, 204
meconates, 310, 424
mercuric salts, 180, 419
mercurous salts, 180, 183
metaphosphates, 310
morphia, 341, 424
nickel, 209
nicotia, 352
nitrates, 256
nitrites, 311
nitrous ether, 379
oxalates, 282, 421
phosphates, 294
phosphites, 313
platinum, 219
potassium, 64
pyrogallic acid, 319
pyrophosphates, 313

Analytical reactions of—
quinia, 344
salicin, 320
silicates, 315
silver, 193
sodium, 74
starch, 356
strontium, 202
strychnia, 347, 423
succinates, 316
sugar, 361
sulphates, 277
sulphides, 271
sulphites, 273
sulphocyanates, 316
sulphuric acid, 411
tannic acid, 317
tartrates, 287
theia, 353
tin, 215, 216
urates, 320
veratria, 254
zinc, 114
Anchusa tinctoria, 415
Anchusin, 415
Aneroid barometer, 447
Anethene, 406
Angelic acid, 406
Angelic powder, 156
Angustura, 355
Angusturin, 355
Anhydride, acetic, 266
antimonic, 156
antimonious, 156
boracic, 297
carbonic, 278
chlorochromic, 212
chromic, 211
nitric, 252, 255
nitrous, 257
phosphoric, 22, 310
silicic, 315
sulphuric, 276
sulphurous, 272
Anhydrides, 70
Anhydrous bodies, 70
nitric acid, 255
perchloride of iron, 125
sulphate of copper, 168
Aniline, 392, 417
colors, 417
Animal charcoal, 95
decolorizing power of, 95
Animal—
rouge, 416
Animals and plants, complementary action of air, 18
Anise, 406
Anise-fruit, 406
Aniseed-oil, 406
Annatto, 415
Anthemidis flores, 355, 406
Anthemis nobilis, 406
Anthracen, 393
Anthracite, 213
Antichlor, 273
Antidotes to acids, 237
alkalies, 237
alkaloids, 340
antimony, 161
arsenic, 153
barium, 88
carbolic acid, 392
copper, 170
cyanides, 250
hydrochloric acid, 241
hydrocyanic acid, 251
lead, 190
mercury, 184
nitric acid, 259
oxalic acid, 283
silver, 195
sulphuric acid, 278
tin, 216
zinc, 115
Antimonial wine, 157
Antimoniate of sodium, 74
potassium, 74
Antimonic anhydride, 157
chloride, 156
oxide, 157
Antimonii chloridi, liquor, 155, 509
oxidum, 156
oxidum, impurities in, 542
et potassæ tartras, 157
oxysulphuretum, 158
sulphuretum, 158
Antimonious anhydride, 156
chloride, 155
oxide, 156
oxychloride, 156
Antimonium nigrum, 155
nigrum, impurities in, 542
sulphuratum, 157
tartaratum, 157, 284
tartaratum, quantitative estimation of antimony in, 509

Antimoniuretted hydrogen, 160
Antimony, 143, 155, 284, 451, 509
analytical reactions of, 159
and arsenic, analytical separation of, 162
from arsenic, to distinguish, 151
and potassium, tartrate of, 157, 284
antidote to, 161
black, 155
butter of, 155
chloride of, 155
crude, 155
derivation of word, 29
hydride of, 160
in organic mixtures, detection of, 419
oxide of, 156
oxychloride of, 156
oxysulphide of, 157
pentachloride of, 157
potassio-tartrate of, 157
quantitative estimation of, 509
solution of chloride of, 155, 509
sulphide of, 155, 159
sulphur salts of, 158
sulphurated, 157
tartarated, 157
Antiseptic, 392
Antozone, 211, 245, 437
Apatite, 295
Apomorphia, 342
Aporetine, 300
Apparatus, ix.
for experiments, ix.
for volumetric analysis, 475
list of, ix.
Apple, essence of, 390
oil, 390
Aqua, 108
Aqua acidi carbolici, 391
acidi carbonici, 278
ammoniæ, 77
ammoniæ fortior, 77
amygdalæ amaræ, 366
anethi, 405
aurantii floris, 405, 406
aurantii floris, impurities in, 542
camphoræ, 409
chlorinii, 25, 240
creasoti, 392
Aqua—
destillata, 109
destillata, impurities in, 542
fortis, 255
laurocerasi, 366
menthæ piperitæ, 405
viridis, 405
regia, 162, 255
rosæ, 405, 407
Arabin, 97
Arachidic acid, 404
Arbor Dianæ, 194
Arbutin, 318, 366
Arctostaphylos uva ursi, 366
Archil, 416
Are, 456
Argal, 284
Argent-ammon-ammonium, nitrate of, 182
Argenti cyanidum, 194
nitras, 193
nitras, impurities in, 542
oxidum, 193
oxidum, impurities in, 542
Argentic chloride, sulphide, etc., *vide* salts of silver.
Argentiferous galena, 191
Argentum, 24, 192
Argentum purificatum, 192
purificatum, impurities in, 542
Argol, 284
Armenian bole, 415
Armoraciæ radix, 406
Arnatto, 415
Arnica, 411
Arnicæ radix, 411
Arnicin, 411
Arnotto, 450
Arrowroot, 357
Arseniates, 146
Arseniate of ammonium, 146
barium, 89, 153
calcium, 153
copper, 153
iron, 147, 492
magnesium and ammonium, 103
silver, 153
sodium, 146
volumetric estimation of, 489
zinc, 153
Arsenic acid, 146

Arsenic—
and arsenical solutions, volumetric estimation of official, 489
anhydride, 146
odor of, 146
in carbonate of potassium, solution of, 144
in hydrochloric acid, solution of, 145
white, 144
Arsenical ores, 144
sulphur, 152
Arsenici iodidum, 143
Arsenicum, 143
analytical reactions of, 148
antidotes to, 153
and antimony, analytical separation of, 162
bromide, 143
chloride, 143
derivation of word, 29
detection of in metallic copper, 149
detection of, in organic mixtures, 419
Fleitmann's test for, 150
from antimony, to distinguish, 151
hydride of, 149
iodide of, 143
Marsh's test for, 149
red native sulphide of, 144
quantitative estimation of, 489, 508
Reinsch's test for, 148
sources of, 144
sulphide of, 144, 151
yellow native sulphide of, 144
Arsenide of cobalt, 207
Arsenio-sulphide of iron, 144
of nickel, 208
Arsenious acid, 144
anhydride, 144
Arsenites, 144
Arsenite of copper, 153
potassium, 144
silver, 153
sodium, 144
Arsenuretted hydrogen, 149
Artemisia, 370
Art of chemistry, 13
Artificial alkaloids, 339
gastric juice, 399
Asbestos, 314
Ash, 86
black-, 73
bone-, 94
soda-, 73
Ashes, analysis of (mixed solids), 331
Asparegin, 310
Assafœtida, 412
-ate, meaning of, 60
Atmosphere, carbonic acid in, 279
composition of, 24
nitrogen in, 23
oxygen in, 15, 24
Atmospheric pressure, measurement of, 446
Atom, definition of, 50
weights, definition of, 45
Atomic proportions, 173, 176
theory, 43
weights, 43
Atomicity, 45
Atoms, 43, 44
quantivalence of, 47
definition of, 48
Atropa belladonna, 350
Atropia, 350
impurities in, 542
Atropiæ, sulphas, 350
sulphas, impurities in, 542
Atropine, 350
Attar of rose, 407
Aurantii cortex, 355, 406
amari cortex, 406
dulcis cortex, 406
flores, 406
Auric chloride, 217
sulphide, 217
Aurum, 31
Avenæ farina, 356
Avignon grains, 414
Avogadro's and Ampère's law, 44, 46

Bael fruit, 318
Baking-powder, 362
Balance, 453
Balloons, coal-gas for, 21
hydrogen for, 21
Balm-of-Gilead fir, 412
Balsam, Canada, 412
copaiva, 411
fir, 408
Peru, 413

Balsam—
Storax, 413
Tolu, 413
Balsamodendron myrrha, 412
Balsamum Peruvianum, 413
Peruvianum, impurities in, 542
Tolutanum, 413
Balsams, 413
Barbaloin, 393
Baric chloride, nitrate, etc., *vide* salts of barium.
Barii carbonas, 87
Barium, 87
acetonitrate of, 108
analytical reactions of, 88
and calcium, separation of, from magnesium, 106
antidotes to, 88
arseniate of, 89
carbonate, 89
native, 87
carbonate of, 87
chloride of, 87
chromate of, 88
derivation of word, 28
detection of, in presence of calcium and magnesium, 85, 106
hydrate of, 88
nitrate of, 87
peroxide of, 88
phosphate of, 89, 295
oxalate of, 89, 282
quantitative estimation, 502
salts, antidote to, 88
silico-fluoride of, 89
sulphate of, 88
sulphide of, 88
sulphite, 274
Barley-sugar, 364
Barometer, 446
Baryta, 88
-water, 88
Basalt, 116
Base, meaning of, 237
organic, 338
Bassorin, 97, 358
Bastard saffron, 415
Bauxite, 116
Basylous radicals, 104
Bay rum, 372
Bay-salt, 67
Bearberry, 318
Beaver, 411
Beberiæ sulphas, 350
sulphas, impurities in, 542
Beberia or beberine, 350
Beer, 257
Beetroot, 361
Belæ fructus, 318
Belladonnæ folia, 350
radix, 350
Bell-metal, 213
Bend glass tubes, to, 16
Benzine-collis, 391
Benzoate of ammonium, 79, 299
Benzoated lard, 401
Benzoates, 298
Benzoic acid, 298, 449, 451
aldehyde, 299
glycocine, 302
Benzoin, 298, 413
Benzoinum, 298, 413
Benzol, 391, 449
Benzoyl, hydrate of, 299
hydride of, 366, 413
Benzyl, benzoate of, 413
cinnamate of, 413
Benzylic alcohol, 413
Berberia or berberine, 351
Bergamot oil, 406
Berlin blue, 416
red, 415
Berryllium, 507
Bi-, the prefix, 59
Bibasic, *vide* Dibasic.
Bibulous paper, 93
Bicarbonate of ammonium, 78
of potassium, 58, 286, 290, 478
of sodium, 69, 286, 290, 478
Bichromate of potassium, 210
Bile, 401
detection of, in urine, 430
test for presence of, 401
Biliary calculi, 441
Bismuth, 222. 451, 467, 510
and ammonium, solution of citrate of, 225
analytical reactions of, 225
carbonate of, 224
citrate of, 225
derivation of word, 31
-lozenge, 224
nitrate of, 223
quantitative estimation of, 510
-salts, composition of, 225

Bismuth—
subcarconate or oxycarbonate, 224
subnitrate or oxynitrate of, 223
subnitrate of, 223
sulphate of, 225
sulphide of, 226
Bismuthi carbonas, 224
carbonas, estimation of bismuth in, 510
carbonas, impurities in, 542
subcarbonas, 224
subnitras, 223
Bismuthum, 223
purificatum, 223
purificatum, impurities in, 543
Bisulphide of carbon, 382
Bitter almonds, oil of, 366, 391
cassava, 356
principles, 355
sweet, 353
Bituminous coal, 213
Bivalence, 47
Bivalent radicals, 47, 105, 108
Bixa orellana, 415
Bixin, 415
Black antimony, 155
-ash, 73
-band, 119
bone-, 94
coloring-matters, 414
dyes, 417
flux, 145
hydrate of iron, 133
ink, 318
-lead, 26
oxide of copper, 169
oxide of iron, 134
oxide of manganese, 203
oxide of mercury, 179
pepper, 353
Black oak, 415
Bladder-green, 416
Blanc de Perle, 224
Bleaching by chlorine, 25
-liquor, 97
-powder, 96
Blende, 109
Block tin, 213
Blood, 396, 437
detection of in organic matter, 437
Blood—
hydrocyanic acid in the, 251
Blood-root, 353
Bloodroot vinegar, 265
Blood-stains, 437
Blowpipe-analysis, 331
-flame, 331
Blue coloring-matters, 416
copperas, 121
indigo, 258
ointment, 171
pill, 171
Prussian, 137, 303
stone, 168
Turnbull's, 304
vitriol, 121, 168
Boiling-points of various substances, 449, 450
"Bonds" (Frankland), 114
Bone-ash, 94
-black, 94
-earth, 292
Bones, composition of, 292
Boracic acid, 296
anhydride, 296
Borates, 296
analytical reactions of, 297
Borax, 297
volumetric estimation of, 480
Borax bead, 205
Bordeaux turpentine, 408
Borneène, 409
Borneo camphor, 409
Boron, 297
chloride of, 297
derivation of word, 30
flame, 298
fluoride of, 297
Borotartrate of potassium, 297
Bos taurus, 401
Bourdon barometer, 447
Brandy, 376
Brass, 109
Brazil wood, 415
Bread, 356, 362
aërated, 362
making, 362
Brezilin, 415
Bright's disease, 430
Britannia metal, 155, 185, 214
British gum, 357
Bromal, 389
alcoholates of, 389

Bromal—
hydrate of, 389
Bromate of potassium, 63
Bromates, 263
Bromic acid, 63, 263
Bromide of ammonium, 242
arsenicum, 143
iron, 124
potassium, 63, 241
potassium, volumetrical estimation of, 487
of silver, 194
of sulphur, 272
Bromides, 241
analytical reactions of, 242
quantitative analysis of, 487, 515
separation of, from chlorides and iodides, 246
Bromine, 241
analytical separation of, 242
derivation of word, 39
its analogy to chlorine and iodine, 243
solution of, 242
volumetric estimation of free, 515
Brominium, 241
Bromum, 241
impurities in, 543
Bronze, 214
aluminium, 116
coinage, 167
Bronzing-powder, 216
Broom-tops, 353
Brown coloring-matters, 417
hæmatite, 119
rosin, 410
sugar, 361
Brucia, 248
Brucine, 248
Brunswick green, 152
Buchu folia, 355
Buchu, oil of, 406
Buckthorn-green, 416
-juice, 367
Bunsen gas-burners, 21
Burette, Mohr's, 476
Burgundy pitch, 411
Burners, gas-, 17, 21
Burnett's disinfecting fluid, 111
Burnt sugar, 361
ochre, 415
umber, 417
Butter, 398
of antimony, 155
of orris, 407
Butyl, 322
sulphocyanate, 382
Butylic alcohol, 322
Butyrates, 322
Butyric acid, 322, 404
By-products, 176

Cacao oil, 402
Cadmii iodidum, 221
iodidum, impurities in, 543
Cadmium, 221
analytical reactions of, 222
carbonate, 222
derivation of word, 31
hydrate of, 222
iodide of, 221
nitrate, 222
sulphate, 222
sulphide of, 222
Cæsalpinia braziliensis, 415
Cæsium, 551
Caffeia, 353
Cajuput oil, 406
Caking coal, 213
Calabar bean, 353
Calamine, 109
Calcic, sulphate, phosphate, etc., *vide* salts of calcium.
Calcii carbonas præcipitata, 92
carbonas præcipitata, impurities in, 543
chloratæ, liquor, 97
chloridum, 90
chloridum, impurities in, 543
hydras, 92
phosphas, 94
phosphas, impurities in, 543
saccharatus, liquor, 92
Calcined magnesia, 102
Calcium, 90
analytical reactions of, 97
and barium, separation from magnesium, 106
carbonate of, 92
prepared, 94
chloride of, 90
chromate of, 98
citrate of, 291
derivation of word, 29
-flame, 98
fluoride of, 90

Calcium—
fluoride of, in bones, 95
gummate of, 97
hydrate of, 91
hypochlorite of, 96
hypophosphite of, 305
hyposulphite of, 270
in presence of barium and magnesium, detection of, 106
oxalate of, 98, 282
oxide of, 91
phosphate of, 90, 94
polysulphide of, 270
quantitative estimation of, 504
silicate of, 90, 314
sulphate of, 90, 97, 271
sulphite of, 274
superphosphate of, 292
tartrate of, 287
Calc-spar, 90
Calculi, urinary, 439
urinary, examination of, 439
Calomel, 171, 176
test for corrosive sublimate in, 178
tests for constituents of, 178
Calumbæ radix, 351
Calx, 91
impurities in, 543
chlorinata, 96
chlorata, 96
chlorata, impurities in, 543
Cambogia, 412
impurities in, 543
Camphor-laurel, 409
mixture, 409
oil, 409
water, 409
Camphora, 409
impurities in, 543
officinarum, 409
Camphors, 409
Camwood, 415
Canada balsam, 412
Canadian turpentine, 408
Canarium commune, 412
Candle-flame, composition of, 21
Canellæ albæ cortex, 355
Cane-sugar, 361
Canna, 357
Cannabin, 411
Cannabis indica, 41
Cantharides, 409
Cantharidic acid, 409
Cantharidin, 409
Cantharis, 409
Caoutchouc, 413
Capacity unit, 455
Capillary, 448
Caproate of glyceryl, 402
Caproic acid, 402, 404
Caproyl, 381
Caprylate of glyceryl, 402
Caprylic acid, 402, 404
Capsici fructus, 351
Capsicia, 351
Capsicine, 351
Capsicum, 351
fruit, resin of, 349
oil of, 351
Caramel, 364
Caraway oil, 407
Carbamate of ammonium, 78
Carbazotic acid, 392
Carbolic acid, 391, 449, 451
acid, antidote to, 392
Carbon, 26
bisulphite of, 382
combustion of, 26
derivation of word, 28
quantitative estimation of, in organic compounds, 525 *et seq.*
Carbo animalis, 95
animalis purificatus, 95
animalis purificatus, impurities in, 543
ligni, 95
ligni, impurities in, 499
Carbonate of ammonium, 78
ammonium, solution of, 78
barium, 89
bismuth, 225
cadmium, 222
calcium, 90, 92
prepared, 94
iron, 122, 492
iron, saccharated, 123, 492
lead, 185
lithium, 201
magnesium, 100
potassium, 52, 478
potassium acid, 58, 478
sodium, 68, 73, 279, 478
sodium, acid, 69, 478
sodium, manufacture of, 86, 279

Carbonate of—
strontium, 202
zinc, 109, 112
Carbonates, 278
acidulous radical in, 278
analytical reactions of, 280
gravimetric estimation of, 519
volumetric estimation of alkaline, 478
Carbonic acid, 27, 279
anhydride, 279
generation of, 59
Carbonic acid gas, solubility of, in water, 71
oxide, 283, 303
Carbonization, 86
Cardamom oil, 406
Cardamomum, 406
Carmine, 300
Carminic acid, 300
Carnallite, 54
Carrageen moss, 358
Carrotin, 415
Carthamin, 416
Carthamus tinctorius, 415
Carvene, 407
Carum, 407
Carvol, 407
Caryophyllin, 407
Cascarilla oil, 407
Cascarilla cortex, 407
Casein, 397
vegetable, 398
Cassia marilandica, 367
Cassia oil, 407
Cassiæ pulpa, 361
Castilloa elastica, 413
Cast-iron, 119, 451
Castor, 411
Castor fiber, 411
Castor oil, 403
Castoreum, 411
Castorin, 411
Catechu, 318
Catechu pallidum, 318
pallidum, impurities in, 543
Cathartic acid, 366
Cathartogenic acid, 367
Caustic, 193
lime, 91
lunar, 191
potash, 53
soda, 68
Cayenne pepper, 351
Cedra oil, 406
Celestine, 202
Cellulin, 359
Cellulose, 359
Celsius's thermometer, 448
Cements, 314
Centiare, 455
Centigrade thermometer, 448
Cephalis ipecacuanha, 352
Cerasin, 358
Ceratum plumbi subacetatis, vide *Unguentum.*
zinci carbonatis, 112
Cera alba, 402
alba, impurities in, 543
flava, 402
flava, impurities in, 543
Cerebrin, 396
Cerite, 203
Cervisiæ fermentum, 372
Cerii oxalas, 203
oxalas, impurities in, 543
Cerium, 203
derivation of word, 30
oxalate of, 203
Ceroleine, 402
Cerotic acid, 402
Cetaceum, 402
impurities in, 543
Cetene, 402
Cetraria, 300
Cetraric acid, 300
Cetyl, hydrate of, 402
palmitate of, 402
Cevadilla, 354
Chalcedony, 314
Chalk, 94
precipitated, 92
prepared, 94
-stones, 441
Chalybeate water, 119
Chameleon, mineral, 205
Chamomile oil, 406
Char, 86
Charcoal, 26
animal, 94
animal, decolorizing power of, 94
wood, 95
Cheese, 397
Chemical action, definition of, 34
Chemical action by symbols, illustration of, 37, 40
affinity, 34

Chemical—
combination, 34
combination by weight, laws of, 40 *et seq.*
combination by volume, laws of, 44 *et seq.*
combination different from mechanical, 33, 35
combination, laws of, 40, 171, 257, 445, 497
compound, definition of, 48
compound, 27
diagram, 49, 54
equation, 49, 54
force, 36
force, conditions for the manifestation of, 36
formula, definition of, 49
formulæ, 37, 38, 39
notation, 37, 38, 39
preparations of the Pharmacopœias, 444
philosophy, principles of, 33 *et seq.*
symbol, definition of, 49
symbols, 37, 38, 39
toxicology, 418
Chemist and Druggist, 14
Chemicals, 14
list of, xi.
Chemism, 34
Chemistry, art of, 13
and physics, differences between, 43
definition of, 48
derivation of the word, 13
inorganic, 338
object of, 14, 43
organic, 338
science of, 13
Chemists, analytical, 14
manufacturing, 14
pharmaceutical, 14
Chenopodium, 408
Cherry-laurel water, 366
Cherry-tree gum, 358
Chestnut-brown, 417
Chian turpentine, 408
Chili saltpetre, 252
Chimaphila, 355, 366
Chimaphila umbellata, 366
Chinese red, 415
yellow, 414
Chirata, 355, 366
Chiratin, 367
Chloral, 386
Chloral hydrate, 386
alcoholates of, 389
Chlorate of potassium, 261
potassium, preparation of oxygen from, 16
Chlorates, 261
analytical reactions of, 262
Chloric acid, 260
Chloride of ammonium, 76
antimony, 155
arsenicum, 143
barium, 87
boron, 297
calcium, 90
calcium, removal of iron from, 90
chromium, 210
gold, 218
iron, 125
lead, 189
lime, 96
magnesium, 99
manganese, 204
mercuric ammonium, 182
mercurous ammonium, 182
mercury, 176
platinum, 219
platinum and ammonium, 83, 503
platinum and lithium, 201
platinum and potassium, 65
silicon, 315
silver, 192
sulphur, 272
tin, 214
solution of, 214
zinc, 111
Chlorides, 238
separation of, from bromides and iodides, 246
tests for, 240
estimation of, 514
Chlorinated lime, 96
volumetric estimation of, 495
soda, solution of, 72
volumetric estimation of, 495
Chlorine, 24, 239, 514
acids, 262
as a disinfectant, 25
bleaching by, 25
collection of, 24

Chlorine—
derivation of word, 28
its analogy to bromine and iodine, 243, 246
preparation of, 24
properties of, 24
relative weight of, 25
solubility in water, 25
the active agent in bleaching-powder, 96
volumetric estimation of, 495
water, 24, 240
Chlorochromic anhydride, 212
Chloroform, 385, 450
impurities in, 543
Chlorophyll, 416, 443
Chocolate, 402
Cholalic acid, 401
Cholate of sodium, 401
Cholesterin, 396, 441
Chondrin, 398
Chondrus crispus, 358
Chromate of barium, 88
calcium, 98
lead, 189
mercury, 212
potassium and ammonium, 89
potassium, standard solution of red, 491
silver, 187
Chromates, 211
analytical reactions of, 211
of potassium, 88, 106, 210
Chrome-alum, 117
-ironstone, 210
-red, 189
-yellow, 189
Chromic acid, 211
anhydride, 211
hydrate, 212
salts, 210
Chromium, 210
analytical reactions of, 212
chloride of, 211
derivation of word, 30
separation of, from aluminium and iron, 213
sulphate of, 211
Chromous salts, 210
Chromule, 416
Chrysophanic acid, 300
Chrysammic acid, 393
Chrysorhamnin, 415
Cicutine, 351
Cinchonæ flavæ cortex, 343
pallidæ cortex, 343
rubræ cortex, 343
Cinchonia, 346
Cinchoniæ sulphas, 346
Cinchonicia, 346
Cinchonicine, 346
Cinchonidia, 346
Cinchonidine, 346
Cinchonine, 346
Cinnabar, 170
Cinnamein, 413
Cinnamic acid, 413
alcohol, 413
Cinnamomi cortex, 407
Cinnamon oil, 407
Cinnamyl, hydride of, 413
Cissampelia, 351
Cissampeline, 351
Cissampelos pareira, 351
Citrate of ammonium, 79
calcium, 291
iron, 130
iron and strychnia, 130
iron and quinine, 131, 344, 582
lithium, 200
magnesium, 289
nicotia, 352
potassium, 60
volumetric estimation of, 481
quinine, 344
silver, 291
Citrates, 60, 289
analytical reactions of, 290
volumetric estimation of, 478, 481
Citric acid, 289
action of heat on, 291
saturating power of, 290, 549
Citronella oil, 407
Citronellol, 407
Citro-tartarate of sodium, 73
Classification of elements, 86, 105, 107, 230
Claviceps purpurea, 411
Clay, 116, 214
ironstone, 119
Cloves, oil of, 407
Club-moss, 403
Coal, 213
products of, 382
-gas, 382

Coal-gas—
for balloons, 21
-tar colors, 417
Cobalt, 207
analytical reactions of, 207
arsenide of, 207
blue, 416
derivation of word, 30
-glance, 207
hydrate of, 207
separation of, from nickel, 209
sulphate of, 207
sulphide of, 207
Cobaltic ultramarine, 416
Cobalticyanide of potasium, 208
of nickel, 209
Cobalticyanides, 208
Coccus, 300
Ilicis, 158
Cochineal, 300
Cocoa, 402
Cocoa-butter, 402
Cocoa nibs, 402
Cocoa-nut, 402
Cocoa-nut oil, 402
Cocos nucifera, 402
Codamine, 341
Codeia, 342
Cod-liver oil, 402
Coinage, copper, 167, 467
gold, 217, 467
silver, 191, 467
Coke, 26
Colchici cormus, 354
semina, 354
Colchicia, 354
Colchicine, 354
Colchicum vinegar, 265
Colcothar, 415
Collection of gases, 16, 17
Collin, 537
Collodion, 360
Collodium, 360
flexile, 360
Colloid bodies, 537
Colocynthidis pulpa, 367
Colocynthin, 367
Colopholic acid, 410
Colophonic acid, 410
hydrate, 410
Colophonine, 411
Colophony, 410
Coloring-matters, 414
Combination, chemical, 38, 40
by volume, 44
Combining proportions, 42, 173, 257, 445, 497
Combustible, 21
Combustion, 21
analysis for carbon and hydrogen, 525 *et seq.*
for nitrogen, 525, 527
definition of, 48
supporters of, 21
Composition of atmosphere, 24
bismuth salts, 225
oils and fats, 400
Compound, chemical, 27
different from mechanical, 32
definition of, 50
Compounds, 13, 32
of the elements, 51
Condensation, 108
Condenser, 108
Condensing tub, 108
worm, 108
Condy's disinfecting fluids, 64, 205
Confections, 442
Conia, conine, or conicine, 351
Conii folia, 352
fructus, 352
Conium maculatum, 352
Constant proportions, law of, 42
Construction of formulæ, 36, 47, 54, 360
Constitution of alkaloids, 338
of salts, 44, 104, 235, 253, 267
of visible matter, 33
Convolvulin, 369
Convolvulinol, 369
Convolvulus scammonia, 371
Conylia, 352
Copaiba, 411
impurities in, 411, 543
Copaiva, 411
oil, 411
Copaivic acid, 411
Copper, 166
acetate of, 168
ammonio-sulphate of, 153, 169, 182
analytical reactions of, 168, 420
antidotes to, 170
arseniate of, 153

Copper—
arsenical, 149
arsenite of, 153
black oxide of, 167
blue, 416
coinage, 167, 467
derivation of word, 29
detection of arsenicum in, 149
foil, 167
hydrate of, 169
iodide of, 245
in organic mixtures, detection of, 420
melting-point of, 416
metallic, 167
oxide of, 167
oxyacetate of, 168
pyrites, 166,
quantitative estimation of, 509
quantivalence of, 167
subacetate of, 168
sulphate of, 168
sulphate of anhydrous, 168
sulphide of, 168
Copperas, blue, 121
green, 121
Coptis trifolia, 351
Coriander oil, 407
Coriandri fructus, 407
Coriandrum, 407
Cork-borers, 16
Correction of the volume of a gas for pressure, 469
for temperature, 469
Corrosive sublimate, 172, 176
test for in calomel, 178
Cotton-wool, 359
Cows' milk, 397
Cream, 397
Cream of tartar, 285
Creasol, 392
Creasote, 392
Creasotum, 392
impurities in, 543
Cresol, 392
Cresylic acid, 392
Creta, 94
præparata, 94
Crocus (mineral), 129
(vegetable), 415
Crocus sativus, 415
Croton oil, 403
Crotonate of glyceryl, 403
Crucibles, 57
Crude antimony, 155
potashes, 54
Crum's test for manganese, 207
Cryolite, 334
Cryptophanic acid, 429
Cryptopia, 341
Crystallization, water of, 70
Crystalloid bodies, 537
Cubeba, 353
Cubeb pepper, 353
Cubebs, oil of, 407
Cubic inches in 1 gallon, 431
Cubic nitre, 252
Cudbear, 416
Cupel, 513
Cupellation, estimation of silver by, 513
Cupr-diammon-diammonium, sulphate of, 182
Cupri subacetas, 168
sulphas, 168
sulphas, impurities in, 543
Cupric arsenite, 153, 169
compounds, 168
ferrocyanide, 169
hydrate, 169
oxide, 167
sulphate, 168
sulphide, 168
Cuprous iodide, 168, 246
oxide, 168, 361
Cuprum, 29, 156
ammoniatum, 169
Curcuma longa, 415
Curcumin, 415
Curds, 362, 397
and whey, 362, 397
Cusparieæ cortex, 355
Cusparin, 355
Cusso, 411
Cyanates, 300
Cyanic acid, 300
Cyanide of mercury, 248
nickel, 209
potassium, 248
silver, 194
Cyanides, 247
analytical reactions of metallic, 250
antidote to, 251
double, 248
quantitative estimation of, 486

Cyanogen, 247, 515
Cyanurets, *vide* Cyanides
Cystin, 433

Dalton's atomic theory, 43
Daphne laureola, 411
mezereum, 411,
Daturia or daturine, 350
Dauglish's bread, 362
Davy's safety-lamp, 21
Deadly nightshade, 350
Decantation, 93
Decimal coinage, 455
weights, 454, 457
Decoctions, 442
Decrepitation, 330
Decolorizing power of animal charcoal, 95
Definition of chemical action, 32
a chemical compound, 48
a chemical equation or diagram, 49
a chemical symbol, 49
a gas, 49
a liquid, 49
a mixture, 48
an atom, 48
an element, 48
a solid, 49
atomic weights, 50
chemical force, 48
chemistry, 48
combustion, 48
law of diffusion, 49
molecular weights, 50
quantivalence of atoms, 50
Deflagrating flux, 335
Deflagration, 62
Deliquescence, 73
Density, 464
of vapors, 470
Deodorizers, 25
Deodorizing liquid, 111
Deposits, urinary, 432
Derivation of names of elements, 27 *et seq.*
Derivatives of ammonium, 182
Desiccation, 498, 500, 519
Destructive distillation, 109
Detonation, 62
De Valangin's solution, 145
De Vry's process for estimating the purity of commercial quinine, 529
Dextrine, 357
Dextroracemic acid, 285
Dextrose, 363
Dextrotartaric acid, 285
Diabetic urine, 362, 430, 534
Diagram, chemical, definition of, 49
Diagrams, chemical, 38, 54
Dialysis, 537
Diamines, 339
Diamond, 26
Dibasic acids, 337
Dibasylous radicals, 337
Didymium, 551
Diethylamine, 339
Diethylia, 339
Diffusion, 22
law of, definition of, 49
Digitalin, 367
Digitalinum, 367
Digitaliretin, 368
Digitalis folia, 368
Dill oil, 406
Dinitrocellulin, 359
Dipterocarpus turbinatus, 412
Disinfectant, chlorine as a, 25
Disinfectants, 25
Disinfecting fluid, Burnett's, 111
carbolic acid, 391
Condy's, 64, 205
powder, 96
Distillation, 108
destructive, 109
dry, 109
fractional, 372
Distilled vinegar, 265
Dithionic acid, 307
Dolomite, 99
Donovan's solution, 174
Dorema ammoniacum, 412
Double chloride of aluminium and sodium, 116
cyanides, 248
salts, 65
Dover's powder, 352
Drachm, 460
Draconyl, 413
Dried alum, 117
Drugs, 15
Dry distillation, 109
Drying apparatus, 498, 500, 519
oils, 402
precipitates, 498, 500, 503, 519

Dryobalanops aromatica, 409
Dulcamara, 353
Dyads, 104
Dyers' saffron, 415
Dyeing, 117, 258
  by mordants, 117
Dynamic electricity, production of, 110
Dynamicity, 47

Earth, bone-, 94
Earthenware, 314
Earths, alkaline, 108
Eau de Cologne, 406
Ebonite, 414
Ecballii fructus, 349
"Effervescing citrate of magnesia," 289
  citro-tartrate of sodium, 73
  potash-water, 59, 500
  soda-water, 71
Efflorescence, 73
Egg, white of, 396
  yolk of, 396
Elæometer, 466
Elæoptens, 405
Elaterin, 359
Elaterium, 359
  impurities in, 543
Elder-flower oil, 408
Electricity, production of dynamic, 110
Elementary particles, 33
Element, definition of, 48
Elements, 13, 14, 27
  and their compounds, 51
  classification of, 86, 104, 107, 230
  classification of according to analogy, 86
  classification of according to quantivalence, 104
  etymology of names of, 27
  of medical or pharmaceutical interest, 14
  metallic, 15
  non-metallic, 15
  of pharmaceutical interest, 14
  symbols of, 27, 37
  symbols, atomic values, and weights of the, 551
  symbols of, and derivation of names of, 27 *et seq.*
Elemi, 412
Elm bark, 318
Emetia, 352
Emetine, 382
Empirical formulæ, 373
Emplastra, 411
Emplastrum cerati saponis, 265
  plumbi, 188
  plumbi iodidi, 188
Emulsin, 366, 393
Emulsion, 413
Enemas, 442
English red, 415
  blue, 416
Epsom salt, 100
Equation, chemical, definition of, 49
Equations, 40
Equivalence, 44
Equivalents, 551
Equisetic acid, 295
Ergot, 411
Ergota, 411
Ergotin, 411
Erlangen blue, 416
Erythroretine, 300
Erucic acid, 404
Eseria, 353
Essence of aniseed, 405
  apple, 389
  greengage, 390
  melon, 390
  mirbane, 391
  mulberry, 390
  pineapple, 390
  quince, 390
  peppermint, 406
Essences, 405
Essentia anisi, 405
  menthæ piperitæ, 406
Essential oils, *vide* Oils.
Estimation of weight, 452
Etching, 304
Ethal, 402
Ether, 376
  nitrous, 378
Ethereal salts, 381
  oil, 394
Etherol, 394
Ethers, 381
Ethiops mineral, 182
Ethyl, 374, 380
  acetate of, 374
  butyrate of, 389
  hydrate of, 374

Ethyl—
hydride of, 380
iodide of, 380
nitrite of, 278
œnanthylate of, 390
oxide of, 374
pelargonate of, 390
sebacate of, 390
suberate of, 390
sulphate of, 374
zinc, 380
Ethylamine, 339
Ethylene, 394
Ethylia, 339
Ethylic alcohol, 374
Etymology of names of elements, 28
Eucalyptol, 407
Eucalyptus globulus, 407
Euchlorine, 263
Eudiometry, 336
Eugenic acid, 407
Eugenin, 407
Euodic aldehyd, 408
Euxanthate of magnesium, 415
Evaporation, 58, 86, 498, 500
in vacuo, 500
Everitt's yellow salt, 249
Examinations of the Pharmaceutical Society of Great Britain, 41 (*vide* Prefatory matter).
Expansion on diluting solution of ammonia, 77
Explosions of gases, 20
Extracts, 442
Extractum cannabis, 411
filicis liquidum, 403
Saturni, 187

Face-rouge, 300, 416
Fæces, 429
Fahrenheit's thermometer, 448
Farina tritici, 356
Fat-acids, 404
Fats and oils, composition of, 400
Fats, etc., to determine the melting-point of, 450
analysis of, 539
Fatty bodies, 400
Fel bovinum purificatum, 401
purificatum, impurities in, 543
Felspar, 335
Fennel oil, 407
Fermentation, 362
Fermentum, 372
Fer réduit, 135
Ferrate of potassium, 120
Ferri acetis tinctura, 127
arsenias, 123
arsenias, impurities in, 543
carbonas, 122
carbonas saccharata, 122
carbonas saccharata, impurities in, 543
citras, 130
et ammoniæ citras, 131
et ammoniæ citras, impurities in, 543
et ammoniæ citras, quantitative estimation of iron in, 507
et ammoniæ sulphas, 117
et ammoniæ tartras, 133
et potassæ tartras, 133, 288
et quinæ citras, 131
et quiniæ citras, impurities in, 543
et strychniæ citras, 133
ferrocyanidum, 303
hypophosphis, 306
iodidum, 27, 184
lactus, 309
oxalas, 282
oxidum magneticum, 133
oxidum magneticum, impurities in, 544
perchloridi, liquor, 126
pernitratis, liquor, 135
peroxidum humidum, 129
peroxidum hydratum, 128
peroxidum hydratum, impurities in, 544
persulphatis, liquor, 127
phosphas, 120
phosphas, impurities in, 544
potassio-tartras, 130
pulvis, 135
pyrophosphas, 136
subcarbonas, 122
sulphas, 121
sulphas, impurities in, 544
sulphas exsiccata, 121
sulphas granulata, 121
sulphas granulata, impurities in, 544
sulphuretum, 124
Ferric acetate, 127
chloride, 125

Ferric—
hydrate, 128
hypophosphite, 306
iodate, 264
nitrate, 134
oxide, 129
oxide, from phosphates and oxalates, separation of, 333
oxyiodate, 264
oxysulphate, 122
peroxyhydrate, 128
pyrophosphate, 136
salts, 125
salts, analytical reactions of, 136
sulphate, 127
sulphocyanate, 138
Ferridcyanide of potassium, 137, 303
Ferridcyanides, 303
Ferridcyanogen, 138, 303
Ferrocyanide of potassium, 248 302
of zinc, 114
Ferrocyanides, 303
Ferrocyanogen, 138, 302
Ferro-ferric hydrate, 133
oxide, 133
Ferrous arseniate, 123, 492
bromide, 124
carbonate, 122, 492
chloride, 126
iodide, 124
phosphate, 123
salts, 121
salts, analytical reactions of, 136
sulphate, 121
sulphide, 124, 136, 137
Ferrum, 29, 119
redactum, 135
tartaratum, 133, 288
tartaratum, estimation of iron in, 507
tartaratum, impurities in, 544
Fibrin, 396
vegetable, 398
Ficus, 362
elastica, 413
Fig, 362
Filix mas, 403
Filter, to dry, 498
Filtering-paper, 93, 497
Filters, 93, 497
Filtrate, 106
Fine gold, 218
Fire-clay, 177
Fire-damp, 382
Fixed and volatile oils, difference between, 405
oils, 400
Flame, oxidizing, 331
reducing, 331
structure of, 21
Flare, 401
Flaxseed, 402
Fleitmann's test for arsenicum, 150
Flexible collodion, 360
Flint, 314
Flores zinci, 113
Flour, 355
Flowers of sulphur, 269
Fluid magnesia, 101
Fluoric acid, 304
Fluoride of boron, 297
calcium, 90
calcium, in bones, 94, 304
silicon, 305
Fluorides, 304
Fluorine, 305
derivation of word, 30
Fluor-spar, 304
Fœniculi fructus, 407
Foil, copper, 167
Food, analysis of, 539
elements of, 398
how disposed of in the bodies of animals, 429
Force, chemical, 34
Forge-scales, 134
Formates, 301
Formic acid, 301, 404
Formica rufa, 301
Formula, chemical, definition of, 49
official, 25
officinal, 25
Formulæ, 39, 40, 528
construction of, 47, 53
empirical, 373, 528
graphic, 115
rational, 373, 528
Fousel oil, 389
Fowler's solution, 144
Foxglove, 367
Fraxinus ornus, 364
Fractional distillation, 371

Frankincense, 412
Frankland's graphic formulæ, 115
Freezing-mixture, 272
French chalk, 417
turpentine, 407
Fruit essences, 389
Fuchsine, 417
Fume-cupboard, 81
Fuming sulphuric acid, 277
Funnel-tubes, 81
"Fur" in water vessels, 281
Furniture of a laboratory, xii.
Fusel oil, 389
Fusibility of metals, table of the, 451
Fusible white precipitate, 181
Fusing-points of fats, 451
Fustic, 414

Galactometer, 466
Galbanum, 412
Galena, 185
argentiferous, 191
Galenical preparations of the British Pharmacopœia, 442
Galipot, 410
Galla, 317
Gallic acid, 318
Gall of the ox, 401
Gallon, 460
Galls, Aleppo, 317
English, 317
Gall-stones, 441
Galvanic test for mercury, 183
Galvanized iron, 109
Gambir, 318
Gamboge, 412, 414
Gambogic acid, 412
Garancin, 415
Garcinia morella, 412
Garlic, essential oil of, 393
Gas-analysis, 319, 336
a, definition of, 49
-burners, 16, 17, 21
for balloons, coal-, 21
illuminating, 368
-lamp, 17, 21
Gases and vapors, density of, 447, 469
collection of, 16, 17
correction of the volume of, 469
for pressure, 469
for temperature, 469
Gases and vapors—
diffusion of, 22
law of solubility of, in liquids, 71
relation of, to liquids and solids, 38
specific gravity of, 469
Gastric juice, 399
artificial, 399
Gaultheria procumbens, 390
Gaultheric acid, 390
Gelatine, 398
vegetable, 358
Gelatinous substances, 398
Gentianæ radix, 355
German silver, 208
Ginger oil, 408
Girdwood and Rogers's method for detecting strychnia, 424
Glacial acetic acid, 266, 451
phosphoric acid, 294
Glass, 314
liquor, 315
rods, 93
soluble, 315
tubes, to bend, 16
to cut, 16
to draw out, 93
Globulin, 396
Glucinum, 551
Glucose, 362
Glucosides, 365
Glue, 398
Gluten and glutin, 356
Glyceric alcohol, 394
Glycerine, 394, 188
Glycerines, 394
Glycerina, 394
impurities in, 544
Glyceritum acidi carbolici, 395
acidi gallici, 395
acidi tannici, 317, 395
picis liquidæ, 395
sodii boratis, 395
Glyceryl, 394, 400
caproate of, 402
caprylate of, 402
crotonate of, 403
hydrate of, 394, 400
laurate of, 402
margarate of, 402
myristate of, 402
oleate of, 400
palmitate of, 402

Glyceryl—
ricinoleate of, 403
rutate of, 402
tristearate of, 400
Glycholates, 401
Glycocine, 401
Glycocoll, 401
Glycol, 394
Glycols, 394
Glycyl, 394
Glycyrrhizæ radix, 364
Glycyrrhizin, 364
Gold, 216
analytical reactions of, 218
coin, 217, 467
derivation of word, 31
earth, 216
fine, 218
jewellers', 217
leaf, 217
mosaic, 216
ochre, 414
perchloride of, 217
sulphide of, 218
yellow, 414
Goldthread, 351
Gossypium, 359
Gothite, 129
Goulard's cerate, 187
extract, 187
water, 187
Graham's dialytic process, 537
law of diffusion, 22
Grain, 453
Grains, 453
Gramme, 455
relation of, to grains, 457, 459
Granati fructus cortex, 318
radicis cortex, 318
Granite, 116
Granulated tin, 214
phosphorus, 293
zinc, 19
Grape-sugar, 361
Graphic formulæ, 115
Graphite, 26
Gravel, 432
Gravimetric analysis, 446, 497
Gravitation, 452
Gravity, 452
Gray powder, 171
Green copperas, 121
chloride of iron, 125
iodide of iron, 124
Green—
iodide of mercury, 173
pigments, 416
sulphate of iron, 121
vitriol, 121
Greengage essence, 390
Griffith's mixture, 123
Group tests, 231
Guaiaci lignum, 369
resina, 369
Guaiacin, 369
Guaiacol, 392
Guaiacum, resin of, 369
Guaiaretin, 369
Guaiaretinic acid, 369
Guano, 320
Guarana, 353
Gum, 358
-acacia, 97, 357
-arabic, 97, 357
British, 357
cherry-tree, 358
-resins, 412
tragacanth, 358
Gummate of calcium, 97, 357
lead, 97
Gummic acid, 357
Gun-cotton, 359
Gun metal, 213
Gunpowder, 258
Gutta percha, 413
Gypsum, 90

Hæmatin, 396
Hæmatite, brown, 119
red, 119
Hæmatoxyli lignum, 318, 416
Hæmatoxylin, 318, 416
Half-sovereign, weight of the, 217
Haloid salts, 254
Hambro' blue, 416
Hardness of water, 281
Hard soap, 400
Heat, latent, 71
source of, 16
Heavy carbonate of magnesium, 101
magnesia, 102
spar, 87
white, 87, 417
Heberden's ink, 138
Hectare, 455
Hellebore, 354
Hemidesmi radix, 301

Hemidesmic acid, 301
Hemlock, 352
Hempseed calculi, 441
Henbane, 352
Hesperidene, 406
Hevea siphonia Braziliensis, 413
Heterologous series, 382
Hexyl, 381
Hippuric acid, 301, 433, 436
Hips, 363
Hoffner's blue, 416
Homologous series, 382, 404
Honey, 363
  dew, 364
Hop, 412
  essential oil of, 412
Hordeum decorticatum, 356
Horehound, *vide* Marrubium
Horsemint, 409
Horseradish oil, 382, 406
Hubbuck's oxide of zinc, 113
Humulus lupulus, 412
Hydrargyri chloridum corrosivum, 176
  chloridum mite, 177
  cyanidum, 248
  iodidum rubrum, 174
  iodidum rubrum, impurities in, 544
  iodidum viride, 172
  iodidum viride, impurities in, 544
  nitrati acidus liquor, 175
  nitratis liquor, 175
  oxidum flavum, 179
  oxidum rubrum, 178
  oxidum rubrum, impurities in, 544
  perchloridum, 176
  subchloridum, 177
  subchloridum, impurities in, 544
  sulphas, 175
  sulphas flava, 176
  sulphas, impurities in, 544
  sulphuretum cum sulphure, 182
  sulphuretum cum sulphure, impurities in, 544
  sulphuretum rubrum, 182
  unguentum, 171
Hydrargyrum, 29, 170
  impurities in, 544
  ammoniatum, 181
  ammoniatum, impurities in, 544
Hydrargyrum—
  cum creta, 171
  cum creta, impurities in, 544
Hydrated peroxide of iron, 129
  substances, 70
Hydrate of aluminium, 117
  ammonium, 76
  benzoyl, 299
  cadmium, 222
  calcium, 92
  cetyl, 402
  chromium, 212
  cobalt, 207
  glyceryl, 402
  manganese, 206
  nickel, 209
  potassium, 53
  sodium, 68
  zinc, 114
Hydrates, composition of, 54, 70
Hydraulic cement, 314
Hydric acetate, chloride, nitrate, sulphate, etc., *vide* the respective acids—acetic, hydrochloric, etc.
Hydride of antimony, 160
  arsenicum, 149
  benzoyl, 366, 413
  cinnamyl, 413
  copper, 307
  ethyl, 382
  methyl, 382
  phosphorus, 306
  silicon, 315
Hydrides, 105, 382
Hydriodic acid, 243
Hydrium, 19
Hydrobromic acid, 241
Hydrocarbons, 405
Hydrochlorate of morphia, 340
Hydrochloric acid, 26, 238
  acid, analytical reactions of, 240
  acid, antidote to, 241
  acid, common, 238
  dilute, 238
  acid in organic mixtures, detection of, 418, 421
  acid, volumetric estimation of, 484
Hydrocotarnine, 341
Hydrocyanic acid, 247
  acid, analytical reactions of, 250, 421

Hydrocyanic—
acid, antidotes to, 251
acid, dilute 249
acid from bitter almond and cherry-laurel, 366
acid in organic mixtures, detection of, 421
acid in the blood, 251
acid, Schönbein's test for, 252
acid, volumetric estimation of, 486
Hydroferridcyanic acid, 303
Hydroferrocyanic acid, 302
Hydrofluoric acid, 304
Hydrogen, 18
antimoniuretted, 160
arseniuretted, 149
benzoate, borate, etc., *vide* the respective acids, benzoic, boracic, etc.
combustion of, 19
derivation of word, 28
explosion of, 20
functions of, 104
in artificial light-producers, 21
lightness of, 21
peroxide of, 88
persulphide of, 271
phosphoretted, 305
preparation of, 19
properties of, 19
quantitative estimation of, in organic compounds, 525 *et seq.*
salts of, 235
siliciuretted, 316
sulphuretted, 81, 270
used for balloons, 21
weight compared with air, 22
weight of 1 litre, 470
weight of 100 cubic inches, 470
Hydrogenium, 19
Hydrometers, 466
Hydrosulphuric acid, 270
Hydrosulphyl, 270
Hydrous chloral, 387
Hydrous compounds, 70, 102
Hydroxyl, 270
Hygiene, 14
Hyoscyamia, 352
Hyoscyami folia, 352
semen, 352
Hyoscyamine, 352
Hyper-, meaning of, 125
Hypo-, meaning of, 308
Hypobromites, 242
Hypochloride of sulphur, 272
Hypochlorite of calcium, 96
sodium, 72
Hypochlorites, 260
Hypochlorous acid, 260
Hypophosphite of iron, 306
of potassium, 306
Hypophosphites, 305
Hypophosphorous acid, 305
Hyposulphite of calcium, 305
sodium, 307
sodium, standard solution of, 493
Hyposulphites, 307
Hyposulphurous acid, 307

-ic, meaning of, 63, 120
Iceland moss, 300
Icthyocolla, 398
-ide, meaning of, 63
Igasuria, 348
Ignatia, 347
Ignition, 86
Illicium anisatum, 406
Illuminating agents, analysis of, 539
Inch, 460
Incineration, 86
of filters in quantitative analysis, 497, 503
Indelible ink, 193
Indian hemp, 411
ink, 417
red, 415
rubber, 413
rubber, vulcanized, 414
yellow, 415
Indican, 258
Indiglucin, 258
Indigo, 258
sulphate of, 258
-blue, 258
-white, 258
Indigogen, 258
Indigotin, 258
Indium, 551
Infusible white precipitate, 182
Infusions, 442
Inhalation of chlorine, 25
conine, 352

Inhalation of—
hydrocyanic acid, 249
Inhalations, 442
Ink, black, 138, 318
Heberden's, 138
indelible, 193
Indian, 417
invisible, 208
marking, 193
printer's, 417
sympathetic, 208
Inorganic chemistry, 338
compounds, 338
Introduction, 13
Inverted sugar, 363
Iodate of potassium, 61, 263
Iodates, 263
Iodic acid, 263
Iodide of arsenicum, 143
cadmium, 221
ethyl, 380
hydrogen, 243
iron, 27, 124
lead, 188
potassium, 61
silver, 194
sulphur, 244
Iodides, 243
analytical reactions of, 244
of mercury, 172, 181
quantitative estimation of, 514
separation of, from bromides and chlorides, 246
Iodine, 27, 243
chloride of, 244
derivation of word, 28
its analogy to chlorine and bromine, 243
solution of, 244
standard solution of, 488
tincture of, 244
volumetric estimation of, 493
-water, 244
Iodoform, 374, 386
Iodum, 243
impurities in, 544
Iodinium, 243
Ipecacuanha, 352
Ipomœa turpethum, 176
Iridium, 221, 551
Iris florentina, 407
Irish moss, 358
Iron, 119
Iron—
acetate of, 127
alum, 117
ammonio-citrate of, 131
ammonio-tartrate of, 133
analytical reactions of, 136
arseniate, 123, 147
arseniate of, volumetric estimation of, 492
black hydrate of, 133
black oxide of, 134
bromide of, 124
carbonate of, 122, 492
cast, 119
chlorides of, 125
compounds, nomenclature of, 120
derivation of word, 29
detection of, in presence of aluminium and zinc, 138
galvanized, 109
hydrated peroxide of, 128
hypophosphite of, 306
in official compounds, estimation of, 492, 507
iodate of, 264
iodide of, 27, 124
lactate of, 309
magnetic oxide of, 133
magnetic oxide of, estimation of iron in, 492
nitrate of, 134
ore, magnetic, 119
ore, needle, 129
ore, spathic, 119
ore, specular, 119
oxide of, 134
oxyhydrates of, 129
oxysulphate of, 122
perchloride of, 125
perhydrate of, 128
pernitrate of, 135
peroxide of, 129
peroxyhydrate of, 129
persulphate, of 127
phosphate of, 123
phosphate of, volumetric estimation of, 492
from phosphates and oxalates, separation of peroxide of, 332
potassio-citrate of, 130
potassio-tartrate of, 133
pyrites, 119

Iron—
pyrophosphate, 136
quantitative estimation of, 492, 507
and quinine, citrate of, 131, 344, 532
red oxide of, 129
reduced, 135
rust of, 119
saccharated carbonate of, 122
saccharated carbonate of, volumetric estimation of, 492
salts, nomenclature of, 120
scale compounds of, 130
separation of, from aluminium and chromium, 213
sodio-citrate of, 130
sodio-tartrate of, 130
-stone, clay, 119
subcarbonate, 122
subsulphate, 127
sulphate of, 121
sulphide of, 124
sulphocyanate of, 130, 138, 251
tersulphate of, 127
wrought, 119
Isinglass, 398
Isomerism, 358
Isomorphism, the doctrine of, 46
Isomorphous bodies, 46, 295
Isonandra gutta, 414
-ite, meaning of, 60
Ivory-black, 417

Jalap resin, 369
Jalapa, 369
Jalapæ resina, 369
resina, impurities in, 544
Jalapic acid, 369
Jalapin, 369
Jalapinol, 369
Jaune brillant, 222
Jelly, 398
vegetable, 358
Jervia, 354
Jervine, 354
Juices, 442
Juniper-oil, 407
Juniperus, 407

Kalium, 28
Kamala, 411
Kelp, 243
Kermes, mineral, 158
Kilbride mineral, 129
Kiln, 91
Kilogram, 456, 457
Kilolitre, 462
Kilometre, 456
Kinate of quinia, 343
King's blue, 416
Kino, 318
Kola-nut, 353
Kousso, 411
Krameriæ radix, 318

Laboratory furniture, x.
Lac, 397
Lac-dye, 416
Lactates, 309
Lactic acid, 309
Lactometer, 397
Lactose, 362
Latuca, 355
Lactucin, 355
Lævogyrate, 363
Lævoracemic acid, 285
Lævorotation, 363
Lævotartaric acid, 285
Lævulose, 363
Lakes, 118
Lampblack, 417
Lamps, gas-, 16, 21
Lana philosophica, 114
Lanthanium, 551
Lard, 401
benzoated, 401
prepared, 401
Larix europæa, 408
Latent heat, 71
Laudanine, 341
Laudanosine, 341
Laughing-gas, 257
Laurate of glyceryl, 402
Laurel-camphor, 409
Lauric aldehyd, 408
Lauric acid, 404
Laurocerasi folia, 366
Lavender-oil, 407
-water, 406
Lavender, oil of, 407
Law, Avogadro's and Ampère's, 44, 45
of chemical combination by weight, 40 *et seq.*, 49
by volume, 44 *et seq.*, 49
concerning molecular weight, 46, 237, 471

Law—
of constant proportions, 41, 445, 497
of diffusion, definition of, 49
multiple proportions, 42, 176, 257
reciprocal proportions, 41
solubility of gases in liquids, 71
Laws of chemical combination, 40, 44, 49
Lead, 185
acetate of, 186
analytical reactions of, 189, 420
antidotes to, 190
carbonate of, 185
chloride of, 189
chromate of, 189
derivation of word, 29
gummate of, 97
hydrato-carbonate of, 185
in organic mixtures, detection of, 420
iodide of, 188
nitrate of, 187
oleate of, 188
oxide of, 185
oxyacetate of, 187
oxychromate of, 189
plaster, 188
puce-colored or peroxide of, 187
quantitative estimation of, 478, 512
red, 187, 415
shot, 185
subacetate of, 186
sugar of, 186
sulphate of, 190
sulphide of, 189
native, 185
test for, in water, 189
-tree, 190
volumetric estimation of solutions of acetate of, 478
white, 185
Leadstone, 119
Leaf-green, 416
Lecanora, 416
Legumin, 398
Lemon-chrome, 189
-juice, 290
-oil, 406
Length unit, 455
Lentish tree, 411
Lepidolite, 201
Levulose, 363
Lichen blue, 416
Light carbonate of magnesium, 100
carburetted hydrogen, 382
magnesia, 102
Lignin, 359
Lime, caustic, 91
chloride of, 96
-kiln, 91
-oil, 406
quick, 91
slaked, 91
superphosphate of, 292
-water, 92
Limestone, 90
magnesian, 100
mountain, 100
Limonis cortex, 406
succus, impurities in, 544
Limonite, 129
Line, 460
Lini farina, 402
semina, 402
Liniment of mercury, 171
Liniments, 442
Linimentum ammoniæ, 401
calcis, 401
Linum, 402
Linseed, 402
-cake, 402
oil, 402
Liqueurs, 372
Liquidambar orientale, 413
Liquid camphor, 409
definition of, 49
Liquids, specific gravity of, 464
official, specific gravity of, 464
Liquor *ammoniæ*, 77
ammoniæ, impurities in, 544
ammoniæ citratis, 79
ammoniæ fortior, 77
ammoniæ fortior, impurities in, 544
ammonii acetatis, 78
antimonii chloridi, 155
antimonii chloridi, impurities in, 544
antimonii chloridi, estimation of antimony in, 509
arsenicalis, 144

Liquor—
arsenicalis, impurities in, 544
arsenici chloridi, 145
arsenici et hydrargyri iodidi, 143
arsenici hydrochloricus, 145
arsenici hydrochloricus, impurities in, 544
atropiæ, 350
atropiæ sulphatis, 350
bismuthi et ammoniæ citratis, estimation of bismuth in, 225
bismuthi et ammoniæ citratis, impurities in, 544
calcis, 92
calcis, impurities in, 544
calcis chloratæ, 96
calcis chloratæ, impurities in, 545
calcis saccharatus, 92
calcis saccharatus, impurities in, 545
chlori, 240
chlori, impurities in, 545
ferri citratis, 130
ferri perchloridi, 126
ferri perchloridi fortior, 126
ferri perchloridi fortior, impurities in, 545
ferri perchloridi fortior, estimation of iron in, 508
ferri pernitratis, 135
ferri pernitratis, impurities in, 545
ferri pernitratis, estimation of iron in, 508
ferri persulphatis, 137
ferri persulphatis, impurities in, 545
ferri persulphatis, estimation of iron in, 508
ferri subsulphatis, 127
ferri tersulphatis, 127
gutta-perchæ, 414
hydrargyri nitratis acidus, 175
hydrargyri nitratis acidus, impurities in, 545
hydrargyri perchloridi, 177
iodi, 244
iodinii compositus, 244
lithiæ effervescens, 201
lithiæ effervescens, impurities in, 545
Liquor—
magnesiæ carbonatis, 101
magnesiæ carbonatis, impurities in, 545
magnesii citratis, 102
morphiæ acetatis, 341
morphiæ hydrochloratis, 341
morphiæ sulphatis, 341
plumbi subacetatis, 187
plumbi subacetatis, impurities in, 545
plumbi subacetatis dilutus, 187
potassæ, 53, 56
potassæ, impurities in, 545
potassæ effervescens, 59
potassæ effervescens, impurities in, 545
potassæ, neutralizing power of, 478
potassæ, specific gravity of, 466
potassæ, to prepare pure, 56
potassii arsenitis, 144
potassii citratis, 60
potassii permanganatis, 204
sodæ, 68
sadæ, impurities in, 545
sodæ chloratæ, 72
sodæ chloratæ, impurities in, 545
sodæ chlorinatæ, 72
sodæ effervescens, 71
sodæ effervescens, impurities in, 545
sodii arseniatis, 146
strychniæ, 248
zinci chloridi, 112
Liquorice-sugar, 364
List of apparatus, ix.
of chemicals, xi.
of reagents, x.
Litharge, 185
Lithates, 320
Lithii carbonas, 201
carbonas, impurities in, 545
citras, 200
citras, impurities in, 545
Lithic acid, 320
Lithium, 200
analytical reactions of, 201
carbonate of, 201
citrate of, 200
derivation of word, 30
flame, 201

Lithium—
fluoride of, 201
silicate of, 201
sulphate of, 201
urate of, 201
Litmus, 83, 416
paper, 83
solution of, 83
tincture of, 83
Litre, relation of, to pints, 456
Liver of sulphur, 56
Lixiviation, 73
Loadstone or lodestone, 119
Lobelia, 352
Lobelia vinegar, 265
Lobelina, 352
Lobeline, 352
Logwood, 25, 415
solution of bleached, by chlorine, 25
Long pepper, 351
Looking-glasses, 214
Lotio hydrargyri flava, 179
hydrargyri nigra, 179
Louisa-blue, 416
Lozenges, 442
Lucifers, 22
Lump-sugar, 361
Lunar caustic, 193
Lupulin, 412
oleo-resin of, 412
Lupulus, 412
Luteolin, 415
Luting, 82
fire-clay, 177
linseed meal, 82
Lycopodium, 403

Mace, 407
oil of, 407
Macis, 407
Madder, 415
Magenta, 417
Magnesia, 102
effervescing citrate of, 289
impurities in, 545
calcined, 102
fluid, 101
hydrous carbonate of, 102
Magnesia levis, 102
levis, impurities in, 545
Magnesian limestone, 100
Magnesii carbonas, 100
carbonas, impurities in, 545
Magnesii—
carbonas levis, 100
carbonas levis, impurities in, 545
carbonatis, liquor, 101
sulphas, 100
sulphas, impurities in, 545
Magnesite, 100
Magnesium, 99
analytical reactions of, 102
and ammonium, arseniate of, 103
and ammonium, phosphate of, 102
carbonate of, 100
chloride of, 99
citrate of, 290
derivation of word, 29
detection of, in presence of barium and calcium, 106
euxanthate of, 415
for analytical purposes, 150
limestone, 99
oxide of, 102
phosphate of, in bones, 94
purrate of, 415
quantitative estimation of, 505
separation from barium and calcium, 106
silicate of, 314
sulphate of, 100, 505
sulphite of, 273
Magnetic iron ore, 119
oxide of iron, 133
Magpie test for mercury, 183
Malachite, 166
Malate of atropine, 350
nicotine, 352
Malates, 309
Male fern oil, 403
Malic acid, 309
Malt, 357
Manganate of potassium, 63, 204
Manganese, 203
analytical reactions of, 204
black oxide of, 203
Crum's test for, 207
derivation of word, 30
quantitative analysis of black oxide of, 506
sulphate of, 206
Manganesii oxidum nigrum, 203
sulphas, 206

Manganous chloride, 204
hydrate, 206
sulphide, 206
Manna, 364
impurities in, 545
Mannite, 364
Manufacturing chemists, 14
Manures, analysis of, 539
Maranta, 357
Marble, 90
Margarine, 402
Marine soap, 402
Marking-ink, 193
Marl, 116
Marmalade, 318
Marmor album, 90
Marsh-gas, 382
Marsh's test of arsenicum, 149
Marrubium, 355
Maryland senna, 367
Massicot, 185
Mastic, 411
Mastiche, 411
Mastichic acid, 411
Masticin, 411
Maticæ folia, 355
Matricaria chamomilla, 406
Mauve, 417
May-apple, 351
Meadow-sweet, oil of, 390
Measurement of temperature, 447
Measures, 453 *et seq.*
Mechanical and chemical combination, difference between, 27, 32
Meconate of morphine, 340
Meconic acid, 310, 424
Meconine, 341
Medicines, analysis of, 336
Meerschaum, 314
Mel, 363
impurities in, 545
boracis, 297
depuratum, 364
sodæ boratis, 297
Melam, 316
Melasses, 364
Melissic acid, 404
Melting-points, Table of, 451
of fats, etc., to determine, 450
of metals, 451
Melissyl, palmitate of, 402
Melon-essence, 390
Memoranda, analytical, 230, 327
Mentha piperita, 407
viridis, 407
Menthene, 407
Menthol, 407
Mercuric ammonium, chloride of, 171
chloride, 172, 176
cyanide, 248
iodide, 172, 174
oxide, 178
oxynitrates, 175
oxysulphate, 178
nitrate, 174
salts, 171
salts, analytical reactions of, 180, 418
sulphate, 175
sulphide, 182
Mercurius vitæ, 156
Mercurous ammonium, chloride of, 181
chloride, 172, 177
chromate, 292
iodide, 172
nitrate, 174
oxide, 179
salts, 171
salts, analytical reactions of, 183
sulphate, 175
sulphide, 182
Mercury, 170
amido-chloride of, 181
ammoniated, 181
ammonio-chloride of, 181
analytical reactions of, 180
antidotes to, 184
basic sulphate of, 176
black oxide of, 179
carbonates of, 184
cyanide of, 248
chlorides of, 176
derivation of word, 29
iodides of, 172, 181
galvanic test for, 183
magpie test for, 183
native sulphide of, 170
nitrates of, 174
nomenclature of salts of, 171
of life, 156
in organic mixtures, detection of, 419
oxides of, 178
oxynitrates of 175

Mercury—
oxysulphate of, 176
oxysulphide of, 182
quantitative estimation of, 510
subchloride of, 177
sulphates of, 175
sulphide of, 170, 182
yellow oxide of, 179
Meta, meaning of, 215
Metaboracic acid, 297
Metacinnaméin, 413
Metagummic acid, 358
Metallic elements, 15
Metalloids, 15
Metals, 15
of minor pharmaceutical importance, 200
quantitative estimation of, 497
Table of the fusibility of, 451
Metamerism, 358
Metantimonic acid, 157
Metaphosphates, 310
Metaphosphoric acid, 310
Metastannates, 215
Metastannic acid, 215, 258
Metastyrol, 413
Metavanadates, 295
Methenyl, 386
Methyl, 381
conia, 352
hydride of, 382
salicylate, 390
Methylamine, 339
Methylated spirit, 383
sweet spirit of nitre, 384
Methylene, dichloride of, 386
Methylic alcohol, 383
detected in presence of ethylic alcohol, 383
Metre, 456
relation of, to inches, 456, 461
Metric system, 454 *et seq.*
of weights and measures, its relation to the English, 456 *et seq.*
system, weights and measures of, 455 *et seq.*
Mezerei cortex, 411
Mezereon, 411
Mica Panis, 362
Microcosmic salt, 332
Microscopic examinations of urinary sediments, 433
Milk, 397
sugar, 362
sulphur, 270
Mimetesite, 295
Mimotannic acid, 318
Mineral acids, detection of in organic mixtures, 421
chameleon, 205
kermes, 158
kilbride, 129
purple, 415
rouge, 415
Minerals, general analysis of, 329 *et seq.*
special analysis of, 549
Minim, 460
Minium, 185
Mirbane, essence of, 391
Mistura ferri aromatica, 138
ferri composita, 122
potassi citratis, 290
Mixture, different from chemical combination, 27
definition of, 48
Mixtures, 442
Mohr's burette, 476
Moist sugar, 361
Molasses, 364
Molecular volume, 46
weight, 46, 237, 471
weights, definition of, 50
Molecule, definition of, 48
Molecules, 36, 48
Molybdenum, 551
Molybdic acid, 427
Monads, 104
Monamines, 339
Monarda, 409
Monobasic acids, 237
Monobasylous radicals, 237
Mononitrocellulin, 360
Monsel's solution, 127
Mordants, 117
Mori succus, 415
Morphia, or Morphine, 340
acetate of, 340
analytical reactions of, 341, 424
hydrochlorate of, 340
in organic mixtures, detection of, 424
quantitative estimation of, 533
Morphiæ acetas, 340

Morphiæ—
hydrochloras, 340
hydrochloras, impurities in, 546
murias, 340
sulphas, 340
Mosaic gold, 216
Moschus, 398
moschiferus, 298
Motion from heat, 71
Mountain-blue, 416
limestone, 99
Mucic acid, 365
Mucilage of gum acacia, 97
starch, 356
tragacanth, 97
Mucilago acaciæ, 97
amyli, 356
tragacanthæ, 97
Mucus in urine, 420
Mulberry calculus, 424
-essence, 390
-juice, 415
Mulder's process for estimating alcohol, 536
Multiple proportions, law of, 42, 173, 257
Murexid, 320
Musk, 398
deer, 298
Mustard, 393
artificial oil of, 393
essential oil of, 393
fixed oil of, 403
Myrcia acris, 372
Myristate of glyceryl, 402
Myristic acid, 404
Myristica, 407
Myristicene, 407
Myristicol, 407
Myronate of potassium, 393
Myroxylon Pereiræ, 413
Toluifera, 413
Myrrh, 412
Myrrha, 412
Myrrhic acid, 412

Naphthalic acid, 299
Naphthalin, 299
Narceia, 341
Narcotine, 341
Narthex assafœtida, 412
Nataloin, 393
Natrium, 28
Nectandra Rodiæi, 350
Nectandræ cortex, 350
Nectandria, 351
Needle iron ore, 129
Neroli oil, 406
Neutral chromate, 89
Nickel, 208
analytical reactions of, 209
arsenio-sulphide of, 208
cobalticyanide, 210
cyanide, 209
derivation of word, 30
hydrate of, 209
separation of, from cobalt, 209
sulphide of, 209
Nicotia, nicotine, nicotina, or nicotylia, 352
Nicotiana tabacum, 352
Nihilum album, 113
Niobium, 507
Nitrate of ammonium, 257
argent - ammon - ammonium, 182
barium, 87
bismuth, 223
cadmium, 222
iron, 134
lead, 188
mercury, 174
potassium, 52, 253
silver, 192
silver, standard solution of, 486
sodium, 68, 253
strontium, 202
Nitrates, 252
analytical reactions of, 252
quantitative estimation of, 515
Nitre, 253
cubic, 253
sweet spirit of, 312, 379
Nitric acid, 252
acid, antidotes to, 259
acid in organic mixtures, detection of, 421
acid, volumetric estimation of, 484
anhydride, 255, 257
oxide, preparation of, 256
peroxide, 256
Nitrite of ethyl, 312
potassium, 311
Nitrites, 311
analytical reactions of, 311

Nitrobenzol, 391
in oil of bitter almonds, test for, 366
Nitrocellulin, 360
Nitrogen, 23
derivation of word, 28
in the atmosphere, 23
oxides of, 256
peroxide of, 256
preparation of, 23
properties of, 23
quantitative estimation of, in organic compounds, 527 *et seq.*
relative weight of, 24
Nitrohydrochloric acid, 162, 255
Nitromuriatic acid, 255
Nitrous acid, 257
anhydride, 257
ether, 312
oxide, 257
Nomenclature of salts:—
alkaloids, 339
anhydrides, 70
anhydrous bodies, 70
-ate, 60
bi, 59
carbonization, evaporation, ignition, incineration, 86
double salts, 65
hydrates, 53
hydrous bodies, 70
hyper, 125
-ic, -ous, 59, 63, 120
-ide, -ite, 63, 120
iron salts, 120
mercury compounds, 171
per, 125
Non-drying oils, 402
Non-metallic elements, 15
Non-metals, 14
Nordhausen sulphuric acid, 277
Notation, 37 *et seq.*
Notes, analytical, 230, 327
Nutmeg, expressed oil of, 407
oil of, 407
Nutrition, plastic elements of, 398
Nux vomica, 347

Oak-bark, 317
black, 415
Oatmeal, 356
Occlusion, 220, 221
Ochre, 414
Octohedral, 148
Œnanthylic acid, 404
Official liquids, specific gravity of, 464
substances, volumetric estimation of, 478, 484, 486, 489, 492, 494
Official formula, 25
Officinal formula, 25
Oil, almond, 402
amber, 315
aniseed, 406
apple, 389
bergamot, 406
bitter almond, 366
bitter almond, artificial, 391
buchu, 406
cacao, 402
cajuput, 406
cake, 402
camphor, 409
capsicum, 351
caraway, 407
cardamoms, 406
cascarilla, 407
cassia, 407
castor, 402, 403
cedra, 406
chamomile, 406
cinnamon, 407
citron, 406
citronella, 407
cloves, 407
cocoa-nut, 402
cod-liver, 402
copaiva, 407
coriander, 407
croton, 402, 403
cubeb, 407
dill, 406
elder-flower, 408
eucalyptus, 407
fennel, 407
garlic, 393
ginger, 408
hop, 412
horsemint, 409
horseradish, 393, 406
juniper, 407
lavender, 407
lemon, 406
lime, 406
linseed, 402
lycopodium, 403

Oil—
male-fern, 403
meadow-sweet, 390
mustard, artificial, 393
mustard, fixed, 403
mustard, volatile, 408
neroli, 406
nutmeg, 402, 407
olive, 403
orange-flower, 406
orange-rind, 406
origanum, 407
orris, 407
pepper, 353
peppermint, 407
pimento, 407
rose, 407
rosemary, 408
rue, 408
sassafras, 408
savin, 408
spearmint, 407
sperm, 402
star-anise, 406
theobroma, 402
thyme, 409
turpentine, 408
valerian, 408
of vitriol, 276
wine, 394
winter-green, 390
wormseed, 408
Oils and fats, composition of, 400
Oils, analysis of, 539
drying, 402
essential, 405
fixed, 402
non-drying, 403
volatile, 405
volatile, process for, 405
Ointments, 442
Olea destillata, impurities in, 546
Oleate of glyceryl, 400
ead, 188
, 400
, gas, 394
Oleic acid, 400
Oleine, 400
Oleo-resins, 411
Oleoresina capsici, 412
cubebæ, 412
lupulinæ, 412
piperis, 412
zingiberis, 412
Oleum amygdalæ amaræ, 366
amygdalæ dulcis, 402
anethi, 406
anisi, 406
anthemidis, 406
bergamii, 406
cajuputi, 406
camphoræ, 409
carui, 407
caryophylli, 407
cinnamomi, 407
copaibæ, 407
coriandri, 407
crotonis, 403
cubebæ, 407
ethereum, 394
fœniculi, 407
gaultheriæ, 390
juniperi, 407
lavendulæ, 407
limonis, 406
lini, 402
menthæ piperitæ, 407
menthæ viridis, 407
morrhuæ, 402
myristicæ, 407
myristicæ expressum, 402
olivæ, 403
origani, 407
pimentæ, 407
ricini, 403
rosæ, 407
rosmarini, 408
rutæ, 408
sabinæ, 408
sassafras, 408
sinapis, 408
succini, 315
succini rectificatum, 315
terebinthinæ, 408
theobromæ, 402
thymi, 409
tiglii, 403
valerianæ, 408
Olive-oil, 403
Omentum, 401
Opal, 315
Opianine, 341
Opium, 340
Opium, detection of in organic mixtures, 424
estimation of morphia in, 532
impurities in, 546
vinegar, 265

Orange-chrome, 189
Orange-flower, 406
-flower oil, 406
-rind oil, 406
-wine, 372
Orchil, 416
Orcin, 416
Ordeal-poison, 353
Orellin, 415
Organic analysis, 525
bases, 338
chemistry, 338
compounds, 338
Orpiment, 415
Orris, butter of, 407
oil of, 407
Ortho, meaning of, 311
Orthophosphates, 312
Orthophosphoric acid, 312
Orthovanadates, 296
Os, 95
Os ustum, 95
Osmium, 221, 551
Otto of rose, 407
Ounce, 453
-ous, meaning of, 63, 120
Ovi vitellus, 396
Ovum, 396
Ox-bile, 401
-gall, 401
Oxalate of ammonium, 80
barium, 282
calcium, 282
cerium, 203
iron, 252
silver, 283
sodium, 283
strontium, 202
Oxalates, 282
analytical reactions of, 282, 421
from phosphates and ferric oxide, separation of, 333
quantitative estimation of, 521
Oxalic acid, 282
acid, antidotes to, 283
acid, in organic mixtures, detection of, 421
acid, standard solution of, 477
Oxide of aluminium, 117
antimony, 156
calcium, 91
chromium, 210
copper, 167
Oxide of—
iron, black, 133
lead, 185
magnesium, 102
manganese, 203
mercury, 178
silicon, 315
silver, 193
tin, 213
zinc, 113
Hubbuck's, 113
Oxides of nitrogen, 257
Oxidizing flame, 331
Oxyacetate of, copper, 168
of lead, 186
Oxyacid salts, 252
Oxyacids of sulphur, 307
Oxycarbonate of bismuth, 224
Oxychloride of antimony, 156
Oxychromate of lead, 189
Oxygen, 15
derivation of word, 28
from ozone and antozone, 245
in the air, 15, 24
its relation to animal and vegetable life, 18
preparation of, 15
properties of, 17
quantitative estimation of, in organic compounds, 525 *et seq.*
solubility in water, 18
specific gravity of, 22
weight of 100 cubic inches, 470
Oxygenated water, 88
Oxyhydrates of iron, 129
Oxyiodate of iron, 264
Oxymel, 364
of squill, 364
Oxynitrates of mercury, 175
bismuth, 224, 225
Oxysalts, 254
Oxysulphate of iron, 122
mercury, 176
Oxysulphide of antimony, 157
mercury, 182
Ozone, 211, 245

Palladium, 221, 551
Palm-oil, 402
Palmitate of cetyl, 402
glyceryl, 402
melissyl, 402

Palmitic acid, 404
Palmitine, 402
Papaver rhœas, 415
somniferum, 340
Papaveris capsulæ, 340
Papaxerine, 341
Paper, bibulous, 93
for filtering, 93, 497
Papers, test-, 83
Para, meaning of, 285
Paratartaric acid, 285
Paraguay tea, 353
Pareiræ radix, 351
Paris blue, 416
red, 415
Particles, elementary, 39
Pearlash, 53
Pearl-barley, 356
-white, 224, 417
Peas, 398
Pectin, 358
Pelargonic acid, 404
Pellitory root, 411
Pelosia, 351
Pelosine, 351
Pentachloride of antimony, 156
Pentathionic acid, 307
Pepper, black, 353
cayenne, 351
cubeb, 353
long, 353
white, 353
oil of, 353
resin of, 411
Peppermint oil, 407
Pepsin, 399
Per-, meaning of, 125
Perbromates, 242
Percha tree, 414
Perchlorate of potassium, 262
Perchloric acid, 261
Perchloride of gold, 217
iron, 125
platinum, 219
tin, 214
Perfumes, 406
Perhydrate of iron, 128
Permanganate of potassium, 64, 204
its use in volumetric analysis, 488
Pernitrate of iron, 134
Peroxide of barium, 88
hydrogen, 88
Peroxide of—
iron, 129
iron, hydrated, 128
lead, 187
nitrogen, 256
Peroxyhydrate of iron, 128
Persian berries, 415
Persulphate of iron, 127
Persulphide of hydrogen, 271
Peru, balsam of, 413
Pervuine, 413
Petalite, 201
Pettenkofer's test for presence of bile, 401
Pewter, 155, 185, 214
Phæoretine, 300
Pharaoh's serpent, 316
Pharmaceutical chemists, 14
Pharmaceutical Society of Great Britain, examinations of, 14
Pharmacists, 14
Pharmacy, 14
Phenic acid, 391
alcohol, 391
Phenol, 391
Phenyl, 391
Phenylamine, 393
Phosphate of ammonium, 79
barium, 295
calcium, 90, 94, 295
iron, 123, 295
magnesium and ammonium, 103
magnesium and ammonium from oxalates and ferric oxide, separation of, 333
magnesium, in bones, 94
silver, 194
sodium, 95
sodium, how prepared from phosphate of calcium, 95
Phosphates, 292
analytical reactions of, 294
quantitative estimation of, 521
Phosphites, 312
test for, 313
Phosphomolybdic acid, 427
Phosphoretted hydrogen, 306
Phosphoric acid, 22, 293, 312
acid, diluted, 293
acid, quantitative estimation of free, 521
anhydride, 22, 310

Phosphorous acid, 312
Phosphorus, 22
combustion of, 22
derivation of word, 28
detection of, in organic mixtures, 422
granulated, 293
properties of, 22
red or amorphous, 359
trihydride, 306
Phthalic acid, 299
Phyllocyanin, 416
Phylloxanthin, 416
Physostigmatis faba, 353
Physostigma, 353
Physostigmine, 353
Picric acid, 392
Pigments, 414
Pills, 440
Pilula ferri carbonatis, 122
ferri iodidi, 27
hydrargyri, 171
hydrargyri subchloridi composita, 178
plumbi cum opio, 187
quiniæ, 344
Pilulæ antimonii compositæ, 178
ferri compositæ, 123
Pimaric acid, 410
Pimento, 407
oil, 407
Pimpinella anisum, 406
Pine-apple, essence of, 390
Pinic acid, 410
Pink saucers, 416
the common, 371
Pins, 214
Pint, 460
Pinus, 408, 412
Piper nigrum, 353
Piperia, 353
Piperidia, 353
Piperidine, 353
Piperine, 353
Pistachia terebinthus, 408
Pitch, 412
burgundy, 411
Pix burgundica, 411
canadensis, 412
liquida, 412
Plants and animals, complementary action on air, 18
Plaster of ammoniacum and mercury, 171
Plaster of—
mercury, 171
Paris, 90, 417
Plasters, 188, 440
Plastic elements of nutrition, 398
Platinic salts, 219
Platinous salts, 219
Platinum, 219
analytical reactions of, 219
and ammonium, chloride of, 83, 499
and potassium, chloride of, 65
black, 220
derivation of word, 31
foil, 64, 219
perchloride of, 219
residues, to recover, 221
spongy, 221
sulphide of, 220
Plumbago, 26
Plumbi acetas, 186
acetas, impurities in, 546
carbonas, 186
carbonas, impurities in, 546
emplastrum, 18
iodidum, 188
nitras, 187
oxidum, 185
oxidum, impurities in, 546
subacetatis, liquor, 187
"Plummer's pills," 178
Plumbic peroxide, 187
acetate, sulphate, etc., *vide* salts of lead.
Plumbum, 29
Pocula emetica, 155
Podophylli radix, 351
resina, 351
Poisonous alkaloids, 423, 425
Poisons, antidotes to, *vide* Antidotes, detection of, in organic mixtures, 418 *et seq.*
Polybasic acids, 237
Polybasylous radicals, 237
Polychroite, 415
Polygala senega, 371
Polygalic acid, 371
Polymerism, 358
Polymorphism, 358
Polymorphous bodies, 359
Polysulphide of calcium, 270
Pomegranate root-bark, 318
Porcelain, 314
Portland cement, 314

Potash alum, 116
solution of caustic, 55
solution of caustic, to prepare pure, 55
sulphurated, 56
vol. estim. of sol. of, 478
-water, 56
Potashes, 52
Potassa, 56
Potassa caustica, 56
caustica, impurities in, 546
sulphurata, 56
sulphurata, impurities in, 546
Potassæ, vide Potassii.
effervescence, liquor, 59
liquor, 53, 56
liquor, to prepare pure, 55
prussias flava, 248, 302
Potassic, hydrate, etc., *vide* salts of potassium.
Potassii acetas, 57
acetas, impurities in, 546
bicarbonas, 58
bicarbonas, impurities in, 546
bichromas, 210
bitartras, 66, 284
bromidum, 63
bromidum, impurities in, 546
carbonas, 52
carbonas pura, 53
carbonas impura, 52
carbonas, impurities in, 546
chloras, 261
chloras, impurities in, 546
citras, 60
citras, impurities in, 546
cyanidum, 248
et sodii tartras, 61, 72
ferridcyanidum, impurities in, 546
ferrocyanidum, 248
hypophosphis, 306
iodidum, 61
iodidum, impurities in, 546
nitras, 60, 252
nitras, impurities in, 546
permanganas, 64, 204
permanganas, impurities in, 546
sulphas, 60, 255.
sulphas, impurities in, 546
sulphis, 270
sulphuretum, 56
tartras, 61, 62
Potassii—
tartras, impurities in, 546
tartras acida, 284
tartras acida, impurities in, 546
Potassio-citrate of iron, 130
-tartrate of antimony, 157, 284
-tartrate of iron, 130
Potassium, 52
acetate of, 57
acid carbonate of, *vide* bicarbonate.
acid tartrate of, 65
analytical reactions of, 64
antimoniate of, 74
bicarbonate of, 58, 478
bichromate of, 210
bitartrate of, 65, 284
borotartrate of, 297
bromate of, 63
bromide of, 63, 415
carbonate of, 53, 478
chlorate of, 16, 261
chloride of, 65
chromate of, 60
and platinum, chloride of, 64
citrate of, 60
cobalticyanide of, 207
cyanate of, 300
cyanide of, 248
derivation of word, 28
ferrate of, 120
ferridcyanide of, 303
ferrocyanide of, 248, 301
-flame-test, 66
hydrate of, 54
hydrate, to prepare pure solution, 55
hypophosphite of, 306
iodate of, 62, 263
iodide of, 61
manganate of, 64, 186
myronate of, 393
nitrate of, 52, 60, 252
oleate of, 400
perchlorate of, 262
permanganate of, 64, 204
preparation of, 53
properties of, 53
quantitative estimation of, 476, 497
quantivalence of, 53

Potassium—
red chromate of, 88, 210
red prussiate of, 303
and sodium, tartrate of, 72
salts, analogy of to sodium salts, 73
sodium, and ammonium, separation of, 85
sources of, 52
sulphate of, 60, 255
sulphides of, 56
sulphite of, 270
sulphocyanate of, 316
sulphurated, 56
tartrate of, 60
tartrate of, acid, 52, 65, 284
yellow chromate of, 60, 210
yellow prussiate of, 247, 301
Potato-oil, 389
Poultices, 442
Pound, 459
Powder, bleaching-, 96
Powders, 442
soda-, 73
specific gravity of, 467
Practical analysis, 84
Precipitant, 65
Precipitate, 65
Precipitated chalk, 92
sulphur, 270
Precipitates, soluble, in solutions of salts, 231, 250
to wash, 92, 93, 490, 508
to weigh, 499, 501, 503
Precipitation, 65
Preparations of the British Pharmacopœia, chemical, 444
galenical, 442
Prepared carbonate of calcium, 94
chalk, 94
lard, 402
suet, 402
Pressure, correction of vol. of gas for, 469
gauges, 447
Principles of Chemical Philosophy, 32
Printer's ink, 417
Prismatic nitre, 252
Proportions, atomic, 41, 173
constant, 41, 49
multiple, 42, 49
reciprocal, 41, 50
Proof spirit, 373
Propenyl, 394
Propionic acid, 404
Propyl, 381,
Propylamine, 339
Protopine, 341
Proximate analysis, 525
Prune, 363
Prunum, 363
Prussian blue, 303, 416
Prussiate of potash, red, 303
of potash, yellow, 248, 302
Prussic acid, 247
Pseudomorphia, 341
Pterocarpi lignum, 415
Pterocarpus santilinus, 415
Ptyalin, 438
Puce-colored oxide of lead, 187
Puddling, iron, 119
Pulvis algarothi, 156
angelicus, 156
antimonialis, 159
ipecacuanhæ compositus, 352
Pulveres effervescentes, 73
aperientes, 287
Purified ox-bile, 401
Purple of Cassius, 218
foxglove, active principle in, 367
Purpurine, 432
Purrate of magnesium, 415
Purree, 415
Pus, in urine, 437
Putty-powder, 215
Pyrethrin, 411
Pyrethri radix, 411
Pyrites, copper, 166
iron, 119
Pyroarseniate of sodium, 146
Pyroarseniates, 146
Pyrogallic acid, 319
acid, use of in gas analysis, 319
Pyroligneous acid, 265
Pyrolusite, 20
Pyrometers, 450
Pyromorphite, 295
Pyrophosphates, 296, 311
Pyrophosphoric acid, 312, 313
Pyrovanadates, 295
Pyroxylic spirit, 383
Pyroxylin, 360
Pyroxylon, 360

Quadrivalence, 47

Qualitative analysis, 84
Quantitative analysis, 404 *et seq.*
Quantivalence, 47, 104
of atoms, definition of, 52
of acidulous radicals, 50
Quartz, 314
Quassiæ lignum, 343
Quassin, 343
Quercitrin, 415
Quercitron, 415
Quercus cortex, 317
tinctoria, 415
Quevenne's iron, 135
Quicklime, 91
Quiniæ sulphas, 343
sulphas, impurities in, 546
valerianas, 344
Quinia, or quinine, 343
analytical reactions of, 344
citrate of iron and, 131
De Vry's process for estimating, 529
disulphate of, 344
kinate of, 343
quantitative estimation of, 528
sulphate of, 344
Quinia wine, 344
Quinicia, 346
Quinicine, 346
Quinidia, 346
Quinidine, 346
Quinine, citrate of, 344
Quinquivalence, 47

Radicals, acidulous, 55, 235
acidulous, formulæ of, 55
alcohol-, 382
basylous, 104
definition of, 54
Racemic acid, 285
Raisins, 363
Rational formulæ, 373
Reactions, analytical, 53
synthetical, 53
Reagents, list of, x.
Real alcohol, 374
Realgar, 144
Reaumur's thermometer, 448
Reciprocal proportions, law of, 42
Rectification, 109
Rectified oil of turpentine, 408
spirit, 109, 373
Red chromate of potassium, 210
Red—
coloring-matters, 415
corpuscles in blood, 437
earth, 415
enamel colors, 416
gravel, 432
hæmatite, 119
iodide of mercury, 173
litmus-paper, 83
lead, 187, 415
ochre, 415
oxide of iron, 129, 415
phosphorus, 259
-poppy petals, 415
precipitate, 178
prussiate of potash, 303
-rose petals, 415
sandal-wood, 415
Venetian, 129
Reduced indigo, 258
iron, 135
Reducing flame, 331
Reinsch's test for arsenicum, 148
Relative weight of hydrogen and oxygen, 22
Rennet, 397
Reseda luteola, 415
Resin, 410
of arnica, 411
of cannabis, 411
of capsicum, 411
of castor, 411
of ergot, 411
of guaiacum, 369
of Indian hemp, 411
of jalap, 369
of kamala, 411
of kousso, 411
of mastic, 411
of mezereon, 411
of pepper, 353
of podophyllum, 351
of pyrethrum, 411
of rottlera, 411
of scammony, 371
Resina, 410
jalapæ, 369
podophylli, 351
scammoniæ, 371
Resinoid substances, 410
Resins, 410
Respiratory materials of food, 398
Retort, 108

Rhœados petala, 415
Rhamni succus, 367, 416
Rhamnus catharticus, 416
infectorius, 416
Rhaponticin, 300
Rhatany root, 318
Rhei radix, 300
radix, impurities in, 300
Rheic acid, 300
Rhein, 300
Rheumin, 300
Rhodium, 221
Rhubarb, oxalate of calcium from, 435
Rhubarbic acid, 300
Rhubarbarin, 300
Rhus cotinus, 414
Ricinoleate of glyceryl, 403
Ricinoleine, 403
Roccella, 416
Rochelle salt, 72, 286
Rock-salt, 67
Roll sulphur, 269
Roman cement, 314
Rosæ caninæ fructus, 363
centifoliæ petala, 407
gallicæ petala, 415
Roscoe's vanadium, 295
Rosaniline, 417
Rose-oil, 407
-water, 405
Rosemary-oil, 408
Rosin, 410
Rottlera tinctoria, 411
Rottlerin, 411
Rouge, animal, 300, 415
mineral, 129, 415
vegetable, 416
Rubia tinctorum, 415
Rubian, 384
Rubidium, 552
Ruby, 116
Rue-oil, 408
Rumicin, 300
Rust of iron, 120
Rutate of glyceryl, 402
Ruthenium, 221, 552
Rutic acid, 402
aldehyd, 408

Sabadilla or sabadilline, 354
Sabinæ oleum, 408
Saccharated carbonate of iron, 122
Saccharated—
carbonate of iron, volumetric estimation of, 492
Saccharic acid, 365
Saccharimetry, 534
Saccharine substances, 355, 361
Saccharometer, 535
Saccharum lactis, 362
purificatum, 361
ustum, 364
Safety-lamp, 21
Safflower, 415
Saffranin, 415
Saffron, 415
bastard, 415
dyer's, 415
Safren, 408
Sago, 356
Sal-ammoniac, 76
Salicin, 370
Salicyl, hydride of, 370, 390
Salicylate of methyl, 390
Salicylous acid, 390
Saligenin, 370
Saliva, 438
Sal prunella, 253
Salt, common, 67
definition of a, 52
of sorrel, 282
Saltpetre, 253
Chili, 250
Salts, acid, 269
action of the blowpipe on, 331
action of heat on, 330
action of sulphuric acid on, 330
of ammonium, volatility of, 84
analogies, of, 73
analysis of insoluble, 328
constitution of, 54, 107, 235, 253, 267
formation of, 58
nomenclature of, 59, 63
of iron, nomenclature of, 120
physical properties of, 329
substitution of for each other, 73
table of the solubility or insolubility of, in water, 325
Sal volatile, 79
Sambucene, 408
Sambuci flores, 408
Sand, 314
-bath, 24

Sand—
-tray, 24, 177
Sandstone, 314
Sanguinaria, 353
vinegar, 265
Santalin, 415
Santonica, 370
Santonin, 370
Santoninum, 370
impurities in, 546
Santoniretin, 370
Sapan-wood, 415
Sap-green, 416
Sapo durus, 400
durus, impurities in, 546
mollis, 400
mollis, impurities in, 546
Saponin, 371
Sapphire, 116
Sarcinæ ventriculi, in urine, 439
Sarcolactic acid, 309
Sarsaparilla, 371
Sarzæ radix, 371
Sassafras-oil, 408
Sassafras radix, 408
Sassafrol, 408
Saturated solutions, boiling-points of, 450
Saturating power of citric acid, 290, 549
power of tartaric acid, 286, 549
Saturation, 57
tables, 286, 290, 549
Saturn, 186
Saturnine colic, 186
Savin-oil, 408
Saxon blue, 416
Saxony blue, 416
Scale compounds of iron, 186
Scammoniæ radix, 371
resina, 371
resina, impurities in, 547
Scammonin, 371
Scammoniol, 371
Scammonium, 371
Scammony, resin of, 371
Scents, 406
Scheele's green, 152
Schist, 116
Schönbein's test for hydrocyanic acid, 251
Schweinfurth green, 152
Science of chemistry, 14
Scilla, 364
Scoparii cacumina, 353
Scoparin, 353
Sea-salt, 67
Sediments, urinary, 432
urinary, microscopic examinations of, 433
Seidlitz powder, 287
Selenium, 552
Senegæ radix, 371
Senna alexandrina, 366
indica, 367
Sepia, 417
Serolin, 396
Serpentariæ radix, 355
Serpent's excrement, 309
Sevum præparatum, 402
Sexivalence, 47
Shale, 116
Sherry-wine, 372
Sienna, 417
Sifting, an aid to analysis, 330
Silica, 314
Silicate of aluminium, 116
calcium, 90, 314
magnesium, 314
Silicates, 314
quantitative estimation of, 524
tests for, 315
Silicic acid, 314
anhydride, 315
Siliciuretted hydrogen, 315
Silico-fluoride of barium, 89
Silicon, chloride of, 315
derivation of word, 30
fluoride of, 315
hydride of, 315
oxide of, 315
Silver, 191
ammonio-nitrate of, 153, 182
analytical reactions of, 193
antidotes to nitrate of, 195
arseniate of, 153
arsenite of, 153
bromide of, 194
chloride of, 192
chromate of, 194
citrate of, 291
coinage, 191, 467
cyanide of, 194
by cupellation, estimation of, 513
derivation of word, 29

Silver—
extraction of, 191
German, 109
iodide of, 194
nitrate of, 191, 192
oxalate of, 283
oxide of, 193
phosphate of, 194
pure, 192
quantitative estimation of, 513
standard solution of nitrate of, 486
sulphide of, 191
sulphite of, 274
tartrate of, 288
tree, 194
volumetric estimation of, 513
Sinalbin, 393
Sinapis, 393
impurities in, 547
Siphon, *vide* Syphon.
Size, 398
Slaked lime, 91
Slate, 116
Smalt, 207, 416
Smilacin, 371
Soap, ammonium, calcium, hard, potassium, sodium, soft, 400
Soap-stone, 417
-wort, 341
"Soda," 279, 482
Soda-alum, 116
-ash, 73, 482
caustic, 68
Soda, 68
caustica, 68
caustica, impurities in, 547
tartarata, 72
tartarata, impurities in, 547
Soda-lime, 527
powders, 73
solution of chlorinated, 72, 495
standard solution of, 483
valerianate of, 321
volumetric estimation of, 478
water, 71
Sodæ, *vide* Sodii.
Sodii acetas, 69
acetas, impurities in, 547
arsenias, 146
arsenias, impurities in, 547
bicarbonas, 69, 70
Sodii—
bicarbonas, impurities in, 547
boras, 296
carbonas, 270
carbonas, impurities in, 547
carbonas, exsiccata, 70
chloratæ, liquor, 72, 495
chloridum, 67
citro-tartras effervescens, 73
hypophosphis, 306
hyposulphis, impurities in, 547
liquor, 68
nitras, 225
nitras, impurities in, 547
phosphas, 95
phosphas, impurities in, 547
sulphas, 239
sulphas, impurities in, 547
sulphis, 273
valerianas, 321
valerianas, impurities in, 547
Sodic carbonate, etc., *vide* salts of sodium.
Sodio-citrate of iron, 130
-tartrate of iron, 130
Sodium, 67
acetate of, 69
acid carbonate of, 69, 478
acid sulphate of, 239
acid tartrate of, 66
analytical reactions of, 74
and aluminium, double chloride of, 115
antimoniate of, 74
arseniate of, 146
arsenite of, 144
bicarbonate of, 69
bisulphite of, 270
bromate of, 73
bromide of, 73
carbonate of, 68, 73, 279, 478
carbonate of, manufacture of, 73, 279
chlorate of, 73
chloride of, 67
citrate of, 73
derivation of word, 28
-flame, 74
hydrate of, 68
hypochlorite of, 72
hypophosphite of, 306
hyposulphite of, 306
iodate of, 73
iodide of, 73

Sodium—
manganate of, 73
nitrate of, 68, 252
other compounds of, 73
oxalate of, 282
permanganate of, 73
phosphate of, 95
phosphate of, how prepared from phosphate of calcium, 95
potassium and ammonium, separation of, 85
pyroarseniate of, 146
quantitative estimation of, 478, 501
salts, analogy of, to potassium salts, 73
salts, sources of, 67
sulphate of, 239
sulphite of, 273
valerianate of, 321
Soft soap, 400
Soils, analysis of, 539
Solania, 353
Solanine, 353
Solanum dulcamara, 353
Solder, 185, 213
Solid, definition of, 49
fats, 400
potash, 56
Solids lighter than water, to take the specific gravity of, 468
to take the specific gravity of, 467 *et seq.*
Solubility of carbonic acid gas in water, 71
of gases in liquids, 71
of precipitates in strong solutions of salts, 231, 250
or insolubility of salts in water, Table of, 325
Soluble cream of tartar, 297
glass, 315
substances, to take the specific gravity of, 468
tartar, 297
Solution of acetate of ammonium, 78
acetate of potassium, 57
acetate of sodium, 69
albumen, 395
ammonia, 77
ammonio-nitrate of silver, 153, 182
Solution of—
ammonio-sulphate of copper, 153, 182
ammonio-sulphate of magnesium, 103, 522
arsenic in acid, 145
arsenic in alkali, 144
boracic acid, 296
bromine, 242
carbonate of ammonium, 79
chloride of ammonium, 76
chloride of antimony, 155
chloride of barium, 87
chloride of calcium, 90
chloride of calcium, saturated, 90
chloride of gold, 217
chloride of tin, 214
chloride of zinc, 112
chlorinated lime, 97, 495
chlorinated soda, 72, 495
chlorine, 24, 25
citrate of ammonium, 79
citrate of magnesium, 101
ferridcyanide of potassium, 304
ferrocyanide of potassium, 302
gelatine, 398
iodate of potassium, 62, 263
iodide of potassium, 62
iodine, 244
lime, 92
litmus, 83
nitrate of mercury, 174
oxalate of ammonium, 80
perchloride of iron, 126, 127
perchloride of mercury, 177
perchloride of platinum, 219
pernitrate of iron, 135
persulphate of iron, 127
phosphate of sodium, 96
phosphoric acid, 293
potash, 53, 55
red prussiate of potash, 304
soda, 68
strychnia, 348
subacetate of lead, 186
sulphate of calcium, 97
sulphate of indigo, 258
sulphate of iron, 121
sulphide of ammonium, 80
sulphydrate of ammonium, 80
tartaric acid, 285

Solution of—
yellow prussiate of potash, 302
Sonnenschien's process for poisonous alkaloids, 426
Soot, 26
Source of heat, 16
Sovereign, weight of the, 217
Spar, fluor-, 304
heavy, 87
Sparteia or sparteine, 353
Spathic iron-ore, 119
Spearmint oil, 407
Specific gravity, 463
gravity of gases, 469
gravity of liquids, 464
gravity of official liquids, 464
gravity of oxygen, 22
gravity of powders, 467
gravity of solids, 467
gravity of solids lighter than water, 468
gravity of soluble substances, 468
weight, 463
Spectrum analysis, 336
Specular iron-ore, 119
Speculum metal, 213
Speiss, 208
Spermaceti, 402, 451
Spermatozoa, in urine, 439
Sperm-oil, 402
Spiræa ulmaria, 370
Spirit of French wine, 376
methylated, 383
myrcia, 372
of nitrous ether, 312, 379
of nitrous ether, adulterated, 384
proof, 373
pyroxylic, 383
rectified, 373
of turpentine, 408
of wine, 373
of wine, impurities in, 487
wood-, 383
Spirits, 442
analysis of, 536
Spiritus ætheris, 378
ætheris nitrosi, 379
ætheris nitrosi, impurities in, 547
ammoniæ, 79
ammoniæ aromaticus, 79
Spiritus—
ammoniæ aromaticus, impurities in, 547
ammoniæ fœtidus, 79
anisi, 406
cajuputi, 405
cinnamomi, 406
chloroformi, impurities in, 547
frumenti, 372
juniperi, 405
lavandulæ, 405
menthæ piperitæ, 406
myrciæ, 372
myristicæ, 405
rectificatus, 448, 473
rectificatus, impurities in, 547
rosmarini, 405
tenuior, 373
tenuior, impurities in, 547
vini gallici, 376
Spodumene, 201
Spongy platinum, 221
Spruce fir, 411
Spurge laurel, 411
Squill, 364
Standard gold, 217
Standard solution of hyposulphite of sodium, 493
solution of iodine, 488
solution of nitrate of silver, 486
solution of oxalic acid, 477
solution of red chromate of potassium, 491
solution of soda, 483
solution of sulphuric acid, 482
Stannate of sodium, 215
Stannates, 215
Stannic acid, 215
anhydride, 215
chloride, 214
oxide, 215
sulphide, 216
anhydrous, 216
Stannous chloride, solid, 214
hydrate, 216
oxide, 216
sulphide, 215
Stannum, 30
Star-anise oil, 406
Starch, 355
blue, 356
quantitative estimation of, 534
-sugar, 363

Stas's process for poisonous alkaloids, 425
Steam-bath, 500
Stearic acid, 400, 404
Stearine, 400
Stearoptens, 405
Steatite, 417
Steel, 119
wine, 133
Stibium, 29
Still, 108
Stoddart's test for quinine, 345
Stone-coal, 213
red, 415
Storax, 413
Stramonii folia, 350
semina, 350
Stream-tin, 213
Strontianite, 202
Strontium, 202
analytical reations of, 202
carbonate of, 202
derivation of word, 30
flame, 202
nitrate of, 202
sulphate of, 202
Structure of flame, 21
Strychnia, 347
Strychniæ sulphas, 347
Strychnia or strychnine, 347
or strychnine, impurities in, 547
analytical reactions of, 347, 423
in organic mixtures, detection of, 423
Strychnos Ignatius, 347
Strychnos nux vomica, 347
Styracin, 413
Styrax benzoin, 413
præparatus, 413
Styrol, 413
Styrone, 413
Subacetate of copper, 168
of lead, 186
Subcarbonate of iron, 122
Subchloride of mercury, 177
Sublimation, 78, 176
Sublimed sulphur, 269
Subnitrate of bismuth, 223
Substances readily deoxidized, quantitative estimation of, 493
readily oxidized, quantitative estimation of, 488
Substitution-products, 386
Succi, 442
Succinic acid, 315
Succinum, 315
Succus limonum, 290
Sucrose, 361
Suet, 402
prepared, 402
Sugar, 361
brown, 361
-candy, 361
cane-, 361
detection of in urine, 430
grape-, 362
inverted, 361, 362
lump, 361
-maple, 361
milk-, 363
moist, 362
of lead, 186
quantitative estimation of, 534
tests for, 361
Sulphate of aluminium, 116
aluminium and ammonium, 116
ammonium, 76
ammonium and iron, 117
barium, 88
bismuth, 225
cadmium, 222
calcium, 90, 97
chromium, 211
cinchonia, 346
cobalt, 207
copper, 168
copper, anhydrous, 168
cupr-diammon-diammonium, 182
indigo, 258
iron, 121
iron, solution of, 121
lead, 89
magnesium, 100, 505
manganese, 206
mercury, 175
potassium, 60, 255
quinine, 343
sodium, 239
strontium, 202
zinc, 110
Sulphates, 275
analytical reactions of, 277
quantitative estimation of, 519

Sulphethylic acid, 377
Sulphide of ammonium, 80
antimony, 155, 157
arsenicum, 151
arsenicum, native, 144
barium, 88
bismuth, 266
cadmium, 222
calcium, 279
cobalt, 207
copper, 168
iron, 121
lead, 189
lead, native, 185
manganese, 206
mercury, 182
mercury, native, 170
nickel, 209
potassium, 56
silver, 194
silver, native, 191
tin, 215
zinc, 114
zinc, native, 110
Sulphides, 269
analytical reactions of, 271
arsenicum, native, 144
quantitative estimation of, 517
Sulphindigotic acid, 258
Sulphindylic acid, 258
Sulphite of barium, 274
calcium, 274
magnesium, 273
potassium, 273
silver, 274
zinc, 109
Sulphites, 272
analytical reactions of, 274
quantitative estimation of, 519
Sulphocarbolates, 392
Sulphocarbolic acid, 392
Sulphocyanate of allyl, 393
butyl, 382
iron, 138
Sulphocyanates, 316
Sulphocyanic acid, 316
Sulphocyanides, 316
Sulphocyanogen, 316
Sulphophenates, 392
Sulphophenic acid, 392
Sulphovinic acid, 377
Sulphur, 26
adulteration of, 271
allotropy of, 359
analytical reactions of, 271
arsenic in, 152
bromide of, 272
chloride of, 272
derivation of word, 28
estimation of, 517
flowers of, 269
hypochloride of, 272
iodide of, 244
liver of, 58
milk of, 270
oxyacids, 307
plastic, 269
precipitated, 270
roll, 269
sublimed, 269
Sulphur lotum, 269
præcipitatum, 270
præcipitatum, impurities in, 547
sublimatum, 269
sublimatum, impurities in, 547
Sulphurated antimony, 159
potash, 56
Sulphurets, *vide* Sulphides.
Sulphuretted hydrogen, 269
Sulphuric acid, 275
acid, antidotes to, 278
acid, aromatic, 276
acid, dilute, 276
acid, fuming, 277
acid, Nordhausen, 277
acid in organic mixtures, detection of, 421
acid, purification of, 277
acid, standard solution of, 482
acid, volumetric estimation of, 484
anhydride, 276
Sulphuris iodidum, 214
iodidum, impurities in, 548
Sulphurous acid, 26, 272
acid, volumetric estimation of, 489
anhydride, 272
Sulphydrate of ammonium, solution of, 81
Sulphydric acid, 81, 269
Sumatra camphor, 409
Sumbul, 412
Superphosphate of lime, 292

Supporters of combustion, 21
Suppositoria acidi tanici, 317
morphiæ, 341
plumbi composita, 186
Suppositories, 442
Surface unit, 455
Surgery, 14
Sweet spirit of nitre, 312, 379
spirit of nitre, adulterated, 384
Sylvic acid, 410
Symbol, function of, 37
Symbols of elements, 27, 37
illustrative of chemical action by, 40
Sympathetic inks, 208
Synaptase, 366
Synthesis, 52
Syphon, 94
Syrup of iodide of iron, 27
Syrups, 442
Syrupi, impurities in, 548
Syrupus aurantii, 406
aurantii floris, 406
ferri iodidi, 27
ferri phosphatis, 123
fuscus, 364

Tabaci folia, 352
Tamarindus, 289
impurities in, 543
Tannic acid, 317
Tanning, 318
Tantalum, 552
Tapioca, 356
Taraxaci radix, 343
Taraxacin, 243
Tartar, meaning of, 284
Tartar, cream of, 53, 66, 284, 478
emetic, 157, 284
emetic, estimation of antimony in, 509
Tartarated antimony, 157
Tartaric acid, 284, 315
saturating power of, 286, 549
solution of, 385
Tartarus boraxatus, 397
Tartrate of ammonium, 84
antimony and potassium, 157, 284
calcium, 287
potassium, acid, 53, 66
potassium, neutral, 66
potassium and sodium, 72
Tartrate of—
silver, 288
sodium, 66
Tartrates, 61, 284
analytical reactions of, 287
volumetric estimation of, 485
Taurine, 401
Taurocholates, 401
Tellurium, 552
Temperature, correction of vol. of gas for, 469
measurement of, 447
Terebinthina, 408
canadensis, 408
Terra di sienna, 417
Terra japonica, 318
Testa præparata, 94
Test-papers, 83
-tube, 16
Tetramines, 339
Tetrathionic acid, 307
Tetryl, 381
Thalleiochin, 344
Thallium, 552
Thebaia, 341
Theia, 353
Theine, 353
Thenard's blue, 416
Theobroma oil, 402
Therapeutics, definition and derivation of, 14
Theriaca, 364
Thermometer, 447
Celsius's, 448
Centigrade, 448
Fahrenheit's, 448
Reaumur's, 448
Thermometric scales, conversion of degrees of, 449
Thionic acids, 307
Thorinum, 552
Thorium, 552
Thorn-apple, 350
Thus americanum, 412
Thyme, oil of, 409
Thymene, 409
Thymol, 409
Tiglic acid, 403
Tin, 213
amalgam, 214
analytical reactions of, 215
antidotes to, 216
block, 213
chloride of, 214

Tin—
derivation of word, 30
dropped or grain, 213
foil, 214
granulated, 214
oxide of, 215
perchloride of, 214
plate, 214
prepare-liquor, 215
-stone, 213
tacks, 214
-white cobalt, 207
Tinctura ferri acetatis, 127
ferri perchloridi, 126
iodi, 244
iodinii, 244
iodinii composita, 244
quiniæ, 344
Tincturæ, 126
Tinctures, 126, 442
Tinnevelly senna, 367
Titanium, 552
Tobacco, 353
Tolu, balsam of, 413
Toluol, 391
Tous les mois, 357
Toxicology, 418
Tragacanth, 97
Tragacantha, 97
Treacle, 366
Triads, 165
Triamines, 339
Triangle, wire, 84
Tribasic acids, 237
Trybasylous radicals, 237
Triethylamine, 339
Triethylia, 339
Trinitro-carbolic acid, 392
Trinitrocellulin, 359
Triphane, 201
Trithionic acid, 307
Trityl, 381
Tritylia, 339
Trivalence, 47
Trivalent radicals, 47, 55, 104
Trochisci acidi tannici, 317
bismuthi, 224
ferri redacti, 135
morphiæ, 341
morphiæ et ipecacuanhæ, 341
potassæ chloratis, 262
sodæ bicarbonatis, 71
Tube-funnels, 81
Tubes for collecting gases, 61
Tubes—
glass, *vide* Glass tubes.
Tungsten, 552
Turgite, 129
Turmeric, 415
Turmeric paper, 83, 297
Turnbull's blue, 304, 416
Turpentine, 408
American, 408
Bordeaux, 408
Canadian, 408
Chian, 408
French, 408
rectified oil of, 408
spirit of, 408
Venice, 408
Turpeth mineral, 176
Turps, 408
Type-metal, 155, 185

Ulmi cortex, 318
Ulmus fulva, 318
Ultimate analysis, 525
Ultramarine blue, 416
green, 416
Umber, 417
Unguentum aconitiæ, 349
antimonii tartarati, 157
atropiæ, 350
cadmii iodidi, 221
cerussæ, 186
hydrargyri, 171
hydrargyri ammoniati, 182
hydrargyri iodidi rubri, 174
hydrargyri nitratis, 175
hydrargyri oxidi rubri, 179
hydrargyri subchloridi, 178
iodi, 244
iodinii compositum, 244
plumbi acetatis, 187
plumbi carbonatis, 186
plumbi iodidi, 188
plumbi subacetatis compositum, 187
sulphuris iodidi, 244
veratriæ, 354
zinci, 112
Units of capacity, 455
surface, 455
weight, 455
Univalence, 47
Univalent radicals, 47, 55, 104
Uranium, 552
Urate of lithium, 201

Urates, 320
Urceola elastica, 493
Urea, 301, 430
artificial, 301, 431
Uric acid, 320, 434
Urinary calculi, 439
calculi, examination of, 439
deposits or sediments, plates of, *vide* 434 *et seq.*
sediments, 432
sediments, microscopical examination of, 433
Urine, 429
diabetic, 362, 430, 534
morbid, examination of, 429
Urinometer, 466
Uvæ, 363
ursi folia, 310

Valerian oil, 408
Valerianæ radix, 408
Valerianate of amyl, 389
of quinia, 344
sodium, 321
zinc, 113, 321
Valerianates, 320
Valerianic acid, 320, 404
Valerol, 408
Vanadates, 296
Vanadinite, 296
Vanadium, 296, 552
relationship to nitrogen, phosphorus, and arsenicum, 296
Vanilla, 413
Vapor acidi hydrocyanici, 249
chlori, 25
coniæ, 352
iodi, 243
Vapor-density, 470
Variolaria, 416
Vegetable albumen, 298
and animal life, relation of, 7
casein, 356, 398
crocus, 415
fibrin, 356, 398
gelatine, 358
green, 416
jelly, 358
oil, 400
rouge, 416
substances, 338 *et seq.*
Venetian red, 129
Venice turpentine, 408
Veratri viridis radix, 354
Veratria, 354
impurities in, 548
Veratria or Veratrine, 354
Veratrum album, 354
Verdigris, 168
Vermilion, 182
Vinegar, 265
of cantharides, 265
squill, 265
Vinum antimonale, 157
aurantii, 372
ferri, 133
ferri citratis, 133
portense, 372
quiniæ, 344
xericum, 372
Vitriol, blue, 121
green, 121
oil of, 276
white, 121
Volatile oils, *vide* Oils.
Volatility of salts of ammonium, 84
Volatilization, 84
Volcanic ammonia, 76
Volume, combination by, 44
of gas, corrections of, 469
molecular, 46
Volumetric analysis, 475
estimation of acetate of lead, 480
estimation of acetic acid, 484
estimation of acids, 483
estimation of alkalies, 476
estimation of alkaline carbonates, 481
estimation of ammonia solutions, 478
estimation of arseniate of iron, 492
estimation of arseniate of sodium, 487
estimation of arsenic and arsenical solutions, 489
estimation of borax, 480
estimation of bromides, 487
estimation of bromide of potassium, 487
estimation of chlorides, 515
estimation of chlorinated lime, 495
estimation of chlorinated soda, 494
estimation of chlorine, 495

Volumetric—
estimation of citrate of potassium, 481
estimation of citrates, 481
estimation of cyanides, 487
estimation of hydrochloric acid, 484
estimation of hydrocyanic acid, 487
estimation of hyposulphite of sodium, 489
estimation of iodides, 487
estimation of magnetic oxide of iron, 492
estimation of nitric acid, 484
estimation of official compounds, 478, 484, 486, 489, 492, 494
estimation of phosphate of iron, 492
estimation of potash, 478
estimation of saccharated carbonate of iron, 492
estimation of soda, 478
estimation of sugar, 534
estimation of sulphides, 517
estimation of sulphites, 519
estimation of sulphuric acid, 484
estimation of sulphurous acid, 489
estimation of tartrates, 481
solutions, 477, 482, 483, 486, 488, 491, 493
Vulcanite, 414
Vulcanized India-rubber, 414

Washing-bottles, 93, 498
precipitates, 93, 499
Warmth of animals, how kept up, 18
Water, 108
aërated, 71
-bath, 500
boiling-point of, 450
chalybeate, 119
composition of, 20
crystallization, 70
quantitative estimation of, 524
cubic inches of, in a gallon, 469
distilled, 109
evaporation of, 58
Water—
formation of, expressed by symbols, 39
hardness of, 281
lime-, 92
of crystallization, 70, 71
-oven, 498
oxygenated, 88
purification of, 108, 281
softness of, 281
weight of 1 cubic inch of, 470
weight of minim, drachm, ounce, pint, and gallon, 460
Wax, 402
Weighing-tubes, 498
Weight, 452
estimation of, 452
molecular, 46
of air, 470
of hydrogen, 470
of water, 470
specific, 463
Weights, atomic, 43
and measures of the British Pharmacopœia of 1867, 459
and measures of the metric decimal system, 454 *et seq.*
balance, 453
relation of metrical to the weights of the U. S. Pharmacopœia, 458, 459
relative, 44
Weld, 415
Welding, 221
Wheaten flour, 355
Whey, 362, 397
Whiskey, 372
White arsenic, 144
indigo, 258
lead, 186
pepper, 353
pigments, 417
precipitate, fusible, 181
infusible, 182
resin, 410
vitriol, 121
wax, 402, 457
Whiting, 94
Willow bark, 370
Wine, 372, 493
antimonial, 157
iron, 133
orange, 372
quinine, 344

Wine—
sherry, 372
steel, 133
Winter-green, oil of, 390
Wire-gauze tray, 24
triangle, 84
Witherite, 87
Wood-charcoal, 95
creasote, 391
naphtha, 383
oil, 412
spirit, 383
tar, 412
Woody nightshade, 353
Wormseed, 408
Wrought iron, 120

Xanthin, 441
Xylol, 391

Yard, 460
Yeast, 372
Yelk of egg, 396
Yellow chromate of potassium, 210
coloring-matters, 414
ochre, 414
oxide of mercury, 179
prussiate of potassium, 248, 302
sienna, 414
wax, 402, 457
wood, 414
Yolk of egg, 396
Yttrium, 552

Zaffre, 207
Zinc, 109
acetate of, 112
analytical reactions of, 114
Zinc—
antidotes to, 115
carbonate of, 109, 112
chloride of, 111
derivation of word, 29
detection of in presence of aluminium and iron, 139
-ethyl, 380
ferrocyanide of, 114
granulated, 19
hydrate of, 114
in organic mixtures, detection of, 421
oxide of, 113
oxide of, Hubbuck's, 113
quantitative estimation of, 506
sulphate of, 110
sulphide of, 114
sulphide of, native, 109
sulphite of, 114
valerianate of, 113
white, 113
Zinci acetas, 113
acetas, impurities in, 548
carbonas, 109, 112
carbonas, impurities in, 548
chloridi, liquor, 112
chloridum, 111
chloridum, impurities in, 548
oxidum, 113
oxidum, impurities in, 548
sulphas, 110
sulphas, impurities in, 548
unguentum, 112
valerianas, 113, 321
valerianas, impurities in, 548
Zincum, 110
granulatum, 19
Zingiber, 408
Zirconium, 552

540
At. 3c 5
Call Number

Overdue books are subject to a fine of 2 cents a day.

Author Attfield, John
Title Chemistry

Name F. Janicek
Address 115 W. Nevada

Univ. of Ill. Lib. Call Slip

UNIVERSITY OF ILLINOIS-URBANA
3 0112 067991387